
iOS 5 Programming Cookbook

Vandad Nahavandipoor

O'REILLY®

Beijing • Cambridge • Farnham • Köln • Sebastopol • Tokyo

iOS 5 Programming Cookbook

by Vandad Nahavandipoor

Revision History for the :

See <http://oreilly.com/catalog/errata.csp?isbn=9781449311438> for release details.

ISBN: 978-1-449-31143-8
1318287906

To Agnieszka Marta Dybowska.

Table of Contents

Preface	ix
1. The Basics	1
1.1 Creating a Simple iOS App in Xcode	2
1.2 Understanding Interface Builder	7
1.3 Compiling iOS Apps	13
1.4 Running iOS Apps on the Simulator	15
1.5 Running iOS Apps on iOS Devices	17
1.6 Packaging iOS Apps For Distribution	21
1.7 Declaring Variables in Objective-C	27
1.8 Comparing Values in Objective-C with an If Statement	29
1.9 Implementing Loops with For Statements	32
1.10 Implementing While Loops	35
1.11 Creating Custom Classes	37
1.12 Defining Functionality for Classes	42
1.13 Defining Two or More Methods with the Same Name	46
1.14 Allocating and Initializing Objects	49
1.15 Adding Properties to Classes	51
1.16 Moving from Manual Reference Counting to Automatic Reference Counting	54
1.17 Typecasting with Automatic Reference Counting	59
1.18 Delegating Tasks with Protocols	63
1.19 Determining Whether Instance or Class Methods are Available	71
1.20 Determining Whether a Class is Available at Run Time	74
1.21 Allocating and Making Use of Strings	75
1.22 Allocating and Making Use of Numbers	79
1.23 Allocating and Making Use of Arrays	81
1.24 Allocating and Making Use of Dictionaries	86
1.25 Allocating and Making Use of Sets	89
1.26 Creating Bundles	92
1.27 Loading Data From the Main Bundle	93
1.28 Loading Data From Other Bundles	97

1.29	Sending Notifications with NSNotificationCenter	100
1.30	Listening for Notifications Sent From NSNotificationCenter	104
2.	Implementing Controllers and Views	109
2.1	Displaying Alerts with UIAlertView	110
2.2	Creating and Using Switches with UISwitch	121
2.3	Picking Values with UIPickerView	126
2.4	Picking Date and Time with UIDatePicker	136
2.5	Implementing Range Pickers with UISlider	144
2.6	Grouping Compact Options with UISegmentedControl	151
2.7	Presenting and Managing Views with UIViewController	159
2.8	Implementing Navigation with UINavigationController	163
2.9	Manipulating a Navigation Controller's Array of View Controllers	170
2.10	Displaying an Image on a Navigation Bar	171
2.11	Adding Buttons to Navigation Bars with UIBarButtonItem	172
2.12	Presenting Multiple View Controllers with UITabBarController	182
2.13	Displaying Static Text with UILabel	191
2.14	Accepting User Text Input with UITextField	196
2.15	Displaying Long Lines of Text with UITextView	208
2.16	Adding Buttons to the User Interface with UIButton	214
2.17	Displaying Images with UIImageView	220
2.18	Creating Scrollable Content with UIScrollView	226
2.19	Loading Web Pages with UIWebView	231
2.20	Presenting Master-Detail Views with UISplitViewController	237
2.21	Enabling Paging with UIPageViewController	245
2.22	Displaying Popovers with UIPopoverController	251
2.23	Displaying Progress with UIProgressView	262
2.24	Listening and Reacting to Keyboard Notifications	264
3.	Constructing and Using Table Views	281
3.1	Instantiating a Table View	281
3.2	Assigning a Delegate to a Table View	284
3.3	Populating a Table View with Data	286
3.4	Receiving and Handling Table View Events	290
3.5	Using Different Types of Accessories in a Table View Cell	291
3.6	Creating Custom Table View Cell Accessories	294
3.7	Displaying Hierarchical Data in Table Views	297
3.8	Enabling Swipe Deletion of Table View Cells	299
3.9	Constructing Headers and Footers in Table Views	302
3.10	Displaying Context Menus on Table Views Cells	314
3.11	Moving Cells and Sections in Table Views	319
3.12	Deleting Cells and Sections from Table Views	326

4. Storyboards	329
4.1 Creating a Project with Storyboards	330
4.2 Adding a Navigation Controller to a Storyboard	333
4.3 Passing Data From One Screen to Another	346
4.4 Adding a Storyboard to an Existing Project	349
5. Concurrency	353
5.1 Constructing Block Objects	358
5.2 Accessing Variables in Block Objects	362
5.3 Invoking Block Objects	369
5.4 Dispatching Tasks to Grand Central Dispatch	370
5.5 Performing UI-Related Tasks with GCD	371
5.6 Performing Non-UI-Related Tasks Synchronously with GCD	376
5.7 Performing Non-UI Related Tasks Asynchronously with GCD	379
5.8 Performing Tasks After a Delay with GCD	385
5.9 Performing a Task at Most Once with GCD	388
5.10 Grouping Tasks Together with GCD	390
5.11 Constructing Your Own Dispatch Queues with GCD	394
5.12 Running Tasks Synchronously with Operations	397
5.13 Running Tasks Asynchronously with Operations	404
5.14 Creating Dependency Between Operations	411
5.15 Creating Concurrency with Timers	413
5.16 Creating Concurrency with Threads	418
5.17 Invoking Background Methods	424
5.18 Exiting Threads and Timers	425
6. Core Location and Maps	429
6.1 Creating a Map View	431
6.2 Handling the Events of a Map View	435
6.3 Pinpointing the Location of a Device	436
6.4 Displaying Pins on a Map View	439
6.5 Displaying Pins with Different Colors on a Map View	443
6.6 Displaying Custom Pins on a Map View	449
6.7 Converting Longitude and Latitude to a Meaningful Address	452
6.8 Converting Meaningful Addresses to Longitude and Latitude	455
7. Implementing Gesture Recognizers	457
7.1 Detecting Swipe Gestures	459
7.2 Detecting Rotation Gestures	461
7.3 Detecting Panning and Dragging Gestures	465
7.4 Detecting Long Press Gestures	467
7.5 Detecting Tap Gestures	470
7.6 Detecting Pinch Gestures	472

8. Networking, JSON, XML and Twitter	475
8.1 Downloading Asynchronously with NSURLConnection	475
8.2 Handling Timeouts in Asynchronous Connections	478
8.3 Downloading Synchronously with NSURLConnection	479
8.4 Modifying a URL Request with NSMutableURLRequest	482
8.5 Sending HTTP GET Requests with NSURLConnection	483
8.6 Sending HTTP POST Requests with NSURLConnection	486
8.7 Sending HTTP DELETE Requests with NSURLConnection	489
8.8 Sending HTTP PUT Requests with NSURLConnection	491
8.9 Serializing Arrays and Dictionaries into JSON	494
8.10 Deserializing JSON into Arrays and Dictionaries	496
8.11 Integrating Twitter Functionality Into Your Apps	499
8.12 Parsing XML with NSXMLParser	508
 9. Audio and Video	 515
9.1 Playing Audio Files	515
9.2 Handling Interruptions While Playing Audio	517
9.3 Recording Audio	518
9.4 Handling Interruptions While Recording Audio	525
9.5 Playing Audio over Other Active Sounds	526
9.6 Playing Video Files	530
9.7 Capturing Thumbnails from a Video File	534
9.8 Accessing the Music Library	537
 10. Address Book	 547
10.1 Getting a Reference to Address Book	550
10.2 Retrieving All the People in the Address Book	552
10.3 Retrieving Properties of Address Book Entries	553
10.4 Inserting a Person Entry into the Address Book	558
10.5 Inserting a Group Entry into the Address Book	562
10.6 Adding Persons to Groups	565
10.7 Searching the Address Book	569
10.8 Retrieving and Setting a Person's Address Book Image	573
 11. Camera and the Photo Library	 581
11.1 Detecting and Probing the Camera	583
11.2 Taking Photos with the Camera	588
11.3 Taking Videos with the Camera	592
11.4 Storing Photos in the Photo Library	595
11.5 Storing Videos in the Photo Library	598
11.6 Retrieving Photos and Videos from the Photo Library	600
11.7 Retrieving Assets from the Assets Library	601
11.8 Editing Videos on an iOS Device	609

12. Multitasking	615
12.1 Detecting the Availability of Multitasking	616
12.2 Completing a Long-Running Task in the Background	617
12.3 Receiving Local Notifications in the Background	621
12.4 Playing Audio in the Background	630
12.5 Handling Location Changes in the Background	633
12.6 Saving and Loading the State of Multitasking iOS Apps	636
12.7 Handling Network Connections in the Background	639
12.8 Handling Notifications Delivered to a Waking App	642
12.9 Responding to Changes in App Settings	644
12.10 Opting Out of Multitasking	647
 13. Core Data	 649
13.1 Creating a Core Data Model with Xcode	653
13.2 Generating Class Files for Core Data Entities	658
13.3 Creating and Saving Data Using Core Data	661
13.4 Reading Data from Core Data	663
13.5 Deleting Data From Core Data	666
13.6 Sorting Data in Core Data	669
13.7 Boosting Data Access in Table Views	671
13.8 Implementing Relationships in Core Data	683
 14. Dates, Calendars and Events	 691
14.1 Retrieving the List of Calendars	694
14.2 Adding Events to Calendars	696
14.3 Accessing the Contents of Calendars	700
14.4 Removing Events from Calendars	705
14.5 Adding Recurring Events to Calendars	709
14.6 Retrieving the Attendees of an Event	714
14.7 Adding Alarms to Calendars	719
14.8 Handling Event Changed Notifications	721
14.9 Presenting Event View Controllers	724
14.10 Presenting Event Edit View Controllers	729
 15. Graphics and Animations	 733
15.1 Enumerating and Loading Fonts	745
15.2 Drawing Text	747
15.3 Constructing, Setting, and Using Colors	749
15.4 Drawing Images	754
15.5 Drawing Lines	759
15.6 Constructing Paths	766
15.7 Drawing Rectangles	771
15.8 Adding Shadows to Shapes	776

15.9	Drawing Gradients	783
15.10	Displacing Shapes Drawn on Graphic Contexts	792
15.11	Scaling Shapes Drawn on Graphic Contexts	796
15.12	Rotating Shapes Drawn on Graphic Contexts	800
15.13	Animating and Moving Views	802
15.14	Animating and Scaling Views	812
15.15	Animating and Rotating Views	814
16.	Core Motion	817
16.1	Detecting the Availability of an Accelerometer	819
16.2	Detecting the Availability of a Gyroscope	821
16.3	Retrieving Accelerometer Data	822
16.4	Detecting Shakes on an iOS Device	825
16.5	Retrieving Gyroscope Data	830
17.	iCloud	833
17.1	Setting Up Your App For iCloud	834
17.2	Storing and Synchronizing Dictionaries in iCloud	840
17.3	Creating and Managing Folders for Apps in iCloud	845
17.4	Searching for Files and Folders in iCloud	852
17.5	Storing User Documents in iCloud	862
Index	879

Preface

I started developing iPhone applications in late 2007. Between then and now, I have worked on various iPhone OS applications for different companies across the globe. As you might have already guessed, iOS is my favorite platform and Objective-C is my favorite programming language. I find that Objective-C helps programmers write clean code and iOS helps developers write user-friendly and useful applications.

I have coded in other programming languages such as Assembly (using NASM and TASM) and Delphi/Pascal for many years, and I still find myself going through disassembled Objective-C code to find out which method of doing a certain thing or accomplishing a certain result in Objective-C is better optimized on a certain device and/or operating system.

After becoming comfortable with the iOS SDK, I gradually built up a thirst to write a book about the iOS SDK, and with the help of wonderful people at O'Reilly, you are now reading the result of the several hundred hours that have been put into writing new material for iOS 3 and iOS 4, editing, reviewing, revising, and publishing.

So, please go ahead and start exploring the recipes. I hope you'll find that they are easy to cook and digest!

Audience

I assume you are comfortable with the iOS development environment and know how to create an app for the iPhone or iPad. This book does not get novice programmers started, but presents useful ways to get things done for iOS programmers ranging from novices to experts.

Organization of This Book

In this book, we will discuss frameworks and classes that are available in iOS 3 and iOS 4. In some recipes, you will find code that runs only on iOS 4 and later; in those recipes, I note that you will need the iOS 4 SDK or later to compile the example code.

Here is a concise breakdown of the material each chapter covers:

Chapter 1, The Basics

Explains how Objective-C classes are structured and how objects can be instantiated. The chapter talks about properties and delegates as well as memory management in Objective-C. Even if you are competent in Objective-C, I strongly suggest that you go through this chapter, even if you are skimming through it, to understand the basic material that is used in the rest of the chapters.

Chapter 2, Implementing Controllers and Views

Describes various approaches to constructing your iOS application's user interface by taking advantage of different tools the SDK provides. This chapter also introduces you to features that are only available on the iPad, such as the popover and split view controllers.

Chapter 3, Constructing and Using Table Views

Shows how you can work with table views to create professional-looking iOS applications. Table views are very dynamic in nature, and as a result, programmers sometimes have difficulty understanding how they should work with them. By reading this chapter and having a look at and trying out the example code, you will gain the knowledge that is required to comfortably work with table views.

Chapter 6, Core Location and Maps

Describes how you should use Map Kit and Core Location APIs to develop location-aware iOS applications. First you will learn about maps, and then you will learn how to detect a device's location and tailor your maps with custom annotations. You will also learn about geocoding and reverse geocoding, as well as some of the methods of the Core Location framework, which are only available in the iOS 4 SDK and later.

Chapter 7, Implementing Gesture Recognizers

Demonstrates how to use gesture recognizers, which enable your users to easily and intuitively manipulate the graphical interface of your iOS applications. In this chapter, you will learn how to use all available gesture recognizers in the iOS SDK, with working examples tested on iOS 3 and iOS 4 on different devices such as the iPhone 3GS, iPhone 4, and iPad.

Chapter 8, Networking, JSON, XML and Twitter

Demonstrates how to download data from a URL and parse XML files. You will learn about synchronous and asynchronous connections and their pros and cons. You will also learn about caching files in memory and on disk to avoid consuming the possibly limited bandwidth of an iOS device on which your application could be running.

Chapter 9, Audio and Video

Discusses the AV Foundation and Media Player frameworks that are available on the iOS SDK. You will learn how to play audio and video files and how to handle interruptions, such as a phone call, while the audio or video is being played on

both iOS 3 and iOS 4. This chapter also explains how to record audio using an iOS device's built-in microphone(s). At the end of the chapter, you will learn how to access the iPod Library and play its media content, all from inside your application.

[Chapter 10, *Address Book*](#)

Explains the Address Book framework and how to retrieve contacts, groups, and their information from the Address Book database on an iOS device. The Address Book framework is composed entirely of C APIs. Because of this, many Objective-C developers find it difficult to use this framework compared to frameworks that provide an Objective-C interface. After reading this chapter and trying the examples for yourself, you will feel much more confident using the Address Book framework.

[Chapter 11, *Camera and the Photo Library*](#)

Demonstrates how you can determine the availability of front- and back-facing cameras on an iOS device. Some of the recipes in this chapter are specific to iOS 4, with the rest working on both iOS 3 and iOS 4. You will also learn how to access the Photo Library using the Assets Library framework which is available in iOS 4 and later. At the end of the chapter, you will learn about editing videos right on an iOS device using a built-in view controller.

[Chapter 12, *Multitasking*](#)

Explains, with examples, how to create multitasking-aware applications that run beautifully on iOS 4. You will learn about background processing, from playing audio and retrieving users' locations in the background, to downloading content from a URL while your application is running in the background.

[Chapter 13, *Core Data*](#)

Describes how to maintain persistent storage for your iOS applications using Core Data. You will learn how to add to, delete from, and edit Core Data objects and how to boost access to data in a table view. In addition, you will learn how to manage relationships between Core Data objects.

[Chapter 14, *Dates, Calendars and Events*](#)

Demonstrates the use of the Event Kit and Event Kit UI frameworks, which are available on iOS 4 and later, in order to manage calendars and events on an iOS device. You will see how to create, modify, save, and delete events. You will also learn, through examples, how to add alarms to calendar events and how to set up CalDAV calendars so that you can share a single calendar among multiple devices.

[Chapter 15, *Graphics and Animations*](#)

Introduces the Core Graphics framework. You will learn how to draw images and text on a graphics context, grab the contents of a graphics context and save it as an image, and much more.

[Chapter 16, *Core Motion*](#)

Explains the Core Motion framework, which is new in iOS 4. Using Core Motion, you will access the accelerometer and the gyroscope on an iOS device. You will also learn how to detect shakes on a device. Of course, not all iOS devices are

equipped with an accelerometer and a gyroscope, so you will also learn how to detect the availability of the required hardware.

Additional Resources

From time to time, I refer to official Apple documentation. Some of Apple’s descriptions are right on the mark, and there is no point in trying to restate them. Throughout this book, I have listed the most important documents and guides in the official Apple documentation that every professional iOS developer should read.

For starters, I suggest that you have a look at the “iPhone Human Interface Guidelines” and the “iPad Human Interface Guidelines.” These two documents will tell you everything you should know about developing engaging and intuitive user interfaces for the iPhone/iPod and the iPad. Every iOS programmer must read these documents. In fact, I believe these documents must be read by the product design and development teams of any company that develops iOS applications.

iPhone Human Interface Guidelines

<http://developer.apple.com/library/ios/#documentation/userexperience/conceptual/mobilehig/Introduction/Introduction.html>

iPad Human Interface Guidelines

<https://developer.apple.com/library/ios/#documentation/General/Conceptual/iPadHIG/Introduction/Introduction.html>

I also suggest that you skim through the “iOS Application Programming Guide” in the iOS Reference Library for some tips and advice on how to make great iOS applications:

<https://developer.apple.com/library/ios/#documentation/iPhone/Conceptual/iPhoneOSProgrammingGuide/Introduction/Introduction.html>

One of the things you will notice when reading [Chapter 12](#) is the use of block objects. This book concisely explains block objects, but if you require further details on the subject, I suggest you read “A Short Practical Guide to Blocks,” available at this URL:

https://developer.apple.com/library/ios/#featuredarticles/Short_Practical_Guide_to_Blocks/index.html%23/apple_ref/doc/uid/TP40009758

<https://developer.apple.com/library/ios/#documentation/Cocoa/Conceptual/KeyValueCoding/KeyValueCoding.html>

Throughout this book, you will see references to “bundles” and loading images and data from bundles. You will read a concise overview about bundles in this book, but if you require further information, head over to the “Bundle Programming Guide,” available at this URL:

<https://developer.apple.com/library/ios/#documentation/CoreFoundation/Conceptual/CFBundles/Introduction/Introduction.html>

Conventions Used in This Book

The following typographical conventions are used in this book:

Italic

Indicates new terms, URLs, filenames, file extensions, and directories

Constant width

Indicates variables and other code elements, the contents of files, and the output from commands

Constant width bold

Highlights text in examples that is new or particularly significant in a recipe

Constant width italic

Shows text that should be replaced with user-supplied values



This icon signifies a tip, suggestion, or general note.

Using Code Examples

This book is here to help you get your job done. In general, you may use the code in this book in your programs and documentation. You do not need to contact us for permission unless you're reproducing a significant portion of the code. For example, writing a program that uses several chunks of code from this book does not require permission. Selling or distributing a CD-ROM of examples from O'Reilly books *does* require permission. Answering a question by citing this book and quoting example code does not require permission. Incorporating a significant amount of example code from this book into your product's documentation *does* require permission.

We appreciate, but do not require, attribution. An attribution usually includes the title, author, publisher, and ISBN. For example: “*iOS 4 Programming Cookbook*, by Vandad Nahavandipoor (O'Reilly). Copyright 2011 Vandad Nahavandipoor, 978-1-449-38822-5.”

If you feel your use of code examples falls outside fair use or the permission given here, feel free to contact us at permissions@oreilly.com.

We'd Like to Hear from You

Every example and code snippet in this book has been tested on the iPhone 4, iPad, iPhone 3GS, and iPhone/iPad Simulator, but occasionally you may encounter problems—for example, if you have a different version of the SDK than the version on which the example code was compiled and tested. The information in this book has

also been verified at each step of the production process. However, mistakes and oversights can occur, and we will gratefully receive details of any you find, as well as any suggestions you would like to make for future editions. You can contact the author and editors at:

O'Reilly Media, Inc.
1005 Gravenstein Highway North
Sebastopol, CA 95472
(800) 998-9938 (in the United States or Canada)
(707) 829-0515 (international or local)
(707) 829-0104 (fax)

We have a web page for this book, where we list errata, examples, and any additional information. You can access this page at:

<http://oreilly.com/catalog/9781449388225>

There is also a companion website to this book where you can see all the examples with color-highlighted syntax:

<http://www.ios4cookbook.com>

To comment or ask technical questions about this book, send email to the following address, mentioning the book's ISBN number (9781449388225):

bookquestions@oreilly.com

For more information about our books, conferences, Resource Centers, and the O'Reilly Network, see our website at:

<http://www.oreilly.com>

Safari® Books Online



Safari Books Online is an on-demand digital library that lets you easily search more than 7,500 technology and creative reference books and videos to find the answers you need quickly.

With a subscription, you can read any page and watch any video from our library online. Read books on your cell phone and mobile devices. Access new titles before they are available for print, and get exclusive access to manuscripts in development and post feedback for the authors. Copy and paste code samples, organize your favorites, download chapters, bookmark key sections, create notes, print out pages, and benefit from tons of other time-saving features.

O'Reilly Media has uploaded this book to the Safari Books Online service. To have full digital access to this book and others on similar topics from O'Reilly and other publishers, sign up for free at <http://my.safaribooksonline.com>.

Acknowledgments

I have always loved writing and running my programs on computers. I look at programming as a way to speak to whatever computer the program runs on. To me, programming is a way to actually connect with the computer and give it instructions and listen to what it says in return.

I have been exceptionally lucky to have almost always found the right people to help me find the right path in whatever journey I've started in my life. First and foremost, I would like to thank my beloved fiancée, Agnieszka Marta Dybowska, for her unconditional love and support throughout the years and for the many hours she had to spend without me while I was working on this book. Your strong enthusiasm for writing and journalism has greatly moved me, and I sincerely hope that one day you will gather enough material to be able to write your book.

I also want to thank Brian Jepson (whose many hidden talents are yet to be discovered!) for giving me a chance to work on this book. This book would have been impossible if it wasn't for Brian's consistent urge to improve the outline and the table of contents that I originally sent him. This reminds me to thank Andy Oram, whom I would like to call the virtual second writer of this book. Andy's perfectionism and his undeniable desire to finely form every single sentence you read in this book are absolutely impressive. I must also thank Sarah Kim and Rachel James for helping me update my profile page on O'Reilly's website. I also appreciate Meghan Blanchette's help in doing the initial paperwork for this book.

I want to say a big thank you to my technical reviewers, Eric Blair and Alasdair Allan, for all their helpful insight. Kirk Pattinson, Gary McCarville, and Sushil Shirke are among the people who have greatly influenced me to become who I am today. Thank you to Sushil for being a great mentor and colleague and for providing continuous support. Thanks to Kirk for believing that I was up to the challenge of working on some high-profile iOS applications. Thank you to Gary for his support while I worked on this project, and for being a wonderful mentor.

Last but not least, I would like to sincerely thank Apple and its employees for making such a wonderful operating system and SDK. It's truly a great pleasure to work with the iOS SDK, and I hope you, the reader, will enjoy working with it as much as I do.

The Basics

1.0 Introduction

A lot has changed in iPhone, iPad, and iPod Touch programming since the introduction of iOS 5. The whole runtime and the way we write Objective-C code has dramatically changed. ARC (Automatic Reference Counting) is now introduced into the LLVM Compiler, which in some ways gives us more flexibility and in other ways makes the runtime more fragile. In this chapter, we will get down and dirty with objects and how we can use them using the modern Objective-C runtime under ARC.

Objects are defined according to *classes*, and therefore these two terms are commonly used interchangeably. But actually, a class is just a specification for defining objects; each object is said to be an *instance* of its class. Each class—and therefore the objects that are created from that class—is a set of properties, tasks, methods, enumerations, and much more. In an object-oriented programming language, classes can inherit from each other much like a person can inherit certain traits and characteristics from his parents.



Objective-C does not allow multiple inheritance. Therefore, every class is the direct descendant of, at most, one other class.

The root class of most Objective-C objects is the `NSObject` class. This class manages the runtime capabilities offered by iOS; as a result, any class that directly or indirectly inherits from `NSObject` will inherit these capabilities as well. As we will see later in this chapter, objects that inherit from `NSObject` can take advantage of Objective-C's distinctive memory management model.




Figure 1-1. The New Project dialog in Xcode

1.1 Creating a Simple iOS App in Xcode

Problem

You've started to learn iOS Programming and you want to create a really simple iOS Project and app in Xcode.

Solution

Create a new iOS Project in Xcode and then run it in the iOS Simulator using Command +Shift+R.

Discussion

I'll assume you have a Mac and you have already installed the Xcode set of tools. Now you want to create an iOS Project and run that App on the iOS Simulator. This process is really straightforward:

1. Open Xcode if you don't have it open yet.
2. Select File on the menu bar, select New, and then select New Project. You will be greeted with a screen similar to that shown in [Figure 1-1](#).

3. In the New Project dialog (Figure 1-1), on the left, make sure the Application category is selected under the iOS main category. Then select Page-Based Application on the right hand side and press the Next button.
4. You will now need to enter your product name (App Name) and your company identifier. This uniquely identifies your product for your own company. Set your product name to *Creating a Simple iOS App in Xcode*. The company identifier is normally a domain name with the components reversed. My company name is Pixolity, and therefore I will set the Company Name to *com.pixolity* as shown in Figure 1-2. Leave the rest of the values in this screen just the way I've left them in Figure 1-2 and press the Next button.




Figure 1-2. Setting the new project's settings

5. You will now be asked to save your project on a disk. Select your desired location and press the Create button, as shown in Figure 1-3. Xcode will now create your project files and the structure of your project.




Figure 1-3. Saving a new iOS project on disk using Xcode

6. Now, before running your app, make sure you have unplugged any iPhones or iPads/iPods that you have connected to your computer. The reason behind this is that if a device is connected to your Mac, Xcode will try to run your apps on the device instead of the simulator, and if you haven't configured your device for development, you might get blocked and not be able to run your apps.
7. From the dropdown on top left corner of Xcode, make sure iPhone Simulator or iPad Simulator is selected. In this example, I will make sure iPad Simulator is selected, as shown in [Figure 1-4](#).




Figure 1-4. Running your iOS App on iPad Simulator

8. Now that everything is ready, press the Command+Shift+R keys on your keyboard or simply go to the Product menu and then press the Run button as shown in [Figure 1-5](#).




Figure 1-5. The Run menu item in Xcode

Congratulations. Now you have a simple app running in iOS Simulator. As you saw, there are various different iOS project templates that you can choose from ([Figure 1-1](#)). Here is a list of some of the handy project templates that you can use:

Master-Detail Application

This project template will set up a split view controller for your use. Split view controllers are explained in [Chapter 2, Implementing Controllers and Views](#).

Page-Based Application

This template will allow your app to have an iBooks user interface, where the user will be able to flip through the pages that are drawn by the app. You'll learn more about this in [Chapter 2, Implementing Controllers and Views](#).

Empty Application

An empty application is simply made out of the most basic components that any iOS app has. I use this template a lot to set up my iOS apps the way I like them to be set up, without any preconfiguration by Xcode.

See Also

XXX

1.2 Understanding Interface Builder

Problem

You want to start designing a user interface for your iOS apps but don't want to waste time coding.

Solution

Use Interface Builder.

Discussion

Interface Builder, or IB, is integrated into Xcode as a tool for creating a user interface for your Mac and iOS apps. IB manipulates *.xib* files, which are called *nib* files to reflect the file extension they had in past Apple products. A nib file is basically an XML file that is managed by IB.

Let's go ahead and start using IB. To do this, first create an iOS App using the Single View Application iOS Project template in Xcode. Follow the instructions in [Recipe 1.1](#), but instead of Page-Based Application template ([Figure 1-1](#)), use the Single View Application template and follow it to the last dialog to save your project to disk. I've named the project Understanding Interface Builder.



Make sure your app is a Universal app, as shown in [Figure 1-2](#).

After your project is created, the first thing you need to do is make sure it is going to run on iPhone Simulator, as shown in [Figure 1-6](#).




Figure 1-6. Choosing to run your app on iPhone Simulator

Now press Command+Shift+R to run your application. You will then see the iOS Simulator showing your empty application, as shown in [Figure 1-7](#).




Figure 1-7. An empty Single View Application running on iOS Simulator

Now find the file *Understanding_Interface_BuilderViewController_iPhone.xib* in your project and click on it. Interface Builder will open up within Xcode and will display your user interface to you. Now that you have IB open, select from Xcode menus the option View and then Utilities, and finally select Show Object Library ([Figure 1-8](#)).




Figure 1-8. UI Objects in the Object Library in Interface Builder

Now if you have a look at the Object Library, you can see that you have plenty of choice as to what you want to put on your interface. This includes buttons, on/off switches, progress bars, table views, etc. For now, drag and drop a button on your user interface. As simple as that (Figure 1-9).




Figure 1-9. A button on a nib

Right after this, from the Xcode menus, select File and then Save to make sure your *Understanding_Interface_BuilderViewController_iPhone.xib* is saved. Then go ahead and run your app on iOS Simulator ([Figure 1-10](#)).




Figure 1-10. A button on the UI of your app

You might be surprised, but for now that is *all* that we need to know about Interface Builder.

See Also

XXX

1.3 Compiling iOS Apps

Problem

You have learned how to create an iOS app and wonder how it behaves.

Solution

Compile and run your iOS apps using Apple's latest compiler. Then test your app on iOS Simulator and also, preferably, on a device.

Discussion

Creating an iOS App can be categorized under the following tasks:

1. Planning
2. Prototyping
3. Designing
4. Implementing and Testing
5. Delivering

During the implementation of an app, you will constantly need to run your app on a simulator or on various devices to make sure it is consistent, adheres to the design guidelines that you or your teammates created for this project, and most importantly, is stable enough for the App Store.



Crashes provide one of the major reasons for app rejections in the Apple App Store. Apps that are not stable and crash often are not good enough for consumers and Apple is very likely to reject them. So always make sure that you thoroughly test your apps on iOS Simulator and on devices.

When we write our code, as we will learn very soon, we need to make sure that what we are writing is correct. The process by which Xcode changes our code into executable instructions is called *compilation*. The compiler does the compilation. In Xcode, we use various build commands to compile our apps:

Build for Running

Use this when you want to debug your applications on the simulator or on a device. Debugging is the process by which you can find mistakes in your code.

Build for Testing

Use this build setting to run unit-tests that you've written for your apps. Unit tests, in short, are a set of instructions that you provide to Xcode. Xcode will run these

instructions before it makes the final build. These instructions have one purpose only: to make sure that each part of the app you've written is in full working order.

Build for Profiling

If you want to test the performance of your app, use this setting. Profiling is the process by which you can find bottlenecks, memory leaks, and other quality-related issues not covered by unit testing.

Build for Archiving

When you are sure your app is production quality or simply want to distribute it to testers, use this setting.

To compile your apps, in Xcode, simply select the Product menu item, choose Build For, and then choose whichever build setting you believe is relevant to the task you want to accomplish.

What do you think happens if you have an error in your code? In [Recipe 1.1](#) we created a simple Page-Based Application, so let's go back to that app. Now open the *RootViewController.m* file in your project and look for this code:

```
- (void)viewWillAppear:(BOOL)animated
{
    [super viewWillAppear:animated];
}
```

Change this code to the following:

```
- (void)viewWillAppear:(BOOL)animated
{
    [super nonExistantMethod];
    [super viewWillAppear:animated];
}
```

If you now try to use Product menu, Build For, and then Build For Running, you will get the following error from Xcode:

```
error: Automatic Reference Counting Issue: Receiver type 'UIViewController'
for instance message does not declare a method
with selector 'nonExistantMethod'
```

This is what the compiler is telling you: the code that you've written cannot be compiled and translated to proper instructions to the CPU. In this particular case, this is because the compiler doesn't understand what *nonExistantMethod* actually is. This illustrates a good compiler that warns of and sometimes stops you from making mistakes that make your apps unstable.

See Also

XXX

1.4 Running iOS Apps on the Simulator

Problem

You've prepared an iOS project in Xcode and would like to run it in iOS Simulator to make sure it works.

Solution

You need to use the Scheme breadcrumb button on top-left corner of Xcode to first select the project that you wish to run on the iOS Simulator and then select the simulator that you wish to run your app on (iPhone/iPad).

Discussion

Follow these steps:

1. Find the Scheme breadcrumb button on top-left corner of Xcode's window. This button looks like that shown in [Figure 1-11](#).




Figure 1-11. The Scheme breadcrumb button in Xcode

2. In Xcode, you can have multiple projects on the same workspace. For example, at the time of writing this recipe, I have one project per recipe, added to one big project that I've created for this book. The left side of the Scheme button shows you the project that's currently selected. So if I click on the left side of the Scheme button, I'll see something similar to [Figure 1-12](#). So go ahead and click on the left side of the Scheme button and select the project that you wish to run on the iOS Simulator.




Figure 1-12. The currently-selected project

3. The right side of the Scheme button lets you choose which device/simulator you wish to run your app on. I've selected iPhone Simulator. Go ahead and press the right side of the Scheme button to select which simulator you would like to run your app on.



Bear in mind that the options presented to you on the right side of the Scheme button depend entirely on how your project is set up. In the second stage of creating an iOS Project, Xcode asks you which device(s) you would like your app to run on (in the Device Family dropdown). You can see this box in [Figure 1-2](#). A Universal app is an app that runs on both iPad and iPhone. There are also options to select to make your app run only on iPhone or only on the iPad.




Figure 1-13. Selecting the iPhone Simulator

Now that you have selected which simulator you would like to run your app on, simply go to the Product menu in Xcode and select Run. Xcode will compile your app ([Recipe 1.3](#)) if it's not compiled yet and will then run it on your selected simulator.

See Also

XXX

1.5 Running iOS Apps on iOS Devices

Problem

You've created an iOS App and now you want to run it on a device.

Solution

Simply plug your device into your computer using the USB cable that comes with your device. Follow the steps in [Recipe 1.4](#) to make sure you have selected the right project in Xcode. Instead of choosing the simulator (as shown in [Recipe 1.4](#)) in the Scheme breadcrumb button, choose your device, go to Product, and press Run.

Discussion

Each version of Xcode supports a series of iOS versions. By *support* I mean that the latest version of Xcode, for instance, is not capable of compiling and running an iOS app on a second generation iPod Touch with iOS 3.0 installed on it. The reason is that the utilities built for each version of Xcode allow you to interact with a limited number of versions of iOS on devices.

The way to detect whether Xcode has detected your device is to plug in your device, wait a few seconds for the sync to happen, and see whether the name of your device appears in the right half of the Scheme breadcrumb button.

If you've waited for the device to sync and still the Scheme button is showing *iOS Device* in its list instead of the name of your device, you need to make sure that your device can be used for development purposes. Simply follow these instructions:

1. Select the Window menu.
2. Under the Window menu, select Organizer.
3. On top of Organizer, make sure the Devices item is selected, as shown in [Figure 1-14](#).




Figure 1-14. Selecting the Devices button in Organizer

4. On the left side of Organizer's Devices screen, make sure you've selected your device by clicking on it (Figure 1-15).




Figure 1-15. A device that is not ready for development

5. As you can see, the device has a gray light instead of green. The gray light tells us that this device is not ready for development. After clicking on the device in the list, you will then see a button on the right side of the screen saying Use for De-

velopment. Press that button. Once you press this button, you will see a progress bar appear on the screen and Xcode will start detecting this device.

6. At this stage, Xcode might show a Login screen. This screen asks for your iOS Developer Portal's credentials. This means that Xcode wants to detect whether the UDID (Unique Device ID) of your device has already been added to your portal or not. If it has not been added, Xcode will add it for you. So just go ahead and provide your iOS Portal credentials to Xcode (see [Figure 1-16](#)) and then press the Login button.




Figure 1-16. Xcode waiting for iOS Portal credentials

7. If everything goes fine and Xcode detects that the iOS version on your device is something that it can support, it will display the green light next to your device on the left hand side of Organizer's Devices screen, as shown in [Figure 1-17](#).




Figure 1-17. An iOS device ready for development

8. Now close Organizer and come back to Xcode. If you now click on the right side of the Scheme breadcrumb button, you will be able to see your device listed there, as shown in [Figure 1-18](#).




Figure 1-18. An iOS device showing up in the Scheme breadcrumb button in Xcode

If Xcode cannot detect the version of iOS installed on your device, it will display an amber light next to it. In this case, you either need to get a version of Xcode that does support your device's iOS version, or you need to change the version of iOS on your device to match what Xcode supports. Xcode will display the list of iOS versions that it supports after displaying the amber light next to your device. Xcode, in fact, will give you the reason why it cannot run iOS apps on your device. If the reason stems from the version of iOS on your device, the supported versions of iOS will certainly be displayed in Organizer's Devices section.

See Also

XXX

1.6 Packaging iOS Apps For Distribution

Problem

You want to send your iOS app to others so that they can test your app or have a look at it, *before* you submit your app to the App Store.

Solution

You need to archive your application.

Discussion

In order to archive an application, you need to follow certain steps:

1. Make sure that you have fully tested the app on the simulator and you are happy that your app is stable.
2. Gather the UDIDs (Unique Device Identifiers) of all those devices on which you want to run your app. You can ask your friends and colleagues for these if the devices belong to them.
3. Add these UDIDs to your iOS Portal.
4. Create an Ad Hoc Distribution provision profile. Provision profiles are a mix of binary and XML content that allow an application to be executed on devices that have been linked to that provision profile.
5. After you have your provision profiles (a file that end with *.mobileprovision* extension), tell Xcode to use that provision profile for release purposes, as we will soon see.
6. Within Xcode, select the Product menu and then choose Archive. Xcode will now archive your application and, when that is done, display Organizer to you. Here you can export your archived application as a file (with the *.ipa* extension) that your testers/colleagues/friends can drag and drop into their iTunes or iPhone Configuration Utility to install your app on their iOS devices.

To distribute your iOS app to testers/colleagues and friends, you have to create an Ad Hoc provision profile. Follow these steps to create your Ad Hoc provision profile:

1. Log into the [iOS Dev Center](#).
2. Select iOS Provision Portal from the right side of the screen.
3. If you have not created a Distribution certificate yet, follow these steps:
 - a. On the left hand side of iOS Provision Profile, select Certificates.
 - b. On the right hand side, select the Distribution tab on the top of the screen.
 - c. Follow the instructions on the screen, which will ask you to use Keychain Access to create a new certificate on your computer and then upload that certificate to the portal. After this you will have your Distribution certificate.
 - d. Click on the Download button to the right side of your Distribution certificate to download it. After you've downloaded it on your computer, double click on it to install it in your Keychain Access.
4. Now move to the Devices item on the left hand side of the screen.
5. Select the Add Devices button on the right side of the screen.
6. Enter the device name and the device UDID in the boxes provided. If entering more than one device, press the + button after every device to make room for a new device. You can add a maximum of 100 devices to each provision portal (except for Enterprise portals, which we won't cover in this book, as they are given only to big organizations).



After a device is added to your iOS portal, it cannot be removed for the period that you hold this portal (which is usually a year). After your portal has expired or when it has been renewed, you will get a chance to delete any unwanted devices, so make sure you are not adding devices to your portal just for fun!

5. Once you are done adding the devices, press the Submit button.
6. Select Provisioning on the left side of the screen.
7. Select the Distribution tab on the right hand side of the screen.
8. Select the New Profile button on the right side of the screen.
9. In the Create iOS Distribution Provisioning Profile screen, make sure the Distribution Method is Ad Hoc.
10. Under Profile Name, give a descriptive name to your provision profile. For instance, something like Wildcard Ad Hoc Profile. Be creative and descriptive.
11. In the App ID dropdown, pick Xcode: Wildcard AppID. This will allow you to provision your apps regardless of their App Identifiers so that you can use the same Ad Hoc provision profile for all your iOS apps.
12. In the Devices section, select all the devices on which you want this provision profile to work. Devices that are not selected in this list will *not* be able to run your apps.
13. After you are done selecting the devices, press the Submit button.

Create iOS Distribution Provisioning Profile

Generate provisioning profiles here. All fields are required unless otherwise noted. To learn more, visit the [How To](#) section.

Distribution Method

☐ App Store ☒ Ad Hoc

Profile Name

Wildcard Ad Hoc Profile

Distribution Certificate

Pixolity Ltd. (expiring on Dec 6, 2011)

App ID

Xcode: Wildcard AppID

Devices (optional)

Select up to 100 devices for distributing the final application; the final application will run only on these selected devices.

Deselect All

☐ Agusia iPhone ☒ Vandad NP's iPad

☒ Vandad's iPhone4

Figure 1-19. Creating a new Ad Hoc provision profile

14. Now head back to the Distribution tab of the Provisioning section and press the Download button for the provision profile that you just created. If the status of this profile is Pending, refresh your page in your browser until the provision profile is created.
15. Now that you have this provision profile downloaded on your computer, drag and drop it into iTunes. iTunes will then install this profile for you.

All done; we are now ready to create an archived app. Follow these steps:

1. Select your profile file in Xcode (this is the file with the blue icon).
2. Now you will see the targets your app supports. Select the desired target.
3. Select Build Settings on the right side of the screen (Figure 1-20).




Figure 1-20. Xcode Displaying the Build Settings of an iOS App

4. In the Build Settings tab, scroll down until you get to the Code Signing category, as shown in Figure 1-20.
5. Under Code Signing Identity→Release and Code Signing Identity→Release→Any iOS SDK, make sure you pick the provision profile that you created earlier in this recipe.
6. On the Scheme breadcrumb (Figure 1-11), make sure you've chosen iOS Device/Your Device Name instead of iOS Simulator (iPad or iPhone). Under the simulator, you cannot create an app for distribution.
7. Head over to the Product menu and choose Archive.

After the archiving process is finished, Xcode will open Organizer for you and will display the Archives tab, as depicted in Figure 1-21.




Figure 1-21. An archived application in Organizer

8. Select the Share button on the top right side of the screen. You will be presented with a dialog similar to that shown in [Figure 1-22](#).




Figure 1-22. Selecting the type of archive we want to create

9. Keep the Contents selection as iOS App Store Package (.ipa file), as shown in [Figure 1-22](#).
10. In the Identity dropdown, again, choose the provision profile with which you want to sign your app. We created this provision profile before, remember? Choose the same profile again. Once you are done, press Next.
11. You will now be asked to specify the location where you would like to save this file. Select your desired location and filename, then press Save.

All done. Now you have a file with an .ipa extension. When sending this file to your friends/colleagues/etc., make sure you send the provision profile (which you created in the iOS Dev Portal) as well. They will need both of these files (the .ipa and the .mobileprovision files) in order to install your archived apps on their devices.

A user can use either iTunes or iPhone Configuration Utility (both are free) in order to install your apps on their devices. I personally recommend iPhone Configuration Utility (or iCU) since it is certainly more robust when it comes to installing Ad Hoc apps on devices. iTunes has some issues when installing archived apps on devices, which I am not going to bore you with. The more you work with these two pieces of software, the more you get to know about their advantages and disadvantages.

See Also

XXX

1.7 Declaring Variables in Objective-C

Problem

You want to use variables with clear names in your iOS apps.

Solution

Apple conventions dictate certain rules for variable names. Determine the type of the variable (for instance, integer, array, string, etc.) and then a descriptive name for it. In an empty line of code, place the type of your variable first, following by its name. Variable names are advised to follow these rules:

1. Follow the camelCase naming convention. If the variable name is one word, all letters must be lower-case. If the variable name is more than one word, the first word must be entirely lower-case and the subsequent words must have their first letter upper-case and the rest of their letters lower-case. For instance, if you want to have a counter variable, you can simply name it `counter`. If you want to call your variable "first counter", declare it `firstCounter`. The variable name "my very long variable name" would become `myVeryLongVariableName`. (Names of that length are quite common in iOS programs.)
2. Variables should ideally have no underline in their names. For instance, `my_variable_name` can and perhaps should be changed to `myVariableName`.
3. Variable names should contain only letters and numbers (no punctuations such as comma and dash). This is a restriction in the Objective-C language.

Let's have a look at a few examples. There are a few primitive data types in Objective-C. A data type is a name that specifies the type of a variable. For instance, you can say that you have an integer variable of type `NSInteger` or an integer variable of type `NSUInteger`, where the former is a signed variable and the latter is unsigned (note the "U" after "NS") in the latter example). So we can then define these variables in our source code like so:



Signed integers *can* contain negative numbers whereas unsigned integers *cannot*.

```
NSInteger signedInteger = -123; /* Can take negative numbers */
NSUInteger unsignedInteger = 123; /* Cannot take negative numbers */
```

There are certain rules, as mentioned before, about naming your variables (for instance, the camelCase rule). However, other aspects of your variable naming convention depend entirely on your choice. In general, I advise that you always assume you are working for a big organization (whether it is your own company or somebody else's company) and follow these rules:

1. Give descriptive names to your variables. Avoid names such as "i" or "x." These names will never make any sense to anybody else but yourself and chances are that they won't make sense to you either if you leave the project for some time and come back to it after a few months. The compiler doesn't really care if the variable name is 50 letters long. If that makes your variable name more descriptive and you cannot do without it, then go for it.
2. Avoid creating vague variable names. For instance, if you have a string variable and you want to place the full name of a person in that variable, avoid giving it names such as "theString" or "theGuy" or "theGirl." These make no sense at all. It is best to give a name such as "fullName" or "firstAndLastName" rather than something that confuses everybody who looks at your source code, including yourself!
3. Avoid giving names to your variables that are likely to lead to mistyping. For instance, it is much better to call your variable "fullName" rather than "__full_____name." It is much better to avoid underlines in variables all together.

Discussion

Variables are placeholders for data that you want to hold in memory. For instance, if you want to delete 100 files from the disk and those files are named *1.png*, *2.png*, on to *100.png*, it would be best to create a counter variable that starts from 1 and goes all the way to 100 and then use the content of that variable (the number) to delete the files. Programmers use variables to do arithmetic or simple operations such as prefixing the last name of a person with their first name to create the resulting full name.

Every variable has to have a type. The type of a variable tells the compiler and the machine that runs that program, what type of variable that is and what sort of value it holds. For example, a variable that is an integer can hold the value 123 but cannot hold a value with decimal places such as 123.456. For the latter, we will need a floating point variable. Integer and floating point here are the data types and in Objective-C are defined with `NSInteger` and `float`. Here are some of the commonly used data types in Objective-C:

`NSInteger`

Variables of this type can store signed (positive or negative) integer values.

`NSUInteger`

Variables of this type can store unsigned (only positive or zero) integer values.

float

Variables of this type can store floating point values (values that have decimals in them, such as 1.23 or 73.12).

NSString

Variables of this type can store strings, such as "my string" or "Mrs Thomson."

NSArray

Variables of this type can store an array of objects. For instance, if you have read 10 files from the disk, you can store their data in an array. An array can contain more than 1 instance of the same value.

NSSet

Variables of this type can store unique instances of variables. Sets are similar to arrays in that they can store multiple value but each value can only appear at most once in a set.

See Also

XXX

1.8 Comparing Values in Objective-C with an If Statement

Problem

You want to compare two values in Objective-C.

Solution

Use if statements. Please refer to the Discussion section of this recipe for more information about different scenarios under which you might want to use if statements.

Discussion

We use if statement in our everyday conversations. For instance, you might say "If I get a hold of him, I'll tell him..." or "I would put the computer to sleep if it didn't take so long to come back up". All these statements have a *condition*. If statements in Objective-C also have a condition. You can even make them more sophisticated, having your app do something if a condition is met and something else if the condition is *not* met. The basic form of a if statement is:

```
if (<replaceable>condition</replaceable>){  
    /* Your code to get executed if the <replaceable>condition</replaceable> is met */  
}
```



As long as the condition is a value other than zero/nil/NULL, the code inside the if statement will run.

An if statement that has an "otherwise" clause in it is known as if-else-statement, and its format is:

```
if (<replaceable>condition</replaceable>){
    /* Your code to get executed if the <replaceable>condition</replaceable> is met */
} else {
    /* Code to get executed if <replaceable>condition</replaceable> is not met */
}
```

The else clause of the if-else-statement can also contain its own if statement! That might sound strange, but consider this scenario. In real life, you can say something similar to this: "I will go get a cup of coffee, if the place is open, I will get a tall latte, if it's closed and the other place is open, I will get a cappuccino, otherwise, I will just come back home and make tea for myself". The part where we said "...if it's closed and the other place is open..." is an else statement with an if statement embedded in it. Here is how you would implement that in Objective-C:

```
if (Coffee place A is open){
    Get a Tall Latte from coffee place A
} else if (Coffee place B is open){
    Get a Cappuccino from coffee place B
} else {
    Come back home and make tea
}
```

The condition for an if statement, regardless of whether it is a standalone if statement (like the first condition in the last example) or embedded inside an else-statement, must resolve to a boolean value. A boolean value is either YES or NO. For instance, the following code will *always* get executed, regardless of which condition/device you run it on:

```
if (YES){
    /* This code will get executed whenever the app gets to it */
} else {
    /* The app will NEVER get here */
}
```

The reason behind this is that the condition for the if statement in this example is always met as long as the YES is the condition. To make things more exciting, you can do comparisons in the condition supplied to an if statement, like so:

```
NSInteger integer1 = 123;
NSInteger integer2 = 456;

if (integer1 == integer2){
    NSLog(@"Integers are equal.");
} else {
    NSLog(@"Integers are not equal.");
}
```



We use the double-equal sign in a conditional because the result of a double-equal is a boolean value, whereas the single-equal sign might confuse the compiler and usually returns the value/object on the left side of the equal sign. It is best to avoid using single-equal signs in a conditional like an if statement. Instead, compare your values using double-equal signs.

If you are comparing objects, it is best to use the `isEqual:` instance method of the `NSObject` class:

```
NSObject *object1 = [[NSObject alloc] init];
NSObject *object2 = object1;

if ([object1 isEqual:object2]){
    NSLog(@"Both objects are equal.");
} else {
    NSLog(@"Objects are not equal.");
}
```



For now you don't have to worry about what objects are. This will be explained in detail in other recipes in this chapter.

Some objects, such as strings, however have their own comparison methods, changing the way we compare two strings. For instance, you can have two string objects that contain the same characters. If you compare them using their `isEqual:` instance method, you will get the result NO, because they are different objects. However, they might still contain the exact same characters. Because of this, different classes expose their own comparison methods in Objective-C. For more information about classes, please refer to [Recipe 1.11](#). To learn more about objects, refer to [Recipe 1.14](#).

An if statement and its else statement can be written with or without curly braces. Using the former syntax (with curly brackets), you can execute multiple lines of code after the condition is satisfied. However, without curly brackets, you can write only one line of code for each condition. Here is an example of the latter syntax without curly braces:

```
NSString *shortString = @"Hello!";

if ([shortString length] == 0)
    NSLog(@"This is an empty string");
else
    NSLog(@"This is not an empty string.");
```



Be extra careful with logging and if statements without curly-brackets. Often, when a product goes to production, a production manager might attempt to comment out all your `NSLog` methods simply by replacing all occurrences of `NSLog` with `//NSLog`. If you have if statements without curly brackets, as in our last example, the production manager's commented-out code will look like this:

```
NSString *shortString = @"Hello!";

if ([shortString length] == 0)
    //NSLog(@"This is an empty string");
else
    //NSLog(@"This is not an empty string.");
```

This will break the code and people in the company will *not* be happy. It doesn't matter whether they are not happy at you or not happy at the production manager. That would be a team effort gone wrong, so you will all be to blame. To avoid this, make sure that you always write your if statements *with* curly braces.

See Also

XXX

1.9 Implementing Loops with For Statements

Problem

You want to implement a code that repeats a certain number of times, perhaps applying the same procedure to every element in an array or some other changing values.

Solution

Use the for statement. The format of this statement is:

```
for (<replaceable>code to execute before loop</replaceable>;
    <replaceable>condition to be met for the loop to terminate</replaceable>;
    <replaceable>code to execute in every iteration of the loop</replaceable>){

}
```



All three clauses of the for loop are optional. In other words, you can have a for loop that looks like this:

```
for (;;) { YOUR CODE HERE }
```

This is known as an infinite-loop or a loop that has no condition to terminate and will run forever. This is a very bad programming practice indeed and you should avoid using it by all means.

Discussion

Loops are useful in programming because you will often need to start a loop from one place to another, from one index to another, or from start to stop. For instance, you might want to loop through all characters inside a string and count how many "A" characters you can find in it. Another example is a loop that finds all files in a directory. This is a loop that finds the number of files and then starts from the first one until it gets to the last one.

Usually, programmers require a counter in their loops. For instance, you might want to read all the characters inside a C-String. For this, you will need the index of each character. If your string is 10 characters long, you will need to go from index 0 to 9. If your string is 20 characters long, you have to read from index 0 to 19. Since the length of your string is a variable, you can put it as the exit-conditional of your loop. Here is an example:

```
char *myString = "This is my string";

NSUInteger counter = 0;
for (counter = 0; /* Start from index 0 */
     counter < strlen(myString); /* Exit loop when we reach last character */
     counter++){ /* Increment the index in every iteration */

    char character = myString[counter];

    NSLog(@"%c", character);
}
```

The code that gets executed before the loop (as noted in the Solution section of this recipe) is obviously optional. In fact, all three main parts of a for loop are optional, but it is recommended that you think about how you intend to use your loops and use the three main parts of the for statement accordingly.

Let's have a look at where you would want to skip the first statement of your for loop. As you could see in the previous section, our `counter` variable was set to 0 before we even started our loop. However, we are setting it to 0 again once our loop is about to start. This is unnecessary in this example, but there is nothing wrong with that approach. If you feel you don't need the redundant code, simply remove it:

```
char *myString = "This is my string";

NSUInteger counter = 0;
for (; /* empty section */
     counter < strlen(myString); /* Exit loop when we reach last character */
     counter++){ /* Increment the index in every iteration */

    char character = myString[counter];

    NSLog(@"%c", character);
}
```

The second clause of any for loop is very important because this is the conditional that allows your loop to exit. Having no condition in the second clause is similar to having a never-ending loop, or an infinite loop as it is known. Therefore, it is best to think about the condition that allows your program to end the loop and continue on its path of execution.

Any variable defined in the first clause of a for loop is accessible inside the loop but not outside it. For instance:

```
for (NSUInteger counter = 0;
     counter < 10;
     counter++){
    NSLog(@"%lu", (unsigned long)counter);
}
/* "counter" is NOT accessible here. This line will throw compile time error */
NSLog(@"%lu", (unsigned long)counter);
```

The third clause inside a for loop is very interesting indeed. This is the statement that gets executed *after* every iteration of your loop. This includes the last iteration. For instance:

```
NSUInteger counter = 0;
for (counter = 0;
     counter < 4;
     counter++){
    NSLog(@"%lu", (unsigned long)counter);
}
NSLog(@"%lu", (unsigned long)counter);
```

This will print the following values to the console:

```
0
1
2
3
4
```

So our counter *did* get to number 4 although in our loop we asked that the counter should be less than 4. This proves the point that when our loop finishes, in the last iteration, the third clause of our for loop gets executed. But the code inside our loop won't be called since the end-condition (second clause) will not be met and our loop will finish.

See Also

XXX

1.10 Implementing While Loops

Problem

You want to let a piece of code run over and over again until a certain condition is met.

Solution

Use while loops and specify your exit condition. Here is the format for the while loop:

```
while (<replaceable>condition</replaceable>){  
    CODE  
}
```



As long as the condition is a value other than zero/nil/NULL, the while loop will run.

Discussion

The while loop is the "arrogant" brother of the for loop (see [Recipe 1.9](#)) because while loops only take a condition that should be met for the loop to run. If the condition is positive, the loop will always run until the condition becomes negative. For instance, a while loop could be implemented to make an icon in the Dock in Mac OS X jump up and down until the user taps on that icon (this is actually a very bad user experience; icons in the Dock shouldn't jump up and down continuously, but for a short interval, or even a fixed number of times, usually 3). The exit condition for the while loop is the user's tapping on that icon. As long as the user hasn't tapped on the icon, the icon will jump up and down.

A while loop is awkward to use with a counter because of its syntax. If you require a counter to control your loop, it is better to use a for loop. If you do require a while loop but still want to have access to a counter, you will need to manage the counter manually, like so:

```
NSUInteger counter = 0;  
while (counter < 10){  
    NSLog(@"Counter = %lu", (unsigned long)counter);  
    counter++;  
}
```

Just as you can have positive conditions for your while loops, you can have negative conditions as well:

```
BOOL shouldExitLoop = NO;  
NSUInteger counter = 0;  
  
while (shouldExitLoop == NO){  
    counter++;  
}
```

```

        if (counter >= 10){
            shouldExitLoop = YES;
        }
    }

    NSLog(@"Counter = %lu", (unsigned long)counter);

```

The output of this program is:

```
Counter = 10
```

So what we are doing is simply running a loop for as long as our counter is less than 10. If the value of the counter (adjusted inside the loop itself) goes over or becomes equal to 10, then we exit our loop. Just like a for loop, you can create an infinite loop using a while loop, although this is a terrible programming practice and you should avoid it by all means:

```

while (YES){
    /* Infinite loop */
}

```

You must make sure that you have an exit strategy in your while and for loops. For this, you need to keep an eye on the condition for your loops and make sure that the condition will be met at some point, without making your loops hogging all the memory and/or system resources while they run.

Here is another usage of a while loop:

```

char *myString = "Some Random String";
NSUInteger counter = 0;
char character;
while ((character = myString[counter++]) != 'R' &&
        counter < strlen(myString)){
    /* Empty */
}
NSLog(@"Found the letter R at character #%lu", (unsigned long)counter+1);

```

Here we are searching inside a string to find the first occurrence of the letter 'R'. As soon as we find it, we exit our while loop. We have been careful to include another condition: if we reach the end of the string (`strlen(myString)`), we end the loop, so that we don't wander off into undefined memory and cause a crash or a security flaw. (Doing so is called a *buffer overflow*.)

This algorithm has a bug, however: it returns a wrong results when the letter 'R' isn't in the string at all. Because the while loop finishes when we get to the end of the string, we always print a message to the console saying that the letter 'R' was found at some index. I will leave it up to you to fix this algorithm. As a hint, you might want to use a Boolean value when you do find the letter 'R' and then later use that flag to determine whether the letter was found. To use that boolean technique, you might need to change the way the while loop is set up, but I think you get the idea.

A while loop is useful for traversing an array. For instance, a C String is an array of characters ending with a zero byte. If you are searching for a specific character in this

array, you can simply write a while loop that starts from the first character and runs until it finds the zero terminator that ends the string. Here is an example:

```
char *cString = "My String";
char *stringPointer = cString;
while (*stringPointer != 0x00){
    NSLog(@"%c", *stringPointer);
    stringPointer++;
}
```

This example will print all the characters inside the string until it gets to the zero terminator of the string. Using a while loop, you can even create a function similar to the `strlen()` function that is able to find the length of a C String, like so:

```
NSUInteger lengthOfCString(const char *paramString){

    NSUInteger result = 0;

    if (paramString == NULL){
        return 0;
    }

    char *stringPointer = (char *)paramString;

    while (*stringPointer != 0x00){
        result++;
        stringPointer++;
    }

    return result;
}
```

See Also

XXX

1.11 Creating Custom Classes

Problem

You want to pack a set of related functionalities into a reusable entity, for immediate or later use.

Solution

Create your own classes.

Discussion

A class is a virtual entity. A class contains methods and other language specific structures. Let's say you want to write a calculator program. You are creating the user interface and you want each button on the calculator to have a black background, white text and have a *bump* user interface, just like a real button. Aren't these all common traits between all the buttons you want to place on your UI? You got it! It's best that we create a class to represent all our buttons and write the code once and reuse multiple times.

Classes in objective-C are normally represented with the following code:

Header file

This is where you define what your class basically does: accept user input, rotate a shape, or whatever. But the header file does *not* implement any of that functionality. Header files have a *.h* extension.

Implementation file

After defining the functionality of your class in the header file, here you write the actual code for all that functionality. Implementation files have a *.m* extension.

Let's go a bit more into detail by going ahead and creating a class. Follow these steps:

1. In Xcode, go to the File menu and then select New File.
2. A dialog will appear, similar to that shown in [Figure 1-23](#). Here simply select *Objective-C class* from the list to the right. Make sure *iOS* is selected on the left hand side. After this, press the Next button.




Figure 1-23. The Add File dialog in Xcode

3. In the next screen, make sure the *Subclass of* text box says `NSObject`. Now press the Next button (Figure 1-24)




Figure 1-24. Setting the base class of our new class

4. In the next screen, as shown in [Figure 1-25](#), make sure that the Save As text box says *Person*, which is what we'll name our class. On the bottom of this dialog, make sure that you are saving your class in the correct group/folder.




Figure 1-25. Creating a class called *Person* in Xcode

Now two files will get added to your project. One is called *Person.h* and the other *Person.m*. The first one is the header and the second one is the implementation. Let's have a look at the contents of the *Person.h* file:

```
#import <Foundation/Foundation.h>

@interface Person : NSObject

@end
```

How about the contents of *Person.m*?

```
#import "Person.h"

@implementation Person

- (id)init
{
    self = [super init];
    if (self) {
        // Initialization code here.
    }

    return self;
}

@end
```

We can see that Xcode has pre-populated these files with some content. We still don't really know what this content is, but it's a start to our code. Now we have a class named `Person`. Where did we get this name? It's *not* the name of the file itself, but Xcode took the file name in [Figure 1-25](#) and used it as the class name. If you have a look at the contents of the *Person.h* again, you will notice this line of code:

```
@interface Person : NSObject
```

In short, what comes after the `@interface` keyword is your class name in this case. If you don't like this name, simply right click on it and then select Refactor and then Rename. This will guide you through a refactoring process through which you can rename your class.

See Also

XXX

1.12 Defining Functionality for Classes

Problem

You want to define some functionality for your classes and allow them to be reused later.

Solution

Create instance or class methods for your classes in order to create reusable blocks of code, or simply call a method in your program.

Discussion

Nearly every programming languages creates *procedures* and *functions* to encapsulate specific functionality, especially functionality that the programmer uses over and over. Some languages consider "procedure" and "function" just terms for the same thing, while others make a distinction between them. A procedure is a block of code with a name and an optional set of parameters. It does not have a return value. In Objective-C, a procedure returns `void` to indicate it does not return a value. A function is similar but does have a return value. Here is a simple procedure (with an empty body) written in C:

```
void sendEmailTo(const char *paramTo,
                 const char *paramSubject,
                 const char *paramEmailMessage){

    /* send the email here ... */
}
```

This procedure is named `sendEmailTo` and has three parameters: `paramTo`, `paramSubject`, and `paramEmailMessage`. We can then call this procedure as follows:


```

sendEmailTo("somebody@somewhere.com",
            "My Subject",
            "Please read my email");

```

Turning this procedure into a function that returns a Boolean value, we will have code similar to this:

```

BOOL sendEmailTo(const char *paramTo,
                 const char *paramSubject,
                 const char *paramEmailMessage){

    /* send the email here ... */

    if (paramTo == nil ||
        paramSubject == nil ||
        paramEmailMessage == nil){
        /* One or some of the parameters are nil */
        NSLog(@"Nil parameter(s) is/are provided.");
        return NO;
    }

    return YES;
}

```

Calling this function is similar to calling the `sendEmailTo` procedure except that with a function, we can retrieve the return value, like so:

```

BOOL isSuccessful = sendEmailTo("somebody@somewhere.com",
                                "My Subject",
                                "Please read my email");

if (isSuccessful){
    /* Successfully sent the email */
} else {
    /* Failed to send the email. Perhaps we should display
    an error message to the user */
}

```

In Objective-C, each method is created for a class. Creating Objective-C methods is quite different from writing procedures and functions in a programming language such as C. Methods fall into two categories: *instance* or *class*. Instance methods are methods that can be called on an instance of the class (that is, on each object you create based on the class), whereas class methods get called on the class itself and do not require an instance of the class to be created by the programmer. To create a method in Objective-C, follow these steps in the *.m* file of your target class:

1. Type - if you want an instance method or + if you want a class method.
2. Choose the return type of your method and enclose it within parentheses—for instance, (void) for no return value, (BOOL) for a Boolean value, (NSObject *) to return an instance of NSObject, and so on.

3. Choose a name for your method. Start the name with a lowercase letter. It is common in Objective-C to start method names with a lowercase letter—for instance, `sendEmailTo` instead of `SendEmailTo`.
4. If you do not want any parameters for your method, jump to step 9.
5. Choose two names for your parameter. One name becomes a part of the method name and will be used from outside the method (this is optional for all parameters except the first). The other name will be used as a parameter name inside the method. There is an exception to this in which the first name of the first parameter of a method is part of the name of the method that you chose in step 3. For this first parameter, you must only choose a second name, which becomes the parameter name used inside the method itself.
6. Once you are done choosing the name for your parameter, choose the data type of the method and enclose it within parentheses.
7. Put a colon after your parameter's first chosen name (if any), and put the parentheses that carry the data type of your method followed by the second name for your parameter.
8. Repeat steps 5 through 7 for any other parameters that you might have.
9. Insert an open curly brace (`{`) after the method name and parameter names (if you have parameters) and a closing curly brace (`}`) at the end.

Going back to the `sendEmailTo` procedure example that we saw earlier, let's attempt to create the same procedure as a method in Objective-C:

```
- (BOOL) sendEmailTo:(NSString *)paramTo
    withSubject:(NSString *)paramSubject
    andEmailMessage:(NSString *)paramEmailMessage{

    /* Send the email and return an appropriate value */

    if ([paramTo length] == 0 ||
        [paramSubject length] == 0 ||
        [paramEmailMessage length] == 0){
        /* One or some of the parameters are empty */
        NSLog(@"Empty parameter(s) is/are provided.");
        return NO;
    }

    return YES;
}
```

This is an instance method (`-`) that returns a Boolean value (`BOOL`). The name of this method is `sendEmailTo:withSubject:andEmailMessage:` and it has three parameters. We can then call this method in this way:

```
[self sendEmailTo:@"someone@somewhere.com"
    withSubject:@"My Subject"
    andEmailMessage:@"Please read my email."];
```


As mentioned previously, the first name of every parameter (except the first) is optional. In other words, we can construct the `sendEmailTo:withSubject:andEmailMessage:` method in another way with a different name:

```
- (BOOL) sendEmailTo:(NSString *)paramTo
           :(NSString *)paramSubject
           :(NSString *)paramEmailMessage{

    /* Send the email and return an appropriate value */

    if (paramTo length] == 0 ||
        [paramSubject length] == 0 ||
        [paramEmailMessage length] == 0){
        NSLog(@"Empty parameter(s) is/are provided.");
        return NO;
    }

    return YES;
}
```



I heavily discourage you from writing methods that have no external names for their parameters. This is indeed a very bad programming practice and will confuse you and those who you work with in the same team, regardless of how well you might have documented your code.

We can call this method like so:

```
[self sendEmailTo:@"someone@somewhere.com"
                 :@"My Subject"
                 :@"Please read my email."];
```

As you can see, the first implementation is easier to understand when you look at the invocation, since you can see the name of each parameter in the call itself.

Declaring and implementing a class method is similar to declaring and implementing an instance method. Here are a couple of things you have to keep in mind when declaring and implementing a class method:

- The method type identifier of a class method is `+` instead of the `-` type identifier for instance methods.
- You can access `self` in a class method. However, the class methods of `self` can be accessed only inside a class method's implementation.
- Class methods are useful when you want to provide new methods of instantiation for your classes. For example, a class method named `allocAndInit` could both allocate and initialize an object and return the object to its caller.

1.13 Defining Two or More Methods with the Same Name

Problem

You would like to implement two or more methods with the same name in one object. In object-oriented programming, this is called *method overloading*. However, in Objective-C, method overloading does not exist in the same way as it does in other programming languages such as C++.



The techniques used and explained in this recipe's [Solution](#) and [Discussion](#) are merely ways to create methods that have different numbers of parameters or have parameters with different names, just to give you an idea of how you can have methods whose first name segments are the same.

Solution

Use the same name for your method, but keep the *number* and/or the *names* of your parameters different in every method:

```
- (void) drawRectangle{
    [self drawRectangleInRect:CGRectMake(0.0f, 0.0f, 4.0f, 4.0f)];
}

- (void) drawRectangleInRect:(CGRect)paramInRect{
    [self drawRectangleInRect:paramInRect
        withColor:[UIColor blueColor]];
}

- (void) drawRectangleInRect:(CGRect)paramInRect
    withColor:(UIColor*)paramColor{
    [self drawRectangleInRect:paramInRect
        withColor:paramColor
        andFilled:YES];
}

- (void) drawRectangleInRect:(CGRect)paramInRect
    withColor:(UIColor*)paramColor
    andFilled:(BOOL)paramFilled{
    /* Draw the rectangle here */
}
```

This example shows a typical pattern in overloading. Each rectangle can be drawn either filled (solid color) or empty (showing just its boundaries). The first procedure is a "convenience procedure" that allows the caller to avoid specifying how to fill the rectangle. In our implementation of the first procedure, we merely call the second procedure, making the choice for the caller (`andFilled:YES`). The second procedure gives the caller control over filling.

Discussion

Method overloading is a programming language feature supported by Objective-C, C++, Java, and a few other languages. Using this feature, programmers can create different methods with the same name, in the same object. However, method overloading in Objective-C differs from that which can be used in C++. For instance, in C++, to overload a method, the programmer needs to assign a different number of parameters to the same method and/or change a parameter's data type.

In Objective-C, however, you simply change the name of at least one parameter. Changing the type of parameters will not work:

```
- (void) method1:(NSInteger)param1{
    /* We have one parameter only */
}

- (void) method1:(NSString *)param1{
    /* This will not compile as we already have a
       method called [method1] with one parameter */
}
```

Changing the return value of these methods will not work either:

```
- (int) method1:(NSInteger)param1{
    /* We have one parameter only */
    return param1;
}

- (NSString *) method1:(NSString *)param1{
    /* This will not compile as we already have a
       method called [method1] with one parameter */
    return param1;
}
```

As a result, you need to change the *number of parameters* or the *name* of (at least) one parameter that each method accepts. Here is an example where we have changed the number of parameters:

```

- (NSInteger) method1:(NSInteger)param1{
    return param1;
}

- (NSString*) method1:(NSString *)param1
    andParam2:(NSString *)param2{

    NSString *result = param1;

    if ([param1 length] > 0 &&
        [param2 length] > 0){
        result = [result stringByAppendingString:param2];
    }

    return result;
}

```

Here is an example of changing the name of a parameter:

```

- (void) drawCircleWithCenter:(CGPoint)paramCenter
    radius:(CGFloat)paramRadius{

    /* Draw the circle here */

}

- (void) drawCircleWithCenter:(CGPoint)paramCenter
    Radius:(CGFloat)paramRadius{

    /* Draw the circle here */

}

```

Can you spot the difference between the declarations of these two methods? The first method's second parameter is called **radius** (with a lowercase *r*) whereas the second method's second parameter is called **Radius** (with an uppercase *R*). This will set these two methods apart and allows your program to get compiled. However, Apple has guidelines for choosing method names as well as what to do and what not to do when constructing methods. For more information, please refer to the “Coding Guidelines for Cocoa” Apple documentation available at this URL:

<http://developer.apple.com/iphone/library/documentation/Cocoa/Conceptual/CodingGuidelines/CodingGuidelines.html>

Here is a concise extract of the things to look out for when constructing and working with methods:

- Have your method names describe what the method does clearly, without using too much jargon and abbreviations. A list of acceptable abbreviations is in the Coding Guidelines.

- Have each parameter name describe the parameter and its purpose. On a method with exactly three parameters, you can use the word *and* to start the name of the last parameter if the method is programmed to perform two separate actions. In any other case, refrain from using *and* to start a parameter name.
- Start method names with a lowercase letter.
- For delegate methods, start the method name with the name of the class that invokes that delegate method.

See Also

[Recipe 1.12](#)

1.14 Allocating and Initializing Objects

Problem

You want to create an instance of a new object, but you don't understand the difference between *allocation* and *initialization* and why you should have to both allocate and initialize an object before you can use it.

Solution

You must both allocate and initialize an object before using it. An object can be *allocated* using the `alloc` instance method. This class method will allocate memory to hold the object and its instance variables and methods. However, allocation leaves memory undefined. So in addition, each object must be *initialized*, which sets the values of its data. One initialization method must be the *designated initializer*, which is normally the initialization method with the most parameters. For instance, the `initWithFrame:` method is the designated initializer of objects of type `UIView`. Always allocate and initialize your objects, in that order, before using them.

When implementing a new object, do not override the `alloc` method. This method is declared in `NSObject`. Instead, override the `init` method and create custom initialization methods that handle required parameters for the specific object you are working on.

Discussion

An object that inherits from `NSObject` must be prepared for use in two steps:

1. Allocation
2. Initialization

The allocation is done by invoking the `alloc` method, which is implemented in the `NSObject` class. This method creates the internal structure of a new object and sets all instance variables' values to zero. After this step is done, the `init` method takes care of

setting up the default values of variables and performing other tasks, such as instantiating other internal objects.

Let's look at an example. We are creating a class named `MyObject`. Here is the `.h` file:

```
#import <Foundation/Foundation.h>

@interface MyObject : NSObject

- (void) doSomething;

@end
```

The implementation of this class is as follows (the `.m` file):

```
#import "MyObject.h"

@implementation MyObject

- (void) doSomething{

    /* Perform a task here */
    NSLog(@"%s", __FUNCTION__);

}

@end
```

The `doSomething` instance method of the `MyObject` object will attempt to print the name of the current function to the console window. Now let's go ahead and invoke this method by instantiating an object of type `MyObject`:

```
MyObject *someObject = [[MyObject alloc] init];
/* Do something with the object, call some methods, etc. */
[someObject doSomething];
```

This code will work absolutely fine. Now try to skip initializing your object:

```
MyObject *someObject = [MyObject alloc];
/* Do something with the object, call some methods, etc. */
[someObject doSomething];
```

If you run this code now, you will realize that it works absolutely fine, too. So, what has happened here? We thought we had to initialize the object before we could use it. Perhaps Apple can explain this behavior better:

An object isn't ready to be used until it has been initialized. The `init` method defined in the `NSObject` class does no initialization; it simply returns self.

Simply put, this means the `init` method is a placeholder for tasks that some classes need to perform before they are used, such as setting up extra data structures or opening files. `NSObject` itself—along with many of the classes you will use—does not have to initialize anything in particular. However, it is a good programming practice to always run the `init` method of an object after allocating it in case the parent of your class has overridden this method to provide a custom initialization. Please bear in mind that the

return value for initializer methods of an object is of type `id`, so the initializer method might even return an object that is not the same object that the `alloc` method returned to you. This technique is called *two-stage creation* and is extremely handy. However, discussing this technique is outside the scope of this book. For more information about two-stage creation, please refer to *Cocoa Design Patterns* by Erik M. Buck and Donald A. Yacktman (Addison-Wesley Professional).

1.15 Adding Properties to Classes

Problem

You want to add properties to your classes so that you can take advantage of dot notation to access those values, as opposed to using methods on your classes.

Solution

Define properties in your classes using the `@property` keyword.

Discussion

Anything addressed via dot notation is a property. Properties are *shortcuts* to methods. What do I mean? Well, let's have a look at an example:

```
NSObject *myObject = [[NSObject alloc] init];
myObject.accessibilityHint = @"Some string";
```

You can see that we allocated and initialized an object of type `NSObject` and used dot notation to access a property called `accessibilityHint` in that object. Where did `accessibilityHint` come from?

It's quite simple. A property is defined using the `@property` keyword. In fact, if you hold down the Command key on your keyboard in Xcode, and simply click on the `accessibilityHint` property in the example that we just saw, you will be redirected to the `NSObject.h` file where you will see this:

```
@property(n nonatomic, copy) NSString *accessibilityHint;
```

But what *are* properties? Well, when we define a property, we tell the compiler that we will write a setter and a getter *method* for this property. If somebody tries to set a value in this property, the runtime will execute our setter method. If somebody tries to read from the property, the runtime will execute the getter method.

Let's see this in detail. In [Recipe 1.11](#) we saw how we create classes. We created a class called `Person`. In [Recipe 1.12](#) we learned how to add methods to our classes, so let's combine the two to learn more about properties. Let's go to the `Person.h` file and define a property called `firstName`:

```
#import <Foundation/Foundation.h>
```

```
@interface Person : NSObject

@property (nonatomic, strong) NSString *firstName;

@end
```

Now try to compile your program by pressing Command+Shift+R. Note that the LLVM Compiler will give you two warnings:

```
warning: property 'firstName' requires method 'firstName' to be defined - use @synthesize, @dynamic or provide method implementation
warning: property 'firstName' requires method 'setFirstName:' to be defined - use @synthesize, @dynamic or provide method implementation
```



You will learn all about new Automatic Reference Counting keywords such as **strong**, in [Recipe 1.16](#).

It's obvious that the property has been created, but the compiler doesn't know what to do in case somebody tries to read this property or assign a value to it. For this reason, we have to write a setter and a getter method. The compiler is clearly telling us that the setter method should be called `setFirstName:` and the getter method should be called `firstName`. Fortunately, we don't have to write these two methods for properties manually. We can use the `@synthesize` keyword in the `.m` file to let the compiler generate the setter and the getter methods for our properties automatically:

```
#import "Person.h"

@implementation Person
@synthesize firstName;

- (id)init
{
    self = [super init];
    if (self) {
        // Initialization code here.
    }

    return self;
}

@end
```

Now we can go ahead and use our `Person` class. Here is an example:

```
#import "SomeOtherClass.h"
#import "Person.h"

@implementation SomeOtherClass

- (void) makeNewPerson{

    Person *newPerson = [[Person alloc] init];
    newPerson.firstName = @"Andrew";
}
```

```

    NSLog(@"First name = %@", newPerson.firstName);
    NSLog(@"First name = %@", [newPerson firstName]);
}

@end

```

The example code prints the first name of `newPerson` twice, first using its `firstName` property and then by calling the `firstName` *getter method* on that object. Both will point to the same method, which `@synthesize` created for us in the *Person.m* file.



In an older version of the Objective-C runtime, for `@property` to work, we also had to define an *instance variable*. An instance variable is a variable whose memory management is done by the programmer herself. Instance variables are also *not* exposed to classes outside the scope of the class that defines them (that is, they are not exposed to any class that simply imports the class with the instance variable). Instance variables are normally called *ivars* by professional Objective-C developers. Ivars is pronounced like I-VAR with the VAR part pronounced like WAR, with a V.

With the new runtime, we don't have to define ivars anymore. We simply define the property and the LLVM compiler defines the ivar for us. If you are using the GCC compiler, which is rather unlikely, you will see big differences from how the LLVM compiler treats ivars. For instance, in GCC 4.2, an ivar is *not* accessible to any subclass of a class, whereas if you are using LLVM Compiler, a subclass of a class can use its superclass's ivars. So make sure you are using Apple's latest compiler, which is LLVM.

If you want to fiddle around with setter and getter methods, you are free to do so. Even if you have used `@synthesize` to allow the compiler to generate the setter and getter methods of a property for you, you can still go ahead and override those methods. For instance, in this example, I change the `setFirstName:` setter method of the `firstName` property of the `Person`:

```

#import "Person.h"

@implementation Person
@synthesize firstName;

- (void) setFirstName:(NSString *)paramFirstName{
    firstName = [paramFirstName stringByAppendingString:@" Jr"];
}

- (id)init
{
    self = [super init];
    if (self) {
        // Initialization code here.
    }
}

```

```

        return self;
    }

@end

```

I have overridden the setter method of my `firstName` property to add a "Jr" suffix to any string that I am told to assign to the `firstName` property. So when the setter and getters are invoked, as before:

```

Person *newPerson = [[Person alloc] init];
newPerson.firstName = @"Andrew";
NSLog(@"First name = %@", newPerson.firstName);
NSLog(@"First name = %@", [newPerson firstName]);

```

We will get the following printed out to the console window:

```

First name = Andrew Jr
First name = Andrew Jr

```

If you want to define a read-only property, all you have to do is to define your property using the `@readonly` keyword, like so:

```

@property (nonatomic, strong, readonly) NSString *lastName;

```



If a property is read-only, the only way that property's value can change is for the class that defines that property to use the ivar of that property to change the property's value.

See Also

XXX

1.16 Moving from Manual Reference Counting to Automatic Reference Counting

Problem

You want to learn about Automatic Reference Counting, Apple's new Compiler solution to solving the headache that programmers had to deal with when working with objects and memory management in Objective-C.

Solution

Study the new storage attributes introduced with the latest LLVM compiler: `strong`, `weak`, and `unsafe_unretained`.

Discussion

In the latest LLVM compiler, to use Automatic Reference Counting (ARC), we will need to deal with storage that is strong, weak, or unsafe and unretained. Any object under ARC is managed with one of these storage attributes. Here is a short explanation for each one:

strong

An object of this type is automatically retained at run-time and will be valid until the end of its scope, where it will automatically be released. For those familiar with Objective-C's traditional way of memory management, this keyword is similar to the `retain` keyword.

weak

This is zeroing weak referencing. If a variable is defined with this keyword, when the object to which this variable points gets deallocated, this value will get set to `nil`. For instance, if you have a strong string property and a weak string property and set the weak property's value to the strong property's value, when the strong property gets deallocated, the weak property's value will get set to `nil`.

unsafe_unretained

This is simply pointing one variable to another. This will not retain the object into the new variable, it will simply assign the object to the variable.

By default, all *local* variables are strong variables. In contrast, properties must explicitly specify their storage attribute. In other words, the compiler won't assume that all properties without a storage attribute are by default strong properties. So do make sure that you specify the storage attributes for your properties. Let's have a look at an example of the `strong` storage attribute. Let's assume we have two properties called `string1` and `string2`:

```
#import <UIKit/UIKit.h>

@interface Moving_from_Manual_Reference_Counting_to_ARCAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (strong, nonatomic) UIWindow *window;

@property (nonatomic, strong) NSString *string1;
@property (nonatomic, strong) NSString *string2;

@end
```

Now if we initialize the `string1` property with the value *String 1* and assign this property's value to the `string2` property, we will see that with the `strong` storage attribute, the `string2` property will keep its value even after `string1` is deallocated:

```
#import "Moving_from_Manual_Reference_Counting_to_ARCAppDelegate.h"

@implementation Moving_from_Manual_Reference_Counting_to_ARCAppDelegate
```

```

@synthesize window = _window;
@synthesize string1;
@synthesize string2;

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.string1 = @"String 1";
    self.string2 = self.string1;
    self.string1 = nil;

    NSLog(@"String 2 = %@", self.string2);

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

The output of this program is this:

```
String 2 = String 1
```

The `strong`, `weak`, and `unsafe_unretained` are most frequently used when declaring properties. You can take advantage of these storage specifiers even when declaring local variables, but you need to change the specifiers a bit. The `strong` specifier's inline equivalent is `__strong`, `weak` specifier's inline equivalent is `__weak`, and `unsafe_unretained` specifier's inline equivalent is `__unsafe_unretained`. (Note that each of those keywords begins with two underline characters.) Here is an example:

```

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    /* All local variables are by default strong so just emphasis that. We
    really don't have to mention __strong for the first variable but
    to make it clear, we will set it. No harm in doing so. */
    __strong NSString *yourString = @"Your String";
    __weak  NSString *myString = yourString;
    yourString = nil;
    __unsafe_unretained NSString *theirString = myString;

    /* All pointers will be nil at this time */
    &#14;
    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

The zeroing weak referencing under ARC is really magical and solves many issues programmers used to face when their objects were being deallocated. The magic in weak

referencing is that a zeroing weak reference's object gets set to `nil` when the object that it points to gets deallocated. The deallocation of that object will go through all the weak referencing pointers that point to that object and one by one, will set them to `nil`.

The `unsafe_unretained` storage specifier is truly unsafe, as its name implies. The reason for it being unsafe is if the object to which an `unsafe_unretained` variable points gets deallocated, this variable will not get set to `nil` and will point to a dangling location in the memory. Accessing this location might cause your application to crash. To avoid this, you should be using the zeroing weak referencing storage specifier, `weak` or its inline equivalent `__weak`.

Let's see an example for zeroing weak referencing. Let's change our `string2` property's storage specifier to `weak` instead of `strong`:

```
#import <UIKit/UIKit.h>

@interface Moving_from_Manual_Reference_Counting_to_ARCAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (strong, nonatomic) UIWindow *window;

@property (nonatomic, strong) NSString *string1;
@property (nonatomic, weak) NSString *string2;

@end
```

When our app starts for the first time, we will initialize the strong `string1` property and will assign `string1` to `string2`. We will then set the value of the `string1` property to `nil`. Then we will wait. This is absolutely crucial. If immediately after setting the value of `string1` to `nil`, you print out the value of `string2`, chances are that you will get incorrect results instead of `nil`. So you need to make sure that your app's runloop has gotten rid of all invalidated objects. In order to achieve this, we will print the value of `strong2` when our app gets sent to the background. (This is caused by the user bringing another app to the foreground.) Once we're running in the background, we know that the runloop has already gotten rid of invalidated objects in the memory and the results that we will get will be accurate:

```
/* 3 */
- (BOOL) application:(UIApplication *)application
    didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.string1 = [[NSString alloc] initWithUTF8String:"String 1"];
    self.string2 = self.string1;
    self.string1 = nil;

    /* All pointers will be nil at this time */

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
```

```

        return YES;
    }

    - (void)applicationDidEnterBackground:(UIApplication *)application{
        NSLog(@"String 2 = %@", self.string2);
    }

```

Now run this app, wait a second or two, and press the Home button on the device/simulator. You will notice that the following results will get printed to the console window:

```
String 2 = (null)
```

This easily proved that the zeroing weak references work perfectly under ARC. Now to check how dangerous the `unsafe_unretained` storage specifier is, let's go ahead and change the `string2` property's storage specifier to `unsafe_unretained` and repeat the exact same practice as we did for the weak property:

```

#import <UIKit/UIKit.h>

@interface Moving_from_Manual_Reference_Counting_to_ARCAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (strong, nonatomic) UIWindow *window;

@property (nonatomic, strong) NSString *string1;
@property (nonatomic, unsafe_unretained) NSString *string2;

@end

```

Now if leave the implementation of your app delegate as we had implemented it in the previous example (printing the value of `string2` property when our app gets sent to the background), and you repeat the same procedure and open your app and send it to the background, you will get a crash! This means that when our app was sent to the background, we tried to print out the contents of an invalidated memory location that the `string2` property was pointing to. Since the `string2` property was `unsafe` and `unretained`, it didn't know that the object that it was pointing to (in `string1`) was already deallocated when `string1` was set to `nil`.

In addition to the aforementioned three storage specifiers, we can also use the `__autoreleasing` specifier. This storage specifier is most handy when we want to pass an object by reference to a method. For instance, if you have a method that needs to pass an error of type `NSError` to the caller method, the caller method will pass an uninitialized and unallocated instance of `NSError` to this method. This means the caller didn't really allocate this error, so our method should do so. To do this, you must specify that this error parameter needs to be automatically released by the runtime when the right time comes:

```

- (void) generateErrorInVariable:(__autoreleasing NSError **)paramError{

    NSArray *objects = [[NSArray alloc] initWithObjects:@"A simple error", nil];

```



```

NSArray *keys =
[[NSArray alloc] initWithObjects:NSLocalizedStringKey, nil];

NSDictionary *errorDictionary = [[NSDictionary alloc] initWithObjects:objects
                                                                    forKeys:keys];

*paramError = [[NSError alloc] initWithDomain:@"MyApp"
                                             code:1
                                             userInfo:errorDictionary];
}

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSError *error = nil;
    [self generateErrorInVariable:&error];

    NSLog(@"Error = %@", error);

    self.window = [[UIWindow alloc] initWithFrame:
                  [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

In this example, the `application:didFinishLaunchingWithOptions:` method didn't allocate the instance of `NSError`; the `generateErrorInVariable` method did. But for the compiler to understand the scope of the error object, the `generateErrorInVariable` method mentioned to the compiler that the object which will be created into its error parameter needs to be automatically released if it is no longer needed.

See Also

XXX

1.17 Typecasting with Automatic Reference Counting

Problem

You want to know how to use new typecasting facilities under Automatic Reference Counting.

Solution

Use the `__bridge`, `__bridge_transfer`, and `__bridge_retained` typecasting specifiers.

Discussion

Typecasting is the process of pointing one value of type A to another value of type B. For instance, if you have a Core Foundation string object of type `CFStringRef` and you would like to place it inside an Objective-C string of type `NSString`, you can easily create an error:

```
- (BOOL)      application:(UIApplication *)application
  didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    CFStringRef coreFoundationString =
    CFStringCreateWithCString(CFAllocatorGetDefault(),
                             "C String",
                             kCFStringEncodingUTF8);

    /* Compile time error!!! */
    NSString *objCString = coreFoundationString;

    self.window = [[UIWindow alloc] initWithFrame:
                   [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

Here we are assigning the value of the Core Foundation string `coreFoundationString` to the Objective-C string of type `NSString` named `objCString`, our compiler will get confused because it doesn't know what we are intending to do with the memory assigned to each one of these objects. Additionally, we will end up with a memory leak because the compiler doesn't know how to get rid of the Core Foundation object for us automatically. Remember that Automatic Reference Counting does *not* work for Core Foundation objects, so we need to assist the compiler. To do this, let's try to understand what each one of these typecasting specifiers does:

`__bridge`

Simply typecasts the object on the right side of the equation to the left side. This will not modify the retain count on any of the objects; neither the one on the left nor the one on the right side of the equation.

`__bridge_transfer`

This typecast will assign the object on the right side to the object on the left and will release the object on the right side. So if you have a Core Foundation string, like the one we saw before, that you have just created and want to place it inside a local variable of type `NSString` (local variables are by default strong, see [Recipe 1.16](#)), then you should use this typecasting option because then you wouldn't have to release the Core Foundation string after the assignment. We will see an example of this soon.

`__bridge_retained`

This is similar to the `__bridge_transfer` typecast, but will retain the object on the right side of the equation as well.

Let's try to fix the example code we saw before. Our goal is to place the Core Foundation string into an instance of `NSString` (strong, by default) and then automatically release the Core Foundation string. To do this, we must use the `__bridge_transfer` typecasting option:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    CFStringRef coreFoundationString =
    CFStringCreateWithCString(CFAllocatorGetDefault(),
                            "C String",
                            kCFStringEncodingUTF8);

    /* Compile time error!!! */
    NSString *objCString = (__bridge_transfer NSString *)coreFoundationString;

    NSLog(@"String = %@", objCString);

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

What happened here was that we created a new Core Foundation object. The retain count on this object is 1 at this time. Then we typecasted and assigned it, using the `__bridge_transfer` typecast option, to a strong local variable of type `NSString`. But this time, because the compiler sees the typecasting, it will retain the Core Foundation string and place it inside the local variable (since the local variable is **strong** by default) and after the assignment, will release the Core Foundation string. Perfect! Exactly what we wanted.

Now let's have a look at when we would use `__bridge_retained`. This typecasting option is used whenever we would like the object on the right side of the equation to still exist after the assignment. Here is an example:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    CFStringRef coreFoundationString =
    CFStringCreateWithCString(CFAllocatorGetDefault(),
                            "C String",
                            kCFStringEncodingUTF8);

    id unknownObjectType = (__bridge id)coreFoundationString;

    CFStringRef anotherString = (__bridge_retained CFStringRef)unknownObjectType;
```

```

NSString *objCString = (__bridge_transfer NSString *)coreFoundationString;
NSLog(@"String = %@", objCString);
objCString = nil;

CFRelease(anotherString);

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

Here is what is happening in this code:

1. We allocated a Core Foundation string and placed it inside the `coreFoundationString` local variable. Since this is a Core Foundation object, ARC will not apply storage attributes to it, so we need to handle its memory manually. Its retain count is 1, as with any newly created variable.
2. Then we typecast this Core Foundation string to a generic object of type `id`. Note that we didn't retain or release this object, so the retain count on both `unknownObjectType` and `coreFoundationString` stays 1. We simply typecasted it to an object of type `id`.
3. Now we are retaining the generic object of type `id` and placing the resulting object into another Core Foundation string. At this time, the retain count on the `coreFoundationString`, `unknownObjectType`, and `anotherString` variables is 2 and all three of these variables point to the same location in the memory.
4. What we are doing after that is to assign the value inside `coreFoundationString` to a strong local `NSString` using the `__bridge_transfer` typecasting option. This will make sure that the `coreFoundationString` object will get released after this assignment (the retain count will go from 2 to 1) and it will again be retained (because of the strong `NSString` variable, shooting the retain count from 1 to 2 again) So now `coreFoundationString`, `unknownObjectType`, `anotherString` and the `objCString` variables all point to the same string with the retain count of 2.
5. Next stop, we are setting our strong local variable `objCString` to `nil`. This will release this variable and our string's retain count will go back to 1. All these local variables are still valid and you can read from them because the retain count of the string that all of them point to is still 1.
6. Then we are explicitly releasing the value in the `anotherString` variable. This will set the release count of our object from 1 to 0 and our string object will get deallocated. At this point, you should not use any of these local variables because they are pointing to a deallocated object—except for the `objCString` strong local variable, whose value was set to `nil` by us.

See Also

XXX

1.18 Delegating Tasks with Protocols

Problem

You want to make sure a certain object implements a set of methods or properties.

Solution

Use a protocol.

Discussion

A protocol is the declaration (as opposed to implementation) of a set of methods and/or properties in a physical file (usually with the extension of *.h*). Any object that you declare to conform to such protocol is responsible for writing the implementation of those methods and properties, depending on whether the protocol specifies them as required or optional.

Think of protocols as set of rules. Any object saying that it conforms to that protocol must follow those rules. Let's see a simple example of this. We will go ahead and define a protocol called *PersonProtocol*. For this, you need to create a new protocol file, so follow these steps first:

1. In Xcode, while having your project open, go to File menu and then choose New→New File...
2. Now make sure iOS is the main category on the left side of the New File dialog and then choose the Cocoa Touch sub-category. Once that is done, choose the Objective-C Protocol item and press Next (see [Figure 1-26](#)).




Figure 1-26. Creating a new protocol

3. Now you will be asked to save this file and specify a name for it. Give it the name *PersonProtocol* and press Save (see [Figure 1-27](#)).




Figure 1-27. Saving the new protocol

Now we have our header file. Let's get on with the actual declaration of our protocol. Our objective with this new `PersonProtocol` protocol is to govern the rules on any class that impersonates a "Person," or in other words, says that it is a Person class. For instance, in your application, you can have a class named Infant, Mother, Father, Son, Daughter, Stranger, etc. You can then make all these classes conform to the `PersonProtocol` protocol, which will define the types of behavior each of these classes must implement. Let's say that, for every person, we need at least a first name, a last name and an age:

```
#import <Foundation/Foundation.h>

@protocol PersonProtocol <NSObject>

@property (nonatomic, strong) NSString *firstName;
@property (nonatomic, strong) NSString *lastName;
@property (nonatomic, unsafe_unretained) NSUInteger age;

@end
```

Now let's create a class called Father and make sure that this class conforms to our `PersonProtocol` protocol. To create this class, follow these steps:

1. In Xcode, while in your project, go to the File menu and then select New→New File...

2. In the New File dialog, make sure iOS is the main category and then choose the Cocoa Touch sub-category. After that is done, select the Objective-C class item in the list on the right hand side. Now press the Next button (see [Figure 1-28](#)).




Figure 1-28. Creating a Father class

3. In this screen (see [Figure 1-29](#)), make sure we are creating a subclass of NSObject. Once that is done, press the Next button.




Figure 1-29. Subclassing NSObject to create a Father class

4. Now you are asked to save the new class. Give it the name of Father, press the *Father* , and press the Create button (see [Figure 1-30](#)).




Figure 1-30. Saving the *Father* class on disk

Fantastic, we now have our `Father` class and the `PersonProtocol` protocol. Open the header file of the `Father` class and make sure that it conforms to the `PersonProtocol` protocol:

```
#import <Foundation/Foundation.h>
#import "PersonProtocol.h"

@interface Father : NSObject <PersonProtocol>

@end
```

Now if you attempt to compile your app (by pressing `Command+Shift+R` simultaneously), you will get warnings from the compiler, similar to those shown in [Figure 1-31](#).




Figure 1-31. Warnings from the compiler related to the protocol we are conforming to

As you can see, the compiler understands that the `Father` class wants to conform to the `PersonProtocol` protocol. However, the `Father` class isn't implementing the required setter and getter methods of the properties defined in the `PersonProtocol` protocol. We are seeing these warnings because anything defined in a protocol by default is a required from its conforming classes. Required methods and properties in a protocol can explicitly be marked with the `@required` keyword. If you want to specify that followers of a protocol are free to choose to implement or not implement your methods or properties, you can simply tell the compiler that those methods/properties are optional, using the `@optional` keyword.

Let's go back to `PersonProtocol.h` and mark the `firstName`, `lastName`, and `age` properties as optional, but add a method to the protocol called `breathe` and make it a required method, because, let's face it, everybody has got to breathe:

```
#import <Foundation/Foundation.h>

@protocol PersonProtocol <NSObject>

@optional
@property (nonatomic, strong) NSString *firstName;
@property (nonatomic, strong) NSString *lastName;
@property (nonatomic, unsafe_unretained) NSUInteger age;

@required
- (void) breathe;

@end
```

Now if you compile your application, you will get completely different warnings (see [Figure 1-32](#)).




Figure 1-32. The *Father* class does not implement the *breathe* method defined in the *PersonProtocol* protocol

Now if you go to the *Father* class and define and implement the *breathe* method, even if the method implementation is empty, the compiler will be happy with that. Remember, the *Father* class now doesn't have to implement the three aforementioned properties because they are now defined as optional in the *PersonProtocol* protocol. Here is now the correct definition of the *Father* class:

```
#import <Foundation/Foundation.h>
#import "PersonProtocol.h"

@interface Father : NSObject <PersonProtocol>

- (void) breathe;

@end
```

And here is the correct implementation of the *Father* class:

```
#import "Father.h"

@implementation Father

- (void) breathe{
    /* Implement this method here */
}

@end
```

Attempt to compile your app now and you'll notice that the compiler is perfectly happy with our implementation.

Cocoa Touch has given protocols a really nice meaning in Objective-C. In Cocoa Touch, protocols are the perfect means for defining *delegate objects*. A delegate object is an object that another object consults when something happens in that object. For instance, your repair man is your delegate if something happens to your car. If something happens to your car, you go to your repair man and ask him to fix the car for you (although some prefer to repair the car themselves, in which case, they are their own delegate for their car). So in Cocoa Touch, many classes expect a delegate object and make sure that whatever object is assigned as their delegate conform to a certain protocol.

For instance, as we will see in [Chapter 3](#), the `UITableView` class defines and implements a property called `delegate`, which is required to conform to the `UITableViewDelegate` protocol. This protocol simply lays down the law to those objects that want to become the delegate object of a table view. The protocol requires those objects to implement certain methods or in some cases, specifies that some methods/properties are optional so the delegate object is free to implement or not implement them. Now, when a user selects a row in a table, the `UITableView` can call the `didSelectRowAtIndexPath:` method with the assurance that the `UITableViewDelegate` at least defined the method. The method may be correctly or incorrectly coded, but at least it's present, so the compiler will not reject the program.

See Also

XXX

1.19 Determining Whether Instance or Class Methods are Available

Problem

Your development SDK is the newest SDK, but you want to support devices running older iOS versions and APIs.

Solution

Use the `instancesRespondToSelector:` class method of `NSObject` to determine whether a specific selector exists in an instance of that class.

To determine whether a class itself responds to a class method, use the `respondsToSelector:` class method of your class. You can use the same method on an instance of a class to determine whether that instance responds to an instance method, as well as the `instancesRespondToSelector:` class method of the `NSObject` class.

Discussion

There are two important concepts with regard to iOS SDK that you need to remember:

Base SDK

The SDK that you use to compile your application. This can be the latest and the greatest SDK with access to all the new APIs available in iOS SDK.

Deployment SDK/Target

This is the SDK that will be used when you compile your app to run on devices.

Because of the fact that you are essentially compiling your apps with two SDKs, one the base and the other the deployment SDK, depending on which profile you are using

(device or simulator), your program might be vulnerable to invoking methods in classes that are available only in the latest SDK, but not the deployment SDK. So you might need to, from time to time, check for the existence of instance or class methods at run-time.

Let me give you an example. The iOS SDK has a class called `NSArray`. As you will see in [Recipe 1.23](#), you can simply allocate and initialize an object of this type and start using its methods. A mutable array (an array that can be changed after it has been constructed) is of type `NSMutableArray` and offers sorting mechanisms that you can use to sort the elements inside the array. There are various sorting methods, some of which are available only in newer SDKs. So what you can do is determine which one of the sorting (instance) methods are available at run-time and then use those methods to sort the array:

```
NSMutableArray *array = [[NSMutableArray alloc] initWithObjects:
    @"Item 1",
    @"Item 4",
    @"Item 2",
    @"Item 5",
    @"Item 3", nil];

NSLog(@"Array = %@", array);

if ([NSArray instancesRespondToSelector:@selector(sortUsingComparator:)]){

    /* Use the sortUsingComparator: instance method of the array to sort it */

}
else if ([NSArray instancesRespondToSelector:
    @selector(sortUsingFunction:context:)]){

    /* Use the sortUsingFunction:context: instance
    method of the array to sort */

}
else {

    /* Do something else */

}
```

So in this example, we are checking the existence of the specific instance methods, using the `instancesRespondToSelector:` class method of the `NSMutableArray` class (which itself is a subclass of `NSArray`). Alternatively, we could use the `respondToSelector:` instance method of our array:

```
NSMutableArray *array = [[NSMutableArray alloc] initWithObjects:
    @"Item 1",
    @"Item 4",
    @"Item 2",
    @"Item 5",
    @"Item 3", nil];
```

```

NSLog(@"Array = %@", array);

if ([array respondsToSelector:@selector(sortUsingComparator:)]){

    /* Use the sortUsingComparator: instance method of the array to sort it */

}
else if ([array respondsToSelector:@selector(sortUsingFunction:context:)]){

    /* Use the sortUsingFunction:context: instance
       method of the array to sort */

}
else {

    /* Do something else */

}

```

Fantastic. We checked the existence of instance methods. How about class methods? The `NSArray` class again has various class methods, two of which are the `arrayWithObjects:` and the `arrayWithObjects:count:` methods. We can determine their availability at run-time and use them to initialize the array:

```

NSArray *array = nil;

if ([NSArray respondsToSelector:@selector(arrayWithObjects:count:)]){
    NSString *strings[4];
    strings[0] = @"String 1";
    strings[1] = @"String 2";
    strings[2] = @"String 3";
    strings[3] = @"String 4";

    array = [NSArray arrayWithObjects:strings
                               count:4];
}
else if ([NSArray respondsToSelector:@selector(arrayWithObjects:)]){
    array = [NSArray arrayWithObjects:
              @"String 1",
              @"String 2",
              @"String 3",
              @"String 4",
              nil];
}
else {
    /* Do something else */
}

NSLog(@"Array = %@", array);

```

See Also

XXX

1.20 Determining Whether a Class is Available at Run Time

Problem

You are using a few classes that are available in the latest SDK but you are unsure whether they are available on devices that will be running your app, because your deployment target is earlier than the latest SDK.

Solution

Use the `NSClassFromString` function. Pass the name of your class to this method as a string. If the return value of this function is `nil`, that class is *not* available on the device that runs your app; otherwise, that class is available on the device and you can go ahead and use it as you wish. Here is an example:

```
if (NSClassFromString(@"NSJSONSerialization") != nil){

    /* You can use this class */
    [NSJSONSerialization JSONObjectWithData:... /* Put data here */
                                     options:... /* Put options here */
                                     error:...]; /* Handle errors here */

} else {

    /* That class is not available */

}
```

Discussion

It's no secret that users are slow in upgrading their operating systems. Working for various companies, I can confirm that usually around 30% of iOS devices today are running iOS versions that are about a year or a year and a half old. If today we are working with iOS 5, there are still iOS devices out there running iOS, 3 for instance. Revenue for developers is important, so we need to make sure that we do support older devices to some extent to be able to create a bigger user-base than by pushing an app that only runs on iOS 5 out to the App Store.

Some of the classes that we use are available only on specific versions of iOS. For instance, the `NSJSONSerialization` class is available only in iOS 5 SDK and only devices running iOS 5 will be able to run such code. However, if you are planning to support iOS 4 as well as iOS 5, then you can, at run-time, detect the availability of the aforementioned class using the `NSClassFromString` function, and pass the name of the class that you want to use as a parameter to this function. If the return value of this function is `nil`, that means the class that you specified cannot be instantiated on the specific device running your app. In this situation, you will need to choose an alternative path and instantiate another class that is available on the device, which carries out similar functionalities as the absent class.

See Also

XXX

1.21 Allocating and Making Use of Strings

Problem

You want work with strings in Objective-C

Solution

Use `NSString` and `NSMutableString` classes.

Discussion

The `NSString` and `NSMutableString` classes allow you to store a string of characters in memory. The `NSString` class is immutable, meaning that once it is created, its contents cannot be modified. Mutable strings represented with the `NSMutableString` can be modified once they are created. We will see an example of both of these classes very soon.

Objective-C strings should be placed inside double quotes. The starting double-quote should be prefixed with an at sign (@). For instance, the sentence `Hello, World`, represented as a string in Objective-C, is written like so:

```
@ "Hello, World"
```

There are various ways of placing a string inside an instance of `NSString` or `NSMutableString` classes. Here is how:

```
NSString *simpleString = @"This is a simple string";

NSString *anotherString =
    [NSString stringWithString:@"This is another simple string"];

NSString *oneMorestring =
    [[NSString alloc] initWithString:@"One more!"];

NSMutableString *mutableOne =
    [NSMutableString stringWithString:@"Mutable String"];

NSMutableString *anotherMutableOne =
    [[NSMutableString alloc] initWithString:@"A retained one"];

NSMutableString *thirdMutableOne =
    [NSMutableString stringWithString:simpleString];
```

If you are working with strings, you are probably going to need the length of your string objects from time to time to make specific decisions at runtime. Imagine this scenario: you have asked your user to enter her name in a text field. When she presses the button

to confirm her name, you would need to check whether she has in fact entered her name. You can do this by calling the `length` method on an instance of `NSString` or any of its subclasses, including `NSMutableString`, as shown here:

```
NSString *userName = ...;

if ([userName length] == 0){
    /* The user didn't enter her name */
} else {
    /* The user did in fact enter her name */
}
```

Another thing that you might want to know about strings is how you to convert a string to its equivalent integral value, i.e., converting a string to an integer, float, or double. You can use the `integerValue`, `floatValue`, and `doubleValue` methods of `NSString` (or any of its subclasses) to retrieve the integer, float and double values of a string, like so:

```
NSString *simpleString = @"123.456";

NSInteger integerValue = [simpleString integerValue];
NSLog(@"integerOfString = %ld", (long)integerValue);

CGFloat floatValue = [simpleString floatValue];
NSLog(@"floatOfString = %f", floatValue);

double doubleOfString = [simpleString doubleValue];
NSLog(@"doubleOfString = %f", doubleOfString);
```

The output of this code is:

```
integerOfString = 123
floatOfString = 123.456001
doubleOfString = 123.456000
```

If you would like to work with C Strings, you can! You will use them like `NSString` *without* the leading at-sign, like so:

```
char *cString = "This is a C String";
```

If you want to convert an `NSString` to a C String, you must use the `UTF8String` method of `NSString`, like so:

```
const char *cString = [@"Objective-C String" UTF8String];
NSLog(@"cString = %s", cString);
```



You can use the `%s` format specifier to print a C String out to the console,. In comparison, use the `%@` format specifier to print out `NSString` objects.

To convert a C String to `NSString`, you must use the `stringWithUTF8String:` method of the `NSString` class, as demonstrated here:

```
NSString *objectString = [NSString stringWithUTF8String:"C String"];
NSLog(@"objectString = %@", objectString);
```

In order to find a string inside another string, you can use the `rangeOfString:` method of `NSString`. The return value of this method is of type `NSRange`:

```
typedef struct _NSRange {
    NSUInteger location;
    NSUInteger length;
} NSRange;
```

If the string that you are looking for (needle) is found inside the target string (haystack), the `location` member of the `NSRange` structure will be set to the zero-based index of the first character of needle in haystack. If needle cannot be found in haystack, the `location` member gets set to `NSNotFound`. Let's have a look at an example:

```
NSString *haystack = @"My Simple String";
NSString *needle = @"Simple";
NSRange range = [haystack rangeOfString:needle];
```

```
if (range.location == NSNotFound){
    /* Could NOT find needle in haystack */
} else {
    /* Found the needle in the haystack */
    NSLog(@"Found %@ in %@ at location %lu",
          needle,
          haystack,
          (unsigned long)range.location);
}
```



The search done by the `rangeOfString:` method of `NSString` class is case-sensitive.

If you want to have more control over how your search is done on a string, you can use the `rangeOfString:options:` method, where the `options` parameter is of type `NSStringCompareOptions`.

```
enum {
    NSCaseInsensitiveSearch = 1,
    NSLiteralSearch = 2,
    NSBackwardsSearch = 4,
    NSAnchoredSearch = 8,
    NSNumericSearch = 64,
    NSDiacriticInsensitiveSearch = 128,
    NSWidthInsensitiveSearch = 256,
    NSForcedOrderingSearch = 512,
    NSRegularExpressionSearch = 1024
};
typedef NSUInteger NSStringCompareOptions;
```

As you can see, the values in this enumeration are multiples of 2. That indicates that you can mix them with the logical OR operator (the | pipe character). Let's say we want to search for a string inside another string but we are not concerned about the case-sensitivity of the search. All we want is to find a string inside another string, whether the case matches or not. Here is how we can do it:

```
NSString *haystack = @"My Simple String";
NSString *needle = @"simple";
NSRange range = [haystack rangeOfString:needle
                                options:NSCaseInsensitiveSearch];

if (range.location == NSNotFound){
    /* Could NOT find needle in haystack */
} else {
    /* Found the needle in the haystack */
    NSLog(@"Found %@ in %@ at location %lu",
          needle,
          haystack,
          (unsigned long)range.location);
}
```

You can see that we are using the `rangeOfString:options:` method of `NSString` with the `NSCaseInsensitiveSearch` value, which tells the runtime that we want the search to be performed without any regard to case-sensitivity.

Mutable strings are similar to immutable strings. However, they can be modified during runtime. Let's see an example:

```
NSMutableString *mutableString =
    [[NSMutableString alloc] initWithString:@"My MacBook"];

/* Add string to the end of this string */
[mutableString appendString:@" Pro"];

/* Remove the "My " string from the string */
[mutableString
 replaceOccurrencesOfString:@"My "
 withString:[NSString string] /* Empty string */
 options:NSCaseInsensitiveSearch /* Case-insensitive */
 range:NSMakeRange(0, [mutableString length])]; /* All to the end */

NSLog(@"mutableString = %@", mutableString);
```

When the `mutableString` string gets printed to the console, you will see this:

```
mutableString = MacBook Pro
```

You can see that we started with the string `"My MacBook"` and then removed the `"My "` string from that original string. So now we have `"MacBook"`. After this, we appended the string `" Pro"` to the end of this string to get the final value, which is `"MacBook Pro"`.

See Also

XXX

1.22 Allocating and Making Use of Numbers

Problem

You need to use integral values or encapsulate numbers in objects.

Solution

Use `NSNumber` for an object-oriented approach to handling numbers. If you require simple numbers (non-objects), use `NSInteger` to hold signed (positive and negative) values, `NSUInteger` to hold unsigned (only positive or zero) values, and `CGFloat` and `double` to hold floating point values.

Discussion

Just as we place strings inside instances of `NSString`, we can place numbers inside instances of `NSNumber`. Why, you might ask? The answer is simple: to have allow an object to carry the value of our numbers so that we can save this value to disk easily, load it from disk, and simply allow a single object to carry signed and unsigned integral and floating point values, without the need for typecasting or defining multiple variables. The possibilities are virtually endless.

Let's have a look at constructing instances of `NSNumber`:

```
NSNumber *signedNumber = [NSNumber numberWithInt:-123456];
NSNumber *unsignedNumber = [NSNumber numberWithUnsignedInteger:123456];
NSNumber *floatNumber = [NSNumber numberWithFloat:123456.123456f];
NSNumber *doubleNumber = [NSNumber numberWithDouble:123456.1234567890];
```

Just as we placed signed and unsigned integers and floating point values into an instance of `NSNumber` class, we can retrieve those values back using some really handy instance methods of `NSNumber` class, as shown here:

```
NSNumber *signedNumber = [NSNumber numberWithInt:-123456];
NSNumber *unsignedNumber = [NSNumber numberWithUnsignedInteger:123456];
NSNumber *floatNumber = [NSNumber numberWithFloat:123.123456f];
NSNumber *doubleNumber = [NSNumber numberWithDouble:123.1234567890];

NSInteger signedValue = [signedNumber integerValue];
NSUInteger unsignedValue = [unsignedNumber unsignedIntegerValue];
CGFloat floatValue = [floatNumber floatValue];
double doubleValue = [doubleNumber doubleValue];

NSLog(@"signedValue = %ld, \n\"
      "unsignedValue = %lu \n\"
      "floatValue = %f \n\"
      "doubleValue = %f",
      (long)signedValue,
      (unsigned long)unsignedValue,
      floatValue,
      doubleValue);
```

Here are the methods of `NSNumber` that we used in this code to actually generate instances of `NSNumber` class:

numberWithInteger:

Encapsulates an integer into an instance of `NSNumber`.

numberWithUnsignedInteger:

Encapsulates an unsigned integer (only positive or zero numbers) into an instance of `NSNumber`.

numberWithFloat:

Encapsulates a floating point value into an instance of `NSNumber`.

numberWithDouble:

Encapsulates a double value into an instance of `NSNumber`.

And here are the methods which we used to extract pure numbers from instances of `NSNumber`:

integerValue

Returns an integer of type `NSInteger` from the `NSNumber` on which this method is called.

unsignedIntegerValue

Returns an unsigned integer of type `NSUInteger` from the `NSNumber` on which this method is called.

floatValue

Returns a floating point value of type `CGFloat` from the `NSNumber` on which this method is called.

doubleValue

Returns a double value of type `double` from the `NSNumber` on which this method is called.

If you want to compare a number to a string, simply convert it to any of the raw integral/float values that you think can contain the whole of that number, and then format your string using a format identifier that suits your data. For instance, to turn an unsigned integer into an instance of `NSString`, you can use the `%lu` format specifier, like so:

```
NSNumber *unsignedNumber = [NSNumber numberWithInt:123456];

/* Convert an unsigned integer inside an NSNumber to NSString */
NSString *numberInString =
    [NSString stringWithFormat:@"%lu",
     (unsigned long)[unsignedNumber unsignedIntegerValue]];

NSLog(@"numberInString = %@", numberInString);
```

Keep in mind that any class method of `NSNumber` class that starts with *numberWith* returns an autorelease instance of that `NSNumber`. To remove the burden on your autorelease pools, you can use the *initWith...* methods of the `NSNumber` class after allocating your number, like so:

```
NSNumber *unsignedNumber =  
    [[NSNumber alloc] initWithUnsignedInteger:123456];
```

See Also

XXX

1.23 Allocating and Making Use of Arrays

Problem

You want to store a series of objects into another object for later use.

Solution

Use `NSArray` and `NSMutableArray` classes to store objects into arrays that are fixed and that you can change, respectively.

Discussion

An object of type `NSArray` or any of its subclasses has the capability to store n number of other objects. These objects can then be accessed using their index. For instance, let's say you have 10 pair of socks. Now imagine placing them all on a flat surface from left to right, you call them, socks 1, socks 2, socks 3, etc. So the leftmost sock is now addressed as socks 1, the one next to it is called socks 2, etc. Isn't that easier than saying something like "the blue socks next to my red socks"? That's exactly what arrays do: they make arranging items much easier.



You can place any object of type `NSObject` or any of its subclasses into an array of type (or subclasses of) `NSArray`

The primary difference between `NSArray` and `NSMutableArray` is that a mutable array *can* be changed/modified after it has been allocated and initialized, whereas an immutable array, `NSArray`, *cannot*.

Let's have a look at an example. Let's create an instance of `NSString` and two instances of `NSNumber` and place them in an immutable array:

```
NSString *stringObject = @"My String";  
NSNumber *signedNumber = [NSNumber numberWithInt:-123];  
NSNumber *unsignedNumber = [NSNumber numberWithUnsignedInteger:123];  
  
NSArray *array = [[NSArray alloc] initWithObjects:  
    stringObject,  
    signedNumber,  
    unsignedNumber, nil];
```

```
NSLog(@"array = %@", array);
```

When you run this program, you get the following text printed to your console:

```
array = (  
    "My String",  
    "-123",  
    123  
)
```

As you can see, we used the `initWithObjects:` initializer of the array. When using this initializer, pass your objects that need to be placed inside the array, one by one. At the end, terminate the list with a `nil` so that the runtime knows when you are terminating your list. If you don't do so, the LLVM Compiler will throw a warning similar to this:

```
warning: Semantic Issue: Missing sentinel in method dispatch
```

We can also use the `arrayWithObjects:` class method of `NSArray` to create an autorelease array, like so:

```
NSArray *array = [NSArray arrayWithObjects:  
    stringObject,  
    signedNumber,  
    unsignedNumber, nil];
```

You can call the `count` method on your array to get the number of objects in that array. You can go through your array using a `for` loop or using an enumerator. Let's have a look at the solution with a `for` loop first:

```
NSArray *array = [NSArray arrayWithObjects:  
    stringObject,  
    signedNumber,  
    unsignedNumber, nil];  
  
NSUInteger counter = 0;  
for (counter = 0;  
     counter < [array count];  
     counter++){  
  
    id object = [array objectAtIndex:counter];  
    NSLog(@"Object = %@", object);  
  
}
```

And here is the output:

```
Object = My String  
Object = -123  
Object = 123
```

As you can see, we use the `objectAtIndex:` method to get an object at a specific index. Remember that indexes are zero-based. In other words, when the counter reaches -1, the loop has to stop because there can be no negative indexes in an array.

As mentioned before, you can also use fast enumeration to go through objects of an array. Fast enumeration is a language feature in Objective-C that allows you to enumerate objects in an array or dictionary (or any other object that supports fast enumeration) without having to use any counter or for loop. The format is as follows:

```
for (Type variableName in array/dictionary/etc){ ... }
```

Support we want to code the previous example *without* the overhead of a counter variable. Here is how we can do it using fast enumeration:

```
for (id object in array){
    NSLog(@"Object = %@", object);
}
```

The results are practically identical to the results we got from the previous version of this code that used a counter variable.

Mutable arrays are very interesting. As you probably have already guessed, immutable arrays cannot be modified once allocated and initialized. Mutable arrays, however, *can* be modified after their allocation and initialization. Let's have a look at an example:

```
NSString *stringObject = @"My String";
NSNumber *signedNumber = [NSNumber numberWithInt:-123];
NSNumber *unsignedNumber = [NSNumber numberWithUnsignedInteger:123];

NSArray *anotherArray = [[NSArray alloc] initWithObjects:
    @"String 1",
    @"String 2",
    @"String 3", nil];

NSMutableArray *array = [[NSMutableArray alloc] initWithObjects:
    stringObject,
    signedNumber, nil];

[array addObject:unsignedNumber];
[array removeObject:signedNumber];
[array addObjectsFromArray:anotherArray];

for (id object in array){
    NSLog(@"Object = %@", object);
}
```

Before we go into analyzing the code, let's have a look at its output:

```
Object = My String
Object = 123
Object = String 1
Object = String 2
Object = String 3
```

You might be asking, "what just happened?". Well, let's have a look what methods of the `NSMutableArray` class we actually used:

addObject:


This method allows us to add an object to the end of a mutable array.

removeObject:

Using this method, we can remove a specific object from the array. Remember that we pass an object to this method, *not* an index of the object. To remove an object using an index into the array, we must use the `removeObjectAtIndex:` method.

addObjectsFromArray:

With this method, we can add objects from one array (either mutable or immutable) into our mutable array.



Please bear in mind that during fast enumeration or a mutable array, you *must not* add to or remove anything from that array or you will get a runtime error. This is the default behaviour of mutable arrays during fast enumeration.

If you are interesting in block objects (and we'll see good reasons to be, later in the book!), you can also enumerate objects in your arrays using the `enumerateObjectsUsingBlock:` method. The block object passed to this method should:

1. Return no value.
2. Have three parameters:
 - a. First parameter of type `id`, which will be the object being enumerated at each loop of enumeration.
 - b. Second parameter of type `NSUInteger`, which will tell you the index of the current object being enumerated.
 - c. Last but not least, a parameter of type `*BOOL`, which you can use to stop the enumeration. This is a pointer to a boolean variable which should be `NO` as long as you want the enumeration to proceed. You can change the value of this pointer to `YES` in order to stop the enumeration at any time. You would use this if you are looking for an object in an array and you would like to stop the enumeration as soon as you've found that object, since there is no point continuing the enumeration if you've already found your object.

```
NSArray *myArray = [[NSArray alloc] initWithObjects:
    @"String 1",
    @"String 2",
    @"String 3",
    @"String 4", nil];

[myArray enumerateObjectsUsingBlock:
 ^(__strong id obj, NSUInteger idx, BOOL *stop) {
<!--

    AO: Shouldn't *stop be set to NO beforehand? Or is that the default?

-->

    NSLog(@"Object = %@", obj);
```

```
});
```

If you need to sort an array, simply use the new block-based sorting methods of `NSArray` or `NSMutableArray`. Just remember that the sorting methods of `NSArray` return a new instance of `NSArray` and leave the original array intact, since `NSArray` cannot be modified (sorting can modify an array) after it has been allocated and initialized. This is in comparison to the sorting methods of `NSMutableArray`, where the original array will be the target of sorting and the sorting methods will *not* return a new array. Let's look at sorting a mutable array:

```
NSMutableArray *myArray = [[NSMutableArray alloc] initWithObjects:
    @"String 2",
    @"String 4",
    @"String 1",
    @"String 3", nil];

[myArray sortUsingComparator:
 ^NSComparisonResult(__strong id obj1, __strong id obj2) {

    NSString *string1 = (NSString *)obj1;
    NSString *string2 = (NSString *)obj2;
    return [string1 compare:string2];

}];

NSLog(@"myArray = %@", myArray);
```

The results will then be printed to the console, as follows:

```
myArray = (
    "String 1",
    "String 2",
    "String 3",
    "String 4"
)
```

So, what happened? We simply called the `sortUsingComparator:` method of our array. This method takes in a block object (marked by the initial `^` character) that has to return a value of type `NSComparisonResult`. This value can be any of the following:

NSOrderedSame

The two values being compared are equal.

NSOrderedAscending

The value on the left of the comparison is smaller than the value on the right. Think of it as this: transition from value 1 (left) to value 2 (right) is ascending, meaning that value 1 is smaller.

NSOrderedDescending

The value on the right is smaller than the value on the left. In other words, the transition from value 1 (left) to value 2 (right) is descending, meaning that value 1 is bigger than value 2.

So if we get *String 3* as value 1 (left) and then get *String 1* as value 2 (right), is that ascending or descending or the same? Of course, it is descending because transition from value 1 (left, String 3) descends to value 2 (right, String 1). Remember that whichever object the `compare:` method gets called is the left object, or value 1.

The block object submitted to the `sortUsingComparator:` method takes two parameters:

First Object of type id

This is the first object in the comparison in each iteration.

Second Object of type id

This is the second object in the comparison in each iteration.

So when sorting the array, simply use a block-based approach. It's the way Apple is pushing developers to go forward with their implementations, so it's good to know about block objects.

See Also

XXX

1.24 Allocating and Making Use of Dictionaries

Problem

You want to store key-value pairs in an object, but arrays won't quite do it for this purpose.

Solution

Use `NSDictionary` and its mutable counterpart, `NSMutableDictionary`

Discussion

A dictionary is a special array in which each item is given a key. That is the only difference between dictionaries and arrays. An array has a numeric index into each item/object that it holds whereas a dictionary holds a key to each item. I'll show you what I mean.

Let's say we want to store a person's first name, last name, and age into an array and then into a dictionary. This is how we would store those values in an array:

```
NSArray *person = [[NSArray alloc] initWithObjects:
    @"Anthony",
    @"Robbins",
    [NSNumber numberWithInt:51], nil];

NSLog(@"First Name = %@", [person objectAtIndex:0]);
NSLog(@"Last Name = %@", [person objectAtIndex:1]);
NSLog(@"Age = %@", [person objectAtIndex:2]);
```

You can see that we are using an index into the array to access each one of these values. With dictionaries, we give each value a *key*, which is an object, and then use that key to access those values. Let's see the same example, using dictionaries. We have a "First Name" key with the value "Anthony" and so on:

```
NSNumber *age = [NSNumber numberWithInt:51];
NSDictionary *person = [[NSDictionary alloc] initWithObjectsAndKeys:
    @"Anthony", @"First Name",
    @"Robbins", @"Last Name",
    age, @"Age",
    nil];

NSLog(@"First Name = %@", [person objectForKey:@"First Name"]);
NSLog(@"Last Name = %@", [person objectForKey:@"Last Name"]);
NSLog(@"Age = %@", [person objectForKey:@"Age"]);
```

The results will then be printed out as shown here:

```
First Name = Anthony
Last Name = Robbins
Age = 51
```

As you can see, we initialized the dictionary with values and keys. We give a value followed by the key for that value. When we used NSLog, we printed out each value by handing the key to the dictionary's `objectForKey:` method.

The mutable version of NSDictionary, NSMutableDictionary, can be modified after it has been allocated and initialized. For instance, if we want to remove the object associated with the key *Age* from our dictionary after its initialization, we would use a mutable dictionary like so:

```
NSNumber *age = [NSNumber numberWithInt:51];
NSMutableDictionary *person = [[NSMutableDictionary alloc]
    initWithObjectsAndKeys:
    @"Anthony", @"First Name",
    @"Robbins", @"Last Name",
    age, @"Age",
    nil];

[person removeObjectForKey:@"Age"];

NSLog(@"First Name = %@", [person objectForKey:@"First Name"]);
NSLog(@"Last Name = %@", [person objectForKey:@"Last Name"]);
NSLog(@"Age = %@", [person objectForKey:@"Age"]);
```

We have simply removed the object associated with the key *Age*. The results printed to the console window will be similar to this:

```
First Name = Anthony
Last Name = Robbins
Age = (null)
```

Note that "Age" is not just empty, but totally missing.

If you want to enumerate all keys with their objects inside a dictionary, you can simply use the `enumerateKeysAndObjectsUsingBlock:` method of the dictionary. In the previous array, the method would print the "First Name" and "Last Name" elements, but not "Age", because we removed it. The parameter to this method is a block object with no return value and three parameters:

Key

An id that tells you which key is being enumerated at the moment.

Object

An id as well, that gives you the object associated with the key being currently enumerated.

A pointer to a value of type BOOL

At any point during the enumeration, if you want to stop the process, you can simply put the value YES into this pointer's memory address. Keep it untouched if you want to enumerate through all the keys in the dictionary.

Let's see an example:

```
NSNumber *age = [NSNumber numberWithInt:51];
NSDictionary *person = [[NSDictionary alloc] initWithObjectsAndKeys:
    @"Anthony", @"First Name",
    @"Robbins", @"Last Name",
    age, @"Age",
    nil];

[person enumerateKeysAndObjectsUsingBlock:
 ^(__strong id key, __strong id obj, BOOL *stop) {

    NSLog(@"Key = %@, Object For Key = %@", key, obj);

}];
```

And the results, which get printed to the console window, are shown here:

```
Key = Last Name, Object For Key = Robbins
Key = First Name, Object For Key = Anthony
Key = Age, Object For Key = 51
```

If you want to do a manual fast enumeration without block objects, you can use the `allKeys` method of the dictionary to go through all methods and, once you enumerate the keys, use the keys to find the objects associated with the keys using the `objectForKey:` method, like so:

```
for (id keyInDictionary in [person allKeys]){

    id objectForKey = [person objectForKey:keyInDictionary];
    NSLog(@"Key = %@, Object For Key = %@", keyInDictionary, objectForKey);

}
```

Bear in mind that you can traverse the keys in a dictionary in various ways. We've just seen two ways of doing this. There is another method that we can use: calling the


keyEnumerator method of the dictionary to get an object of type NSEnumerator. Here is an example:

```
NSEnumerator *keys = [person keyEnumerator];
id keyInDictionary = nil;

while ((keyInDictionary = [keys nextObject]) != nil){

    id objectForKey = [person objectForKey:keyInDictionary];
    NSLog(@"Key = %@, Object For Key = %@", keyInDictionary, objectForKey);

}
```



When using the keyEnumerator method of a mutable dictionary, you are *not* allowed to change the values inside the dictionary while going through the keys. The same rule, if you remember, applies to mutable arrays as well.

See Also

XXX

1.25 Allocating and Making Use of Sets

Problem

You would like to store an array of objects but you don't want any one object to appear more than once in the array.

Solution

Use sets instead of arrays.

Discussion

Sets are very similar to arrays. The big difference is that sets allow objects to be added only once. The second time you try to add the same object, it will be rejected by the set. We use NSSet for immutable and NSMutableSet for mutable sets. Let's have a look at an example of an immutable set:

```
NSString *hisName = @"Robert";
NSString *hisLastName = @"Kiyosaki";

NSString *herName = @"Kim";
NSString *herLastName = @"Kiyosaki";

NSSet *setOfNames = [[NSSet alloc] initWithObjects:
                    hisName,
                    hisLastName,
                    herName,
```

```

        herLastName, nil];

NSLog(@"Set = %@", setOfNames);

```

We created an immutable set and passed 4 string objects to its initializer method. So let's see what gets printed out to the console window with our `NSLog`:

```

Set = {(
    Kim,
    Robert,
    Kiyosaki
)}

```

You can see that the last name *Kiyosaki* was added only once to the list. Our set rejected the second addition of the same object to the list. It is *very* important to understand that a set doesn't just do a comparison on where in memory an object sits, but it actually looks into its contents. `hisLastName` and `herLastName` are two separate variables, and they will sit in two different places in the memory. Our set, however, managed to understand that we are passing instances of `NSString` to it and did a comparison on the *contents* of these strings to find out that we had already added the *Kiyosaki* last name to the set. So only one instance ended up in the set.

Now let's have a look at constructing mutable sets:

```

NSMutableDictionary *setOfNames = [[NSMutableDictionary alloc] initWithObjects:
    hisName,
    herLastName, nil];

[setOfNames addObject:herName];
[setOfNames addObject:herLastName];

```

We simply used the `addObject:` method of `NSMutableDictionary` to add new objects to our set. You can also use the `removeObject:` method to remove an object. Again, remember that the contents of the object matter, not its memory address. So if you want to remove a string from the set, simply pass that string to the `removeObject:` method, even if your new string is in a different variable or somewhere else in memory. As long as the contents of that string/object are the same, you will get the results you want:

```

NSMutableDictionary *setOfNames = [[NSMutableDictionary alloc] initWithObjects:
    hisName,
    herLastName,
    herName,
    herLastName, nil];

[setOfNames removeObject:@"Kiyosaki"];

NSLog(@"Set = %@", setOfNames);

```

And the results get printed to the console window:

```

Set = {(
    Kim,
    Robert
)}

```


If you want to fast enumerate all objects in a set, use the `enumerateObjectsUsingBlock:` method. The block object that you pass to this method should return no value and should have two parameters:

A key of type id

Contains the object in the set that is being currently enumerated.

A pointer to a boolean value of type BOOL

If you want to stop the enumeration at any time, simply place a boolean value of type YES into the memory address of this variable.

Let's have a look at an example. Let's say I want to try to find the string *Kiyosaki* in a set that I have:

```
[setOfNames enumerateObjectsUsingBlock:^(__strong id obj, BOOL *stop) {  
  
    if ([obj isKindOfClass:[NSString class]]){  
        NSString *string = (NSString *)obj;  
        if ([string isEqualToString:@"Kiyosaki"]){  
            NSLog(@"Found %@ in the set", string);  
            *stop = YES;  
        }  
    }  
}];
```

If the enumeration can find a string with the value of *Kiyosaki* in the set, we print a string to the console and terminate the enumeration by placing the value of YES into the second parameter of our enumerator block object.

There are other handy methods for sets. Use the `count` method to get the number of objects currently in a set. You can also use the `allObjects` method to get an array of all the objects in the set. If you want to extract an object from the set, with no concern or which one, call the `anyObject` on your set. This method will return, as its name implies, a random object in the set, no matter where in the set it is. You will get `nil` from this method if the set is empty.



Remember that an *immutable* empty set is absolutely useless. It's empty and it will remain empty throughout its lifetime.

See Also

XXX

1.26 Creating Bundles

Problem

You want to group your resources into hierarchical structures and be able to access those resources at run time with ease.

Solution

Follow these steps to successfully create a bundle:

1. Create a root folder on your disk that will later become your bundle. For instance, let's give this folder the name *Resources*.
2. Under the *Resources* folder, create three more folders named *Images*, *Videos*, and *Sounds*.
3. Under the three aforementioned folders, place related resources. For instance, place one or more images in the *Images* folder and one or more video files under the *Videos* folder and so on.
4. Once you are done, rename your *Resources* folder to *Resources.bundle*. Once you add this extension to your folder name, OS X will ask for your confirmation and a dialog similar to that shown in [Figure 1-33](#) will appear on the screen. Press Add on the dialog to add the *.bundle* extension to the *Resources* folder.




Figure 1-33. Adding a *.bundle* extension to a folder name in order to turn it into a bundle

Discussion

Bundles are simple folders with a *.bundle* extension. They have two main distinctions from regular folders:

1. Cocoa Touch provides an interface through which you can access bundles and their resources really easily.

2. If a bundle is added to the Navigator on the left hand side of Xcode, any files added to or removed from the bundle outside Xcode will, respectively, appear in or disappear immediately from Xcode's navigator. In contrast, if you had added a normal folder to Xcode's navigator and then went and deleted a file from that folder on disk, without using Xcode's help, you would see that file marked with red color in Xcode rather than getting deleted immediately. Bundles can be very useful, especially if you want to add files to your folders manually using Finder, instead of using Xcode.

Every iOS application comes with at least one bundle, called the main bundle. The main bundle contains your app's binary code and any other resource you are using inside your application, such as retina images, sounds, HTML files, and whatnot. The main bundle, in other words, contains the resources that get compiled into your final binary that you will submit to the App Store or distribute in your organization. These resources can then be dynamically loaded using the `NSBundle` class's `mainBundle` class method.



Although you can add two or more bundles with the same name to one iOS project, it is best not to complicate things like that. The reason this situation could get complicated is that when we start loading resources from our bundles, we will first need to find our bundles by their path. If you have two bundles with the same name, it will become quite difficult to detect which is which. So as a good practice, make sure that your bundles have different names when you add them to your Xcode projects.

See Also

XXX

1.27 Loading Data From the Main Bundle

Problem

You have added a resource (such as an image) to your Xcode project and now, at run time, you would like to access that resource.

Solution

Use the `mainBundle` class method of the `NSBundle` class in order to retrieve your main bundle. Once that is done, use the `pathForResource:ofType:` method of your main bundle to retrieve the path for that specific resource. Once the path is detected, depending on the type of resource, you can either pass the path to your file to a class such as `UIImage` or `NSData`, or you can manually access the file using `NSFileManager`.



It is highly recommended that you give a unique name to each resource inside your bundles. For instance, it is not good practice to have a file named *Default.png* in more than one place inside your main bundle. Different ways of loading a resource from a bundle could then yield different results. As a result, make sure you give unique names to your files inside any bundle, regardless of whether it is the main bundle or a custom bundle that you've created (see [Recipe 1.26](#)).

Discussion

To access the main bundle, we can use the `mainBundle` class method of the `NSBundle` class. Bundles are all of type `NSBundle` and once you have an instance of a bundle, you can load resources from that bundle.



Every app's main bundle has a flat hierarchy on disk when it is compiled for submission to App Store. That means all the files that get wrapped up in your app bundle will be placed on the root folder of the main bundle. In other words, the main bundle has only one folder, the root folder, and all files and resources are stored in that folder. Even if you have a folder on disk with a few images in it and drag and drop it into Xcode, only the files in that folder will be placed in the main bundle's file hierarchy, not the folder itself.

For instance, let's say that you have an image called *AlanSugar.png* sitting on your desktop. Simply drag and drop it into Xcode. At this point, Xcode will display a dialog to you, asking you which project this file has to be added to and whether you want this file to be copied over to the project's folder, if need be. This dialog will look similar to that shown in [Figure 1-34](#).




Figure 1-34. Xcode asking which project a file has to be added to

In this dialog, make sure that the "Copy items into destination group's folder (if needed)" item is selected. This will copy the file that you drop into Xcode to the target app's folder. Now, if you delete the file on your desktop, it won't get deleted from your project because your project has its own copy. It's generally good practice to do this unless for specific reasons you decide not to (and I've experienced many of these reasons myself). After you drag and drop the file, the file *AlanSugar.png* is in the project's main bundle and you can retrieve its path in this way:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSString *alanSugarFilePath =
    [[NSBundle mainBundle] pathForResource:@"AlanSugar"
                                     ofType:@"png"];

    if ([alanSugarFilePath length] > 0){
        UIImage *image = [UIImage imageWithContentsOfFile:alanSugarFilePath];
        if (image != nil){
            NSLog(@"Successfully loaded the file as an image.");
        } else {
            NSLog(@"Failed to load the file as an image.");
        }
    }

    } else {
        NSLog(@"Could not find this file in the main bundle.");
    }
}
```

```

    }

    self.window = [[UIWindow alloc] initWithFrame:
                  [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

The output of the `pathForResource ofType:` method of `NSBundle` will be either a valid path or nil if the specified resource cannot be found in the target bundle. So after you call this method, it is best to check whether the path could actually be retrieved. If so, the code shown passes the path of the file to the `UIImage` class in order to load the *AlanSugar.png* file into memory as an image.

Similarly, if you wanted to load the data of that file into memory, instead of retrieving this image as an image object, you could use the `NSData` class:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSString *alanSugarFilePath =
    [[NSBundle mainBundle] pathForResource:@"AlanSugar"
                                         ofType:@"png"];

    if ([alanSugarFilePath length] > 0){

        NSError *readError = nil;

        NSData *dataForFile =
        [[NSData alloc] initWithContentsOfFile:alanSugarFilePath
                                         options:NSMappedRead
                                         error:&readError];

        if (readError == nil &&
            dataForFile != nil){
            NSLog(@"Successfully loaded the data.");
        } else if (readError == nil &&
                   dataForFile == nil){
            NSLog(@"No data could be loaded.");
        } else {
            NSLog(@"An error occurred while loading data. Error = %@", readError);
        }

    } else {
        NSLog(@"Could not find this file in the main bundle.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
                  [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
}

```

```
    return YES;  
}
```

See Also

XXX

1.28 Loading Data From Other Bundles

Problem

You have included a few images or other resources in a separate bundle inside your main bundle and you would like to access those resources at run time.

Solution

Find the path to your bundle at run time using the `pathForResource:ofType:` method of your your main bundle. Once you have the path to your bundle, simply access it using the `bundleWithPath:` class method of `NSBundle`.



Before continuing with this recipe, please follow the instructions in [Recipe 1.26](#) to create a bundle called *Resources.bundle* and place it inside your main bundle.

Discussion

If you have followed the instructions in [Recipe 1.26](#), you now have a bundle called *Resources.bundle* inside this bundle you have a folder called *Images*. Let's now put an image inside this folder. After I placed an image called *AlanSugar.png* into the bundle [Figure 1-35](#) shows what the bundle contains.




Figure 1-35. Placing an image inside the bundle which we created before

Since the *Resources.bundle* is added to our app's main bundle, we will need to use the main bundle in order to find the path to our *Resources.bundle*. Once that is done, we can directly access the files (only *AlanSugar.png* right now) inside this bundle. Since bundles other than the main bundle can have folders embedded inside them, to access files inside folders of a bundle other than the main bundle it is best to use the `pathForResource ofType:inDirectory:` method of `NSBundle` to explicitly specify the folder in which a specific file/resource exists.

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSString *resourcesBundlePath =
    [[NSBundle mainBundle] pathForResource:@"Resources"
                                     ofType:@"bundle"];

    if ([resourcesBundlePath length] > 0){

        NSBundle *resourcesBundle = [NSBundle bundleWithPath:resourcesBundlePath];

        if (resourcesBundle != nil){

            NSString *pathToAlanSugarImage =
            [resourcesBundle pathForResource:@"AlanSugar"
                                     ofType:@"png"
                               inDirectory:@"Images"];

            if ([pathToAlanSugarImage length] > 0){
```



```

UIImage *image = [UIImage imageWithContentsOfFile:pathToAlanSugarImage];

if (image != nil){
    NSLog(@"Successfully loaded the image from the bundle.");
} else {
    NSLog(@"Failed to load the image.");
}

} else {
    NSLog(@"Failed to find the file inside the bundle.");
}

} else {
    NSLog(@"Failed to load the bundle.");
}

} else {
    NSLog(@"Could not find the bundle.");
}

self.window = [[UIWindow alloc] initWithFrame:
                [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

If you are attempting to find all the resources which are stored in a specific folder inside a bundle, you can use the `pathsForResourceOfType:inDirectory:` method of the `NSBundle` class. In this code, we will attempt to find the path to all the `.png` files inside the `Images` folder of our `Resources.bundle` bundle:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSString *resourcesBundlePath =
    [[NSBundle mainBundle] pathForResource:@"Resources"
                                         ofType:@"bundle"];

    if ([resourcesBundlePath length] > 0){

        NSBundle *resourcesBundle = [NSBundle bundleWithPath:resourcesBundlePath];

        if (resourcesBundle != nil){

            NSArray *PNGPaths = [resourcesBundle pathsForResourceOfType:@"png"
                                                                    inDirectory:@"images"];

            [PNGPaths
             enumerateObjectsUsingBlock:^(id obj, NSUInteger idx, BOOL *stop) {
                 NSLog(@"Path %lu = %@", (unsigned long)idx+1, obj);
             }];

        } else {

```

```

        NSLog(@"Failed to load the bundle.");
    }

    } else {
        NSLog(@"Could not find the bundle.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```



The `enumerateObjectsUsingBlock:` method of `NSArray` accepts a block object as its parameter. For more information about `enumerateObjectUsingBlock:` and the block object it accepts, please refer to [Recipe 1.25](#).

See Also

XXX

1.29 Sending Notifications with NSNotificationCenter

Problem

You want to broadcast an event in your app and allow any object that is willing to listen to it to take action, depending on the notification that you are broadcasting.

Solution

Use the `postNotificationName:object:userInfo:` method of the default notification center of type `NSNotificationCenter` to post a notification that carries an object (usually the object that fires the notification) and a user-info dictionary that can carry extra information about the notification and/or the object that fires the notification.

Discussion

Notification centers are dispatch centrals for *notification objects*. For instance, when the keyboard pops up anywhere while the user is inside your app, iOS will send a notification to your app. Any object inside your app willing to listen to this notification can add itself to the default notification center as an *observer* for that particular notification. Once your object's lifetime comes to an end, it must remove itself from the notification center's dispatch table. As a result, a notification is a message that gets broadcasted to observers through a notification center. A notification center is an instance of `NSNoti`

ficationCenter class. We retrieve the default notification center object using the defaultCenter class method of NSNotificationCenter.

Notifications are objects of type `NSNotification`. A notification object has a name (specified as `NSString`) and can carry two key pieces of information:




You can specify the name of your notifications yourself. You don't have to use an API for that. Just make sure that your notification names are unique enough that they won't clash with a system notification.

Sender Object

This is the instance of the object that fires the notification. The observer can access this object using the `object` instance method of the `NSNotification` class.

User-Info Dictionary

This is an optional dictionary that the sender object can create and send alongside a notification object. This dictionary usually contains more information about the notification. For instance, when a keyboard is about to get displayed in iOS for any component inside your app, iOS sends the `UIKeyboardWillShowNotification` notification to the default notification center. The user-info dictionary of this notification contains values such as the rectangle of the keyboard before and after animation and the animation duration of the keyboard. Using this data, an observer can make a decision as to, for instance, what to do with UI components that potentially will be obstructed once the keyboard gets displayed on the screen.



Notifications are a great way of implementing decoupled code. By that I mean, using notifications, you can get rid of completion handlers and delegation. However, there is one potential caveat about notifications: they are not delivered immediately. They are dispatched by notification centers, and the implementation of `NSNotificationCenter` is hidden from application programmers. Delivery might sometimes be delayed by a few milliseconds or in extreme cases (which I have never encountered) a few seconds. As a result, it is up to you to decide where to and where not to use notifications.

In order to construct a notification of type `NSNotification`, use the `notificationWithName:object:userInfo:` class method of `NSNotification` like so:



It is best to suffix your notification names with the word `Notification`. For instance, it is permitted to give your notification a name similar to `ResultOfAppendingTwoStrings`. However, it is better to give the name `ResultOfAppendingTwoStringsNotification`, as that clearly says what this name belongs to.

Let's have a look at an example. We'll simply take a first name and a last name, append them to create one string (first name + last name) and then broadcast the result using the default notification center. We will do that in the implementation of our app delegate as soon as the user launches our app:

```
#import "AppDelegate.h"

@implementation AppDelegate

@synthesize window = _window;

/* The notification name */
const NSString *ResultOfAppendingTwoStringsNotification =
    @"ResultOfAppendingTwoStringsNotification";

/* Keys inside the dictionary that our notification sends */
const NSString
    *ResultOfAppendingTwoStringsFirstStringInfoKey = @"firstString";

const NSString
    *ResultOfAppendingTwoStringsSecondStringInfoKey = @"secondString";

const NSString
    *ResultOfAppendingTwoStringsResultStringInfoKey = @"resultString";

- (BOOL) application:(UIApplication *)application
    didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSString *firstName = @"Anthony";
    NSString *lastName = @"Robbins";
    NSString *fullName = [firstName stringByAppendingString:lastName];

    NSArray *objects = [[NSArray alloc] initWithObjects:
        firstName,
        lastName,
        fullName,
        nil];

    NSArray *keys = [[NSArray alloc] initWithObjects:
        ResultOfAppendingTwoStringsFirstStringInfoKey,
        ResultOfAppendingTwoStringsSecondStringInfoKey,
        ResultOfAppendingTwoStringsResultStringInfoKey,
        nil];

    NSDictionary *userInfo = [[NSDictionary alloc] initWithObjects:objects
        forKeys:keys];

    NSNotification *notificationObject =
    [NSNotification
        notificationWithName:(NSString *)ResultOfAppendingTwoStringsNotification
        object:self
        userInfo:userInfo];

    [[NSNotificationCenter defaultCenter] postNotification:notificationObject];
```

```

self.window = [[UIWindow alloc] initWithFrame:
                [[UIScreen mainScreen] bounds]];
self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

Of course, you don't have to specify an object or a user-info dictionary for every notification that you wish to broadcast. However, if you are working with a team of developers on the same app or if you are writing a static library, I suggest that you fully document your notifications and clearly mention whether your notifications carry an object and/or an user-info dictionary with them. If they do, you must say what object each notification carries and what keys and values are inside the user-info dictionary. If you are planning on not sending an object or a user-info dictionary, then I suggest you use the `postNotificationName:object:` instance method of `NSBundle`. Specify a string that represents the name of your notification as the first parameter, and `nil` as the second parameter, which is the object that should be carried with the notification. Here is an example:

```

#import "AppDelegate.h"

@implementation AppDelegate

@synthesize window = _window;

/* The notification name */
const NSString *NetworkConnectivityWasFoundNotification =
    @"NetworkConnectivityWasFoundNotification";

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [[NSNotificationCenter defaultCenter]
     postNotificationName:(NSString *)NetworkConnectivityWasFoundNotification
     object:nil];

    self.window = [[UIWindow alloc] initWithFrame:
                    [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

See Also

XXX

1.30 Listening for Notifications Sent From NSNotificationCenter

Problem

You want to listen for different system and custom notifications broadcast using `NSNotificationCenter`.

Solution

Add your observer object to the notification center using the `addObserver:selector:name:object:` instance method of `NSNotificationCenter` before a notification is broadcast. To stop observing a notification, use the `removeObserver:name:object:` instance method of `NSNotificationCenter` and pass your observer object, then the name of the notification that you want to stop observing and the object that you originally subscribed to (this will be explained in detail in the Discussion section of this recipe).

Discussion

Any object can broadcast a notification and any object within the same app can opt into listening for notifications with specific names. Two notifications with the same name can be broadcast, but they must come from two different objects. For instance, you can have a notification with the name of `DOWNLOAD_COMPLETED` that gets fired from two classes, one being a download manager that downloads images from the internet and another being a download manager that downloads data from an accessory connected to the iOS device. An observer might be interested only in the notifications of this name coming from a specific object, for instance, the download manager that downloads data from the accessory. You can specify this source object (broadcaster) when you start listening for notifications, using the `object` parameter of the `addObserver:selector:name:object:` method of the notification center.

Here is a brief description of each of the parameters that the `addObserver:selector:name:object:` accepts:

`addObserver`

The object that will receive the notifications (observer).

`selector`

The selector (method) to be called on the observer when the notification is broadcast and received by the observer. This method takes a single argument of type `NSNotification`.

`name`

The name of the notification to observe.

object

Optionally specifies the source of the broadcast notification. If this parameter is nil, notifications of the specified name will be received by the observer regardless of which object broadcasts them. If this parameter is set, only the notifications of the specified name that are broadcast by the given object will be observed.

In [Recipe 1.29](#) we learned how to post notifications. Let's now try observing the notification that we learned to post there.

```
#import "AppDelegate.h"

@implementation AppDelegate

@synthesize window = _window;

/* The notification name */
const NSString *ResultOfAppendingTwoStringsNotification =
    @"ResultOfAppendingTwoStringsNotification";

/* Keys inside the dictionary that our notification sends */
const NSString
    *ResultOfAppendingTwoStringsFirstStringInfoKey = @"firstString";

const NSString
    *ResultOfAppendingTwoStringsSecondStringInfoKey = @"secondString";

const NSString
    *ResultOfAppendingTwoStringsResultStringInfoKey = @"resultString";

- (void) broadcastNotification{

    NSString *firstName = @"Anthony";
    NSString *lastName = @"Robbins";
    NSString *fullName = [firstName stringByAppendingString:lastName];

    NSArray *objects = [[NSArray alloc] initWithObjects:
        firstName,
        lastName,
        fullName,
        nil];

    NSArray *keys = [[NSArray alloc] initWithObjects:
        ResultOfAppendingTwoStringsFirstStringInfoKey,
        ResultOfAppendingTwoStringsSecondStringInfoKey,
        ResultOfAppendingTwoStringsResultStringInfoKey,
        nil];

    NSDictionary *userInfo = [[NSDictionary alloc] initWithObjects:objects
        forKeys:keys];

    NSNotification *notificationObject =
    [NSNotification
    notificationWithName:(NSString *)ResultOfAppendingTwoStringsNotification
    object:self
```

```

        userInfo:userInfo];

[[NSNotificationCenter defaultCenter] postNotification:notificationObject];
}

- (void) appendingIsFinished:(NSNotification *)paramNotification{
    NSLog(@"Notification is received.");
    NSLog(@"Notification Object = %@", [paramNotification object]);
    NSLog(@"Notification User-Info Dict = %@", [paramNotification userInfo]);
}

- (BOOL)          application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    /* Listen for the notification */
    [[NSNotificationCenter defaultCenter]
     addObserver:self
     selector:@selector(appendingIsFinished:)
     name:(NSString *)ResultOfAppendingTwoStringsNotification
     object:self];

    [self broadcastNotification];

    self.window = [[UIWindow alloc] initWithFrame:
                    [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

- (void)applicationWillTerminate:(UIApplication *)application{
    /* We no longer observe ANY notifications */
    [[NSNotificationCenter defaultCenter] removeObserver:self];
}

```

When you run this app, you will see something similar to the following printed to the console window:

```

Notification is received.
Notification Object = <AppDelegate: 0x7408490>
Notification User-Info Dict = {
    firstString = Anthony;
    resultString = AnthonyRobbins;
    secondString = Robbins;
}

```

As you can see, we are using the `removeObserver:` method of our notification center to remove our object as an observer of all notifications. There are different ways of removing your objects from the chain of observers. Either you can quit cold-turkey, as we have done here—that is, remove your object completely from observing any notification, or

you can remove your object from observing specific notifications at specific times during the lifetime of your application. If you want to specify the notifications from which you are removing your object from observing, simply call the `removeObserver:name:object:` method of your notification center and specify the name of the notification from which you are unsubscribing as well as (optionally) the object that was sending the notifications.

See Also

XXX

Implementing Controllers and Views

2.0 Introduction

We write iOS applications using the MVC architecture. MVC is an abbreviation for Model-View-Controller. These are the three main components of an iOS application from an architectural perspective. The model is the brain of the application. It does the calculations; it creates a virtual world for itself that can live without the views and controllers. In other words, think of a model as a virtual copy of your application, without a face!

Controllers in Xcode usually refer to view controllers. Think of view controllers as a bridge between the model and your views. A view is the *window* through which your users interact with your application. It displays what's inside the model most of the time, but in addition to that, it accepts users' interactions. Any interaction between the user and your application is sent to a view, which then can be captured by a view controller and sent to the model.

In this chapter, you will learn how the structure of iOS applications is created and how to use views and view controllers to create intuitive applications.



In this chapter, for most of the UI (User Interface) components that we create, we are using a Single View Application template in Xcode. Follow the instructions in [Recipe 1.1](#) but instead of a Page-Based Application, create a Single View Application. Make sure that your app is Universal, as opposed to iPhone or an iPad app. A Universal app can run on both iPhone and iPad.

2.1 Displaying Alerts with UIAlertView

Problem

You want to display a message to your users, in form of an alert to either ask them for confirmation, ask for their username and password or simply ask them to enter a simple text that you can use depending on your app's requirements.

Solution

Utilize UIAlertView.

Discussion

If you are an iOS user, you have most certainly already seen an alert view. [Figure 2-1](#) depicts an example of this:



Figure 2-1. An alert view telling the user that she needs an active internet connection

The best way to initialize an alert view is, of course, through using its designated initializer:

```
UIAlertView *alertView = [[UIAlertView alloc]
    initWithTitle:@"Title"
    message:@"Message"
    delegate:nil
    cancelButtonTitle:@"Cancel"
    otherButtonTitles:@"Ok", nil];

[alertView show];
```

When this alert view is displayed to the user, she will see something similar to that shown in [Figure 2-2](#):



Figure 2-2. A simple alert view displayed to the user

In order to display an alert view to the user, we use the alert view's `show` method. Let's have a look at the description for each one of the parameters that we passed to the initializer of the alert view:

title

This is the string that the alert view will display on the top when it is shown to the user. This string is *Title* in [Figure 2-2](#).

`message`

This is the actual message that gets displayed to the user. In [Figure 2-2](#), this message is set to *Message*.

`delegate`


This is the optional delegate object that we pass to the alert view. This object will then get notified whenever the alert's state changes, for instance, when the user taps on a button on the alert view. The object passed to this parameter must conform to the `UIAlertViewDelegate` protocol.

`cancelButtonTitle`

This is a string that will get assigned to the cancel button on an alert view. An alert view that has a cancel button usually asks the user for an action. If the user isn't comfortable with performing that action, he or she will press the cancel button. This button's title does *not* necessarily have to say *Cancel*. It is up to you to specify a title for this button. This parameter is optional.

`otherButtonTitles`

Any other buttons that you want to have appear on the alert view, you pass their titles here. Separate the titles with a comma and make sure you terminate the list of titles with a `nil` or as it's called, a sentinel. This parameter is optional.



It is possible to create an alert view without any buttons. An alert view without a button cannot be dismissed by the user so you, as the programmer, need to make sure this alert view will get dismissed automatically, for instance, 3 seconds after it is displayed. An alert view without any buttons that does not dismiss itself automatically gives a really poor user experience and not only will your app get low ratings on the App Store for blocking the UI from user-access, chances are that your app will get rejected by Apple.

Alert views can take various styles. The `UIAlertView` class has a property called `alertViewStyle` of type `UIAlertViewStyle`:

```
typedef enum {
    UIAlertViewStyleDefault = 0,
    UIAlertViewStyleSecureTextInput,
    UIAlertViewStylePlainTextInput,
    UIAlertViewStyleLoginAndPasswordInput
} UIAlertViewStyle;
```

Here is what each of these styles will do:

`UIAlertViewStyleDefault`

This is the default style of an alert view, as we saw in [Figure 2-2](#).

`UIAlertViewStyleSecureTextInput`

With this style, the alert view will contain a secure text field for secure text entry. For instance, if you are asking the user for her online banking credentials, then you can potentially use this style of alert view.

UIAlertViewStylePlainTextInput

Under this style, the alert view will display a non-secure text field to the user. This style is great if you simply want to ask the user for plain text entry, such as the user's phone number.

UIAlertViewStyleLoginAndPasswordInput

With this style, the alert view will display two text fields. One non-secure for user-name and another, a secure text field, for password.

Once you decide that you need to get notified when the user interacts with the alert view, it is time that you specify a delegate object to your alert view. This delegate must conform to the `UIAlertViewDelegate` protocol. The most important method defined in this protocol is the `alertView:clickedButtonAtIndex:` method which gets called as soon as the user taps on one of the buttons in the alert view. The button index is passed to you through the `clickedButtonAtIndex` parameter.

Let's, as an example, display an alert view to the user and ask whether she could be bothered to rate our app in the App Store. We will display two buttons on our alert view: Yes and No. In our alert view delegate, we will detect which button she tapped on and will take action accordingly.

Let's first implement two very simple methods that return the title of our two buttons:

```
- (NSString *) yesButtonTitle{
    return @"Yes";
}

- (NSString *) noButtonTitle{
    return @"No";
}
```

Now we need to make sure that we are conforming to the `UIAlertViewDelegate` protocol in our view controller:

```
#import <UIKit/UIKit.h>

@interface Displaying_Alerts_with UIAlertViewViewController
    : UIViewController <UIAlertViewDelegate>

@end
```

All good. The next step would be to create and display our alert view to the user:

```
- (void)viewDidAppear:(BOOL)animated{
    [super viewDidAppear:animated];

    self.view.backgroundColor = [UIColor whiteColor];

    UIAlertView *alertView = [[UIAlertView alloc]
                              initWithTitle:@"Rating"
                              message:@"Can you please rate our app?"
                              delegate:self
                              cancelButtonTitle:[self noButtonTitle]
                              otherButtonTitles:[self yesButtonTitle], nil];
```



```
[alertView show];  
}
```

So now, our alert view will look similar to that shown in [Figure 2-3](#):



Figure 2-3. An alert view with Yes and No buttons

Now we need a way to know whether the user selected the Yes or the No option in our alert view. For this, we will need to implement the `alertView:clickedButtonAtIndex:` method of our alert view delegate:

```

- (void)      alertView:(UIAlertView *)alertView
  clickedButtonAtIndex:(NSInteger)buttonIndex{

    NSString *buttonTitle = [alertView buttonTitleAtIndex:buttonIndex];

    if ([buttonTitle isEqualToString:[self yesButtonTitle]]){
        NSLog(@"User pressed the Yes button.");
    }
    else if ([buttonTitle isEqualToString:[self noButtonTitle]]){
        NSLog(@"User pressed the No button.");
    }
}

```

As you can see, we are using the `buttonTitleAtIndex:` method of `UIAlertView`. We pass the zero-based index of a button inside that alert view to this method and we will get the string that represents the title of that button, if any. Using this method, we can determine which button the user has tapped on. The index of that button will be passed to us as the `buttonIndex` parameter of the `alertView:clickedButtonAtIndex:` method but if you need the title of that button, you will then need to use the `buttonTitleAtIndex:` method of `UIAlertView`. That is it; job done!

You can also use an alert view to ask the user for text entry, for instance, if you would like to ask the user for their credit card number or their address. For this, as mentioned before, we need to use the `UIAlertViewStyleTextInput` alert view style. Here is an example:

```

- (void) viewDidAppear:(BOOL)animated{
    [super viewDidAppear:animated];

    UIAlertView *alertView = [[UIAlertView alloc]
        initWithTitle:@"Credit Card Number"
        message:@"Please enter your credit card number:"
        delegate:self
        cancelButtonTitle:@"Cancel"
        otherButtonTitles:@"Ok", nil];
    [alertView setAlertViewStyle:UIAlertViewStyleTextInput];

    /* Display a numerical keypad for this text field */
    UITextField *textField = [alertView textFieldAtIndex:0];
    textField.keyboardType = UIKeyboardTypeNumberPad;

    [alertView show];
}

```

If we run our app on the simulator now, we will get result similar to that shown here:



Figure 2-4. An alert view with plain text input

We did change the alert view's style to `UIAlertViewStylePlainTextInput` in this code but we did something else as well. We retrieved the reference to the first and the only text field that we knew we would have on the alert view after changing its style to `UIAlertViewStylePlainTextInput`, and we used that text field's reference to change the keyboard type of the text field. For more information about text fields, please refer to [Recipe 2.14](#).

In addition to a plain text entry, you can ask the user for secure text. You would normally use this if the text that the user is entering needs to be secured. For instance, if you are asking the user to enter her password. Here is an example:

```
- (void) viewWillAppear:(BOOL)animated{
    [super viewWillAppear:animated];

    UIAlertView *alertView = [[UIAlertView alloc]
                               initWithTitle:@"Password"
                               message:@"Please enter your password:"
                               delegate:self
                               cancelButtonTitle:@"Cancel"
                               otherButtonTitles:@"Ok", nil];

    [alertView setAlertViewStyle:UIAlertViewStyleSecureTextInput];
    [alertView show];
}
```



Figure 2-5. Secure text entry in an alert view

And as you can see, the style that we've chosen is `UIAlertViewStyleSecureTextInput`. This style is very similar to the `UIAlertViewStyleTextInput` style except that the text field is set to secure the entered text.

The next style which is quite useful displays two text fields. One for username and the other one for password. So, one plain text entry and the other one secure:

```
- (void) viewDidLoad:(BOOL)animated{
    [super viewDidLoad:animated];

    UIAlertView *alertView = [[UIAlertView alloc]
```

```

initWithTitle:@"Password"
message:@"Please enter your credentials:"
delegate:self
cancelButtonTitle:@"Cancel"
otherButtonTitles:@"Ok", nil];

[alertView setAlertViewStyle:UIAlertViewStyleLoginAndPasswordInput];
[alertView show];
}

```

And the results will look similar to that shown in [Figure 2-6](#):



Figure 2-6. Login and Password style of alert view

See Also

XXX

2.2 Creating and Using Switches with UISwitch

Problem

You would like to, through your UI, give your users the ability to turn an option on or off.

Solution

Use the UISwitch class.

Discussion

The UISwitch class provides an On/Off user control like the ones shown in [Figure 2-7](#) for Auto-Capitalization, Auto-Correction and so on...




Figure 2-7. UISwitch used in the Settings app on an iPhone

In order to create a switch, you can either use Interface Builder or you can simply create your instance in code. Let's do this through code. So, now the challenge is: finding the class where we have to place our code in. We need to place our code in a View Controller's class. We don't yet know what a View Controller really is but depending on the name of your project, the view controller's *.h* (header) file name ends with *...ViewController.h*. For instance, I have named my project *Creating and Using Switches with UISwitch* and the *.h* (header) file of my view controller is called *Creating_and_Using_Switches_with_UISwitchViewController.h*. Open that file now.

Let's create a property of type `UISwitch` and call it *mySwitch*:

```
#import <UIKit/UIKit.h>

@interface Creating_and_Using_Switches_with_UISwitchViewController
    : UIViewController

@property (nonatomic, strong) UISwitch *mySwitch;

@end
```

Now let's go to the view controller's implementation file (*.m* file) and synthesize our *mySwitch* property:

```
#import "Creating_and_Using_Switches_with_UISwitchViewController.h"

@implementation Creating_and_Using_Switches_with_UISwitchViewController

@synthesize mySwitch;

...
```

We are now in a place where we can go ahead and create our switch. Find the `viewDidLoad` method in your view controller's implementation file:

```
- (void)viewDidLoad{
    [super viewDidLoad];
}
```

Now let's create our switch and place it on our view controller's view:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    /* Make sure our view is white */
    self.view.backgroundColor = [UIColor whiteColor];

    /* Create the switch */
    self.mySwitch = [[UISwitch alloc] initWithFrame:
        CGRectMake(100, 100, 0, 0)];
    [self.view addSubview:self.mySwitch];
}
```

So we are allocating an object of type `UISwitch` and using the `initWithFrame:` initializer to initialize our switch. Note that the parameter that we have to pass to this method is of type `CGRect`. A `CGRect` denotes the boundaries of a rectangle using (x, y) position of the top left corner of the rectangle and the width and height of it. We can construct a `CGRect` using the `CGRectMake` inline method where the first two parameters passed to this method are the (x, y) positions and the next two are width and height of the rectangle.

After we've created the switch, we are simply adding it to our view controller's view.



In this example, we are changing the background color of our view controller's view to white (as opposed to the default Single View Application's gray background color), just to make our app look nicer.

Now let's run our app on iPhone Simulator and see what happens:



Figure 2-8. A switch placed on a view

As you can see, the switch's default state is off. We can change this by changing the value of the `on` property of the instance of `UISwitch`. Alternatively, you can call the `setOn:` method on the switch, as shown here:

```
[self.mySwitch setOn:YES];
```

We can also use the `setOn:animated:` method of the switch. The `animated` parameter accepts a boolean value. If this boolean value is set to `YES`, the change in the switch's state (from on to off or off to on) will be animated, just as if the user was interacting with it.

Obviously, you can read from the `on` property of the switch to find out if the switch is on or off at the moment. Alternatively, you can use the `isOn` method of the switch, as shown here:

```
if ([self.mySwitch isOn]){
    NSLog(@"The switch is on.");
} else {
    NSLog(@"The switch is off.");
}
```

If you want to get notified *when* the switch gets turned on or turned off, then you will need to add your class as the *target* for the switch, using the `addTarget:action:forControlEvents:` method of `UISwitch`, as shown here:

```
[self.mySwitch addTarget:self
                    action:@selector(switchIsChanged:)
                    forControlEvents:UIControlEventValueChanged];
```

And then we will go ahead and implement the `switchIsChanged:` method. Note that when the runtime calls this method for the `UIControlEventValueChanged` event of the switch, it will pass the switch as the parameter to this method so we can find out which switch has fired this event:

```
- (void) switchIsChanged:(UISwitch *)paramSender{
    NSLog(@"Sender is = %@", paramSender);

    if ([paramSender isOn]){
        NSLog(@"The switch is turned on.");
    } else {
        NSLog(@"The switch is turned off.");
    }
}
```

Now go ahead and run the app on iOS Simulator. You will see messages similar to this in the console window:

```
Sender is = <UISwitch: 0x6e13500;
    frame = (100 100; 79 27);
    layer = <CALayer: 0x6e13700>>
The switch is turned off.
Sender is = <UISwitch: 0x6e13500;
```

```
frame = (100 100; 79 27);  
layer = <CALayer: 0x6e13700>>  
The switch is turned on.
```

See Also

XXX

2.3 Picking Values with UIPickerView

Problem

You want to allow the users of your app to select from a list of values.

Solution

Use the UIPickerView class.

Discussion

A picker view is something that allows you to display series of values to your users and allow them to pick one. The Timer section of the Clock app on the iPhone is a great example of this:




Figure 2-9. A picker view on top of the screen

As you can see, this specific picker view has 2 *components*. One is on the left and one is on the right. The left component is displaying hours (such as 0 hours, 1, 2, etc) and the component on the right is displaying minutes such as (18, 19, 20 mins, 21, 22, etc). So these two items (one on the left and the other on the right) are called *components*. Each component has rows. Any item in any of the components is in fact represented by a row, as we will soon see. For instance, 0 hours, 1 and 2 are, each and all, rows in the left component.

Let's go ahead and create a picker view on our view controller's view. If you don't know where your view controller's source code is, please have a look at the [Recipe 2.2](#) recipe where this subject is discussed.

First let's go to the *.h* (header) file of our view controller and define our picker view:

```
#import <UIKit/UIKit.h>

@interface Picking_Values_with_UIPickerViewController
: UIViewController
```

```
@property (nonatomic, strong) UIPickerView *myPicker;

@end
```

Then we will synthesize it in the *.m* (implementation) file of our view controller:

```
#import "Picking_Values_with_UIPickerViewController.h"

@implementation Picking_Values_with_UIPickerViewController

@synthesize myPicker;

...
```

Now let's go ahead and create the picker view in the `viewDidLoad` method of our view controller:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myPicker = [[UIPickerView alloc] init];
    self.myPicker.center = self.view.center;
    [self.view addSubview:self.myPicker];
}
```

It's worth noting that in this example, we are centering our picker view at the center of our view so when you run this app, you will see something similar to that shown in [Figure 2-10](#):




Figure 2-10. An unpopulated and empty picker with its default black color

The reason this picker view is showing up as plain black color is that we have not yet populated with any value. Let's do that. We do that by specifying a data source for the picker view and then making sure that our view controller sticks to the protocol that the data source requires. The data source of an instance of `UIPickerView` must conform to the `UIPickerViewDataSource` protocol, so, let's go ahead and make our view controller conform to this protocol, in the `.h` file:

```
#import <UIKit/UIKit.h>

@interface Picking_Values_with_UIPickerViewController
```

```

        : UIViewController <UIPickerViewDataSource>

@property (nonatomic, strong) UIPickerView *myPicker;

@end

```

Good. Let's now change our code in the implementation file to make sure we elect the current view controller as the data source of the picker view:

```

- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myPicker = [[UIPickerView alloc] init];
    self.myPicker.dataSource = self;
    self.myPicker.center = self.view.center;
    [self.view addSubview:self.myPicker];
}

```

After this, if you try to compile your application, you will see that you are getting warnings from the compiler. These warnings are telling you that you have *not* yet implemented some of the methods which the UIPickerViewDataSource protocol wants you to implement. The way to fix this is to go back to our *.h* (header) file, hold down the Command key and then click on the UIPickerViewDataSource text. At this moment, you will be sent to where this protocol is defined, where you will see something similar to this:

```

@protocol UIPickerViewDataSource<NSObject>
@required

// returns the number of 'columns' to display.
- (NSInteger)numberOfComponentsInPickerView:(UIPickerView *)pickerView;

// returns the # of rows in each component..
- (NSInteger)pickerView:(UIPickerView *)pickerView
    numberOfRowsInComponent:(NSInteger)component;
@end

```

Can you see the **@required** keyword there? That is telling us that whichever class wants to become the data source of a picker view *must* implement these methods. Good deal. Let's go implement them in our view controller's implementation file:

```

- (NSInteger)numberOfComponentsInPickerView:(UIPickerView *)pickerView{

    NSInteger result = 0;
    if ([pickerView isEqual:self.myPicker]){
        result = 1;
    }
    return result;
}

- (NSInteger) pickerView:(UIPickerView *)pickerView

```



```

        numberOfRowsInComponent:(NSInteger)component{

        NSInteger result = 0;
        if ([pickerView isEqual:self.myPicker]){
            result = 10;
        }
        return result;
    }
}

```

So what is happening here? Let's have a look at what each one of these data source methods expect:

numberOfComponentsInPickerView:

This method passes you a picker view object as its parameter and expect you to return an integer, telling the runtime how many components you would like that picker view to render.

pickerView:numberOfRowsInComponent:

For each component that gets added to a picker view, you will need to tell the system about the number of rows that you would like to render in that component. This method passes you an instance of picker view and you will need to return an integer to it, telling the runtime how many rows you want the system to render for that component.

So in this case, we are asking the system to display 1 component with 10 rows only for a picker view which we have created before, called `myPicker`.

Compile and run your application on the iPhone Simulator. Ewww, what is that?




Figure 2-11. A picker view, not knowing what to render

It looks like our picker view knows how many components it should have and how many rows it should render in that component but what it doesn't know is *what text* to display for each row. That is something we need to do now and we do that by providing a delegate to the picker view. The delegate of an instance of `UIPickerView` has to conform to the `UIPickerViewDelegate` protocol and implement all the `@required` methods of that protocol. Let's start with our view controller's header file:

```
@interface Picking_Values_with_UIPickerViewController
    : UIViewController
    <UIPickerViewDataSource, UIPickerViewDelegate>
```

```
@property (nonatomic, strong) UIPickerView *myPicker;

@end
```

There is only one method in the `UIPickerViewDelegate` which we are interested in and that is the `pickerView:titleForRow:forComponent:` method. This method will pass you the index of the current section and the index of the current row in that section for a picker view and it expects you to return an instance of `NSString`. This string will then get rendered for that specific row inside the component. In here, I would simply like to display the first row as Row 1, and then continue to Row 2, Row 3 till the end. Remember, we also have to set the `delegate` property of our picker view:

```
self.myPicker.delegate = self;
```

And now we will handle the delegate method which we just learned about:

```
- (NSString *)pickerView:(UIPickerView *)pickerView
    titleForRow:(NSInteger)row
    forComponent:(NSInteger)component{

    NSString *result = nil;
    if ([pickerView isEqual:self.myPicker]){

        /* Row is zero-based and we want the first row (with index 0)
           to be rendered as Row 1 so we have to +1 every row index */
        result = [NSString stringWithFormat:@"Row %ld", (long)row + 1];

    }
    return result;
}
```

Now let's run our app and see what happens:




Figure 2-12. A picker view with one section and a few rows

All good? If you now refer back to [Figure 2-9](#) you will notice a horizontal bar running across the picker view. It turns out `UIPickerView` has a property called `showsSelectionIndicator` which by default is set to `NO`. You can either directly set the value of this property to `YES` or use the `setShowsSelectionIndicator:` method of the picker view to turn this indicator on:

```
self.myPicker.showsSelectionIndicator = YES;
```

And now we will run our app in iOS Simulator and see how it is looking:




Figure 2-13. A picker view with selection indicator

Now imagine that you have create this picker view in your final application. What is the use of a picker view if we cannot detect what the user has actually selected in each one of its components? Well, it's good that Apple has already thought of that and given us the ability to ask the picker view about this. We can call the **`selectedRowInComponent:`** method of a **`UIPickerView`** and pass the zero-based index of a component to get an integer back and this integer will be the zero-based index of the row which is currently selected in that component.

If at runtime, you need to modify the values in your picker view, you need to make sure that your picker view reloads its data from its data source and delegate. To do that, you can either force all the components to reload their data, using the `reloadAllComponents` or you can ask a specific component to reload its data, using the `reloadComponent:` method and passing the index of the component that has to be reloaded.

See Also

XXX

2.4 Picking Date and Time with UIDatePicker

Problem

You want to allow the users of your app to select date and time using an intuitive and read-made user interface

Solution

Use the `UIDatePicker` class.

Discussion

The `UIDatePicker` is very similar to the `UIPickerView` class. The date picker is in fact a pre-populated picker view. A good example of the date picker control is in the Calendar app on the iPhone:



Figure 2-14. A date picker shown at the bottom of the screen

Let's get started by first declaring a property of type `UIDatePicker` and then allocating and initializing this property and adding it to the view of our view controller:

```
#import <UIKit/UIKit.h>

@interface Picking_Date_and_Time_with_UIDatePickerViewController
    : UIViewController

@property (nonatomic, strong) UIDatePicker *myDatePicker;

@end
```

Let's synthesize the property now:

```
#import "Picking_Date_and_Time_with_UIDatePickerViewController.h"

@implementation Picking_Date_and_Time_with_UIDatePickerViewController

@synthesize myDatePicker;
```

...

And now let's instantiate the date picker, as planned:

```
- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.myDatePicker = [[UIDatePicker alloc] init];
    self.myDatePicker.center = self.view.center;
    [self.view addSubview:self.myDatePicker];
}
```

Now let's run the app and see how it looks like:



Figure 2-15. A simple date picker

You can see that the date picker, by default, has picked today's date. The first thing that we need to know about date pickers is that they can have different styles or modes. This mode can be changed through the `datePickerMode` property which is of type `UIDatePickerMode`:

```
typedef enum {
    UIDatePickerModeTime,
    UIDatePickerModeDate,
    UIDatePickerModeDateAndTime,
    UIDatePickerModeCountDownTimer,
} UIDatePickerMode;
```

Depending on what you need, you can set the mode of your date picker to any of the values listed in the `UIDatePickerMode` enumeration.

Now that you have successfully displayed a date picker on the screen, you can attempt to retrieve its currently-selected date using its `date` property or alternatively, you can call the `date` method on the date picker, like so:

```
NSDate *currentDate = self.myDatePicker.date;
NSLog(@"Date = %@", currentDate);
```

Just like the `UISwitch` class, a date picker also sends action messages to its targets whenever the selection of date in it has changed. To respond to these messages, the receiver must add itself as the *target* of the date picker, using the `addTarget:action:forControlEvents:` method, like so:

```
- (void) datePickerDateChanged:(UIDatePicker *)paramDatePicker{

    if ([paramDatePicker isEqual:self.myDatePicker]){
        NSLog(@"Selected date = %@", paramDatePicker.date);
    }

}

- (void) viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.myDatePicker = [[UIDatePicker alloc] init];
    self.myDatePicker.center = self.view.center;
    [self.view addSubview:self.myDatePicker];

    [self.myDatePicker addTarget:self
                        action:@selector(datePickerDateChanged:)
                        forControlEvents:UIControlEventValueChanged];

}
```

Now ever time the date changes, you will get a message from the date picker.

With date picker, you also have the ability to set the minimum and the maximum dates that can be displayed in a date picker. For this, let's first switch our date picker mode to `UIDatePickerModeDate` and then using the `maximumDate` and the `minimumDate` properties, adjust this range:

```
- (void) viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.myDatePicker = [[UIDatePicker alloc] init];
    self.myDatePicker.center = self.view.center;
    self.myDatePicker.datePickerMode = UIDatePickerModeDate;
    [self.view addSubview:self.myDatePicker];

    NSTimeInterval oneYearTime = 365 * 24 * 60 * 60;
    NSDate *todayDate = [NSDate date];
```

```
NSDate *oneYearFromToday = [todayDate
                             dateByAddingTimeInterval:oneYearTime];

NSDate *twoYearsFromToday = [todayDate
                              dateByAddingTimeInterval:2 * oneYearTime];

self.myDatePicker.minimumDate = oneYearFromToday;
self.myDatePicker.maximumDate = twoYearsFromToday;
}
```

So with these two properties, we can then limit the user's selection on the date to a specific range, as shown in [Figure 2-16](#). In this example code, we have limited the user's input of the dates to the range of a year to two years from now. So suppose the current date is 01/Jan/2012. With this code, the user can only select a date between 01/Jan/2013 and 01/Jan/2014.



Figure 2-16. Minimum and maximum dates applied to a date picker

If you want to use the date picker as a countdown timer, then you must set your date picker mode to `UIDatePickerModeCountDownTimer` and use the `countDownDuration` property of the date picker to specify the default countdown duration. For instance, if you want to present a countdown picker to the user and set the default countdown duration to 2 minutes, you would write your code like this:

```
- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.myDatePicker = [[UIDatePicker alloc] init];
```

```

self.myDatePicker.center = self.view.center;
self.myDatePicker.datePickerMode = UIDatePickerModeCountDownTimer;
[self.view addSubview:self.myDatePicker];

NSTimeInterval twoMinutes = 2 * 60;
[self.myDatePicker setCountDownDuration:twoMinutes];
}

```

And the results are shown in [Figure 2-17](#):



Figure 2-17. A two minute countdown duration set on a date picker

See Also

XXX

2.5 Implementing Range Pickers with UISlider

Problem

You would like to allow your users to specify a value within a range, using an easy-to-use and intuitive UI.

Solution

Use the `UISlider` class.

Discussion

You've certainly seen sliders before. Here is an example:




Figure 2-18. The volume slider at the bottom of the screen

We instantiate objects of type `UISlider` to create sliders. Let's dive right in and create a slider and place it on our view controller's view. Let's start with our view controller's header file:

```
#import <UIKit/UIKit.h>

@interface Implementing_Range_Pickers_with_UISliderViewController
: UIViewController

@property (nonatomic, strong) UISlider *mySlider;

@end
```

And then let's synthesize the `mySlider` property:

```
#import "Implementing_Range_Pickers_with_UISliderViewController.h"

@implementation Implementing_Range_Pickers_with_UISliderViewController
```

```
@synthesize mySlider;
```

```
...
```

And now let's go to the `viewDidLoad` method and create our slider component. In this code, we are going to ask our slider to have a range between 0 to 100 and we want the default position of the slider to be half way to the end.



Range of a slider has *nothing* to do with its appearance. We use the range specifiers of a slider to tell the slider to calculate its value based on the range. For instance, if the range of a slider is provided as 0 to 100, when the knob on the slider is to the leftmost part, the `value` property of the slider would be 0 and if the knob is to the rightmost side of the slider, the `value` property would be 100.

```
- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.mySlider = [[UISlider alloc] initWithFrame:CGRectMake(0.0f,
                                                                0.0f,
                                                                200.0f,
                                                                23.0f)];

    self.mySlider.center = self.view.center;
    self.mySlider.minimumValue = 0.0f;
    self.mySlider.maximumValue = 100.0f;
    self.mySlider.value = self.mySlider.maximumValue / 2.0;
    [self.view addSubview:self.mySlider];
}
```

What do the results look like? You can now run the app on the simulator and you'll get results like that shown in [Figure 2-19](#):




Figure 2-19. A simple slider at the center of the screen

We used a few properties of the slider to get the results we wanted. What were they?

minimumValue

Specifies the minimum value of the range that the slider should support.

maximumValue

Specifies the maximum value that the slider should support.

value

The current value of the slider. This is a readwrite property, meaning that you can both read from it and write to it. If you want the slider's knob to be moved to this

value in an animated mode, you can call the `setValue:animated:` method of the slider and pass `YES` as the `animated` parameter.



The little knob on a slider is called *thumb*. We will soon see how we can customize the slider and I will be using the term *thumb* to describe the knob on the slider so please keep that in mind.

If you wish to receive an event whenever the slider's thumb has moved, you must add your object as the target of the slider, using the slider's `addTarget:action:forControlEvents:` method:

```
- (void) sliderValueChanged:(UISlider *)paramSender{

    if ([paramSender isEqual:self.mySlider]){
        NSLog(@"New value = %f", paramSender.value);
    }
}

- (void) viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.mySlider = [[UISlider alloc] initWithFrame:CGRectMake(0.0f,
                                                                0.0f,
                                                                200.0f,
                                                                23.0f)];

    self.mySlider.center = self.view.center;
    self.mySlider.minimumValue = 0.0f;
    self.mySlider.maximumValue = 100.0f;
    self.mySlider.value = self.mySlider.maximumValue / 2.0;
    [self.view addSubview:self.mySlider];

    [self.mySlider addTarget:self
                    action:@selector(sliderValueChanged:)
                    forControlEvents:UIControlEventValueChanged];
}
```

If you run the application on the simulator now, you will notice that the `sliderValueChanged:` target method gets called *whenever and as soon as* the slider's thumb moves. This might be what you want but in some cases, you might need to get notified only after the user has let go of the thumb on the slider and let it settle. In that case, you must set the `continuous` property of the slider to `NO`. This property, when set to `YES` (it's default value), will call the slider's targets continuously *as* the thumb moves.

iOS SDK also gives us the ability to modify how a slider looks like. For instance, the thumb on the slider can have a different image. To change the image of the thumb, simply use the `setThumbImage:forState:` method and pass an image and a second parameter which can be any of these values:

`UIControlStateNormal`

The normal state of the thumb, with no user finger on this component.

`UIControlStateHighlighted`

The image that has to be displayed for the thumb while the user is moving her finger on this component.

I have prepared two images: one for the normal state of the thumb and the other one for the highlighted (touched) state of the thumb. Let's go ahead and add them to the slider:

```
[self.mySlider setThumbImage:[UIImage imageNamed:@"ThumbNormal.png"]
                    forState:UIControlStateNormal];
[self.mySlider setThumbImage:[UIImage imageNamed:@"ThumbHighlighted.png"]
                    forState:UIControlStateHighlighted];
```

And now let's have a look and see how it looks like in the simulator:




Figure 2-20. A slider with a custom thumb image

See Also

XXX

2.6 Grouping Compact Options with UISegmentedControl

Problem

You would like to present a few options to your users from which they can pick one and you would like the UI to be compact, simple and easy to understand.

Solution

Use the `UISegmentedControl` class, an example of which is shown in [Figure 2-21](#).



Figure 2-21. A segmented control displaying 4 options

Discussion

A segmented control is a UI component that allows us to display, in a compact UI, series of options for the user to choose from. We create an instance of `UISegmentedControl` in order to instantiate a segmented control. Let's start with our view controller's `.h` file:

```
#import <UIKit/UIKit.h>

@interface Grouping_Compact_Options_with_UISegmentedViewController
```

```

        : UIViewController

@property (nonatomic, strong) UISegmentedControl *mySegmentedControl;

@end

```

Now let's go ahead and synthesize the `mySegmentedControl` property:

```

#import "Grouping_Compact_Options_with_UISegmentedControlViewController.h"

@implementation
    Grouping_Compact_Options_with_UISegmentedControlViewController

@synthesize mySegmentedControl;

...

```

And now let's create the segmented control in the `viewDidLoad` method of our view controller:

```

- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    NSArray *segments = [[NSArray alloc] initWithObjects:
        @"iPhone",
        @"iPad",
        @"iPod",
        @"iMac", nil];

    self.mySegmentedControl = [[UISegmentedControl alloc]
        initWithItems:segments];
    self.mySegmentedControl.center = self.view.center;
    [self.view addSubview:self.mySegmentedControl];
}

```

We are simply using an array of string to provide the different options that our segmented control has to display. We initialize our segmented control using the `initWithObjects:` initializer and pass the array of strings and images to the segmented control. The results will look like what we saw in [Figure 2-21](#).

Now the user will have the ability to pick *one* of the options in the segmented control. Let's say she has picked *iPad*. The segmented control will then change its user interface to show the user what option she has selected, as depicted in [Figure 2-22](#).



Figure 2-22. User has selected one of the items in a segmented control

Now the question is, how do we recognize when the user selects a new option in a segmented control? The answer is simple. Just like a `UISwitch` or a `UISlider`, we will use the `addTarget:action:forControlEvents:` method of the segmented control to add a target to it. We will provide the value of `UIControlEventValueChanged` for the `forControlEvents` parameter because that is the event that gets fired when the user selects a new option in a segmented control:

```
- (void) segmentChanged:(UISegmentedControl *)paramSender{  
    if ([paramSender isEqual:self.mySegmentedControl]){  
        NSInteger selectedSegmentIndex = [paramSender selectedSegmentIndex];
```



```

NSString *selectedSegmentText =
    [paramSender titleForSegmentAtIndex:selectedSegmentIndex];

NSLog(@"Segment %ld with %@ text is selected",
      (long)selectedSegmentIndex,
      selectedSegmentText);
}
}

- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    NSArray *segments = [[NSArray alloc] initWithObjects:
        @"iPhone",
        @"iPad",
        @"iPod",
        @"iMac", nil];

    self.mySegmentedControl = [[UISegmentedControl alloc]
        initWithItems:segments];
    self.mySegmentedControl.center = self.view.center;
    [self.view addSubview:self.mySegmentedControl];

    [self.mySegmentedControl addTarget:self
        action:@selector(segmentChanged:)
        forControlEvents:UIControlEventValueChanged];
}

```

If the user starts from the left side and selects each one of the options in [Figure 2-21](#) all the way to the right side of the control, we will get the following text printed out to the console:

```

Segment 0 with iPhone text is selected
Segment 1 with iPad text is selected
Segment 2 with iPod text is selected
Segment 3 with iMac text is selected

```

As you can see, we used the `selectedSegmentIndex` method of the segmented control to find the index of the currently selected item. If no item is selected, this method will return the value of -1 to us. We also used the `titleForSegmentAtIndex:` method. We simply pass the index of an option in the segmented control to this method and the segmented control will return the text for that item. Simple, isn't it?

As you might have noticed, once the user selects an option in a segmented control, that option will get selected and will *remain* selected, as shown in [Figure 2-22](#). If you want the user to be able to select an option but you would like the button for that option to bounce back to its original shape once it has been selected (just like a normal button that bounces back up once it is tapped), then you need to set the `momentary` property of the segmented control to YES:

```

self.mySegmentedControl.momentary = YES;

```

One of the really neat features of segmented controls is that they can contain images instead of text. To do this, simply use the `initWithObjects:` initializer and pass images and strings as parameter to this method, like so:

```
- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    NSArray *segments = [[NSArray alloc] initWithObjects:
        @"iPhone",
        [UIImage imageNamed:@"iPad.png"],
        @"iPod",
        @"iMac", nil];

    self.mySegmentedControl = [[UISegmentedControl alloc]
        initWithItems:segments];

    CGRect segmentedFrame = self.mySegmentedControl.frame;
    segmentedFrame.size.height = 64.0f;
    segmentedFrame.size.width = 300.0f;
    self.mySegmentedControl.frame = segmentedFrame;

    self.mySegmentedControl.center = self.view.center;

    [self.view addSubview:self.mySegmentedControl];
}
```



In this example, the *iPad.png* file is simply an image of an iPad, with resolution of 36x47 pixels.

The results are shown here:



Figure 2-23. A segmented control with an option displayed as an image

One of the features of segmented controls is that we can select their style using the `segmentedControlStyle` property. This property is of type `UISegmentedControlStyle`:

```
typedef enum {
    UISegmentedControlStylePlain,
    UISegmentedControlStyleBordered,
    UISegmentedControlStyleBar,
    UISegmentedControlStyleBezeled,
} UISegmentedControlStyle;
```

The default style of a segmented control is `UISegmentedControlStylePlain`. You can go ahead and change the style of your segmented controls to any of the values listed in the `UISegmentedControlStyle` enumeration. Here is an example of a Bezeled segmented control:




Figure 2-24. A beveled segmented control

See Also

XXX

2.7 Presenting and Managing Views with UIViewController

Problem

You want to manage different views in your application.

Solution

Use the `UIViewController` class.

Discussion

Apple's strategy for iOS development was to use MVC. MVC is Model-View-Controller. Views are what get displayed to users, model is the data that the app manages, the engine of the app in other words. The controller is the bridge between the model and the view. The controller, or in this case, view controller, manages the relationship between the view and the model. Why doesn't the view do that instead? Well the answer is quite simple: the view's code will get messy and that process will tightly couple our views with the model which is not a good practice.



You need to have an Xcode project already created. Follow the instructions in [Recipe 1.1](#) but instead of a Pages-Based Application, create an Empty Application.

View controllers can be loaded from *.xib* files (for use with Interface Builder), or they can simply be created programmatically. We will first have a look at creating a view controller *without* a *.xib* file.

Xcode helps us create view controllers. Now that you have created an application using the Empty Application template in Xcode, follow these steps to create a new view controller *without* a *.xib* file, for your app:

1. In Xcode, select the File menu and then choose New→New File...
2. In the New File dialog, make sure iOS is the selected category on left and that Cocoa Touch is the chosen sub-category. Once you've done that, select UIViewController subclass from the right hand side of the dialog and then press Next, as shown in [Figure 2-25](#).




Figure 2-25. New view controller subclass

3. In the next screen, make sure that the Subclass of text field says `UIViewController` and also make sure neither the Targeted for iPad, nor the With XIB for user interface check boxes are selected, as shown in Figure 2-26. Press Next.




Figure 2-26. A custom view controller with no xib file

4. On the next screen (Save As), give your view controller's file the name of *RootViewController* and press the Save button, as shown in [Figure 2-27](#).




Figure 2-27. Saving a view controller without an xib file

1. Now find your application delegate's *.h* file. I have named my project *Presenting and Managing Views with UIViewController* and because of this, my application delegate's class is called *Presenting_and_Managing_Views_with_UINavigationControllerAppDelegate*. The *.h* file of my app delegate is therefore *Presenting_and_Managing_Views_with_UINavigationControllerAppDelegate.h*. In this file, declare a property of type *RootViewController*:

```
#import <UIKit/UIKit.h>

@class RootViewController;

@interface Presenting_and_Managing_Views_with_UINavigationControllerAppDelegate :
    UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) RootViewController *rootViewController;

@end
```

2. Then we need to synthesize the view controller in the *.m* file of our application delegate:

```
#import "Presenting_and_Managing_Views_with_UINavigationControllerAppDelegate.h"
#import "RootViewController.h"

@implementation
    Presenting_and_Managing_Views_with_UINavigationControllerAppDelegate
```

```
@synthesize window = _window;
@synthesize rootViewController;
```

...

3. Now find the `application:didFinishLaunchingWithOptions:` method of the app delegate, inside the implementation (*.m*) file, and instantiate the view controller and add it to our window:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.window = [[UIWindow alloc]
                    initWithFrame:[UIScreen mainScreen] bounds]];

    [self.window makeKeyAndVisible];

    self.rootViewController = [[RootViewController alloc]
                                initWithNibName:nil
                                bundle:NULL];
    [self.window addSubview:self.rootViewController.view];

    return YES;
}
```



We add the *view of the view controller* to the window, *not* the view controller itself.

Now if you run your app on the simulator, you will see a black screen. The reason is that our view controller's view doesn't have a background color yet so go to the *RootViewController.m* file and find the `viewDidLoad` method which is in a state similar to this:

```
/*
- (void)viewDidLoad
{
    [super viewDidLoad];
}
*/
```

Remove the comment lines from around this method:

```
- (void)viewDidLoad{
    [super viewDidLoad];
}
```

Now let's set the background color of our view controller's view to white:

```
- (void)viewDidLoad{
    [super viewDidLoad];
```



```

        self.view.backgroundColor = [UIColor whiteColor];
    }

```

Go ahead and run the app on the simulator. You will now see a plain white view on the screen. Congratulations, you just created a view controller and now you have access to the view controller and its view object.

While creating the view controller (Figure 2-26), if you had selected the With XIB for user interface checkbox, then Xcode would have also generated an *.xib* file for you. In such case, we would have to load our view controller *from* that *.xib* file by passing the *.xib* file's full name to the `initWithNibName:bundle:` method of the view controller, like so:

```

- (BOOL) application:(UIApplication *)application
  didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.window = [[UIWindow alloc]
                   initWithFrame:[UIScreen mainScreen] bounds]];

    [self.window makeKeyAndVisible];

    self.rootViewController = [[RootViewController alloc]
                               initWithNibName:@"RootViewController"
                               bundle:NULL];
    [self.window addSubview:self.rootViewController.view];

    return YES;
}

```

If you *did* create a *.xib* file while creating your view controller, you can now select on that file in Xcode and design your user interface with Interface Builder.

See Also

XXX

2.8 Implementing Navigation with UINavigationController

Problem

You would like to allow your users to move from one view controller to the other with a smooth and built-in animation.

Solution

Use UINavigationController.

Discussion

If you've used an iPhone, iPod Touch or an iPad before, chances are that you have already seen a navigation controller in action. For instance, if you go to the Settings app on your phone and then press an option such as Wallpaper (Figure 2-28), you will see the Settings' main screen get pulled out of the screen from the left and the Wallpaper screen pushing its way into the screen from the right. That is the magic of navigation controllers. They allow you to *push* and *pop* view controllers, where pushing a view controller means pushing it into the stack of view controllers and popping a view controller means removing that view controller from the stack. The view controller on top of the stack is the top view controller and that is the view controller which the user sees at any given moment. So we can conclude that only the top view controller gets displayed to the user unless that view controller is popped or another view controller is pushed onto the stack in which case the new view controller becomes the top view controller and the one getting displayed to the user.



Figure 2-28. Settings view controller pushing the Wallpaper view controller

Now we are going to add a navigation controller to our project but we need a project first. Please follow the instructions in [Recipe 2.7](#) to create an empty application with a simple view controller. In this recipe we will expand on the recipe in [Recipe 2.7](#). Let's start with the *.h* file of our app delegate:

```
#import <UIKit/UIKit.h>

@class RootViewController;

@interface Implementing_Navigation_with_UINavigationControllerAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) UINavigationController *navigationController;
@property (nonatomic, strong) RootViewController *rootViewController;

@end
```

And then we need to make sure we have synthesized our navigation controller's property:

```
#import "Implementing_Navigation_with_UINavigationControllerAppDelegate.h"
#import "RootViewController.h"

@implementation
    Implementing_Navigation_with_UINavigationControllerAppDelegate

    @synthesize window = _window;
    @synthesize navigationController;
    @synthesize rootViewController;

    ...
end
```

Now we have to initialize our navigation controller using its `initWithRootViewController:` method and pass our root view controller as its parameter. Then we will add the navigation controller's view to the window:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.window = [[UIWindow alloc]
        initWithFrame:[[UIScreen mainScreen] bounds]];

    [self.window makeKeyAndVisible];

    self.rootViewController = [[RootViewController alloc]
        initWithNibName:nil
        bundle:NULL];

    self.navigationController =
    [[UINavigationController alloc]
        initWithRootViewController:self.rootViewController];

    [self.window addSubview:self.navigationController.view];
}
```

```
    return YES;  
}
```

Now let's run our app in the simulator:




Figure 2-29. An empty view controller displayed inside a navigation controller

The first thing you might notice in [Figure 2-29](#) is the bar on top of the screen. The screen isn't plain white anymore. There is a bar on top. What is that, you might ask? Well, that is a navigation bar. We will be using that bar a lot for navigation, placing buttons there and etc. That bar is also capable of displaying a title. Each view controller specifies a title for itself and the navigation controller will automatically display that

title once the view controller is pushed into the stack. Let's go to our root view controller's implementation file and inside the `viewDidLoad` method set the `title` property of our view controller to *First Controller*:

```
- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.title = @"First Controller";
}
```

Run the app again and you will see something similar to that shown in [Figure 2-30](#):



Figure 2-30. A view controller with title

Now let's go and create a second view controller, *without* a *.xib* file, and call it *SecondViewController*. Follow the same process that you learnt in [Recipe 2.7](#). Once you are done creating this view controller, give it a title of *Second Controller*.

```
#import "SecondViewController.h"

@implementation SecondViewController

- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.title = @"Second Controller";
}

...
```

Our plan is to *push* the second view controller on top of the first view controller 5 seconds after the first view controller appears on the screen so let's first import the second view controller in the first one:

```
#import "RootViewController.h"
#import "SecondViewController.h"

@implementation RootViewController

...
```

Now go back to the implementation of the root view controller and code the `viewDidAppear:` like this:

```
- (void) pushSecondController{
    SecondViewController *secondController = [[SecondViewController alloc]
                                              initWithNibName:nil
                                              bundle:NULL];

    [self.navigationController pushViewController:secondController
                                             animated:YES];
}

- (void) viewDidAppear:(BOOL)paramAnimated{
    [super viewDidAppear:paramAnimated];
    [self performSelector:@selector(pushSecondController)
                    withObject:nil
                    afterDelay:5.0f];
}
```

We are using the `performSelector:withObject:afterDelay:` method of `NSObject` to call our new method `pushSecondController` 5 seconds after our first view controller successfully displays its view. In the `pushSecondController` method we are simply using the `navigationController` property of our view controller (this is built into `UIViewController` and is *not* something that *we* coded) to push an instance of `SecondViewController` into the stack of view controllers. The result? Similar to what you can see in [Figure 2-31](#).



Figure 2-31. A view controller is pushed on top of another one

You can see that the navigation bar is displaying the title of the top view controller and it even displays a back button which will take the user back to the previous view controller. You can push as many view controllers as you would like into the stack and the navigation controller will work the navigation bar to display the relevant back buttons which allow the user to back through your application's UI, all the way to the first screen.

We learnt about pushing a view controller. How about popping or removing a view controller from the stack of the navigation controller? The answer is straightforward:

using the `popViewControllerAnimated:` method of the navigation controller. Let's make our second view controller pop itself off of the stack automatically 5 seconds after it is displayed on the screen:

```
- (void) goBack{
    [self.navigationController popViewControllerAnimated:YES];
}

- (void) viewDidAppear:(BOOL)paramAnimated{
    [super viewDidAppear:paramAnimated];
    [self performSelector:@selector(goBack)
        withObject:nil
        afterDelay:5.0f];
}
```

So if you open the app in the simulator now and wait 5 seconds after the first view controller is displayed, you will see that the second view controller will automatically get displayed on the screen. Wait another 5 seconds now and the second view controller will automatically go back to the first view controller.

See Also

XXX

2.9 Manipulating a Navigation Controller's Array of View Controllers

Problem

You would like to directly manipulate the array of view controllers associated with a specific navigation controller.

Solution

Use the `viewControllers` property of the `UINavigationController` class to access and modify the array of view controllers associated with a navigation controller:

```
- (void) goBack{
    /* Get the current array of View Controllers */
    NSArray *currentControllers = self.navigationController.viewControllers;

    /* Create a mutable array out of this array */
    NSMutableArray *newControllers = [NSMutableArray
        arrayWithArray:currentControllers];

    /* Remove the last object from the array */
    [newControllers removeLastObject];

    /* Assign this array to the Navigation Controller */
}
```



```

        self.navigationController.viewControllers = newControllers
    }

```

You can call this method inside any view controller in order to pop the last view controller from the hierarchy of the navigation controller associated with the current view controller.

Discussion

An instance of the `UINavigationController` class holds an array of `UIViewController` objects. After retrieving this array, you can manipulate it in any way that you wish. For instance, you can remove a view controller from an arbitrary place in the array.

Manipulating the view controllers of a navigation controller directly by assigning an array to the `viewControllers` property of the navigation controller will commit the operation without a transition/animation. If you wish this operation to be animated, use the `setViewControllers:animated:` method of the `UINavigationController` class, as shown in the following snippet:

```

- (void) goBack{
    /* Get the current array of View Controllers */
    NSArray *currentControllers = self.navigationController.viewControllers;

    /* Create a mutable array out of this array */
    NSMutableArray *newControllers = [NSMutableArray
                                     arrayWithArray:currentControllers];

    /* Remove the last object from the array */
    [newControllers removeLastObject];

    /* Assign this array to the Navigation Controller with animation */
    [self.navigationController setViewControllers:newControllers
                             animated:YES];
}

```

See Also

XXX

2.10 Displaying an Image on a Navigation Bar

Problem

You want to display an image instead of text as the title of the current view controller on the navigation controller.

Solution

Use the `titleView` property of the view controller's navigation item:

```

- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];

    /* Create an Image View to replace the Title View */
    UIImageView *imageView =
    [[UIImageView alloc]
    initWithFrame:CGRectMake(0.0f, 0.0f, 100.0f, 40.0f)];

    imageView.contentMode = UIViewContentModeScaleAspectFit;

    /* Load an image. Be careful, this image will be cached */
    UIImage *image = [UIImage imageNamed:@"FullSizeLogo.png"];

    /* Set the image of the Image View */
    [imageView setImage:image];

    /* Set the Title View */
    self.navigationItem.titleView = imageView;
}

```



The preceding code must be executed in a view controller that is placed inside a navigation controller.

Discussion

The navigation item of every view controller can display a title for the view controller to which it is assigned in two different ways:

- By displaying simple text
- By displaying a view

If you want to use text, you can use the `title` property of the navigation item. However, if you want more control over the title or if you simply want to display an image or any other view up on the navigation bar, you can use the `titleView` property of the navigation item of a view controller. You can assign any object that is a subclass of the `UIView` class. In the example, we created an image view and assigned an image to it. Then we displayed it as the title of the current view controller on the navigation controller.

2.11 Adding Buttons to Navigation Bars with `UIBarButtonItem`

Problem

You want to add different buttons to a navigation bar.

Solution

Use the `UIBarButtonItem` class.

Discussion

A navigation bar can contain different items. On the left and on the right side of a navigation bar, there are usually some buttons that are getting displayed. These buttons are of class `UIBarButtonItem` and they can take many different shapes and forms. Let's have a look at an example:




Figure 2-32. Different buttons displayed on a navigation bar

You might be surprised that the bar on the *bottom* of Figure 2-32 is also a navigation bar! Navigation bars are of class `UINavigationController` and can be created at any time and added to any view. So just look at all the different buttons with different shapes which have been added to the navigation bars in Figure 2-32. The ones on the top right have a up and down arrow, the one on the top left has an arrow pointing to the left, the ones

on the bottom navigation bar have all sorts of shapes. We will have a look at creating some of these buttons in this recipe.



For this recipe, you must follow the instructions in [Recipe 1.1](#) to create an Empty application. Then follow the instructions in [Recipe 2.8](#) to add a navigation controller to your app delegate.

In order to create a navigation button, we must:

1. Create an instance of `UIBarButtonItem`.
2. Add that button to the navigation bar of a view controller using the view controller's `navigationItem` property. The `navigationItem` property allows us to interact with the navigation bar. This property has two properties on itself, namely `rightBarButtonItem` and `leftBarButtonItem`. Both these properties are of type `UIBarButtonItem`.

Let's then have a look at an example where we add a button to the right side of our navigation bar. In this button we will display the text *Add*:

```
- (void) performAdd:(id)paramSender{
    NSLog(@"Action method got called.");
}

- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.title = @"First Controller";

    self.navigationItem.rightBarButtonItem =
        [[UIBarButtonItem alloc] initWithTitle:@"Add"
                                             style:UIBarButtonItemStylePlain
                                             target:self
                                             action:@selector(performAdd:)]];
}
```

When we run our app now, we will see something similar to this:



Figure 2-33. A navigation button added to a navigation bar

That was simple and easy. But if you are an iOS user, you probably have noticed that the system apps that come preconfigured on iOS have a different Add button. Have you noticed that? Here is an example in the Alarm section of the Clock app on the iPhone. Notice the + button on the top right of the navigation bar:




Figure 2-34. The proper way of creating an Add button

It turns out, iOS SDK allows us to create *system* buttons on the navigation bar. We do that by using the `initWithBarButtonSystemItem:target:action:` initializer of the `UIBarButtonItem` class:

```
- (void) performAdd:(id)paramSender{
    NSLog(@"Action method got called.");
}

- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.title = @"First Controller";

    self.navigationItem.rightBarButtonItem =
    [[UIBarButtonItem alloc]
     initWithBarButtonSystemItem:UIBarButtonSystemItemAdd
     target:self
     action:@selector(performAdd:)]];
}
```

And the results are exactly what we were looking for:




Figure 2-35. A system Add button

The first parameter of the `initWithBarButtonSystemItem:target:action:` initializer method of the navigation button can have any of the values listed in the `UIBarButtonItemSystemItem` enumeration:

```
typedef enum {  
    UIBarButtonItemSystemItemDone,  
    UIBarButtonItemSystemItemCancel,  
    UIBarButtonItemSystemItemEdit,  
    UIBarButtonItemSystemItemSave,  
}
```

```

UIBarButtonItemSystemItemAdd,
UIBarButtonItemSystemItemFlexibleSpace,
UIBarButtonItemSystemItemFixedSpace,
UIBarButtonItemSystemItemCompose,
UIBarButtonItemSystemItemReply,
UIBarButtonItemSystemItemAction,
UIBarButtonItemSystemItemOrganize,
UIBarButtonItemSystemItemBookmarks,
UIBarButtonItemSystemItemSearch,
UIBarButtonItemSystemItemRefresh,
UIBarButtonItemSystemItemStop,
UIBarButtonItemSystemItemCamera,
UIBarButtonItemSystemItemTrash,
UIBarButtonItemSystemItemPlay,
UIBarButtonItemSystemItemPause,
UIBarButtonItemSystemItemRewind,
UIBarButtonItemSystemItemFastForward,
UIBarButtonItemSystemItemUndo,
UIBarButtonItemSystemItemRedo,
UIBarButtonItemSystemItemPageCurl,
} UIBarButtonItem;

```

One of the really great initializers of the `UIBarButtonItem` class is the `initWithCustomView:` method. As its parameter, this method accepts any view. This means, we can even add a `UISwitch` (see [Recipe 2.2](#)) as a button on the navigation bar. This won't look very good though but let's give it a try:

```

- (void) switchIsChanged:(UISwitch *)paramSender{
    if ([paramSender isOn]){
        NSLog(@"Switch is on.");
    } else {
        NSLog(@"Switch is off.");
    }
}

- (void) viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.title = @"First Controller";

    UISwitch *simpleSwitch = [[UISwitch alloc] init];
    simpleSwitch.on = YES;
    [simpleSwitch addTarget:self
                      action:@selector(switchIsChanged:)
                      forControlEvents:UIControlEventValueChanged];

    self.navigationItem.rightBarButtonItem =
    [[UIBarButtonItem alloc] initWithCustomView:simpleSwitch];
}

```

And here are the results:



Figure 2-36. A switch added to a navigation bar

You can create pretty amazing navigation bar buttons. Just take a look at what Apple has done with the up and down arrows on the top right corner of [Figure 2-32](#). Let's do the same thing, shall we?

Well it looks like the button is actually containing a segmented control (see [Recipe 2.6](#)). So we should create a segmented control with two segments and add it to a navigation button and finally place the navigation button on the navigation bar. Let's get started:

```
- (void) segmentedControlTapped:(UISegmentedControl *)paramSender{
```

```

if ([paramSender selectedSegmentIndex] == 0){
    /* Up button */
    NSLog(@"Up");
} else if ([paramSender selectedSegmentIndex] == 1){
    /* Down button */
    NSLog(@"Down");
}

}

- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
    self.title = @"First Controller";

    NSArray *items = [[NSArray alloc] initWithObjects:
                      [UIImage imageNamed:@"UpArrow.png"],
                      [UIImage imageNamed:@"DownArrow.png"], nil];

    UISegmentedControl *segmentedControl = [[UISegmentedControl alloc]
                                             initWithItems:items];

    segmentedControl.segmentedControlStyle = UISegmentedControlStyleBar;
    segmentedControl.momentary = YES;

    [segmentedControl addTarget:self
                        action:@selector(segmentedControlTapped:)
                        forControlEvents:UIControlEventValueChanged];

    self.navigationItem.rightBarButtonItem =
    [[UIBarButtonItem alloc] initWithCustomView:segmentedControl];
}

```



I manually created the arrow images. They are not present in the iOS SDK. Creating these images is quite easy though. They are simple triangles: one pointing up and the other pointing down. If you are graphically challenged, maybe you could find some images using a search engine?

And this is how the output looks like:



Figure 2-37. A segmented control inside a navigation button

The `navigationItem` of every view controller also has two very interesting methods:

`setRightBarButtonItem:animated:`

Sets the navigation bar's right button but allows you to specify whether you want the placement to be animated or not. Pass the value of `YES` to the `animated` parameter if you want this placement to be animated.

`setLeftBarButtonItem:animated:`

Sets the navigation bar's left button but allows you to specify whether you want the placement to be animated or not. Pass the value of `YES` to the `animated` parameter if you want this placement to be animated.

Here is an example:

```
UIBarButtonItem *rightBarButton =  
[[UIBarButtonItem alloc] initWithCustomView:segmentedControl];  
  
[self.navigationItem setRightBarButtonItem:rightBarButton  
                    animated:YES];
```

See Also

XXX

2.12 Presenting Multiple View Controllers with UINavigationController

Problem

You would like to give your users the option to switch from one section of your app to another, with ease.

Solution

Use the `UITabBarController` class.

Discussion

If you use your iPhone as an alarm clock, then you certainly have seen a tab bar. Have a look at [Figure 2-34](#). The bottom icons saying World Clock, Alarm, Stopwatch and Timer are parts of a tab bar. The whole black bar at the bottom of the screen is a tab bar and the aforementioned items are tab bar items.

A tab bar is a container controller. In other words, we create instances of `UITabBarController` and add them to the window of our application. For each tab bar item, we add a navigation controller or a view controller to the tab bar and those items will appear as tab bar items. A tab bar controller contains a tab bar of type `UITabBar`.

So let's assume we have two view controllers with class names `FirstViewController` and `SecondViewController`. We now go into our app delegate and define our view controllers and our tab bar:

```
#import <UIKit/UIKit.h>  
  
@class FirstViewController;  
@class SecondViewController;
```

```

@interface Presenting_Multiple_View_Controllers_with_UITabBarControllerAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) FirstViewController *firstViewController;
@property (nonatomic, strong) SecondViewController *secondViewController;
@property (nonatomic, strong) UITabBarController *tabBarController;

@end

```

Now let's go and synthesize our properties and create our view controllers and tab bar controller:

```

#import "Presenting_Multiple_View_Controllers_with_UITabBarControllerAppDelegate.h"
#import "FirstViewController.h"
#import "SecondViewController.h"

@implementation Presenting_Multiple_View_Controllers_with_UITabBarControllerAppDelegate

@synthesize window = _window;
@synthesize firstViewController;
@synthesize secondViewController;
@synthesize tabBarController;

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    // Override point for customization after application launch.
    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    [self.window makeKeyAndVisible];

    self.firstViewController = [[FirstViewController alloc]
        initWithNibName:nil
        bundle:NULL];
    self.secondViewController = [[SecondViewController alloc]
        initWithNibName:nil
        bundle:NULL];

    NSArray *twoViewControllers = [[NSArray alloc]
        initWithObjects:
            self.firstViewController,
            self.secondViewController, nil];


    self.tabBarController = [[UITabBarController alloc] init];
    [self.tabBarController setViewControllers:twoViewControllers];

    [self.window addSubview:self.tabBarController.view];

    return YES;
}

```

A tab bar, when displayed on the screen, will display tab bar items just like we saw in [Figure 2-34](#). The name of each one of these tab bar items comes from the title of the view controller that is representing that tab bar item so let's go ahead and set the title for both our view controllers.



When a tab bar loads up, it only loads the view of the first view controller in its items. All other view controllers will be initialized but their views won't be loaded. This means, any code that you have written in the `viewDidLoad` of the second view controller will *not* get executed until after the user taps on the second tab bar item for the first time. So if you assign a title to the second view controller in its `viewDidLoad` and run your app, you will realize that the title in the tab bar item is still empty.

For the first view controller we choose the title *First*:

```
#import "FirstViewController.h"

@implementation FirstViewController

- (id)initWithNibName:(NSString *)nibNameOrNil
    bundle:(NSBundle *)nibBundleOrNil{

    self = [super initWithNibName:nibNameOrNil
                          bundle:nibBundleOrNil];

    if (self != nil) {
        self.title = @"First";
    }
    return self;
}

- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
}

...
```

And for the second view controller, we pick the title *Second*:

```
#import "SecondViewController.h"

@implementation SecondViewController

- (id)initWithNibName:(NSString *)nibNameOrNil
    bundle:(NSBundle *)nibBundleOrNil{

    self = [super initWithNibName:nibNameOrNil
                          bundle:nibBundleOrNil];

    if (self != nil) {
        self.title = @"Second";
    }
    return self;
}
```

```
}  
  
- (void)viewDidLoad{  
    [super viewDidLoad];  
    self.view.backgroundColor = [UIColor whiteColor];  
}  
  
...
```

Now let's run our app and see what happens:



Figure 2-38. A very simple tab bar populated with two view controllers

You can see that our view controllers do *not* have a navigation bar. What should we do? It's easy. Remember that a UINavigationController is actually a subclass of UIViewController. So, we can add instances of navigation controller to a tab bar and inside each navigation controller, we can load a view controller. What are we waiting for then? Let's start with the header file of our app delegate:

```
#import <UIKit/UIKit.h>

@class FirstViewController;
@class SecondViewController;

@interface Presenting_Multiple_View_Controllers_with_UITabBarControllerAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;

@property (nonatomic, strong) FirstViewController *firstViewController;
@property (nonatomic, strong)
    UINavigationController *firstNavigationController;

@property (nonatomic, strong) SecondViewController *secondViewController;
@property (nonatomic, strong)
    UINavigationController *secondNavigationController;

@property (nonatomic, strong) UITabBarController *tabBarController;

@end
```

Now that we have the declaration in place, let's implement the tab bar controller in the implementation file of our app delegate:

```
@synthesize window = _window;
@synthesize firstViewController;
@synthesize firstNavigationController;
@synthesize secondViewController;
@synthesize secondNavigationController;
@synthesize tabBarController;

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    // Override point for customization after application launch.
    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    [self.window makeKeyAndVisible];

    self.firstViewController = [[FirstViewController alloc]
        initWithNibName:nil
        bundle:NULL];
    self.firstNavigationController =
        [[UINavigationController alloc]
            initWithRootViewController:self.firstViewController];

    self.secondViewController = [[SecondViewController alloc]
```



```

        initWithNibName:nil
        bundle:NULL];
self.secondNavigationController =
    [[UINavigationController alloc]
     initWithRootViewController:self.secondViewController];

NSArray *twoNavController = [[NSArray alloc]
                              initWithObjects:
                               self.firstNavigationController,
                               self.secondNavigationController, nil];

self.tabBarController = [[UITabBarController alloc] init];
[self.tabBarController setViewControllers:twoNavController];

[self.window addSubview:self.tabBarController.view];

return YES;
}

```

And the results? Exactly what we wanted:




Figure 2-39. A tab bar displaying view controllers inside navigation controllers

As we can see in [Figure 2-34](#), each tab bar item can have text and an image. We've learnt the using the `title` property of a view controller, we can specify this text but what about the image? It turns out every view controller has a property called `tabItem`. This property is the tab item for the current view controller and you can use this property to set the image of the tab bar item, through the `image` property of the tab item. I've already designed two images. One a rectangle and one a circle and I'm going to display them as the tab bar item image for each of my view controllers. Here is for the first view controller:

```
#import "FirstViewController.h"

@implementation FirstViewController

- (id)initWithNibName:(NSString *)nibNameOrNil
                  bundle:(NSBundle *)nibBundleOrNil{

    self = [super initWithNibName:nibNameOrNil
                          bundle:nibBundleOrNil];

    if (self != nil) {
        self.title = @"First";
        self.tabBarItem.image = [UIImage imageNamed:@"FirstTab.png"];
    }
    return self;
}

...
```

And here is for the second view controller:

```
#import "SecondViewController.h"

@implementation SecondViewController

- (id)initWithNibName:(NSString *)nibNameOrNil
                  bundle:(NSBundle *)nibBundleOrNil{

    self = [super initWithNibName:nibNameOrNil
                          bundle:nibBundleOrNil];

    if (self != nil) {
        self.title = @"Second";
        self.tabBarItem.image = [UIImage imageNamed:@"SecondTab.png"];
    }
    return self;
}

...
```

And running the app in the simulator, we will see that the images are displayed properly:




Figure 2-40. Tab bar items with images

See Also

XXX

2.13 Displaying Static Text with UILabel

Problem

You want to display static text to your users. You would also like to control using which font and color the text is rendered.

Solution

Use the `UILabel` class.

Discussion

Labels are everywhere in iOS. You can practically see them in every application, except for games where the content is usually rendered with OpenGL ES instead of the core drawing frameworks in iOS. Here is an example of labels, in the Settings app on the iPhone:



Figure 2-41. Labels as titles of each one of the settings

You can see that the labels are displaying text in the Settings app, such as General, iCloud, Twitter, Phone, FaceTime and etc. To create a label, we instantiate an object of type `UILabel`. Setting or getting the text of a label can be done through its `text` property. So let's define a label in our view controller's header file:

```
#import <UIKit/UIKit.h>

@interface Displaying_Static_Text_with_UILabelViewController
    : UIViewController

@property (nonatomic, strong) UILabel *myLabel;

@end
```

Then synthesize it:

```
#import "Displaying_Static_Text_with_UILabelViewController.h"

@implementation Displaying_Static_Text_with_UILabelViewController
```

```
@synthesize myLabel;
```

```
...
```

And in the `viewDidLoad`, instantiate the label:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];
    CGRect labelFrame = CGRectMake(0.0f,
                                    0.0f,
                                    100.0f,
                                    23.0f);
    self.myLabel = [[UILabel alloc] initWithFrame:labelFrame];
    self.myLabel.text = @"iOS 5 Programming Cookbook";
    self.myLabel.font = [UIFont boldSystemFontOfSize:14.0f];
    self.myLabel.center = self.view.center;
    [self.view addSubview:self.myLabel];
}
```

Now let's run our app and see what happens:



Figure 2-42. A label that is too small in width to contain its contents

You can see that the contents of the label are truncated with trailing full stops because the width of the label isn't enough to contain the whole contents. One solution would be to make the width longer but how about the height? What if we wanted the text to wrap to the next line? Ok, go ahead and change the height from *23.0f* to *50.0f*:

```
CGRect labelFrame = CGRectMake(0.0f,  
                                0.0f,  
                                100.0f,  
                                50.0f);
```


If you run your app now, you will get *exactly* the same results that you got in [Figure 2-42](#). But you might ask, I increased the height, why didn't the content wrap to the next line? It turns out that `UILabel` class has a property called `numberOfLines` that needs to be adjusted to the number of lines the label has to wrap the text to, in case it runs out of horizontal space. If you set this value to 3, it tells the label that you want the text to wrap to three lines if it cannot fit the text into one line:

```
self.myLabel.numberOfLines = 3;
```

If you run the app now, you will get the desired results:



Figure 2-43. A label wrapping its contents to 3 lines



In some situations, you might not know how many lines is required to display a certain text in a label. In those instances, you need to set the `numberOfLines` property of your label to 0.

If you want your label's frame to stay static and you want the font inside your label to adjust itself to fit into the boundaries of the label, then you need to set the `adjustsFontSizeToFitWidth` property of your label to `YES`. For instance, if the height of our label was to be `23.0f` as we say in [Figure 2-42](#), we could adjust the font of the label to fit into the boundaries. Here is how it works:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];
    CGRect labelFrame = CGRectMake(0.0f,
                                   0.0f,
                                   100.0f,
                                   23.0f);

    self.myLabel = [[UILabel alloc] initWithFrame:labelFrame];
    self.myLabel.adjustsFontSizeToFitWidth = YES;
    self.myLabel.text = @"iOS 5 Programming Cookbook";
    self.myLabel.font = [UIFont boldSystemFontOfSize:14.0f];
    self.myLabel.center = self.view.center;
    [self.view addSubview:self.myLabel];
}
```

See Also

XXX

2.14 Accepting User Text Input with UITextField

Problem

You want to accept text input in your user interface.

Solution

Use the `UITextField` class.

Discussion

A text field is very much like a label in that it can display text but a text field can also accept text entry at runtime. Here is an example of two text fields, in the Twitter section of the Settings app on an iPhone:



Figure 2-44. Username and Password text fields allowing text entry



A text field allows only 1 line of text to be input/displayed as a result, the default height of a text field is only 31 points. In Interface Builder, this height cannot be modified but if you are creating your text field in code, you can change the text field's height, although this will *not* change the number of lines you can render in a text field, which is 1.

Let's start with the header file of our view controller to define our text field:

```
#import <UIKit/UIKit.h>

@interface Accepting_User_Text_Input_with_UITextFieldViewController
: UIViewController

@property (nonatomic, strong) UITextField *myTextField;

@end
```

This is followed by synthesizing the `myTextField` property:

```
#import "Accepting_User_Text_Input_with_UITextFieldViewController.h"

@implementation Accepting_User_Text_Input_with_UITextFieldViewController

@synthesize myTextField;

...
```

And then let's create the text field:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];
    CGRect textFieldFrame = CGRectMake(0.0f,
                                       0.0f,
                                       200.0f,
                                       31.0f);

    self.myTextField = [[UITextField alloc]
                        initWithFrame:textFieldFrame];
    self.myTextField.borderStyle = UITextBorderStyleRoundedRect;

    self.myTextField.contentVerticalAlignment =
        UIControlContentVerticalAlignmentCenter;

    self.myTextField.textAlignment = NSTextAlignmentCenter;

    self.myTextField.text = @"Sir Richard Branson";
    self.myTextField.center = self.view.center;
    [self.view addSubview:self.myTextField];
}
```

Let's first have a look at the results and then we will see the details about the code:



Figure 2-45. A simple text field with center aligned text

In order to create this text field, we used various properties of `UITextField`. These are:

`borderStyle`

This property is of type `UITextBorderStyle` and it specifies how the text field should render its borders.

`contentVerticalAlignment`

This value is of type `UIControlContentVerticalAlignment` and it tells the text field how the text should appear, vertically, in the boundaries of the control. If we didn't

center the text vertically, it would appear on the top left corner of the text field by default.

`textAlignment`

This property is of type `UITextAlignment` and it specifies the horizontal alignment of the text in a text field. In this example, we have centered the text horizontally (as well as vertically).

`text`

This is a readwrite property. You can either read from it or write to it. Reading from it will return the text field's current text and writing to it will set the text field's text to the value that you specify.

A text field sends delegate messages to its delegate object. These messages get sent, for instance, when the user starts editing the text inside a text field or when the user finishes editing or when the user enters any character in the text field. To get notified of these events, we need to set the `delegate` property of the text field to our object. The delegate of a text field must conform to the `UITextFieldDelegate` protocol so let's first take care of this:

```
#import <UIKit/UIKit.h>

@interface Accepting_User_Text_Input_with_UITextFieldViewController
    : UIViewController <UITextFieldDelegate>

@property (nonatomic, strong) UITextField *myTextField;

@end
```

Hold down the Command key on your computer and click on the `UITextFieldDelegate` protocol in Xcode. You will see all the methods that this protocol gives us control over. Here are those methods with description of when they get called:

`textFieldShouldBeginEditing:`

A method that returns a `BOOL` telling the text field (the parameter to this method) whether that text field should start getting edited by the user or not. Return `NO` if you don't want the user to edit your text field.

`textFieldDidBeginEditing:`

Gets called when the text field starts to get edited by the user.

`textFieldShouldEndEditing:`

A method that returns a `BOOL` telling the text field whether it should end its current editing session or not. If you return `NO` from this method, the user will not be able to stop editing this text field.

`textFieldDidEndEditing:`

Gets called when the editing session of the text field ends.

`textField:shouldChangeCharactersInRange:replacementString:`

Gets called whenever the text inside the text field is modified. The return value of this method is a boolean. If you return `YES`, you say that you allow the text to be

changed. If you return `NO`, the change in the text of the text field will *not* be confirmed and will not happen.

`textFieldShouldClear:`

Each text field has a *clear* button which is usually a circular X button. When the user presses this button, the contents of the text field will automatically get erased. We need to manually enable the clear button though. If you have enabled the clear button and you return `NO` method, that gives the user the impression that your app isn't working so make sure you know what you are doing because the user sees a clear button, presses it but never sees the text in the text field get erased.

`textFieldShouldReturn:`

This method gets called when the user has pressed the Return/Enter key on the keyboard, trying to dismiss the keyboard. You should resign the text field as the first responder in this method.

Let's mix this recipe with [Recipe 2.13](#) and create a label under our text field and display the total number of characters entered in our text field, in the label. Let's start with our header file:

```
#import <UIKit/UIKit.h>

@interface Accepting_User_Text_Input_with_UITextFieldViewController
    : UIViewController <UITextFieldDelegate>

@property (nonatomic, strong) UITextField *myTextField;
@property (nonatomic, strong) UILabel *labelCounter;

@end
```

Now synthesizing both of these components:

```
#import "Accepting_User_Text_Input_with_UITextFieldViewController.h"

@implementation Accepting_User_Text_Input_with_UITextFieldViewController

@synthesize myTextField;
@synthesize labelCounter;

...
```

And then the creation of the text field and the label and the text field delegate methods which we require. We skip implementing all the `UITextFieldDelegate` methods as we don't need all of them in this example:

```
- (void) calculateAndDisplayTextFieldLengthWithText:(NSString *)paramText{

    NSString *characterOrCharacters = @"Characters";
    if ([paramText length] == 1){
        characterOrCharacters = @"Character";
    }

    self.labelCounter.text = [NSString stringWithFormat:@"%lu %@",
        (unsigned long)[paramText length],
```

```

        characterOrCharacters];
    }

- (BOOL)textField:(UITextField *)textField
  shouldChangeCharactersInRange:(NSRange)range
    replacementString:(NSString *)string{

    BOOL result = YES;

    if ([textField isEqual:self.myTextField]){
        NSString *wholeText =
            [textField.text stringByReplacingCharactersInRange:range
                                withString:string];
        [self calculateAndDisplayTextFieldLengthWithText:wholeText];
    }

    return result;
}

- (BOOL)textFieldShouldReturn:(UITextField *)textField{
    [textField resignFirstResponder];
    return YES;
}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];
    CGRect textFieldFrame = CGRectMake(38.0f,
                                        30.0f,
                                        220.0f,
                                        31.0f);

    self.myTextField = [[UITextField alloc]
                        initWithFrame:textFieldFrame];

    self.myTextField.delegate = self;

    self.myTextField.borderStyle = UITextBorderStyleRoundedRect;

    self.myTextField.contentVerticalAlignment =
        UIControlContentVerticalAlignmentCenter;

    self.myTextField.textAlignment = UITextAlignmentCenter;

    self.myTextField.text = @"Sir Richard Branson";
    [self.view addSubview:self.myTextField];

    CGRect labelCounterFrame = self.myTextField.frame;
    labelCounterFrame.origin.y += textFieldFrame.size.height + 10;
    self.labelCounter = [[UILabel alloc] initWithFrame:labelCounterFrame];
    [self.view addSubview:self.labelCounter];

    [self calculateAndDisplayTextFieldLengthWithText:self.myTextField.text];
}

```



```
}
```

One important calculation which we are doing is in the `textField:shouldChangeCharactersInRange:replacementString:` method. There, we've declared and used a variable called `wholeText`. When this method gets called, the `replacementString` parameter specifies the string that the user has entered into the text field. You might be thinking that the user can only enter one character at a time, so why is this a string? Don't forget the user can paste a whole chunk of text into a text field so this parameter needs to be a string. The `shouldChangeCharactersInRange` parameter specifies where, in terms of location inside the text field's text, the user is entering the text. So using these two parameter, we will create a string that first reads the whole text inside the text field and will use the given range to place the new text inside the old text. With this, we will come up with the text that will appear in the text field *after* the `textField:shouldChangeCharactersInRange:replacementString:` method returns YES. Now here is how our app looks like when it gets run on the simulator:



Figure 2-46. Responding to delegate messages of a text field

In addition to displaying text, a text field can also display a *placeholder*. A placeholder is the text that gets displayed *before* the user has entered any text in the text field, while the text field's text property is empty. This can be any string that you wish it to be and setting it will help give the user an indication as to what this text field actually is. Many use this placeholder to tell the user what type of value she can enter in that text field. For instance, in [Figure 2-44](#), the two text fields (username and password) have placeholders that say Required. You can use the `placeholder` property of the text field to set or get the current placeholder. Here is an example:

```
self.myTextField = [[UITextField alloc]
                    initWithFrame:textFieldFrame];

self.myTextField.delegate = self;

self.myTextField.borderStyle = UITextBorderStyleRoundedRect;

self.myTextField.contentVerticalAlignment =
    UIControlContentVerticalAlignmentCenter;

self.myTextField.textAlignment = NSTextAlignmentCenter;

self.myTextField.placeholder = @"Enter text here...";
[self.view addSubview:self.myTextField];
```

And the results are shown here:



Figure 2-47. A placeholder is shown when there is no text in a text field

Text fields have two really neat properties called `leftView` and `rightView`. These two properties are of type `UIView` and are readwrite. They appear, as their names imply, on the left and the right side of a text field if you assign a view to them. One place you might use a left view, for instance, is if you are displaying a currency text field where you would like to display the user's current country's currency in the left view, as a `UILabel`. Here is how we can accomplish that:

```
UILabel *currencyLabel = [[UILabel alloc] initWithFrame:CGRectZero];
currencyLabel.text = [[[NSNumberFormatter alloc] init] currencySymbol];
currencyLabel.font = self.myTextField.font;
```

```
[currencyLabel sizeToFit];
self.myTextField.leftView = currencyLabel;
self.myTextField.leftViewMode = UITextFieldViewModeAlways;
```

If we simply assign a view to the `leftView` or to the `rightView` properties of a text field, those views will not appear automatically by default. When these two views appear on the screen depends on the mode that governs their appearance and you can control that mode using the `leftViewMode` and the `rightViewMode` properties, in that order. These modes are of type `UITextFieldViewMode`:

```
typedef enum {
    UITextFieldViewModeNever,
    UITextFieldViewModeWhileEditing,
    UITextFieldViewModeUnlessEditing,
    UITextFieldViewModeAlways
} UITextFieldViewMode;
```

So if you, for instance, set the left view mode to `UITextFieldViewModeWhileEditing`, the left view, if a value is assigned to it, will only appear while the user is editing the text field. Conversely, if you set this value to `UITextFieldViewModeUnlessEditing`, the left view will appear only while the user is *not* editing the text field and as soon as editing starts, the left view will disappear. Let's have a look at our code now in the simulator:



Figure 2-48. A text field with a left view

See Also

XXX

2.15 Displaying Long Lines of Text with UITextView

Problem

You want to display multiple lines of text in your UI inside one scrollable view.

Solution

Use the UITextView class.

Discussion

The UITextView class can display multiple lines of text and it has scrollable content, meaning that if the contents run off the boundaries of the text view, the text view's internal components will allow the user to scroll the text up and down to see different parts of the text as they wish. An example of where a text view has been used in an iOS app is the Notes app on the iPhone:



Figure 2-49. Notes app on the iPhone uses a text view to render text

Let's create a text view and see how it works. We start off by declaring the text view in our view controller's header file:

```
#import <UIKit/UIKit.h>
```

```

@interface Displaying_Long_Lines_of_Text_with_UITextViewViewController
    : UIViewController

@property (nonatomic, strong) UITextView *myTextView;

@end

```

And that is followed by synthesizing the text view:

```

#import "Displaying_Long_Lines_of_Text_with_UITextViewViewController.h"

@implementation Displaying_Long_Lines_of_Text_with_UITextViewViewController

@synthesize myTextView;

...

```

Now it's time to create the text view itself. We will make the text view as big as the big as the view controller's view:

```

- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myTextView = [[UITextView alloc] initWithFrame:self.view.bounds];
    self.myTextView.text = @"Some text here...";
    self.myTextView.font = [UIFont systemFontOfSize:16.0f];
    [self.view addSubview:self.myTextView];
}

```

Now let's run the app in iOS Simulator and see how it looks like:



Figure 2-50. A text view consuming the entire boundary of the screen

Now if you tap on the text field, you will notice that a keyboard will popup from the bottom of the screen, concealing almost half of the entire boundaries of the our text view. That means, if the user starts typing text and gets to the middle of the text view, the rest of the text that she types will *not* be visible to her:



Figure 2-51. Keyboard concealing half the size of a text view

To remedy this, we have to listen for certain notifications:

UIKeyboardWillShowNotification

Gets sent by the system whenever the keyboard is getting displayed on the screen, for any component, be it a text field or a text view or etc.

UIKeyboardDidShowNotification

Gets sent by the system when the keyboard has already gotten displayed.

UIKeyboardWillHideNotification

Gets sent by the system when the keyboard is about to hide.

UIKeyboardDidHideNotification

Gets sent by the system when the keyboard is now fully hidden.

So our strategy is to find out when the keyboard is getting displayed and then somehow resize our text view. For this, we will use the `contentInset` property of `UITextView` to specify the margins of contents in the text view from top, left, bottom and right.



The keyboard notifications contain a dictionary, accessible through the `userInfo` property, that specifies the boundaries of the keyboard on the screen. This property is of type `NSDictionary`. One of the keys in this dictionary is `UIKeyboardFrameEndUserInfoKey` which contains an object of type `NSValue` which itself contains the rectangular boundaries of the keyboard when it is fully shown. This rectangular area is denoted with a `CGRect`.

```
- (void) handleKeyboardDidShow:(NSNotification *)paramNotification{

    /* Get the frame of the keyboard */
    NSValue *keyboardRectAsObject =
        [[paramNotification userInfo]
         objectForKey:UIKeyboardFrameEndUserInfoKey];

    /* Place it in a CGRect */
    CGRect keyboardRect;

    [keyboardRectAsObject getValue:&keyboardRect];

    /* Give a bottom margin to our text view as much
    as the height of the keyboard */
    self.myTextView.contentInset =
        UIEdgeInsetsMake(0.0f,
                        0.0f,
                        keyboardRect.size.height,
                        0.0f);
}

- (void) handleKeyboardWillHide:(NSNotification *)paramNotification{
    /* Make the text view as big as the whole view again */
    self.myTextView.contentInset = UIEdgeInsetsZero;
}

- (void) viewWillAppear:(BOOL)paramAnimated{
    [super viewWillAppear:paramAnimated];

    [[NSNotificationCenter defaultCenter]
     addObserver:self
     selector:@selector(handleKeyboardDidShow:)
     name:UIKeyboardDidShowNotification
     object:nil];

    [[NSNotificationCenter defaultCenter]
     addObserver:self
```

```

        selector:@selector(handleKeyboardWillHide:)
        name:UIKeyboardWillHideNotification
        object:nil];

self.view.backgroundColor = [UIColor whiteColor];

self.myTextView = [[UITextView alloc] initWithFrame:self.view.bounds];
self.myTextView.text = @"Some text here...";
self.myTextView.font = [UIFont systemFontOfSize:16.0f];
[self.view addSubview:self.myTextView];
}

- (void) viewWillDisappear:(BOOL)paramAnimated{
    [super viewWillDisappear:paramAnimated];

    [[NSNotificationCenter defaultCenter] removeObserver:self];
}

```

In this code, we start looking for keyboard notifications in `viewWillAppear:` and we stop listening to keyboard notifications in `viewWillDisappear:`. The reason behind this is that if we don't remove our view controller as the listener to keyboard notifications when our view controller is no longer displayed, any other view controller's components firing keyboard notifications will cause the notification center to send those notifications to our view controller as well. However, when our view controller is not on the screen at the moment (has disappeared), we should not really be processing keyboard notifications unless this is something that you actually intend to do. I've seen many applications programmers break their apps by not taking care of this simple logic.

Perfect, now if the user tries to enter some text into the text view, the keyboard will pop up and we take the height of the keyboard and assign that value as the bottom margin of the contents inside the text view. This makes our text view smaller in size of its contents and allows the user to enter as much text as she wishes without the keyboard blocking her view.

See Also

XXX

2.16 Adding Buttons to the User Interface with UIButton

Problem

You want to display a button on your UI and handle the touch events for that button.

Solution

Use the `UIButton` class.

Discussion

Buttons are ways of allowing users to initiate an action in your apps. For instance, the iCloud Settings bundle in the Settings app presents a Delete Account button. If you press this button, the iCloud app will take action. The action depends on the app. Not all apps act the same when a Delete button is pressed by the user. Buttons can have images in them as we will soon see.



Figure 2-52. A button reading *Delete Account*

A button can have actions assigned to different triggers. For instance, a button can fire an action when the user puts her finger down on the button and another action when she lifts her finger off of the button. These become actions and the objects implementing the actions become targets. Let's go ahead and define a button in our view controller's header file:

```
#import <UIKit/UIKit.h>

@interface Adding_Buttons_to_the_User_Interface_with_UIButtonViewController
```

```

        : UIViewController

@property (nonatomic, strong) UIButton *myButton;

@end

```



The default height of UIButton is 37.0f points.

Next step is to synthesize this property:

```

#import "Adding_Buttons_to_the_User_Interface_with_UIButtonViewController.h"

@implementation
    Adding_Buttons_to_the_User_Interface_with_UIButtonViewController

@synthesize myButton;

...

```

And then to the implementation of the button:

```

- (void) buttonIsPressed:(UIButton *)paramSender{
    NSLog(@"Button is pressed.");
}

- (void) buttonIsTapped:(UIButton *)paramSender{
    NSLog(@"Button is tapped.");
}

- (void) viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];

    self.myButton = [UIButton buttonWithType:UIButtonTypeRoundedRect];

    self.myButton.frame = CGRectMake(110.0f,
                                     200.0f,
                                     100.0f,
                                     37.0f);

    [self.myButton setTitle:@"Press Me"
                     forState:UIControlStateNormal];

    [self.myButton setTitle:@"I'm Pressed"
                     forState:UIControlStateHighlighted];

    [self.myButton addTarget:self
                      action:@selector(buttonIsPressed:)
                    forControlEvents:UIControlEventTouchUpInside];

    [self.myButton addTarget:self
                      action:@selector(buttonIsTapped:)
                    forControlEvents:UIControlEventTouchUpInside];

```

```
        forControlEvents:UIControlEventTouchUpInside];  
  
    [self.view addSubview:self.myButton];  
  
}
```

In this example code, we are using the `setTitle:forState:` method of our button to set two different titles for the button. The title is the text that gets displayed on the button. A button can display a title per state and there are variety of states a button can be in, such as normal and highlighted (pressed down). So in this case, when the user sees the button for the first time she will read *Press Me*. Once she presses the button, the title of the button will change to *I'm Pressed*.

We did a similar thing with the actions that the button fires. We used the `addTarget:action:forControlEvents:` method to specify two actions for our button:

1. An action to be fired when the user presses the button down.
2. Another action to be fired when the user has pressed the button and has lifted her finger off the button. This completes a *touch-up-inside* action.



Figure 2-53. A rounded rectangle button in the middle of the screen

The other thing that you need to know about `UIButton` is that we always initialize them using a class method called `buttonWithType:`, as you saw in the example code. As the parameter to this method, we pass a value of type `UIButtonType`:

```
typedef enum {  
    UIButtonTypeCustom = 0,  
    UIButtonTypeRoundedRect,  
    UIButtonTypeDetailDisclosure,  
    UIButtonTypeInfoLight,  
    UIButtonTypeInfoDark,  
};
```



```
        UIButtonTypeContactAdd,  
    } UIButtonType;
```

A button can also render an image. An image will replace the default look and feel of the button. When you have an image or series of images that you want to assign to different states of a button, make sure your button is of type `UIButtonTypeCustom`. I have prepared two images here: one for the normal state of the button and the other for the highlighted (pressed) state. I will now go ahead and create my custom button and assign two images to it. One image is for the normal state of the button and the other one for the highlighted (pressed) state.

```
UIImage *normalImage = [UIImage imageNamed:@"NormalBlueButton.png"];  
UIImage *highlightedImage = [UIImage imageNamed:@"HighlightedBlueButton.png"];  
  
self.myButton = [UIButton buttonWithTypeCustom];  
  
self.myButton.frame = CGRectMake(110.0f,  
                                200.0f,  
                                100.0f,  
                                37.0f);  
  
[self.myButton setBackgroundImage:normalImage  
                                forState:UIControlStateNormal];  
[self.myButton setTitle:@"Normal"  
                                forState:UIControlStateNormal];  
  
[self.myButton setBackgroundImage:highlightedImage  
                                forState:UIControlStateHighlighted];  
[self.myButton setTitle:@"Pressed"  
                                forState:UIControlStateHighlighted];
```

Figure 2-54 shows how the app looks like when we run it in the iOS Simulator. We are using the `setBackgroundImage:forState:` method of the button to set a background image. With a background image, we can still use the `setTitle:forState:` methods to render text on top of the background image. If your images contain text and you don't need the title for a button, you can use the `setImage:forState:` method instead or simply remove the titles from the button.




Figure 2-54. A button with background image

See Also

XXX

2.17 Displaying Images with UIImageView

Problem

You would like to display images to your users on your app's UI.

Solution

Use the `UIImageView` class.

Discussion

The `UIImageView` is one of the least complicated classes in the iOS SDK. In fact, thinking about it, none of the classes are *complicated* and they are all well documented. As you know, an image view is responsible for displaying images. There are no tips or tricks involved. All you have to do is to instantiate an object of type `UIImageView` and add it to your views. It's that simple. Now, I have a picture of Apple MacBook Air and I would like to display it in an image view. Let's start with our view controller's header file:

```
#import <UIKit/UIKit.h>

@interface Displaying_Images_with_UIImageViewViewController
    : UIViewController

@property (nonatomic, strong) UIImageView *myImageView;

@end
```

Then synthesize the property in your implementation file:

```
#import "Displaying_Images_with_UIImageViewViewController.h"

@implementation Displaying_Images_with_UIImageViewViewController

@synthesize myImageView;

...
```

And go ahead and instantiate the image view and place the image in it:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    UIImage *macBookAir = [UIImage imageNamed:@"MacBookAir.png"];
    self.myImageView = [[UIImageView alloc] initWithImage:macBookAir];
    self.myImageView.center = self.view.center;
    [self.view addSubview:self.myImageView];
}
```

Now if we run the app, we will see something similar to this:



Figure 2-55. An image view that is too big to fit into the screen

I should mention that the MacBook Air image that I'm loading into this image view is 980x519 pixels and as you can see, it certainly not fitting into the iPhone screen. So how do we solve this problem? First, we need to make sure that we are initializing our image view using the `initWithFrame:` method instead of the `initWithImage:` method as the latter will set the width and height of the image view to the exact width and height of the image. So let's remedy that first:

```
- (void)viewDidLoad{  
    [super viewDidLoad];
```

```
self.view.backgroundColor = [UIColor whiteColor];

UIImage *macBookAir = [UIImage imageNamed:@"MacBookAir.png"];
self.myImageView = [[UIImageView alloc] initWithImage:macBookAir];
self.myImageView.center = self.view.center;
[self.view addSubview:self.myImageView];

}
```

So how does the app look like now?



Figure 2-56. An image whose width is squished to fit the width of the screen

This isn't really what we wanted to do, is it? Of course we got the frame of the image view right but the way the image is rendered in the image view isn't quite right. So what can we do? We can rectify this by setting the `contentMode` property of the image view. This property is of type `UIContentMode`:

```
typedef enum {
    UIViewContentModeScaleToFill,
    UIViewContentModeScaleAspectFit,
    UIViewContentModeScaleAspectFill,
    UIViewContentModeRedraw,
    UIViewContentModeCenter,
    UIViewContentModeTop,
    UIViewContentModeBottom,
    UIViewContentModeLeft,
    UIViewContentModeRight,
    UIViewContentModeTopLeft,
    UIViewContentModeTopRight,
    UIViewContentModeBottomLeft,
    UIViewContentModeBottomRight,
} UIViewContentMode;
```

Here is the explanation of some of the most useful values that are listed in the `UIViewContentMode` enumeration:

`UIViewContentModeScaleToFill`

This will scale the image inside the image view to fill the entire boundaries of the image view.

`UIViewContentModeScaleAspectFit`

This will make sure the image inside the image view will have the right aspect ratio and it will also make sure the image fits inside the image view's boundaries.

`UIViewContentModeScaleAspectFill`

This will make sure the image inside the image view will have the right aspect ratio and that it fills the entire boundaries of the image view. For this value to work properly, make sure that you have set the `clipsToBounds` property of the image view to YES.

So to make sure the image fits into the image view's boundaries and that the aspect ratio of the image is right, we need to use the `UIViewContentModeScaleAspectFit` content mode:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    UIImage *macBookAir = [UIImage imageNamed:@"MacBookAir.png"];
    self.myImageView = [[UIImageView alloc] initWithFrame:self.view.bounds];
    self.myImageView.image = macBookAir;
    self.myImageView.center = self.view.center;
    [self.view addSubview:self.myImageView];
```

}

And the results will be exactly what we expected:



Figure 2-57. The aspect ratio of image view is absolutely spot on

See Also

XXX

2.18 Creating Scrollable Content with UIScrollView

Problem

You have content that needs to get displayed on the screen but it requires more real estate than what the device's screen allows for.

Solution

Use the `UIScrollView` class.

Discussion

Scroll views are one of the features that make iOS a really neat operating system. They are practically everywhere. You've been to the Clock or the Contacts apps, haven't you? Have you seen how the content can be scrolled up and down? Well that's the magic of scroll views.

There really is one thing that we need to learn about scroll views and that is the *content size* of a scroll view. The content size is a value of type `CGSize` which specifies the width and the height of the contents of a scroll view. A scroll view, as its name implies, is a subclass of `UIView` so you can simply add your views to a scroll view using its `addSubview:` method. However, you need to make sure that the scroll view's content size is set properly, otherwise, the contents inside the scroll view will *not* scroll.

As an example, let's find a big image and load it to an image view. I will add the same image that I added in [Recipe 2.17](#): a MacBook Air image. I will add it to an image view and I will place it in a scroll view. Then I will use the `contentSize` of the scroll view to make sure this content size is equal to the size of the image (width and height). First, let's start with the header file of our view controller:

```
#import <UIKit/UIKit.h>

@interface Creating_Scrollable_Content_with_UIScrollViewViewController
    : UIViewController

@property (nonatomic, strong) UIImageView *myImageView;
@property (nonatomic, strong) UIScrollView *myScrollView;

@end
```

Let's synthesize our properties:

```
#import "Creating_Scrollable_Content_with_UIScrollViewViewController.h"

@implementation Creating_Scrollable_Content_with_UIScrollViewViewController

@synthesize myImageView;
@synthesize myScrollView;

...
```


And let's place the image view inside the scroll view:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    UIImage *imageToLoad = [UIImage imageNamed:@"MacBookAir.png"];
    self.myImageView = [[UIImageView alloc] initWithImage:imageToLoad];
    self.myScrollView = [[UIScrollView alloc] initWithFrame:self.view.bounds];
    [self.myScrollView addSubview:self.myImageView];
    self.myScrollView.contentSize = self.myImageView.bounds.size;
    [self.view addSubview:self.myScrollView];
}
```

If you now load up the app in iOS Simulator, you will see that you can scroll the image horizontally and vertically. The challenge here of course is to provide an image that is bigger than the screen's boundaries. If you provide an image that is, for example, 20x20 pixels, the scroll view won't be of much use to you. In fact, it would be wrong to place such an image into a scroll view as the scroll view would practically be useless in that scenario (since there is nothing to scroll as the image is smaller than the screen size).

One of the handy features of `UIScrollView` is that it supports delegation. Scroll views are capable of reporting really important events to their delegates. A delegate for a scroll view must conform to the `UIScrollViewDelegate` protocol. Some of the methods which are defined in this protocol are explained here:

scrollViewDidScroll:

Gets called whenever the contents of a scroll view get scrolled.

scrollViewWillBeginDecelerating:

Gets called when the user scrolls the contents of a scroll view and lifts her finger off of the screen, as the scroll view scrolls.

scrollViewDidEndDecelerating:

Gets called when the scroll view has finished scrolling its contents.

scrollViewDidEndDragging:willDecelerate:

Gets called when the user finishes dragging the contents of the scroll view. This method is very similar to the `scrollViewDidEndDecelerating:` method *but* you need to bear in mind that the user can drag the contents of a scroll view without scrolling the contents. She can simply put her finger on the content, move her finger to any location on the screen and without giving the contents any momentum to move, lift off her finger. This is dragging as opposed to scrolling. Scrolling is similar to dragging but the user will give momentum to the contents' movement by lifting her finger off the screen while the content is being dragged around, and not waiting for the content to stop before lifting the finger off the screen. It's similar to driving a car (dragging) and coasting with a car (scrolling).

So let's add some fun to our previous app. Not the goal is to set the alpha level of the image inside our image view to 0.50f (half transparent) when the user starts to scroll the scroll view and set this alpha back to 1.0f (opaque) when the user finishes scrolling. Let's begin by conforming to the UIScrollViewDelegate protocol:

```
#import <UIKit/UIKit.h>

@interface Creating_Scrollable_Content_with_UIScrollViewViewController
    : UIViewController <UIScrollViewDelegate>

@property (nonatomic, strong) UIImageView *myImageView;
@property (nonatomic, strong) UIScrollView *myScrollView;

@end
```

Then let's implement this functionality:

```
- (void)scrollViewDidScroll:(UIScrollView *)scrollView{
    /* Gets called when user scrolls or drags */
    self.myScrollView.alpha = 0.50f;
}

- (void)scrollViewDidEndDecelerating:(UIScrollView *)scrollView{
    /* Gets called only after scrolling */
    self.myScrollView.alpha = 1.0f;
}

- (void)scrollViewDidEndDragging:(UIScrollView *)scrollView
    willDecelerate:(BOOL)decelerate{
    /* Make sure the alpha is reset even if the user is dragging */
    self.myScrollView.alpha = 1.0f;
}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    UIImage *imageToLoad = [UIImage imageNamed:@"MacBookAir.png"];
    self.myImageView = [[UIImageView alloc] initWithImage:imageToLoad];
    self.myScrollView = [[UIScrollView alloc] initWithFrame:self.view.bounds];
    [self.myScrollView addSubview:self.myImageView];
    self.myScrollView.contentSize = self.myImageView.bounds.size;
    self.myScrollView.delegate = self;
    [self.view addSubview:self.myScrollView];
}
```

As you might have noticed, scroll views have *indicators*. An indicator is the little tracking line that appears on the sides of a scroll view when its contents are getting scrolled and moved. Here is an example:



Figure 2-58. Black indicators appearing on the right and bottom of a scroll view

Indicators simply show the user where in the content the current view. They are similar to scroll bars while you are browsing the internet with your browser. You can control how the indicators look like by changing the value of the `indicatorStyle` property. For instance, here I have changed the indicator style of my scroll view to white:

```
self.myScrollView.indicatorStyle = UIScrollViewIndicatorStyleWhite;
```

One of the great features of scroll views is that they allow pagination. Pagination is the same as scrolling but locks the scrolling when the user moves to the next *page*. You have perhaps already seen this if you've ever used the Photos app on the iPhone or iPad.

When you are looking at photos, you can swipe between them. When one photo is on the screen, your swiping will bring the next/previous photo onto the screen. Your swiping never scrolls all the way to the end or all the way to the start. When the scrolling happens, the scroll view detects the next image to display, scrolls and bounces to that image and will stop the scrolling animation. That, is pagination. If you haven't tried it already I urge you to do so because otherwise I could go on and on and none of this would make sense unless you looked at the Photos app.

For this example code, I've prepared three images: an image of an iPhone, iPad and a MacBook Air and I've placed them in their individual image views and added them to a scroll view. Then we can enable pagination by setting the value of the `pagingEnabled` property of the scroll view to `YES`:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    UIImage *iPhone = [UIImage imageNamed:@"iPhone.png"];
    UIImage *iPad = [UIImage imageNamed:@"iPad.png"];
    UIImage *macBookAir = [UIImage imageNamed:@"MacBookAir.png"];

    CGRect scrollViewRect = self.view.bounds;

    self.myScrollView = [[UIScrollView alloc] initWithFrame:scrollViewRect];
    self.myScrollView.pagingEnabled = YES;
    self.myScrollView.contentSize = CGSizeMake(scrollViewRect.size.width * 3.0f,
                                                scrollViewRect.size.height);
    [self.view addSubview:self.myScrollView];

    CGRect imageViewRect = self.view.bounds;
    UIImageView *iPhoneImageView = [self newImageViewWithImage:iPhone
                                                            frame:imageViewRect];
    [self.myScrollView addSubview:iPhoneImageView];

    /* Go to next page by moving the x position of the next image view */
    imageViewRect.origin.x += imageViewRect.size.width;
    UIImageView *iPadImageView = [self newImageViewWithImage:iPad
                                                            frame:imageViewRect];
    [self.myScrollView addSubview:iPadImageView];

    /* Go to next page by moving the x position of the next image view */
    imageViewRect.origin.x += imageViewRect.size.width;
    UIImageView *macBookAirImageView =
        [self newImageViewWithImage:macBookAir
                                frame:imageViewRect];
    [self.myScrollView addSubview:macBookAirImageView];
}
```

Now we have 3 pages of scrollable content:




Figure 2-59. Scrolling through pages in a page-enabled scroll view

See Also

XXX

2.19 Loading Web Pages with UIWebView

Problem

You want to be able to dynamically load a web page right inside your iOS app.

Solution

Use the `UIWebView` class.

Discussion

A web view is what the Safari browser uses on iOS in order to load web content. You have the whole power of Safari in your iOS apps through the use of `UIWebView` class. All you have to do is to place a web view on your UI and use one of its loading methods:

`loadData:MIMETYPE:textEncodingName:baseUrl:`

Loads an instance of `NSData` into the web view.

`loadHTMLString:baseUrl:`

This loads an instance of `NSString` into the web view. The string should be a valid HTML, or in other words, something that a web browser can render.

`loadRequest:`

Loads an instance of `NSURLRequest`. This is useful when you want to load the contents of a remote URL into a web view inside your application.

Let's see an example. We'll start with the header file of our view controller:

```
#import <UIKit/UIKit.h>

@interface Loading_Web_Pages_with_UIWebViewViewController
    : UIViewController

@property (nonatomic, strong) UIWebView *myWebView;

@end
```

And as you know, we will now synthesize our property:

```
#import "Loading_Web_Pages_with_UIWebViewViewController.h"

@implementation Loading_Web_Pages_with_UIWebViewViewController

@synthesize myWebView;

...
```

And then I would like to load the string *iOS 5 Programming Cookbook* into the web view. To prove things are working as expected and that our web view is capable of rendering rich text, I will go ahead and make the *Programming* part bold and I'll leave the rest of the text intact:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myWebView = [[UIWebView alloc] initWithFrame:self.view.bounds];
    [self.view addSubview:self.myWebView];
```

```
NSString *htmlString = @"iOS 5 Programming <strong>Cookbook</strong>";

[self.myWebView loadHTMLString:htmlString
                        baseURL:nil];
}
```



Figure 2-60. Loading rich text into a web view

Another way to use a web view is to load a remote URL into them. For this purpose, we can use the `loadRequest:` method. Let's go ahead and have a look at an example where we will load Apple's main page into a web view in our iOS app:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myWebView = [[UIWebView alloc] initWithFrame:self.view.bounds];
    self.myWebView.scalesPageToFit = YES;
    [self.view addSubview:self.myWebView];

    NSURL *url = [NSURL URLWithString:@"http://www.apple.com"];
    NSURLRequest *request = [NSURLRequest requestWithURL:url];

    [self.myWebView loadRequest:request];
}
```




Figure 2-61. Apple's home page loaded into a web view

It might take quite a while for a web view to load the contents that you pass to it. If you've noticed, when loading contents in Safari, you will get a little activity indicator on top left corner of the screen telling you that the device is in fact loading the contents. Here is an example:



Figure 2-62. A progress bar indicating a loading process

The way iOS does this is through delegation. We will subscribe as the delegate of a web view and the web view will tell us when it starts to load contents. When the content is fully loaded, we get a message from web view informing us about this. We do this through the `delegate` property of the web view. A delegate of a web view must conform to the `UIWebViewDelegate` protocol. Let's go ahead and implement the little activity indicator in our view controller. Please bear in mind that the activity indicator is already a part of the application and we don't have to create it. We can control it using the `setNetworkActivityIndicatorVisible:` method of `UIApplication`. So let's start with the header file of our view controller:

```
#import <UIKit/UIKit.h>

@interface Loading_Web_Pages_with_UIWebViewViewController
    : UIViewController <UIWebViewDelegate>

@property (nonatomic, strong) UIWebView *myWebView;

@end
```

And then do the implementation. Here we will use three of the methods declared in the `UIWebViewDelegate` protocol:

webViewDidStartLoad:

This method gets called as soon as the web view starts loading contents.

webViewDidFinishLoad:

This method gets called as soon as the web view finishes loading contents.

webView:didFailLoadWithError:

This method gets called when the web view stops loading contents because of an error, for instance, broken network connection.

```

- (void)webViewDidStartLoad:(UIWebView *)webView{
    [[UIApplication sharedApplication] setNetworkActivityIndicatorVisible:YES];
}

- (void)webViewDidFinishLoad:(UIWebView *)webView{
    [[UIApplication sharedApplication] setNetworkActivityIndicatorVisible:NO];
}

- (void)webView:(UIWebView *)webView didFailLoadWithError:(NSError *)error{
    [[UIApplication sharedApplication] setNetworkActivityIndicatorVisible:NO];
}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myWebView = [[UIWebView alloc] initWithFrame:self.view.bounds];
    self.myWebView.delegate = self;
    self.myWebView.scalesPageToFit = YES;
    [self.view addSubview:self.myWebView];

    NSURL *url = [NSURL URLWithString:@"http://www.apple.com"];
    NSURLRequest *request = [NSURLRequest requestWithURL:url];

    [self.myWebView loadRequest:request];
}

```

See Also

XXX

2.20 Presenting Master-Detail Views with UISplitViewController

Problem

You want to take maximum advantage of iPad's massive screen by presenting two side by side view controllers.

Solution

Use the `UISplitViewController` class.


Discussion

Split view controllers are present only on the iPad. If you've used an iPad, you've most probably already seen them. Just open the Settings app in landscape mode and have a look:



Figure 2-63. Split view controller in the Settings app on the iPad

Can you see the split view controller there in [Figure 2-63](#). There is a left and a right side to the split view controller. The left side displays the main settings and tapping on each one of those settings shows the details of that setting item on the right side of the split view controller.



Never attempt to instantiate an object of type `UISplitViewController` on a device other than an iPad. This will raise an exception.

Apple has made it extremely easy to create split view controller based applications. Simply follow these steps to create your app based on split view controllers:

1. In Xcode, navigate to the File menu and choose New→New Project...
2. In the New Project screen, pick iOS→Application on the left side and then pick Master-Detail Application, as shown in [Figure 2-64](#) and press Next.




Figure 2-64. Picking the Master-Detail Application project template in Xcode

3. In this screen, pick your Product Name and make sure your Device Family is Universal. We want to make sure our app runs both on the iPhone and the iPad. Once you are done, press Next (see [Figure 2-65](#))




Figure 2-65. Setting the master-detail project settings in Xcode

4. Now pick where you would like to save your project. Once done, press the Create button (see [Figure 2-66](#)).




Figure 2-66. Saving the new master-detail application on disk

Now the project is created. In the Scheme breadcrumb button on top left corner of Xcode, make sure your app is set to run on the iPad Simulator instead of the iPhone Simulator. If you create a universal master-detail app in Xcode, Xcode makes sure that your app runs on the iPhone as well but when you run your app on the iPhone, the structure of the app will be different in that you will have a navigation controller with a view controller inside it whereas running the same app on the iPad will use a split view controller with two view controllers inside it.

There are two files that are very important to note in the split view controller project template:

RootViewController

Is the master view controller that appears on the left side of the split view controller on the iPad. On the iPhone, it is the first view controller that the user sees.

DetailViewController

Is the detail view controller that appears on the right side of the split view controller on the iPad. On the iPhone, it is the view controller that gets pushed onto the stack once the user taps on any of the items on the root (first, master) view controller.

The communication between the master and the detail view controller is something that we need to think about. Do we want the communication to be done through the app delegate or do we want the master view controller to send messages to the detail view controller directly? That's really up to us.

If you run the app in iPad Simulator, you'll notice that in landscape mode, we can see our master and detail view controllers in the split view controller but as soon as we rotate the orientation to portrait, our master view controller is gone and is replaced with a *Master* navigation button on top left side of the navigation bar of the detail view controller. Although this is good, we weren't expecting it, since we were comparing it with the Settings app on the iPad. If you rotate the settings app to portrait on an iPad, you can still see both the master and the detail view controllers. How can we do this? It turns out Apple has exposed an API to us through which we can accomplish this. Simply go to the *DetailViewController.m* file and implement this method:

```
- (BOOL) splitViewController:(UISplitViewController *)svc
    shouldHideViewController:(UIViewController *)vc
    inOrientation:(UIInterfaceOrientation)orientation{
    return NO;
}
```



This method is available only in iOS SDK 5.0.

If you return *NO* from this method, iOS will *not* the master view controller in either orientation so that is a relief. Now that we implemented this method, we won't need these two methods anymore:

```
- (void)splitViewController:(UISplitViewController *)svc
    willHideViewController:(UIViewController *)aViewController
    withBarButtonItem:(UIBarButtonItem *)barButtonItem
    forPopoverController: (UIPopoverController *)pc{
    barButtonItem.title = @"Master";
    NSMutableArray *items = [[self.toolbar items] mutableCopy];
    [items insertObject:barButtonItem atIndex:0];
    [self.toolbar setItems:items animated:YES];
    self.popoverController = pc;
}

- (void)splitViewController:(UISplitViewController *)svc
    willShowViewController:(UIViewController *)aViewController
    invalidatingBarButtonItem:(UIBarButtonItem *)barButtonItem{
    NSMutableArray *items = [[self.toolbar items] mutableCopy];
```



```

        [items removeObjectAtIndex:0];
        [self.toolbar setItems:items animated:YES];
        self.popoverController = nil;
    }

```

These methods were there simply to manage the navigation bar button for us but now that we are not using that button anymore, we can get rid of these methods. So comment them out or just remove them from the *DetailViewController.m* file.

At the moment, the communication between the master and the detail view controller through messaging seems impossible as the master doesn't have a reference to the detail view controller. Let's remedy that, shall we? The app delegate is the object that created both these view controllers so we can keep the reference to the detail view controller in app delegate and read it in the master view controller. Let's add a property to our app delegate and call it `detailViewController`:

```

#import <UIKit/UIKit.h>

@class DetailViewController;

@interface Presenting_Master_Detail_Views_with UISplitViewControllerAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) UINavigationController *navigationController;
@property (nonatomic, strong) UISplitViewController *splitViewController;

@property (nonatomic, readonly, strong)
    DetailViewController *detailViewController;

@end

```

And now in the implementation of the app delegate, we need to first synthesize our new property:

```
@synthesize detailViewController;
```

In the app delegate's implementation file, we can see the `application:didFinishLaunchingWithOptions:` selector. Find this line of code in that method:

```

DetailViewController *detailViewController =
    [[DetailViewController alloc] initWithNibName:@"DetailViewController_iPad"
        bundle:nil];

```

There, the app will instantiate an object of type `DetailViewController` and will place it inside the split view controller. However, as you can see, `detailViewController` in this code is a local variable and it shadows our property that has the same name so we need to remove the local variable declaration and change it to this:

```

detailViewController =
    [[DetailViewController alloc] initWithNibName:@"DetailViewController_iPad"
        bundle:nil];

```

All good, now in the root view controller (master), find this method:

```

- (void) tableView:(UITableView *)tableView
didSelectRowAtIndexPath:(NSIndexPath *)indexPath{

    if ([[UIDevice currentDevice] userInterfaceIdiom]
        == UIUserInterfaceIdiomPhone) {

        DetailViewController *detailViewController =
            [[DetailViewController alloc]
             initWithNibName:@"DetailViewController_iPhone"
             bundle:nil];
        [self.navigationController pushViewController:detailViewController
         animated:YES];

    } else {
        /* iPad */
    }
}

```

This method gets called whenever the user taps on one of the items in the master view controller. As you can see, the logic is empty if the device is an iPad so let's go ahead and in here, retrieve the reference to the detail view controller through the app delegate:

```

- (void) tableView:(UITableView *)tableView
didSelectRowAtIndexPath:(NSIndexPath *)indexPath{

    if ([[UIDevice currentDevice] userInterfaceIdiom]
        == UIUserInterfaceIdiomPhone) {

        DetailViewController *detailViewController =
            [[DetailViewController alloc]
             initWithNibName:@"DetailViewController_iPhone"
             bundle:nil];
        [self.navigationController pushViewController:detailViewController
         animated:YES];

    } else {
        /* iPad */

        Presenting_Master_Detail_VIEWS_with UISplitViewControllerAppDelegate
        *appDelegate = [[UIApplication sharedApplication] delegate];

        NSLog(@"%@", appDelegate.detailViewController);

    }
}

```

Great, now we have a reference to the detail view controller. Using this reference, you can now send messages to the detail view controller and ask it to perform various tasks based on the user's selection on the master view controller.

See Also

XXX

2.21 Enabling Paging with UIPageViewController

Problem

You want to create an app that is similar to iBooks where the user can flip through the pages of a book as if it was a real book, to provide an intuitive and real user experience.

Solution

Use `UIPageViewController`.

Discussion

Xcode has a template for page view controllers. It's best we first see how they look like before we read an explanation of what they actually are. So follow these steps to create your app to use page view controllers:



Page view controllers work both on the iPhone and the iPad.

1. In Xcode, go to the File menu and then choose New→New Project...
2. On the left hand side of the New Project window, make sure you've selected iOS and then Application. Once that is done, pick the Page-Based Application template from the right side and press Next, as shown in [Figure 2-67](#).




Figure 2-67. Creating a Page-Based Application in Xcode

3. Now select a product name and make sure the Device Family that you've chosen is Universal, as we would want our app to run on both the iPhone and the iPad (see [Figure 2-68](#)). Once you are done, press Next.




Figure 2-68. Setting the project settings of a page-based app

4. Select where you want to save your project. Once you are done, press the Create button. We've now successfully created our project.

You can now see that Xcode has created quite a few classes in your project. Let's have a quick look at what each one of these classes does:

Delegate Class

The app delegate simply creates an instance of `RootViewController` class and presents it to the user. There is one `.xib` for iPad and another one of iPhone but both are using the aforementioned class; just keep that in mind.

RootViewController

Creates an instance of `UIPageViewController` and adds that view controller to itself so the UI of this view controller is actually a mix of two view controllers, one of itself and the other of a page view controller. This view controller also sets itself as the delegate of the page view controller and creates an instance of the `ModelController` class and sets it as the datasource of the page view controller.

DataViewController

For every page in the page view controller, an instance of this class gets presented to this user. This class is a subclass of `UIViewController`.

ModelController

This is simply a subclass of `NSObject` which conforms to the `UIPageViewControllerDataSource` protocol. This class is the data source of the page view controller.

So you can see that a page view controller has both a delegate and a data source and with Xcode's default page-based application template, the root view controller becomes the delegate and the model controller becomes the data source of the page view controller. In order to understand how a page view controller really works, we need to understand its delegation and data source protocols. Let's start with the delegate, `UIPageViewControllerDelegate`. This protocol has two important methods:

- (void)pageViewController:(UIPageViewController *)pageViewController
didFinishAnimating:(BOOL)finished
previousViewControllers:(NSArray *)previousViewControllers
transitionCompleted:(BOOL)completed;
- (UIPageViewControllerSpineLocation)
pageViewController:(UIPageViewController *)pageViewController
spineLocationForInterfaceOrientation:(UIInterfaceOrientation)orientation;

The first method gets called when the user turns to the next or the previous page *or* if the user initiates the movement from one page to the other but decides against it while the page is moving in which case, the user gets sent back to the page she was in before. The `transitionCompleted` will get set to YES if this was a successful page animation or gets set to NO if the user decided against the movement and cancelled it in the middle of the animation.

The second method gets called whenever the device orientation changes. You can use this method to specify the location of the spine for the pages by returning a value of type `UIPageViewControllerSpineLocation`:

```
enum {  
    UIPageViewControllerSpineLocationNone = 0,  
    UIPageViewControllerSpineLocationMin = 1,  
    UIPageViewControllerSpineLocationMid = 2,  
    UIPageViewControllerSpineLocationMax = 3  
};  
typedef NSInteger UIPageViewControllerSpineLocation;
```

This might be a bit confusing to you but let me demonstrate. If we are using a `UIPageViewControllerSpineLocationMin` spine location, the page view controller will only require 1 view controller to present to the user and when the goes to the next page, a new view controller will be presented to her. However, if we set the spine location to `UIPageViewControllerSpineLocationMid`, we will be required to display 2 view controllers at the same time. One on the left and another on the right with the spine sitting between them. Let me show you what I mean. In [Figure 2-69](#) you can see an example of a page view controller in landscape mode with spine location set to `UIPageViewControllerSpineLocationMin`:




Figure 2-69. One view controller presented in a page view controller in landscape mode

Now if we return the spine location of `UIPageViewControllerSpineLocationMid`, we will get results similar to this:




Figure 2-70. Two view controllers displayed in a page view controller in landscape mode

As you can see in [Figure 2-70](#), the spine is located exactly in the center of the screen between two view controllers. Once the user flips a page from right to the left, the page rests on the left and the page view controller reveals a new view controller on the right side. This whole logic is in this delegate method:

```
- (UIPageViewControllerSpineLocation)
    pageViewController:(UIPageViewController *)pageViewController
    spineLocationForInterfaceOrientation:(UIInterfaceOrientation)orientation;
```

We talked about the delegate of the page view controller but how about the data source? The data source of a page view controller must conform to the `UIPageViewControllerDataSource`. Two of the very important methods that this protocol exposes are:

```
- (UIViewController *)
    pageViewController:(UIPageViewController *)pageViewController
    viewControllerBeforeViewController:(UIViewController *)viewController;

- (UIViewController *)
    pageViewController:(UIPageViewController *)pageViewController
    viewControllerAfterViewController:(UIViewController *)viewController;
```

The first method gets called when the page view controller already has a view controller on the screen and now needs to know what the next view controller to render is. This

happens when the user decides to flip to the next page. The second method is called when the page view controller wants to figure out which view controller to display after the view controller which is being flipped.

Xcode, as you've already seen it, has greatly simplified setting up a page-based application. All you really need to do now is to provide content to the data model (**Model Controller**) and on you go. If you need to customize the colors and images in your view controllers, simply do so by either using the Interface Builder to modify the *.xib* files directly or write your own code in the implementation of each of the view controllers.

See Also

XXX

2.22 Displaying Popovers with UIPopoverController

Problem

You want to display content on an iPad without blocking the whole screen.

Solution

Use popovers.

Discussion

Popovers are used to display additional information on the iPad screen. An example is the Safari app on the iPad. When the user taps on the Bookmarks button, she will see a popover displaying the bookmarks content on the screen (see [Figure 2-71](#)).




Figure 2-71. The bookmarks popover in the Safari app on an iPad

The default behaviour of popovers is that when the user taps somewhere outside the region of the popover, the popover will automatically get dismissed. We can ask the popover to not get dismissed if the user taps on specific parts of the screen, as we will see later. Popovers present their content by using a view controller. Note that you can also navigation controllers inside popovers as navigation controllers subclass `UIViewController`.



Popovers can only be used on iPad devices. If you have a view controller whose code runs both on an iPad and on an iPhone, you need to make sure that you are not instantiating the popover on a device other than the iPad.

Popovers can be presented to the user in two ways:

1. From inside a navigation button, an instance of `UIBarButtonItem`.
2. From inside a rectangular area in a view.

When a device orientation is changed (the device is rotated), popovers are either dismissed or hid temporarily. You need to make sure that you give your users a good experience by redisplaying the popover after the orientation change has settled, if possible. In certain cases, your popover might get dismissed automatically after an orientation change. For instance, if the user taps on a navigation button in landscape mode you might display a popover on the screen. Your app is designed in a way that when the orientation changes to portrait, you will remove that navigation button from the

navigation bar, for whatever reason. Now, the correct user experience would be to hide the popover associated with that navigation bar after the orientation of the device is changed to portrait. In some instances though, you will need to play with popovers a bit to give your users a good experience because not in all instances handling a device orientation is as straightforward as the aforementioned scenario.

To create the demo popover app, we need to first come up with a strategy based on our requirements: we want to build an app with a view controller loaded inside a navigation controller. The root view controller will display a + button on the right corner of its navigation bar. When the + button is tapped on an iPad device, it will display a popover with two buttons on it. The first button will say "Photo" and the second button will say "Audio". When the same navigation button is tapped on an iPhone device, we will display an alert view with three buttons. The two aforementioned buttons and a cancel button so that the user can cancel the alert view if she wishes to. When these buttons are tapped (whether on the alert view on an iPhone or the popover on an iPad, we won't really do anything. We will simply dismiss the alert view or the popover.

Let's go ahead and create a Single View universal project in Xcode and name the project *Displaying_Popovers_with_UIPopoverControllerViewController* and then let's go to our app delegate's header file and define a navigation controller first:

```
#import <UIKit/UIKit.h>

@class Displaying_Popovers_with_UIPopoverControllerViewController;

@interface Displaying_Popovers_with_UIPopoverControllerAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;

@property (nonatomic, strong)
    Displaying_Popovers_with_UIPopoverControllerViewController *viewController;

@property (nonatomic, strong) UINavigationController *navigationController;

@end
```

Next, we will synthesize and instantiate our navigation controller in the app delegate's implementation file and instead of the view controller, we will display the navigation controller to the user:

```
#import "Displaying_Popovers_with_UIPopoverControllerAppDelegate.h"

#import "Displaying_Popovers_with_UIPopoverControllerViewController.h"

@implementation Displaying_Popovers_with_UIPopoverControllerAppDelegate

@synthesize window = _window;
@synthesize viewController = _viewController;
@synthesize navigationController;

- (BOOL)application:(UIApplication *)application
```

```

didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    UIUserInterfaceIdiom uiIdiom = [[UIDevice currentDevice] userInterfaceIdiom];

    NSString *viewControllerClass =
        @"Displaying_Popovers_with_UIPopoverControllerViewController_iPad";

    if (uiIdiom == UIUserInterfaceIdiomPhone) {
        viewControllerClass =
            @"Displaying_Popovers_with_UIPopoverControllerViewController_iPhone";
    }

    self.viewController =
    [[Displaying_Popovers_with_UIPopoverControllerViewController alloc]
        initWithNibName:viewControllerClass
        bundle:nil];

    self.navigationController = [[UINavigationController alloc]
        initWithRootViewController:self.viewController];

    self.window.rootViewController = self.navigationController;
    [self.window makeKeyAndVisible];
    return YES;
}

```

After this, we need to go into the definition file of our view controller and define a property of type `UIPopoverController`:

```

#import <UIKit/UIKit.h>

@interface Displaying_Popovers_with_UIPopoverControllerViewController
    : UIViewController <UIAlertViewDelegate>

@property (nonatomic, strong) UIPopoverController *popoverController;
@property (nonatomic, strong) UIBarButtonItem *barButtonItem;

@end

```

You can see that we are also defining a property called `barButtonItem` in our view controller. This is the navigation button which we will add on our navigation bar and our plan is to display our popover when the user taps on this button (you can read more about navigation buttons in [Recipe 2.11](#)). However, we need to make sure we instantiate the popover only if the device is an iPad. Before we go ahead and implement our root view controller with the navigation button, let's go ahead and create a subclass of `UIViewController` and name it *PopoverContentViewController*. We will display the contents of this view controller inside our popover later. See [Recipe 2.7](#) for information about view controllers and ways of creating them.

The content view controller displayed inside the popover will have two buttons (as per our requirements). However, this view controller will need to have reference to the

popover controller in order to dismiss the popover when the user taps on any of the buttons. For this, we need to define a property in our content view controller to refer to the popover:

```
#import <UIKit/UIKit.h>

@interface PopoverContentViewController : UIViewController

@property (nonatomic, strong) UIButton *buttonPhoto;
@property (nonatomic, strong) UIButton *buttonAudio;
/* We shouldn't define this as strong. That will create a retain cycle
between the popover controller and the content view controller since the
popover controller retains the content view controller and the view controller will
retain the popover controller */
@property (nonatomic, weak) UIPopoverController *popoverController;

@end
```

Now we will go and synthesize these properties in the implementation file of our content view controller:

```
#import "PopoverContentViewController.h"

@implementation PopoverContentViewController

@synthesize buttonPhoto;
@synthesize buttonAudio;
@synthesize popoverController;

...
```

After this, we shall go ahead and create our two buttons in the content view controller and link them to their action methods. These methods shall take care of dismissing the popover that is displaying this view controller. Remember, the popover controller will be responsible for assigning itself to the `popoverController` property of the content view controller:

```
#import "PopoverContentViewController.h"

@implementation PopoverContentViewController

@synthesize buttonPhoto;
@synthesize buttonAudio;
@synthesize popoverController;

- (BOOL) isInPopover{

    Class popoverClass = NSClassFromString(@"UIPopoverController");

    if (popoverClass != nil &&
        UI_USER_INTERFACE_IDIOM() == UIUserInterfaceIdiomPad &&
        self.popoverController != nil){
        return YES;
    } else {
        return NO;
    }
}
```

```

    }

}

- (void) gotoAppleWebsite:(id)paramSender{

    if ([self isInPopover]){
        /* Go to website and then dismiss popover */
        [self.popoverController dismissPopoverAnimated:YES];
    } else {
        /* Handle case for iPhone */
    }

}

- (void) gotoAppleStoreWebsite:(id)paramSender{

    if ([self isInPopover]){
        /* Go to website and then dismiss popover */
        [self.popoverController dismissPopoverAnimated:YES];
    } else {
        /* Handle case for iPhone */
    }

}

- (void) viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.contentSizeForViewInPopover = CGSizeMake(200.0f, 125.0f);

    CGRect buttonRect = CGRectMake(20.0f,
                                    20.0f,
                                    160.0f,
                                    37.0f);

    self.buttonPhoto = [UIButton buttonWithType:UIButtonTypeRoundedRect];
    [self.buttonPhoto setTitle:@"Photo"
                      forState:UIControlStateNormal];
    [self.buttonPhoto addTarget:self
                      action:@selector(gotoAppleWebsite:)
                      forControlEvents:UIControlEventTouchUpInside];

    self.buttonPhoto.frame = buttonRect;

    [self.view addSubview:self.buttonPhoto];

    buttonRect.origin.y += 50.0f;
    self.buttonAudio = [UIButton buttonWithType:UIButtonTypeRoundedRect];

    [self.buttonAudio setTitle:@"Audio"

```

```

        forState:UIControlStateNormal];
[self.buttonAudio addTarget:self
                        action:@selector(gotoAppleStoreWebsite:)
                        forControlEvents:UIControlEventTouchUpInside];

self.buttonAudio.frame = buttonRect;

[self.view addSubview:self.buttonAudio];
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.buttonPhoto = nil;
    self.buttonAudio = nil;
}

- (BOOL)shouldAutorotateToInterfaceOrientation
    :(UIInterfaceOrientation)interfaceOrientation{
    return YES;
}

@end

```

Now good? Now let's go back to our root view controller and synthesize our properties:

```

#import "Displaying_Popovers_with_UIPopoverControllerViewController.h"
#import "PopoverContentViewController.h"

@implementation Displaying_Popovers_with_UIPopoverControllerViewController

@synthesize popoverController;
@synthesize barButtonAdd;

...

```

Now in the `viewDidLoad` method of our root view controller, we will create our navigation button and based on the device type, when the navigation bar is tapped, we will either display a popover (on the iPad) or an alert view (on the iPhone):

```

- (void)viewDidLoad{
    [super viewDidLoad];

    /* See if this class exists on the iOS running the app */
    Class popoverClass = NSClassFromString(@"UIPopoverController");

    if (popoverClass != nil &&
        UI_USER_INTERFACE_IDIOM() == UIUserInterfaceIdiomPad){

        PopoverContentViewController *content =
            [[PopoverContentViewController alloc] initWithNibName:nil
                                                         bundle:nil];

        self.popoverController = [[UIPopoverController alloc]
                                   initWithContentViewController:content];
    }
}

```

```

content.popoverController = self.popoverController;

self.barButtonItem = [[UIBarButtonItem alloc]
    initWithBarButtonSystemItem:UIBarButtonSystemItemAdd
    target:self
    action:@selector(performAddWithPopover:)];

} else {

    self.barButtonItem = [[UIBarButtonItem alloc]
        initWithBarButtonSystemItem:UIBarButtonSystemItemAdd
        target:self
        action:@selector(performAddWithAlertView:)];

}

[self.navigationItem setRightBarButtonItem:self.barButtonItem
    animated:NO];

}

- (void)viewDidLoad{
    [super viewDidLoad];
    self.barButtonItem = nil;
}

- (BOOL)shouldAutorotateToInterfaceOrientation
    :(UIInterfaceOrientation)interfaceOrientation{
    return YES;
}

```



The popover controller sets a reference to itself in the content view controller after its initialization. This is very important. A popover controller *cannot* be initialized without a content view controller. Once the popover is initialized with a content view controller, you can go ahead and change the content view controller in the popover controller, but not during the initialization.

We have elected the `performAddWithPopover:` method to be invoked when the + navigation bar button is tapped on an iPad device. If the device isn't an iPad, we've asked the + navigation bar button to invoke the `performAddWithAlertView:` method so let's go ahead and implement these methods and also take care of the delegate methods of our alert view, so that we know what alert view button the user tapped on, on an iPhone:

```

- (NSString *) photoButtonTitle{
    return @"Photo";
}

- (NSString *) audioButtonTitle{
    return @"Audio";
}

```



```

}

- (void)      alertView:(UIAlertView *)alertView
didDismissWithButtonIndex:(NSInteger)buttonIndex{

    NSString *buttonTitle = [alertView buttonTitleAtIndex:buttonIndex];

    if ([buttonTitle isEqualToString:[self photoButtonTitle]]){
        /* Adding a photo ... */
    }
    else if ([buttonTitle isEqualToString:[self audioButtonTitle]]){
        /* Adding an audio... */
    }
}

}

- (void) performAddWithAlertView:(id)paramSender{

    [[[UIAlertView alloc] initWithTitle:nil
                                   message:@"Add..."
                                   delegate:self
                                   cancelButtonTitle:@"Cancel"
                                   otherButtonTitles:
        [self photoButtonTitle],
        [self audioButtonTitle], nil] show];

}

- (void) performAddWithPopover:(id)paramSender{

    [self.popoverController
     presentPopoverFromBarButtonItem:self.barButtonAdd
     permittedArrowDirections:UIPopoverArrowDirectionAny
     animated:YES];

}

```

If you now go ahead and run your app on iPad Simulator and tap on the + button on the navigation bar, you will see an interface similar to that shown in [Figure 2-72](#):




Figure 2-72. Our simple popover displayed when a navigation button was tapped

If you run the same universal app on the iPhone Simulator and tap the + button on the navigation bar, you will see results similar to that shown in [Figure 2-73](#):



Figure 2-73. Popovers are replaced by alert view in a universal app

We used an important property of our content view controller and that was the `contentSizeForViewInPopover` property. The popover, when displaying its content view controller, will read the value of this property automatically and will adjust its size (width and height) to this size. Also, we used the `presentPopoverFromBarButtonItem:permittedArrowDirections:animated:` method of our popover in our root view controller to display the popover over a navigation bar button. The first parameter to this method is the navigation bar button from which the popover controller has to be displayed. The second parameter specifies the direction of the popover on appearing, in relation to the object from which it appears. For example, in [Figure 2-72](#) you can see that our

popover's arrow is pointing up towards the navigation bar button. The value that you pass to this parameter must be of type `UIPopoverArrowDirection`:

```
enum {
    UIPopoverArrowDirectionUp = 1UL << 0,
    UIPopoverArrowDirectionDown = 1UL << 1,
    UIPopoverArrowDirectionLeft = 1UL << 2,
    UIPopoverArrowDirectionRight = 1UL << 3,
    UIPopoverArrowDirectionAny = UIPopoverArrowDirectionUp |
        UIPopoverArrowDirectionDown |
        UIPopoverArrowDirectionLeft |
        UIPopoverArrowDirectionRight,
    UIPopoverArrowDirectionUnknown = NSUIntegerMax
};
typedef NSUInteger UIPopoverArrowDirection;
```

See Also

XXX

2.23 Displaying Progress with `UIProgressView`

Problem

You want to display a progress bar on the screen, depicting the progress of a certain task, for instance, the progress of downloading a file from a URL.

Solution

Instantiate a view of type `UIProgressView` and place it on another view.

Discussion

A progress view is what programmers know of, as progress bar. An example of a progress view is depicted in a figure to come.

Progress views are generally displayed to users to show them the progress of a task that has a well-defined start and ending point. For instance, downloading 30 files is a well-defined task with a specific start and ending point. This task obviously finishes when all 30 files have been downloaded. A progress view is an instance of `UIProgressView` and is initialized using the designated initializer of this class, the `initWithProgressViewStyle:` method. This method takes in the style of the progress bar to be created, as a parameter. This parameter is of type `UIProgressViewStyle` and can therefore be one of the following values:

`UIProgressViewStyleDefault`

This is the default style of the progress view. An example of this is the progress view shown in a figure to come.

UIProgressViewStyleBar

Is similar to the `UIProgressViewStyleDefault` but is meant to be used for progress views that are to be added to a tool-bar.

An instance of `UIProgressView` defines a property called `progress` (of type `float`). This property tells iOS how the bar inside the progress view should be rendered. This value must be in the range +0 to +1.0. If the value of +0 is given, the progress will appear to have not yet started. Value of +1.0 shows the progress of 100%. The progress depicted in figure to come is 0.5 (or 50%). To get used to creating progress views, let's immediately go and create one similar to what we saw earlier in a figure to come. First thing's first, we need to define a property for our progress view:

```
#import <UIKit/UIKit.h>

@interface ViewController : UIViewController

@property (nonatomic, strong) UIProgressView *progressView;

@end
```

On to synthesizing our property...:

```
#import "ViewController.h"

@implementation ViewController

@synthesize progressView;

...
```

And eventually we will instantiate an object of type `UIProgressView`:

```
- (void)viewDidLoad{

    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];

    self.progressView = [[UIProgressView alloc]
                        initWithProgressViewStyle:UIProgressViewStyleBar];
    self.progressView.center = self.view.center;
    self.progressView.progress = 0.5f;


    [self.view addSubview:self.progressView];
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.progressView = nil;
}
```

Obviously, creating a progress view is very straightforward. All you really need to take care of is to display your progress correctly because the `progress` property of a progress view should be in the range +0 to +1.0 (which is a normalized value) so if you have 30

tasks to take care of and you have completed 20 of them so far, you need to assign the result of the following equation to the **progress** property of your progress view:

```
self.progressView.progress = 20.0f / 30.0f;
```



The reason the values 20 and 30 are passed to the equation as floating point values is to tell the compiler that the division has to happen on floating point values, producing a value with decimal numbers. However, you provided the result of 20/30 to the compiler to place inside the **progress** property of your progress view, you would get the integral value of 0 out of the division because your division will all of a sudden become a division between two integers and clearly, 20 cannot be divided by 30 so the result will be 0, ultimately setting the progress of your progress view to zero; not what you'd expect.

See Also

XXX

2.24 Listening and Reacting to Keyboard Notifications

Problem

You are allowing the user to enter some text in your UI, using a text field or a text view or other components that require the keyboard's presence. However, when the keyboard pops up on the screen, it obstructs a good half of your UI, rendering it useless. You want to avoid this situation.

Solution

Listen to keyboard notifications and move your UI components up/down or completely reshuffle your components so that with the keyboard obstructing the screen, what is essential to the user is still visible to her. For more information about the actual notifications sent by the keyboard, please refer to the Discussion section of this recipe.

Discussion

iOS devices do not have a physical keyboard. They have a software keyboard which pops up whenever the user has to enter some text into a text entry such as a text field (UITextField, see [Recipe 2.14](#) for more information) or a text view (UITextView, see [Recipe 2.15](#) for more information). On the iPad, the user can even split the keyboard and move it up and down. These are some of the edge cases that you might want to take care of when designing your user interface. You can work with the UI designers in your company (if you are working with one) and let them know about the possibility of the user splitting the keyboard on the iPad. They will need to know about that before making the artworks and creatives. We will discuss that edge-case in this recipe.

Let's have a look at the keyboard in iPhone first. The keyboard can get displayed in portrait and landscape mode. In portrait, the keyboard on an iPhone looks like this:



Figure 2-74. Portrait mode keyboard on an iPhone

The keyboard in landscape mode on an iPhone will look similar to that shown in [Figure 2-75](#):




Figure 2-75. The keyboard in landscape mode on an iPhone

On the iPad however, the keyboard is a bit different. The most obvious difference is that the keyboard is actually much bigger in size compared to the iPhone, since the iPad screen is physically bigger. Also the user can split the keyboard if she wants to. Here is an example of the iPad keyboard in portrait mode:




Figure 2-76. The iPad keyboard in portrait mode

The landscape keyboard on an iPad is wider obviously but contains the same keys as the portrait-mode keyboard does:




Figure 2-77. The iPad keyboard in landscape mode

And here is an example of the split keyboard on the iPad, in landscape mode (the keyboard can be split in landscape mode as well as the portrait mode):




Figure 2-78. Split keyboard on the iPad in landscape mode

iOS broadcasts various notifications related to the keyboard on the screen. Here is a list of these notifications and a brief explanation for each one:

UIKeyboardWillShowNotification

This notification gets sent when the keyboard is about to get displayed on the screen. This notification carries with it a user-info dictionary that contains various information about the keyboard, the animation that the keyboard will use to get displayed on the screen and etc.

UIKeyboardDidShowNotification

This notification gets broadcasted when the keyboard gets displayed on the screen.

UIKeyboardWillHideNotification

This notification is broadcasted when the keyboard is about to get removed from the screen. This notification will carry with it a user-info dictionary that contains various bits and pieces of information about the keyboard, the keyboard's animation when it is hiding, the duration of the animation and etc.

UIKeyboardDidHideNotification

This notification is broadcasted when the keyboard gets fully hidden after it was being shown on the screen.

As already mentioned, only the `UIKeyboardWillShowNotification` and the `UIKeyboardWillHideNotification` notifications carry a user-info dictionary with them with valid keys and values in those dictionaries. Here are the keys in those dictionaries that you might be interested in:

`UIKeyboardAnimationCurveUserInfoKey`

The value of this key specifies the type of animation curve the keyboard is using to show or hide itself. This key contains a value (encapsulated in an object of type `NSValue`) of type `NSNumber` which itself contains an unsigned integer of type `NSUInteger`.

`UIKeyboardAnimationDurationUserInfoKey`

The value of this key specifies the duration of animation the keyboard is using to show or hide itself. This key contains a value (encapsulated in an object of type `NSValue`) of type `NSNumber` which itself contains a double value of type `double`.

`UIKeyboardFrameBeginUserInfoKey`

The value of this key specifies the frame of the keyboard before the animation happens. If the keyboard is about to get displayed, this will be the frame before the keyboard animates up to get displayed. If the keyboard is already displayed and is about to hide, this will be the frame of the keyboard as it is on the screen, before it animates out of the screen. This key contains a value (encapsulated in an object of type `NSValue`) of type `CGRect`.

`UIKeyboardFrameEndUserInfoKey`

The value of this key specifies the frame of the keyboard after the animation happens. If the keyboard is about to get displayed, this will be the frame after the keyboard animates up and is fully displayed. If the keyboard is already displayed and is about to hide, this will be the frame of the keyboard after it is fully hidden. This key contains a value (encapsulated in an object of type `NSValue`) of type `CGRect`.



The frames that get reported by iOS as the beginning and ending frames of the keyboard do not take into account the orientation of the device. We will need to convert the reported `CGRect` values to a relevant orientation-aware coordinate, as we will see soon in this recipe.

Let's have a look at a simple example, shall we? Let's create a simple table view on our view controller's view and change its content inset (the margins from top, right, bottom and left side of the table view) when the keyboard gets displayed. We will populate this table view with 100 cells, enough to fill the entire screen, on both the iPhone and the iPad (in a Universal app) so let's start with the header file of our view controller:

```
#import <UIKit/UIKit.h>

@interface ViewController : UIViewController
    <UITableViewDelegate, UITableViewDataSource, UITextFieldDelegate>

@property (nonatomic, strong) UITableView *myTableView;
```

```
@end
```

Now we need to synthesize the table view property in our view controller's implementation file:

```
#import "ViewController.h"

@implementation ViewController

@synthesize myTableView;

...
```

Next, we will instantiate the table view when our view loads and we will balance the memory management by setting the table view to nil in the `viewDidUnload` method:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.myTableView = [[UITableView alloc]
                        initWithFrame:self.view.bounds
                        style:UITableViewStyleGrouped];

    self.myTableView.delegate = self;
    self.myTableView.dataSource = self;
    self.myTableView.autoresizingMask = UIViewAutoresizingFlexibleWidth |
                                       UIViewAutoresizingFlexibleHeight;
    [self.view addSubview:self.myTableView];
}

- (void)viewDidUnload{
    [self setMyTableView:nil];
    [super viewDidUnload];
}
```

After this, we will need to populate our table view with 100 cells and in each cell, we will create a text field as the accessory view. We do this to allow the user to trigger the keyboard to popup. If we don't have a text field or some means for user to enter text, we will never be able to get the keyboard on the screen so let's do that now:

```
- (BOOL)textFieldShouldReturn:(UITextField *)textField{
    /* Make sure the Done button on the keyboard for each text field
    (accessory views of each cell) dismisses the keyboard */
    [textField resignFirstResponder];
    return YES;
}

- (NSInteger) numberOfSectionsInTableView:(UITableView *)tableView{
    return 1;
}

- (NSInteger) tableView:(UITableView *)tableView
    numberOfRowsInSection:(NSInteger)section{
    return 100;
}
```

```

}

- (UITableViewCell *) tableView:(UITableView *)tableView
  cellForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCell *result = nil;

    static NSString *CellIdentifier = @"CellIdentifier";

    result = [tableView dequeueReusableCellWithIdentifier:CellIdentifier];

    if (result == nil){
        result = [[UITableViewCell alloc] initWithStyle:UITableViewCellStyleDefault
                                           reuseIdentifier:CellIdentifier];
        result.selectionStyle = UITableViewCellSelectionStyleNone;
    }

    result.textLabel.text = [NSString stringWithFormat:
                           @"Cell %ld", (long)indexPath.row];

    CGRect accessoryRect = CGRectMake(0.0f,
                                      0.0f,
                                      150.0f,
                                      31.0f);

    UITextField *accessory = [[UITextField alloc] initWithFrame:accessoryRect];
    accessory.borderStyle = UITextBorderStyleRoundedRect;
    accessory.contentVerticalAlignment = UIControlContentVerticalAlignmentCenter;
    accessory.placeholder = @"Enter Text";
    accessory.delegate = self;
    result.accessoryView = accessory;

    return result;
}

```

Fantastic. If you now run your app on iPhone Simulator, you will see something similar to that shown in [Figure 2-79](#):



Figure 2-79. A table view with text fields for accessory view of each cell

Go ahead now and tap on the first text field (in the first cell). Now scroll the table view all the way down to the last cell and see what happens! You cannot see the last 5-6 cells, can you? What you can see in portrait mode on an iPhone will be similar to that shown in [Figure 2-80](#):



Figure 2-80. Keyboard obstructing the bottom half of a table view

What we can now do is to listen for the `UIKeyboardWillShowNotification` and the `UIKeyboardWillHideNotification` notifications and adjust our table view's content inset accordingly:

```
- (void) viewWillAppear:(BOOL)paramAnimated{
    [super viewWillAppear:paramAnimated];

    NotificationCenter *center = [NSNotificationCenter defaultCenter];


    [center addObserver:self
                 selector:@selector(handleKeyboardWillShow:)
```

```

        name:UIKeyboardWillShowNotification
        object:nil];
[center addObserver:self
 selector:@selector(handleKeyboardWillHide:)
 name:UIKeyboardWillHideNotification
 object:nil];
}

- (void) viewDidDisappear:(BOOL)paramAnimated{
    [super viewDidDisappear:paramAnimated];
    [[NSNotificationCenter defaultCenter] removeObserver:self];
}

```



A common mistake programmers make is to keep listening for keyboard notifications even if their view controller's view is not on the screen. They start listening for notifications in the `viewDidLoad` method and remove themselves as the observer in `viewDidUnload` and/or the `dealloc` method if they don't have ARC enabled. This is a problematic approach because when your view is off the screen, you should not be adjusting any components on your screen if the keyboard is getting displayed on some other view/view controller. Keep in mind that keyboard notifications, just like any other notification, are broadcasted to all observer objects and therefore you need to take extra care to make sure that you do not react to keyboard notifications while your view is off screen.

Now that we have started listening for keyboard notifications, we can implement the observer methods which we submitted to `NSNotificationCenter`. The `handleKeyboardWillShow:` method will be responsible for setting the content inset of our table view:

```

- (void) handleKeyboardWillShow:(NSNotification *)paramNotification{
    NSDictionary *userInfo = [paramNotification userInfo];

    NSValue *animationCurveObject =
        [userInfo valueForKey:UIKeyboardAnimationCurveUserInfoKey];

    NSValue *animationDurationObject =
        [userInfo valueForKey:UIKeyboardAnimationDurationUserInfoKey];

    NSValue *keyboardEndRectObject =
        [userInfo valueForKey:UIKeyboardFrameEndUserInfoKey];

    NSInteger animationCurve = 0;
    double animationDuration = 0.0f;
    CGRect keyboardEndRect = CGRectMake(0, 0, 0, 0);

    [animationCurveObject getValue:&animationCurve];
    [animationDurationObject getValue:&animationDuration];
    [keyboardEndRectObject getValue:&keyboardEndRect];

    [UIView beginAnimations:@"changeTableViewContentInset"
     context:NULL];
}

```



```

[UIView setAnimationDuration:animationDuration];
[UIView setAnimationCurve:(UIViewAnimationCurve)animationCurve];

UIWindow *window = [[[UIApplication sharedApplication] delegate] window];

CGRect intersectionOfKeyboardRectAndWindowRect =
    CGRectIntersection(window.frame, keyboardEndRect);

CGFloat bottomInset = intersectionOfKeyboardRectAndWindowRect.size.height;

self.myTableView.contentInset = UIEdgeInsetsMake(0.0f,
                                                    0.0f,
                                                    bottomInset,
                                                    0.0f);

NSIndexPath *indexPathOfOwnerCell = nil;
/* Also, make sure the selected text field is visible on the screen */
NSInteger numberOfCells = [self.myTableView.dataSource
                           tableView:self.myTableView
                           numberOfRowsInSection:0];

/* So let's go through all the cells and find their accessory text fields.
Once we have the refernece to those text fields, we can see which one of
them is the first responder (has the keyboard) and we will make a call
to the table view to make sure after the keyboard is displayed,
that specific cell is NOT obstructed by the keyboard */
for (NSInteger counter = 0;
     counter < numberOfCells;
     counter++){
    NSIndexPath *indexPath = [NSIndexPath indexPathForRow:counter
                                                    inSection:0];
    UITableViewCell *cell = [self.myTableView cellForRowAtIndexPath:indexPath];
    UITextField *textField = (UITextField *)cell.accessoryView;
    if ([textField isKindOfClass:[UITextField class]] == NO){
        continue;
    }
    if ([textField isFirstResponder]){
        indexPathOfOwnerCell = indexPath;
        break;
    }
}

[UIView commitAnimations];

if (indexPathOfOwnerCell != nil){
    [self.myTableView scrollToRowAtIndexPath:indexPathOfOwnerCell
                                atScrollPosition:UITableViewScrollPositionMiddle
                                animated:YES];
}
}

```

So here is what we are doing in this method, in that order:

1. Retrieve the different animation properties of the keyboard, including its animation time, curve and the frame that the keyboard will have once its animation finished. We do this using the user-info dictionary of the `UIKeyboardWillShowNotification` notification.
2. We will then start an animation block using which we will change the content inset of our table view. Before we do this, we need to know how much of the area of our table view the keyboard will be obstructing.
3. Using the `CGRectIntersection` function, we retrieve the intersection between our window's frame and the frame of the keyboard when it has finished its animation. Using this technique, we can find out how much of the area of our window will be obstructed by the keyboard after its animation, so that we can set the bottom content inset of the table view, accordingly.
4. Set the properties of our animation block, such as its curve and duration and eventually commit the animation. The animation block, as mentioned before, will simply change the content inset of our table view to fit the whole content into the visible area of the screen after the keyboard pops up.



The `CGRectIntersection` function is defined and implemented in the CoreGraphics framework. To be able to compile this code, you will need to make sure that you have linked your app against the aforementioned framework. You can do so by selecting your project's icon in Xcode, then selecting your target from the list that appears on the right hand side. Now you need to select the Build Phases tab and in the Link Binary With Libraries box make sure that your target is linked against this framework. If not, you can press the + button in that box and simply add that framework to the list of framework to which your app links against.

Now we need to move on to the implementation of the `handleKeyboardWillHide:` method:

```
- (void) handleKeyboardWillHide:(NSNotification *)paramNotification{

    if (UIEdgeInsetsEqualToEdgeInsets(self.myTableView.contentInset,
                                      UIEdgeInsetsZero)){
        /* Our table view's content inset is intact so no need to reset it */
        return;
    }

    NSDictionary *userInfo = [paramNotification userInfo];

    NSValue *animationCurveObject =
    [userInfo valueForKey:UIKeyboardAnimationCurveUserInfoKey];

    NSValue *animationDurationObject =
    [userInfo valueForKey:UIKeyboardAnimationDurationUserInfoKey];
```

```

    NSValue *keyboardEndRectObject =
    [userInfo valueForKey:UIKeyboardFrameEndUserInfoKey];

    NSInteger animationCurve = 0;
    double animationDuration = 0.0f;
    CGRect keyboardEndRect = CGRectMake(0, 0, 0, 0);

    [animationCurveObject getValue:&animationCurve];
    [animationDurationObject getValue:&animationDuration];
    [keyboardEndRectObject getValue:&keyboardEndRect];

    [UIView beginAnimations:@"changeTableViewContentInset"
                    context:NULL];
    [UIView setAnimationDuration:animationDuration];
    [UIView setAnimationCurve:(UIViewAnimationCurve)animationCurve];

    self.myTableView.contentInset = UIEdgeInsetsZero;

    [UIView commitAnimations];
}

```

In the `handleKeyboardWillHide:` method, we are doing the following, in that order:

1. Find out if the content inset of our table view has already been changed. If our table view's content inset wasn't changed, then we realistically shouldn't take any further action. We will just assume that we received this notification by mistake or some other object on another view on our view controller caused this notification to get broadcasted.
2. We then, using the user-info dictionary of the `UIKeyboardWillHideNotification` notification, get the duration and curve of the keyboard's animation while it is tucking away. Using this information, we will create an animation block.
3. We set our table view's content inset to `UIEdgeInsetsZero` and commit our animation.

As mentioned before, when the keyboard notifications are broadcasted, the current orientation of the device is *not* taken into account to construct the starting and ending frames of our table view. For instance, if we log the ending frame of our keyboard in the `handleKeyboardWillShow:` method of our view controller on an iPhone in portrait mode, we will get the following values:

```
{{0, 264}, {320, 216}}
```

If you now rotate the orientation to landscape and log the values again, you will see the following value printed out to the console window:

```
{{0, 0}, {162, 480}}
```

It is immediately obvious that the values are incorrect. As you can see, the Y position of the keyboard is reported as 0 whereas we all know when the keyboard is displayed in landscape mode on an iPhone, the Y position is certainly not at 0, the width is the width of the whole screen, which obviously is not 162.0 in landscape and the height is

almost half of the screen, which makes the value 480 incorrect. The reason for the *incorrect* values is that iOS does *not* take into account the orientation of the device when reporting these values to your apps. The frames reported to your app are in the app's main window's coordinate system. Therefore, to convert these reported frames from the window's coordinate system to your view's coordinate system, use the `convertRect:fromView:` method of your view and pass your app's window as the `fromView` parameter:

Now let's modify the implementation of the `handleKeyboardWillShow:` method slightly to take into account the conversion of coordinate systems, from the window's to our view's coordinate system:



The implementation of the `handleKeyboardWillHide:` method does not use the rectangles in the user-info dictionary. In this method we always assume that the keyboard is hiding and its rectangle is (0, 0, 0, 0).

```
- (void) handleKeyboardWillShow:(NSNotification *)paramNotification{
    NSDictionary *userInfo = [paramNotification userInfo];

    NSValue *animationCurveObject =
    [userInfo valueForKey:UIKeyboardAnimationCurveUserInfoKey];

    NSValue *animationDurationObject =
    [userInfo valueForKey:UIKeyboardAnimationDurationUserInfoKey];

    NSValue *keyboardEndRectObject =
    [userInfo valueForKey:UIKeyboardFrameEndUserInfoKey];

    NSInteger animationCurve = 0;
    double animationDuration = 0.0f;
    CGRect keyboardEndRect = CGRectMake(0, 0, 0, 0);

    [animationCurveObject getValue:&animationCurve];
    [animationDurationObject getValue:&animationDuration];
    [keyboardEndRectObject getValue:&keyboardEndRect];

    UIWindow *window = [[[UIApplication sharedApplication] delegate] window];

    /* Convert the frame from window's coordinate system to
       our view's coordinate system */
    keyboardEndRect = [self.view convertRect:keyboardEndRect
                                   fromView:window];

    [UIView beginAnimations:@"changeTableViewContentInset"
                      context:NULL];
    [UIView setAnimationDuration:animationDuration];
    [UIView setAnimationCurve:(UIViewAnimationCurve)animationCurve];

    CGRect intersectionOfKeyboardRectAndWindowRect =
```

```

CGRectIntersection(window.frame, keyboardEndRect);

CGFloat bottomInset = intersectionOfKeyboardRectAndWindowRect.size.height;

self.myTableView.contentInset = UIEdgeInsetsMake(0.0f,
                                                  0.0f,
                                                  bottomInset,
                                                  0.0f);

NSIndexPath *indexPathOfOwnerCell = nil;
/* Also, make sure the selected text field is visible on the screen */
NSInteger numberOfCells = [self.myTableView.dataSource
                           tableView:self.myTableView
                           numberOfRowsInSection:0];

/* So let's go through all the cells and find their accessory text fields.
Once we have the refernece to those text fields, we can see which one of
them is the first responder (has the keyboard) and we will make a call
to the table view to make sure after the keyboard is displayed,
that specific cell is NOT obstructed by the keyboard */
for (NSInteger counter = 0;
     counter < numberOfCells;
     counter++){
    NSIndexPath *indexPath = [NSIndexPath indexPathForRow:counter
                                                    inSection:0];
    UITableViewCell *cell = [self.myTableView cellForRowAtIndexPath:indexPath];
    UITextField *textField = (UITextField *)cell.accessoryView;
    if ([textField isKindOfClass:[UITextField class]] == NO){
        continue;
    }
    if ([textField isFirstResponder]){
        indexPathOfOwnerCell = indexPath;
        break;
    }
}

[UIView commitAnimations];

if (indexPathOfOwnerCell != nil){
    [self.myTableView scrollToRowAtIndexPath:indexPathOfOwnerCell
                        atScrollPosition:UITableViewScrollPositionMiddle
                        animated:YES];
}
}

```

Brilliant; now run the app on iPhone Simulator and rotate the simulator's orientation to landscape and tap on one of the text fields. When the keyboard is displayed, scroll all the way down to the end of the table view's content to make sure that we have given the right content inset, taking into account the coordinate system conversion, to our table view:




Figure 2-81. Calculating the correct edge inset by taking into account the coordinate system of keyboard

See Also

XXX

Constructing and Using Table Views

3.0 Introduction

A table view is simply a scrolling view that is separated into sections, each of which is further separated into rows. Each row is an instance of the `UITableViewCell` class, and you can create custom table view rows by *subclassing* this class.

Using table views is an ideal way to present a list of items to users. You can embed images, text, and whatnot into your table view cells; you can customize their height, shape, grouping, and much more. The simplicity of the structure of table views is what makes them highly customizable.

A table view can be fed with data using a table view data source, and you can receive various events and control the physical appearance of table views using a table view delegate object. These are defined, respectively, in the `UITableViewDataSource` and `UITableViewDelegate` protocols.

Although an instance of `UITableView` subclasses `UIScrollView`, table views can only scroll vertically. This is more a feature than a limitation. In this chapter, we will discuss the different ways of creating, managing, and customizing table views.

3.1 Instantiating a Table View

Problem

You want to place a table view on your UI.

Solution

Instantiate an object of type `UITableView` and add it as a subview of any of your views.

Discussion

There are two ways of instantiating a table view:

1. Through code
2. Using Interface Builder

If you are using Interface Builder, creating a table view is as simple as dragging and dropping a table view from the object library into your *.xib* file. If you are more comfortable creating your components using code, then that is no problem either. All you have to do is to instantiate an object of type `UITableView`. Let's start by defining our table view in our view controller's header file:

```
#import <UIKit/UIKit.h>

@interface Instantiating_a_Table_ViewViewController : UIViewController

@property (nonatomic, strong) UITableView *myTableView;

@end
```

And then we will go ahead and synthesize the table view in the implementation file of our view controller:

```
#import "Instantiating_a_Table_ViewViewController.h"

@implementation Instantiating_a_Table_ViewViewController

@synthesize myTableView;

...
```

And creating the view controller is as easy as just allocating and initializing an instance of `UITableView`:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myTableView =
        [[UITableView alloc] initWithFrame:self.view.bounds
                                         style:UITableViewStylePlain];

    [self.view addSubview:self.myTableView];
}
```

The `style` parameter of the `initWithFrame:style:` initializer of the view controller allows us to specify what type of table view we need. There are two styles that we can choose from:

`UITableViewStylePlain`

Creates a plain table view with no background images.

`UITableViewStyleGrouped`

Creates a table view with a background image and rounded group borders, similar to the Settings app.

If you run your app right now on the iPhone Simulator, you will see the table view sitting there with no table view cells populated inside it:



Figure 3-1. A plain table view with no content

See Also

XXX

3.2 Assigning a Delegate to a Table View

Problem

You have decided to assign a delegate to a table view.

Solution

Assign an object that conforms to the `UITableViewDelegate` protocol to the `delegate` property of your table view:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    /* We want a full-screen Table View which is as
       big as the View which is attached to the current
       View Controller */
    CGRect tableViewFrame = self.view.bounds;

    self.myTableView = [[UITableView alloc]
                        initWithFrame:tableViewFrame
                        style:UITableViewStylePlain];

    self.myTableView.delegate = self;

    /* Add this Table View to our View */
    [self.view addSubview:self.myTableView];
}
```

The highlighted statement assigns the current object as the delegate of the table view. `myTableView` is a property of type `UITableView` belonging to the calling view controller. The statement is embedded in the `viewDidLoad` method because the calling object here is an instance of `UIViewController`, and this method is the right place to put the statement so that the association is made just once.

Discussion

The `UITableView` class defines a property called `delegate`. The table view should assign to this property an object that conforms to the `UITableViewDelegate` protocol. In other words, this delegate must *promise* to reply to the messages defined in this protocol, which are sent to the delegate object by the table view itself. Think of the delegate of a table view as an object that listens to various events sent by the table view, such as when a cell is selected or when the table view wants to figure out the height of each of its cells. We can modify the visual appearance of a table and its cells, to some extent, using Interface Builder, too. Just open Interface Builder and select a table view that you created previously, and then select Tools→Size Inspector. In the Size Inspector panel, you can modify the visual appearance of the table view by changing values such as the height of the table view's cells.

To make the delegate object that you choose for a table view conform to the `UITableViewDelegate` protocol, you need to add that protocol to that object's interface declaration in this way:

```
#import <UIKit/UIKit.h>

@interface Assigning_a_Delegate_to_a_Table_ViewViewController
    : UIViewController <UITableViewDelegate>

@property (nonatomic, strong) UITableView *myTableView;

@end
```



It is mandatory for the delegate object to respond to messages that are marked as `@required` by the `UITableViewDelegate` protocol. Responding to other messages is optional, but the delegate must respond to any messages you want to affect the table view.

Messages sent to the delegate object of a table view carry a parameter that tells the delegate object which table view has fired that message in its delegate. This is very important to make note of because you might, under certain circumstances, require more than one table view to be placed on one object (usually a view). Because of this, it is highly recommended that you make your decisions based on which table view has actually sent that specific message to your delegate object, like so:

```
- (CGFloat) tableView:(UITableView *)tableView
    heightForRowAtIndexPath:(NSIndexPath *)indexPath{

    CGFloat result = 20.0f;

    if ([tableView isEqual:self.myTableView]){
        result = 40.0f;
    }

    return result;
}
```

It is worth noting that the location of a cell in a table view is represented by its index path. An index path is the combination of the section and the row index, where the section index is the zero-based index specifying which grouping or section each cell belongs to, and the cell index is the zero-based index of that particular cell in its section.

See Also

[Recipe 3.4](#)

3.3 Populating a Table View with Data

Problem

You would like to populate your table view with data.

Solution

Conform to the `UITableViewDataSource` protocol in an object and assign that object to the `dataSource` property of a table view.

Discussion

Create an object that conforms to the `UITableViewDataSource` protocol and assign it to a table view instance. Then, by responding to the data source messages, provide information to your table view. For this example, let's go ahead and declare the `.h` file of our view controller, which will later create a table view on its own view, in code:

```
#import <UIKit/UIKit.h>

@interface Populating_a_Table_View_with_DataViewController
    : UIViewController <UITableViewDataSource>

@property (nonatomic, strong) UITableView *myTableView;

@end
```

Now let's synthesize our table view:

```
#import "Populating_a_Table_View_with_DataViewController.h"

@implementation Populating_a_Table_View_with_DataViewController

@synthesize myTableView;

...
```

In the `viewDidLoad` method of our view controller, we will create the table view and will assign our view controller as its data source:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myTableView =
        [[UITableView alloc] initWithFrame:self.view.bounds
                                         style:UITableViewStylePlain];

    self.myTableView.dataSource = self;

    /* Make sure our table view resizes correctly */
    self.myTableView.autoresizingMask =
```

```

        UIViewAutoresizingFlexibleWidth |
        UIViewAutoresizingFlexibleHeight;

[self.view addSubview:self.myTableView];

}

```

Now we need to make sure our table view responds to the `@required` methods of the `UITableViewDataSource` protocol. Hold down the Command key on your keyboard and click on the `UITableViewDataSource` protocol's mention in your view controller's `.h` file. This will show you the required methods for this protocol.

The `UITableView` class defines a property called `dataSource`. This is an untyped object that must conform to the `UITableViewDataSource` protocol. Every time a table view is refreshed and reloaded using the `reloadData` method, the table view will call various methods in its data source to find out about the data you intend to populate it with. A table view data source can implement three important methods, two of which are mandatory for every data source:

`numberOfSectionsInTableView:`

This method allows the data source to inform the table view of the number of sections that must be loaded into the table.

`tableView:numberOfRowsInSection:`

This method tells the view controller how many cells or rows have to be loaded for each section. The section number is passed to the data source in the `numberOfRowsInSection` parameter. The implementation of this method is mandatory in the data source object.

`tableView:cellForRowAtIndexPath:`

This method is responsible for returning instances of the `UITableViewCell` class as rows that have to be populated into the table view. The implementation of this method is mandatory in the data source object.

So let's go ahead and implement these methods in our view controller, one by one. First, let's tell the table view that we want it to render 3 sections:

```

- (NSInteger)numberOfSectionsInTableView:(UITableView *)tableView{

    NSInteger result = 0;
    if ([tableView isEqual:self.myTableView]){
        result = 3;
    }
    return result;

}

```

Then we tell the table view how many rows we want it to render, for each section:

```

- (NSInteger)tableView:(UITableView *)tableView
numberOfRowsInSection:(NSInteger)section{

    NSInteger result = 0;

```

```

    if ([tableView isEqual:self.myTableView]){
        switch (section){
            case 0:{
                result = 3;
                break;
            }
            case 1:{
                result = 5;
                break;
            }
            case 2:{
                result = 8;
                break;
            }
        }
    }
}
return result;
}

```

So up to now, we have asked the table view to render 3 sections with 3 rows in the first, 5 rows in the second and 8 rows in the third section. What's next? Returning instances of table view cell to the table view. The cells that we want the table view to render:

```

- (UITableViewCell *) tableView:(UITableView *)tableView
  cellForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCell *result = nil;

    if ([tableView isEqual:self.myTableView]){

        static NSString *TableViewCellIdentifier = @"MyCells";

        result = [tableView
            dequeueReusableCellWithIdentifier:TableViewCellIdentifier];

        if (result == nil){
            result = [[UITableViewCell alloc]
                initWithStyle:UITableViewCellStyleDefault
                reuseIdentifier:TableViewCellIdentifier];
        }

        result.textLabel.text = [NSString stringWithFormat:@"Section %ld, Cell %ld",
            (long)indexPath.section,
            (long)indexPath.row];

    }

    return result;
}

```

Now if we run our app in iPhone Simulator, we will see the results of our work:




Figure 3-2. A plain table view with three sections

When a table view is reloaded or refreshed, it queries its data source through the `UITableViewDataSource` protocol, asking for various bits of information. Among the important methods mentioned previously, the table view will first ask for the number of sections. Each section is responsible for holding rows or cells. After the data source specifies the number of sections, the table view will ask for the number of rows that have to be loaded into each section. The data source gets the zero-based index of each section and, based on this, can decide how many cells have to be loaded into each section.

The table view, after determining the number of cells in the sections, will continue to ask the data source about the view that will represent each cell in each section. You can allocate instances of the `UITableViewCell` class and return them to the table view. There are, of course, properties that can be set for each cell, including the title, subtitle, and color of each cell, among other properties.

3.4 Receiving and Handling Table View Events

Problem

You would like to respond to various events that a table view can generate.

Solution

Provide your table view with a delegate object.

Here is an excerpt of the `.h` file of a view controller with a table view:

```
#import <UIKit/UIKit.h>

@interface Receiving_and_Handling_Table_View_EventsViewController
    : UIViewController <UITableViewDelegate, UITableViewDataSource>

@property (nonatomic, strong) UITableView *myTableView;

@end
```

The `.m` file of the same view controller implements a method defined in the `UITableViewDelegate` protocol:

```
- (void) tableView:(UITableView *)tableView
didSelectRowAtIndexPath:(NSIndexPath *)indexPath{

    if ([tableView isEqual:self.myTableView]){

        NSLog(@"%@",
            [NSString stringWithFormat:@"Cell %ld in Section %ld is selected",
                (long)indexPath.row, (long)indexPath.section]);
    }
}

- (void) viewDidLoad {
    [super viewDidLoad];

    self.myTableView = [[UITableView alloc]
        initWithFrame:self.view.bounds
        style:UITableViewStylePlain];

    self.myTableView.autoresizingMask =
        UIViewAutoresizingFlexibleHeight |
        UIViewAutoresizingFlexibleWidth;
```



```

self.myTableView.dataSource = self;
self.myTableView.delegate = self;

[self.view addSubview:self.myTableView];

}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.myTableView = nil;
}

```

Discussion

While a data source is responsible for providing data to the table view, the table view consults the delegate whenever an event occurs, or if the table view needs further information before it can complete a task. For instance, the table view invokes a delegate's method:

- When and before a cell is selected or deselected
- When the table view needs to find the height of each cell
- When the table view needs to construct the header and footer of every section

As you can see in the example code in this recipe's [Solution](#), the current object is set as the delegate of a table view. The delegate implements the `tableView:didSelectRowAtIndexPath:` selector in order to get notified when the user selects a cell or a row on a table view. The documentation for the `UITableViewDelegate` protocol in the SDK shows you all the methods that the delegate can define and the view can invoke.

See Also

“UITableViewDelegate Protocol Reference,” http://developer.apple.com/library/ios/#documentation/uikit/reference/UITableViewDelegate_Protocol/Reference/Reference.html

3.5 Using Different Types of Accessories in a Table View Cell

Problem

You want to grab users' attention in a table view by displaying accessories, and offer different ways to interact with each cell in your table view.

Solution

Use the `accessoryType` of the `UITableViewCell` class, instances of which you provide to your table view in its data source object:

```

- (UITableViewCell *)tableView:(UITableView *)tableView
    cellForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCell* result = nil;

    if ([tableView isEqual:self.myTableView]){

        static NSString *MyCellIdentifier = @"SimpleCell";

        /* We will try to retrieve an existing cell
         with the given identifier */
        result = [tableView
            dequeueReusableCellWithIdentifier:MyCellIdentifier];

        if (result == nil){
            /* If a cell with the given identifier does not
             exist, we will create the cell with the identifier
             and hand it to the table view */

            result = [[UITableViewCell alloc]
                initWithStyle:UITableViewCellStyleDefault
                reuseIdentifier:MyCellIdentifier];
        }

        result.textLabel.text =
            [NSString stringWithFormat:@"Section %ld, Cell %ld",
                (long)indexPath.section,
                (long)indexPath.row];

        result.accessoryType = UITableViewCellAccessoryDetailDisclosureButton;
    }

    return result;
}

- (NSInteger) tableView:(UITableView *)tableView
    numberOfRowsInSection:(NSInteger)section{
    return 10;
}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.myTableView = [[UITableView alloc] initWithFrame:self.view.bounds
        style:UITableViewStylePlain];

    self.myTableView.dataSource = self;
    self.myTableView.delegate = self;

    self.myTableView.autoresizingMask =
        UIViewAutoresizingFlexibleWidth |
        UIViewAutoresizingFlexibleHeight;
}

```

```

        [self.view addSubview:self.myTableView];
    }

    - (void)viewDidUnload{
        [super viewDidUnload];
        self.myTableView = nil;
    }

```

Discussion

You can assign any of the values defined in the `UITableViewCellAccessoryType` enumeration to the `accessoryType` property of an instance of the `UITableViewCell` class. Two very useful accessories are the *disclosure indicator* and the *detail disclosure button*. They both display a chevron indicating to users that if they tap on the associated table view cell, a new view or view controller will be displayed. In other words, the users will be taken to a new screen with further information about their current selector. The difference between these two accessories is that the disclosure indicator produces no event, whereas the detail disclosure button fires an event to the delegate when pressed. In other words, pressing the button has a different effect from pressing the cell itself. Thus, the detail disclosure button allows the user to perform two separate but related actions on the same row.

Figure 3-3 shows these two different accessories on a table view. The first row has a disclosure indicator and the second row has a detail disclosure button.




Figure 3-3. Two table view cells with different accessories

If you tap any detail disclosure button assigned to a table view cell, you will immediately realize that it truly is a separate button. Now the question is: how does the table view know when the user taps this button?

Table views, as explained before, fire events on their delegate object. The detail disclosure button on a table view cell also fires an event that can be captured by the delegate object of a table view:

```
- (void) tableView:(UITableView *)tableView
accessoryButtonTappedForRowWithIndexPath:(NSIndexPath *)indexPath{

    /* Do something when the accessory button is tapped */
    NSLog(@"Accessory button is tapped for cell at index path = %@", indexPath);

    UITableViewCell *ownerCell = [tableView cellForRowAtIndexPath:indexPath];

    NSLog(@"Cell Title = %@", ownerCell.textLabel.text);

}
```

This code finds the table view cell whose detail disclosure button has been tapped and prints the contents of the text label of that cell into the console screen. As a reminder, you can display the console screen in Xcode by selecting Run→Console.

3.6 Creating Custom Table View Cell Accessories

Problem

The accessories provided to you by the iOS SDK are not sufficient, and you would like to create your own accessories.

Solution

Assign an instance of the `UIView` class to the `accessoryView` property of any instance of the `UITableViewCell` class:

```
- (UITableViewCell *)tableView:(UITableView *)tableView
cellForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCell* result = nil;

    static NSString *MyCellIdentifier = @"SimpleCell";

    /* We will try to retrieve an existing cell
    with the given identifier */
    result = [tableView dequeueReusableCellWithIdentifier:MyCellIdentifier];

    if (result == nil){
        result = [[UITableViewCell alloc] initWithStyle:UITableViewCellStyleDefault
                                           reuseIdentifier:MyCellIdentifier];
    }

    result.textLabel.text = [NSString stringWithFormat:@"Section %ld, Cell %ld",
                                                         (long)indexPath.section,
                                                         (long)indexPath.row];

}
```

```

UIButton *button = [UIButton buttonWithType:UIButtonTypeRoundedRect];
button.frame = CGRectMake(0.0f, 0.0f, 150.0f, 25.0f);

[button setTitle:@"Expand"
           forState:UIControlStateNormal];

[button addTarget:self
              action:@selector(performExpand:)
          forControlEvents:UIControlEventTouchUpInside];

result.accessoryView = button;

return result;
}

```

As you can see, this code uses the `performExpand:` method as the selector for each button. Here is the definition of this method:

```

- (void) performExpand:(id)paramSender{
    /* Take an action here */
}

```

This example code snippet assigns a custom button to the accessory view of every row in the targeted table. The result is shown in [Figure 3-4](#).



Figure 3-4. Table view cells with custom accessory views

Discussion

An object of type `UITableViewCell` retains a property named `accessoryView`. This is the view you can assign a value to if you are not completely happy with the built-in iOS

SDK table view cell accessories. After this property is set, Cocoa Touch will ignore the value of the `accessoryType` property and will use the view assigned to the `accessoryView` property as the accessory assigned to the cell.

The code listed in this recipe's [Solution](#) creates buttons for all the cells populated into the table view. When a button is pressed in any cell, the `performExpand:` method gets called, and if you are like me, you have probably already started thinking about how you can determine which cell the sender button belongs to. So, now we have to somehow link our buttons with the cells to which they belong.

One way to handle this situation is to retrieve the superview of the button that fires the event. Since the accessory view of the cells of a table view adds the cells' accessory views as their subviews, retrieving the superview of the button will return the table view cell that owns the button as its accessory view:

```
- (void) performExpand:(UIButton *)paramSender{

    UITableViewCell *ownerCell = (UITableViewCell*)paramSender.superview;

    if (ownerCell != nil){

        /* Now we will retrieve the index path of the cell
           which contains the section and the row of the cell */

        NSIndexPath *ownerCellIndexPath =
            [self.myTableView indexPathForCell:ownerCell];

        NSLog(@"Accessory in index path is tapped. Index path = %@",
              ownerCellIndexPath);

        /* Now we can use these two values to truly determine that
           the accessory button of which cell was the sender of this event:

           OwnerCellIndexPath.section
           OwnerCellIndexPath.row

           */

        if (ownerCellIndexPath.section == 0 &&
            ownerCellIndexPath.row == 1){
            /* This is the second row in the first section */
        }

        /* And so forth with the other checks ... */

    }

}
```

3.7 Displaying Hierarchical Data in Table Views

Problem

You want to be able to display hierarchical data in a table view.

Solution

Use the indentation functionality of table view cells:

```
- (UITableViewCell *)tableView:(UITableView *)tableView
    cellForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCell* result = nil;

    static NSString *MyCellIdentifier = @"SimpleCells";

    result = [tableView dequeueReusableCellWithIdentifier:MyCellIdentifier];

    if (result == nil){
        result = [[UITableViewCell alloc] initWithStyle:UITableViewCellStyleDefault
                                           reuseIdentifier:MyCellIdentifier];
    }

    result.textLabel.text = [NSString stringWithFormat:@"Section %ld, Cell %ld",
                                                         (long)indexPath.section,
                                                         (long)indexPath.row];

    result.indentationLevel = indexPath.row;
    result.indentationWidth = 10.0f;

    return result;
}
```

The indentation level is simply multiplied by the indentation width in order to give a margin to the content view of each cell. [Figure 3-5](#) depicts how these cells look when displayed inside a table view.

Carrier	6:14 PM	100%
Section 0, Cell 0		
Section 0, Cell 1		
Section 1, Cell 0		
Section 1, Cell 1		
Section 1, Cell 2		
Section 1, Cell 3		
Section 2, Cell 0		
Section 2, Cell 1		
Section 2, Cell 2		
Section 2, Cell 3		
Section 2, Cell 4		
Section 2, Cell 5		
Section 2, Cell 6		
Section 2, Cell 7		
Section 3, Cell 0		
Section 3, Cell 1		
Section 3, Cell 2		
Section 3, Cell 3		
Section 3, Cell 4		
Section 3, Cell 5		
Section 3, Cell 6		
Section 3, Cell 7		
Section 3, Cell 8		

Figure 3-5. Table view cells with indentation

Discussion

Although you might rarely find it useful, you can apply indentation to table view cells in the iOS SDK. Each cell can have two properties related to indentation: *indentation level* and *indentation width*. The indentation level is simply multiplied by the indentation width, and the resultant value is the offset by which the table view cell's content is shifted to the right or left.

For instance, if the indentation level of a cell is set to 2 and its indentation width is set to 3, the resultant value is 6. This means the content view of the cell is shifted to the right by six pixels when displayed in a table view.



The indentation level is defined as a signed integer value, making it possible for you to assign negative values to it. This will obviously shift the content view of your cells to the left.

The indentation level assigned to table view cells enables programmers to present hierarchical data, and it is up to the programmer to determine the indentation level and the indentation width of each cell.

3.8 Enabling Swipe Deletion of Table View Cells

Problem

You want your application users to be able to delete rows from a table view easily.

Solution

Implement the `tableView:editingStyleForRowAtIndexPath:` selector in the delegate and the `tableView:commitEditingStyle:forRowAtIndexPath:` selector in the data source of your table view:

```
- (UITableViewCellEditingStyle)tableView:(UITableView *)tableView
    editingStyleForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCellEditingStyle result = UITableViewCellEditingStyleNone;

    if ([tableView isEqual:self.myTableView]){
        result = UITableViewCellEditingStyleDelete;
    }

    return result;
}

- (void) setEditing:(BOOL)editing
    animated:(BOOL)animated{
```

```

        [super setEditing:editing
             animated:animated];

        [self.myTableView setEditing:editing
             animated:animated];

    }

    - (void) tableView:(UITableView *)tableView
    commitEditingStyle:(UITableViewCellEditingStyle)editingStyle
    forRowAtIndexPath:(NSIndexPath *)indexPath{

        if (editingStyle == UITableViewCellEditingStyleDelete){

            if (indexPath.row < [self.arrayOfRows count]){

                /* First remove this object from the source */
                [self.arrayOfRows removeObjectAtIndex:indexPath.row];

                /* Then remove the associated cell from the Table View */
                [tableView deleteRowsAtIndexPaths:[NSArray arrayWithObject:indexPath]
                    withRowAnimation:UITableViewRowAnimationLeft];

            }

        }

    }
}

```

The `tableView:editingStyleForRowAtIndexPath:` method can enable deletions. It is called by the table view and its return value determines what the table view allows the user to do (insertion, deletion, etc.). The `tableView:commitEditingStyle:forRowAtIndexPath:` method carries out the user's requested deletion. The latter method is defined in the delegate, but its functionality is a bit overloaded: not only do you use the method to delete data, but you also have to delete rows from the table here.

Discussion

The table view responds to the swipe by showing a button on the right side of the targeted row (Figure 3-6). As you can see, the table view is *not* in editing mode, but the button allows the user to delete the row.

This mode is enabled by implementing the `tableView:editingStyleForRowAtIndexPath:` method (declared in the `UITableViewDelegate` protocol), whose return value indicates whether the table should allow insertions, deletions, both, or neither. By implementing the `tableView:commitEditingStyle:forRowAtIndexPath:` method in the data source of a table view, you can then get notified if a user has performed an insertion or deletion.



Figure 3-6. Delete button appearing on a table view cell

The second parameter of the `deleteRowsAtIndexPaths:withRowAnimation:` method allows you to specify an animation method that will be performed when rows are deleted from a table view. Our example specifies that we want rows to disappear when moving from right to left when deleted.

3.9 Constructing Headers and Footers in Table Views

Problem

You want to create a header and/or a footer for a table view.

Solution

Create a view (could be a label, image view, etc, anything that directly or indirectly subclasses `UIView`, and assign that view to the header and/or the footer of a section of a table view. You can also allocate specific number of points in height for a header or a footer, as we will soon see.

Discussion

A table view can have multiple headers and footers. Each section in a table view can have its own header and footer so if you have 3 sections in a table view, you can have maximum of 3 headers and maximum of 3 footers. You are *not* obliged to provide headers and footers for any of these sections. It is up to you to tell the table view whether you want a header and/or a footer for a section and you pass these views to the table view through its delegate, should you wish to provide header(s)/footer(s) for section(s) of your table view. Headers and footers in a table view become a part of the table view meaning that when the table view's contents scroll, so do the header(s) and footer(s) inside that table view. Let's have a look at a sample header and footer in a table view:




Figure 3-7. A footer for the top section and the Shortcuts header for the last section of a table view

As you can see, the top section with items such as "Check Spelling" and "Enable Caps Lock" has a footer that says "Double tapping the space bar will insert a period followed by a space.". That is the footer of the top section of that table view. The reason why it is a footer rather than a header is because it is attached to the bottom of that section rather than the top of the section. The last section in this table view also has a header that reads "Shortcuts". The reason why this is a header rather than a footer is because it is appearing on the top of the section rather than the bottom.



Specifying the height of a header and footer in a section inside a table view is done through methods defined in the `UITableViewDataSource`. Specifying the actual view that has to be displayed for the header/footer of a section in a table view is done through methods defined in the `UITableViewDelegate` protocol.

Let's go ahead and create a simple app with one table view in it. Then let's provide two labels, of type `UILabel`, one as the header and the other as the footer of the one and only section in our table view and let's populate this one section with only three cells. In the header we will place the text "Section 1 Header" and in the footer label we will place the text "Section 1 Footer". Starting with the header file of our root view controller, we will define a table view:

```
#import <UIKit/UIKit.h>

@interface Constructing_Headers_and_Footers_in_Table_ViewsViewController
    : UIViewController <UITableViewDataSource, UITableViewDelegate>

@property (nonatomic, strong) UITableView *myTableView;

@end
```

Then we will go and synthesize this property in the implementation file of the view controller:

```
#import "Constructing_Headers_and_Footers_in_Table_ViewsViewController.h"

@implementation Constructing_Headers_and_Footers_in_Table_ViewsViewController

@synthesize myTableView;

...
```

Now we will create a grouped table view and load three cells into it:

```
- (UITableViewCell *) tableView:(UITableView *)tableView
    cellForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCell *result = nil;

    static NSString *CellIdentifier = @"CellIdentifier";

    result = [tableView dequeueReusableCellWithIdentifier:CellIdentifier];

    if (result == nil){
        result = [[UITableViewCell alloc] initWithStyle:UITableViewCellStyleDefault
                                           reuseIdentifier:CellIdentifier];
    }

    result.textLabel.text = [[NSString alloc] initWithFormat:@"Cell %ld",
                                                                (long)indexPath.row];

    return result;
}
```

```

}

- (NSInteger) tableView:(UITableView *)tableView
  numberOfRowsInSection:(NSInteger)section{
    return 3;
}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.myTableView =
    [[UITableView alloc] initWithFrame:self.view.bounds
                                     style:UITableViewStyleGrouped];

    self.myTableView.dataSource = self;
    self.myTableView.delegate = self;
    self.myTableView.autoresizingMask = UIViewAutoresizingFlexibleWidth |
                                       UIViewAutoresizingFlexibleHeight;

    [self.view addSubview:self.myTableView];
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.myTableView = nil;
}

- (BOOL)shouldAutorotateToInterfaceOrientation
    :(UIInterfaceOrientation)interfaceOrientation{
    return YES;
}

```

Here is the exciting part. We can now use two important methods which are defined in `UITableViewDelegate` to provide a label for the header and another label for the footer of the one and only section that we have loaded into our table view. These methods are:

tableView:viewForHeaderInSection:

This method expects a return value of type `UIView`. The view returned from this method will be displayed as the header of the section specified by the `viewForHeaderInSection` parameter.

tableView:viewForFooterInSection:

This method expects a return value of type `UIView`. The view returned from this method will be displayed as the footer of the section specified by the `viewForFooterInSection` parameter.

Our task is now to implement these methods and return an instance of `UILabel` from them. On the header label we will place the "Section 1 Header" and on the footer label the text "Section 1 Footer", as we had planned:

```

- (UIView *) tableView:(UITableView *)tableView
viewForHeaderInSection:(NSInteger)section{

    UILabel *result = nil;

    if ([tableView isEqual:self.myTableView] &&
        section == 0){
        result = [[UILabel alloc] initWithFrame:CGRectMake(0,0,100,100)];
        result.text = @"Section 1 Header";
        result.backgroundColor = [UIColor clearColor];
        [result sizeToFit];
    }

    return result;
}

- (UIView *) tableView:(UITableView *)tableView
viewForFooterInSection:(NSInteger)section{

    UILabel *result = nil;

    if ([tableView isEqual:self.myTableView] &&
        section == 0){
        result = [[UILabel alloc] initWithFrame:CGRectMake(0,0,100,100)];
        result.text = @"Section 1 Footer";
        result.backgroundColor = [UIColor clearColor];
        [result sizeToFit];
    }

    return result;
}

```

If you run your app on the iPhone Simulator now, you will certainly see something strange, as shown in [Figure 3-8](#):



Figure 3-8. The header and footer labels of a table view are not aligned properly

The reason for this misalignment of the labels is because the table view doesn't really know the height of these views. To specify the height of the header and footer views, we need to use the following two methods which are defined in the `UITableViewDelegate` protocol:

`tableView:heightForHeaderInSection:`

The return value of this method is of type `CGFloat` and it specifies the height of the header for a section in a table view. The section's index is passed through the `heightForHeaderInSection` parameter.

`tableView:heightForFooterInSection:`

The return value of this method is of type `CGFloat` and it specifies the height of the footer for a section in a table view. The section's index is passed through the `heightForHeaderInSection` parameter.

```
- (CGFloat) tableView:(UITableView *)tableView
heightForHeaderInSection:(NSInteger)section{

    CGFloat result = 0.0f;

    if ([tableView isEqual:self.myTableView] &&
        section == 0){
        result = 30.0f;
    }

    return result;
}

- (CGFloat) tableView:(UITableView *)tableView
heightForFooterInSection:(NSInteger)section{

    CGFloat result = 0.0f;

    if ([tableView isEqual:self.myTableView] &&
        section == 0){
        result = 30.0f;
    }

    return result;
}
```

Running the app, you can see that the height of the header and the footer labels is fixed. There is still something wrong with the code we've written and that is the left margin of our header and footer labels. Take a look for yourself (see [Figure 3-9](#)):



Figure 3-9. The left margin of our header and footer labels is not correct

The reason behind this is that the table view by default places header and footer views at x point 0.0f. You might think that changing the frame of your header and footer labels will fix this issue but unfortunately it doesn't. The solution to this problem is creating a generic `UIView` and placing your header and footer labels on that view. Return the generic view as the header/footer but change the x position of your labels within the generic view. We now need to modify our implementation of the `tableView:viewForHeaderInSection:` and the `tableView:viewForFooterInSection:` methods:

```
- (UIView *) tableView:(UITableView *)tableView
viewForHeaderInSection:(NSInteger)section{
```

```

UIView *result = nil;

if ([tableView isEqual:self.myTableView] &&
    section == 0){

    UILabel *label = [[UILabel alloc] initWithFrame:CGRectZero];
    label.text = @"Section 1 Header";
    label.backgroundColor = [UIColor clearColor];
    [label sizeToFit];

    /* Move the label 10 points to the right */
    label.frame = CGRectMake(label.frame.origin.x + 10.0f,
                             5.0f, /* Go 5 points down in y axis */
                             label.frame.size.width,
                             label.frame.size.height);

    /* Give the container view 10 points more in width than our label
       because the label needs a 10 extra points left-margin */
    CGRect resultFrame = CGRectMake(0.0f,
                                     0.0f,
                                     label.frame.size.height,
                                     label.frame.size.width + 10.0f);

    result = [[UIView alloc] initWithFrame:resultFrame];
    [result addSubview:label];

}

return result;
}

- (UIView *) tableView:(UITableView *)tableView
viewForFooterInSection:(NSInteger)section{

    UIView *result = nil;

    if ([tableView isEqual:self.myTableView] &&
        section == 0){

        UILabel *label = [[UILabel alloc] initWithFrame:CGRectZero];
        label.text = @"Section 1 Footer";
        label.backgroundColor = [UIColor clearColor];
        [label sizeToFit];

        /* Move the label 10 points to the right */
        label.frame = CGRectMake(label.frame.origin.x + 10.0f,
                                 5.0f, /* Go 5 points down in y axis */
                                 label.frame.size.width,
                                 label.frame.size.height);

        /* Give the container view 10 points more in width than our label
           because the label needs a 10 extra points left-margin */
        CGRect resultFrame = CGRectMake(0.0f,
                                         0.0f,

```

```

        label.frame.size.height,
        label.frame.size.width + 10.0f);
result = [[UIView alloc] initWithFrame:resultFrame];
[result addSubview:label];

}

return result;

}

```

Now if you run your app, you will get results similar to that shown in [Figure 3-10](#):




Figure 3-10. Our header and footer labels displayed in a table view

With these methods that you just learned about, you can even place images as the header/footer of your table views. Instances of `UIImageView` have `UIView` as their super class so you can easily place your images in image views and return them as headers/footers of a table view. If all you want to place is text as the header/footer of table views, you can use two handy methods defined in the `UITableViewDataSource` protocol which will save you a lot of hassle and time. Instead of creating your own labels and returning them as headers/footers of your table view, you can simply use these methods:

tableView:titleForHeaderInSection:

The return value of this method is of type `NSString`. This string will automatically be placed inside a label by the table view and will be displayed as the header of the section which is specified in the `titleForHeaderInSection` parameter.

tableView:titleForFooterInSection:

The return value of this method is of type `NSString`. This string will automatically be placed inside a label by the table view and will be displayed as the footer of the section which is specified in the `titleForFooterInSection` parameter.

So to make our app's code simpler, let's get rid of our implementation of the `tableView:viewForHeaderInSection:` and the `tableView:viewForFooterInSection:` methods and replace them with the implementation of the `tableView:titleForHeaderInSection:` and the `tableView:titleForFooterInSection:` methods:

```
- (NSString *) tableView:(UITableView *)tableView
titleForHeaderInSection:(NSInteger)section{

    NSString *result = nil;

    if ([tableView isEqual:self.myTableView] &&
        section == 0){
        result = @"Section 1 Header";
    }

    return result;
}

- (NSString *) tableView:(UITableView *)tableView
titleForFooterInSection:(NSInteger)section{

    NSString *result = nil;

    if ([tableView isEqual:self.myTableView] &&
        section == 0){
        result = @"Section 1 Footer";
    }

    return result;
}
```

Now run your app in the iPhone Simulator and you will see that the table view has automatically created a left aligned label for the header and a center aligned label for the footer of the one and only section in our table view. The alignment of these labels is the default alignment that the every table view creates its header/footer labels with (see [Figure 3-11](#)):



Figure 3-11. A table view rendering text in headers and footers

See Also

XXX

3.10 Displaying Context Menus on Table Views Cells

Problem

You want to give your users the ability to use copy/paste options among other operations that they can choose from, by holding down one of their fingers on a table view cell in your app.

Solution

Implement the following three methods of the `UITableViewDelegate` protocol in the delegate object of your table view:

`tableView:shouldShowMenuForRowAtIndexPath:`

The return value of this method is of type `BOOL`. If you return `YES` from this method, iOS will display the context menu for the table view cell whose index gets passed to you through the `shouldShowMenuForRowAtIndexPath` parameter.

`tableView:canPerformAction:forRowAtIndexPath:withSender:`

The return value of this method is also of type `BOOL`. Once you allow iOS to display context menu for a table view cell, iOS will call this method multiple times and pass you the selector of the action that you can choose to display in the context menu or not. So if iOS wants to ask you whether you would like to show the "Copy" menu to be displayed to the user, this method will get called in your table view's delegate object and the `canPerformAction` parameter of this method will be equal to `@selector(copy:)`. We will read more information about this in this recipe's [Discussion](#).

`tableView:performAction:forRowAtIndexPath:withSender:`

Once you allow a certain action to be displayed in the context menu of a table view cell, once the user picks that action from the menu, this method will get called in your table view's delegate object. In here, you must do whatever that needs to be done to satisfy the user's request. For instance, if it is the "Copy" menu that the user has selected, you will need to use a pasteboard to place the chosen table view cell's content into the pasteboard.

Discussion

A table view can give a yes/no answer to iOS, allowing or disallowing it to display available system menu items for a table view cell. iOS attempts to display a context menu on a table view cell when the user has held down her finger on the cell for a certain period of time, roughly about 1 second. iOS then asks the table view whose cell was the source of the trigger for the menu. If the table view gives a yes answer to iOS, iOS will then tell the table view what options are available to be displayed in the context menu and the table view will be able to say yes or no to any of those items. If there are

5 menu items available for instance and the table view says yes to only 2 of them, then only those 2 items will get displayed.

After the menu items are displayed to the user, the user can either tap on one of the items or tap outside the context menu to cancel it. Once the user taps on one of the menu items, iOS will send a delegate message to the table view informing it of the menu item that the user has picked. Based on all this information, the table view can make a decision as to what to do with the selected action.

I suggest that first we go ahead and see what actions are actually available for a context menu on table view cell so let's create our table view and then display a few cells inside it:

```
- (NSInteger) tableView:(UITableView *)tableView
    numberOfRowsInSection:(NSInteger)section{
    return 3;
}

- (UITableViewCell *) tableView:(UITableView *)tableView
    cellForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCell *result = nil;

    static NSString *CellIdentifier = @"CellIdentifier";

    result = [tableView dequeueReusableCellWithIdentifier:CellIdentifier];

    if (result == nil){
        result = [[UITableViewCell alloc] initWithStyle:UITableViewCellStyleDefault
                                           reuseIdentifier:CellIdentifier];
    }

    result.textLabel.text = [[NSString alloc]
                            initWithFormat:@"Section %ld Cell %ld",
                            (long)indexPath.section,
                            (long)indexPath.row];

    return result;
}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myTableView = [[UITableView alloc]
                        initWithFrame:self.view.bounds
                        style:UITableViewStylePlain];

    self.myTableView.autoresizingMask = UIViewAutoresizingFlexibleWidth |
                                         UIViewAutoresizingFlexibleHeight;

    self.myTableView.dataSource = self;
```

```

        self.myTableView.delegate = self;

        [self.view addSubview:self.myTableView];
    }

    - (void)viewDidUnload{
        [super viewDidUnload];
        self.myTableView = nil;
    }

```

Now we will implement the 3 aforementioned methods defined in the `UITableViewDelegate` protocol and simply convert the available actions (of type SEL) to string and print them out to the console:

```

- (BOOL) tableView:(UITableView *)tableView
  shouldShowMenuForRowAtIndexPath:(NSIndexPath *)indexPath{

    /* Allow the context menu to be displayed on every cell */
    return YES;
}

- (BOOL) tableView:(UITableView *)tableView
  canPerformAction:(SEL)action
  forRowAtIndexPath:(NSIndexPath *)indexPath
  withSender:(id)sender{

    NSLog(@"%@", NSStringFromSelector(action));

    /* Allow every action for now */
    return YES;
}

- (void) tableView:(UITableView *)tableView
  performAction:(SEL)action
  forRowAtIndexPath:(NSIndexPath *)indexPath
  withSender:(id)sender{

    /* Empty for now */
}

```

Now run your app in the simulator or on the device. You will then see 3 cells loaded into the table view. Hold down your finger (if on device) or your pointer (if using iOS Simulator) on one of the cells and observe what gets printed out to the console window:

```

cut:
copy:
select:
selectAll:
paste:
delete:
_promptForReplace:
_showTextStyleOptions:

```

```

_define:
_accessibilitySpeak:
_accessibilityPauseSpeaking:
makeTextWritingDirectionRightToLeft:
makeTextWritingDirectionLeftToRight:
cut:
copy:
select:
selectAll:
paste:
delete:
_promptForReplace:
_showTextStyleOptions:
_define:
_accessibilitySpeak:
_accessibilityPauseSpeaking:
makeTextWritingDirectionRightToLeft:
makeTextWritingDirectionLeftToRight:

```

These are all the actions that iOS will allow you to expose to your users should you need them. So for instance, if you would just like to allow your users to have the Copy option, in the `tableView:canPerformAction:forRowAtIndexPath:withSender:` method simply find out which action it is that iOS is asking for your permission before displaying, and either return YES or NO:

```

- (BOOL) tableView:(UITableView *)tableView
  canPerformAction:(SEL)action
  forRowAtIndexPath:(NSIndexPath *)indexPath
    withSender:(id)sender{

    if (action == @selector(copy:)){
        return YES;
    }

    return NO;
}

```




Figure 3-12. The Copy action displayed inside a context menu on a table view cell

The next step would be to intercept what menu item the user actually selected from the context menu. Based on this information we can then take an appropriate action. For instance, if the user selected the Copy item in the context menu, then we can use `UIPasteBoard` to copy that cell into the pasteboard, for later use:

```
- (void) tableView:(UITableView *)tableView
    performAction:(SEL)action
    forRowAtIndexPath:(NSIndexPath *)indexPath
    withSender:(id)sender{

    if (action == @selector(copy:)){
```

```

UITableViewCell *cell = [tableView cellForRowAtIndexPath:indexPath];
UIPasteboard *pasteBoard = [UIPasteboard generalPasteboard];
[pasteBoard setString:cell.textLabel.text];

}

}

```

See Also

XXX

3.11 Moving Cells and Sections in Table Views

Problem

You want to move and shuffle cells and sections inside a table view, with smooth and intuitive animations.

Solution

Use the `moveSection:toSection:` method of the table view to move a section to a new position. You can also use the `moveRowAtIndexPath:toIndexPath:` method to move a table view cell from its current place to a new place.

Discussion

Moving table view cells and sections differs from exchanging them. Let's have a look at an example that will make this easier to understand. Let's say you have 3 sections in your table view. Section A, B and C. If you move Section A to Section C, the table view will notice this move and will then shift Section B to the previous position of Section A and will move Section B to the previous position of Section B. However, if Section B was to be moved to Section C, the table view will not have to move Section A at all as it is sitting on top and doesn't interfere with the repositioning of Section B and C. In this case, Section B will be moved to Section C and Section C to Section B. The same logic will be used by the table view when moving cells.

To demonstrate this, let's create a table view and preload it with 3 section each of which contains 3 cells of its own. Let's start with the header file of our view controller:

```

#import <UIKit/UIKit.h>

@interface Moving_Cells_and_Sections_in_Table_ViewsViewController
    : UIViewController <UITableViewDelegate, UITableViewDataSource>

@property (nonatomic, strong) UITableView *myTableView;

/* Each section is an array on its own, containing objects of type NSString */

```

```
@property (nonatomic, strong) NSMutableArray *arrayOfSections;

@end
```

Our view controller will become the data source of the table view. The table view has sections and each section has rows. So we will keep an array of arrays. The first array being our array of sections and that array will itself contain other arrays that contain our cells. The `arrayOfSections` defined in the header file of our view controller will bear that responsibility then. Let's go ahead and in the implementation of our view controller populate this array:

```
#import "Moving_Cells_and_Sections_in_Table_ViewsViewController.h"

@implementation Moving_Cells_and_Sections_in_Table_ViewsViewController

@synthesize myTableView;
@synthesize arrayOfSections;

- (NSMutableArray *) newSectionWithIndex:(NSUInteger)paramIndex
    withCellCount:(NSUInteger)paramCellCount{

    NSMutableArray *result = [[NSMutableArray alloc] init];

    NSUInteger counter = 0;
    for (counter = 0;
        counter < paramCellCount;
        counter++){

        [result addObject:[NSString alloc] initWithFormat:@"Section %lu Cell %lu",
            (unsigned long)paramIndex,
            (unsigned long)counter+1]];

    }

    return result;
}

- (id) initWithNibName:(NSString *)nibNameOrNil
    bundle:(NSBundle *)nibBundleOrNil{

    self = [super initWithNibName:nibNameOrNil
        bundle:nibBundleOrNil];

    if (self != nil){

        arrayOfSections = [[NSMutableArray alloc] init];

        NSMutableArray *section1 = [self newSectionWithIndex:1
            withCellCount:3];
        NSMutableArray *section2 = [self newSectionWithIndex:2
            withCellCount:3];
        NSMutableArray *section3 = [self newSectionWithIndex:3
            withCellCount:3];
        [arrayOfSections addObject:section1];
    }
}
```

```

        [arrayOfSections addObject:section2];
        [arrayOfSections addObject:section3];
    }

    return self;
}

```

We shall then instantiate our table view and implement the necessary methods in the `UITableViewDataSource` protocol to populate our table view with data:

```

- (NSInteger) numberOfSectionsInTableView:(UITableView *)tableView{

    NSInteger result = 0;

    if ([tableView isEqual:self.myTableView]){
        result = (NSInteger)[self.arrayOfSections count];
    }

    return result;
}

- (NSInteger) tableView:(UITableView *)tableView
numberOfRowsInSection:(NSInteger)section{

    NSInteger result = 0;

    if ([tableView isEqual:self.myTableView]){

        if ([self.arrayOfSections count] > section){

            NSMutableArray *sectionArray = [self.arrayOfSections
                                             objectAtIndex:section];
            result = (NSInteger)[sectionArray count];

        }

    }

    return result;
}

- (UITableViewCell *)tableView:(UITableView *)tableView
cellForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCell *result = nil;

    if ([tableView isEqual:self.myTableView]){

        static NSString *CellIdentifier = @"CellIdentifier";

        result = [tableView dequeueReusableCellWithIdentifier:CellIdentifier];
    }
}

```

```

        if (result == nil){
            result = [[UITableViewCell alloc]
                      initWithStyle:UITableViewCellStyleDefault
                      reuseIdentifier:CellIdentifier];
        }

        NSMutableArray *sectionArray = [self.arrayOfSections
                                         objectAtIndex:indexPath.section];

        result.textLabel.text = [sectionArray objectAtIndex:indexPath.row];
    }

    return result;
}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.myTableView =
    [[UITableView alloc] initWithFrame:self.view.bounds
                                style:UITableViewStyleGrouped];

    self.myTableView.autoresizingMask = UIViewAutoresizingFlexibleWidth |
                                         UIViewAutoresizingFlexibleHeight;

    self.myTableView.delegate = self;
    self.myTableView.dataSource = self;

    [self.view addSubview:self.myTableView];
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.myTableView = nil;
}

```

Show time! Shall we first have a look at how sections can be moved to a new position? Let's write a method that will move Section 1 to 3:

```

- (void) moveSection1ToSection3{

    NSMutableArray *section1 = [self.arrayOfSections objectAtIndex:0];
    [self.arrayOfSections removeObject:section1];
    [self.arrayOfSections addObject:section1];

    [self.myTableView moveSection:0
                             toSection:2];
}

```


I will leave it up to you to decide when you would like to invoke this method as we don't have a button on our UI at the moment. You can simply create a navigation controller and place navigation button on it and then invoke this method.

Once you run the app as normal, you will see the sections lined up from 1 to 3:



Figure 3-13. A table view with three sections each of which containing three cells

After you invoke the `moveSection1ToSection3` method, you will see that Section 1 gets moved to Section 3 and Section 3 moves to Section 2's previous position and finally Section 2 moves to Section 1's previous position:



Figure 3-14. Section 1 is moved to Section 3 and other sections are subsequently moved as well

Moving of cells is very similar to moving sections. To move cells, all we have to do is to use the `moveRowAtIndexPath:toIndexPath:` method. Remember that you can move a cell from one section to the same section or to a new section. Let's make it easy and move cell 1 in section 1 to cell 2 in the same section and see what happens:

```
- (void) moveCell1InSection1ToCell2InSection1{  
    NSMutableArray *section1 = [self.arrayOfSections objectAtIndex:0];  
    NSString *cell1InSection1 = [section1 objectAtIndex:0];  
    [section1 removeObject:cell1InSection1];  
    [section1 insertObject:cell1InSection1
```

```

        atIndex:1];

NSIndexPath *sourceIndexPath = [NSIndexPath indexPathForRow:0
                                inSection:0];
NSIndexPath *destinationIndexPath = [NSIndexPath indexPathForRow:1
                                inSection:0];

[self.myTableView moveRowAtIndexPath:sourceIndexPath
                        toIndexPath:destinationIndexPath];
}

```

So what is going on in this code? Well, we need to make sure our data source holds the correct data that needs to get displayed in our table view after we have moved the cells around so we are removing cell 1 in section 1 first. That moves cell 2 to cell 1 and cell 3 to cell 2 with the total of 2 cells in the array. Then we will insert cell 1 into index 1 (second object) of the array. That will make our array contain cell 2, cell 1 and then cell 3. After that is done, we are doing the actual movement of cells in our table view.

Let's make this a bit more difficult. How about moving cell 2 in section 1 to the first cell in section 2?

```

- (void) moveCell2InSection1ToCell1InSection2{

    NSMutableArray *section1 = [self.arrayOfSections objectAtIndex:0];
    NSMutableArray *section2 = [self.arrayOfSections objectAtIndex:1];

    NSString *cell2InSection1 = [section1 objectAtIndex:1];
    [section1 removeObject:cell2InSection1];

    [section2 insertObject:cell2InSection1
                    atIndex:0];

    NSIndexPath *sourceIndexPath = [NSIndexPath indexPathForRow:1
                                inSection:0];
    NSIndexPath *destinationIndexPath = [NSIndexPath indexPathForRow:0
                                inSection:1];

    [self.myTableView moveRowAtIndexPath:sourceIndexPath
                        toIndexPath:destinationIndexPath];
}

```

The results of this transition are shown in [Figure 3-15](#):




Figure 3-15. Cell 2 in section 1 is moved to cell 1 in section 2

See Also

XXX

3.12 Deleting Cells and Sections from Table Views

Problem

Solution

Discussion

See Also

XXX

Storyboards

4.0 Introduction

We are all used to using view controllers now. We know how to use navigation controllers in order to push and pop view controllers. Apple believes this can be done easier and that's the whole story behind storyboards. Storyboarding is the new way of defining the connection between different screens in your app. For instance, if you have 20 unique view controllers in your app which you coded a year ago, looking at the source code *now* you will need to find your way around the connection between these view controllers and what view controller is pushed when a certain action is taken by the user. This can be very difficult especially if you have not documented your code. Storyboards to the rescue. With storyboards, you can now view/create your entire app's UI and the connection between each view controller in one screen. It's that simple.

For you to be able to take advantage of storyboarding, you need to get acquainted with Interface Builder. That is all covered in this chapter so you don't have to worry about that at all.

With storyboards, one screen's worth of content is called a scene. A scene on the iPhone can be thought of as the view of a view controller, where you put all your contents on the screen to be presented to the user at the same time. On the iPad, more than one scene can be presented to the user at the same time because of the bigger screen. Storyboarding supports transitioning from one scene to another, similar to a navigation controller pushing a view controller on top of another. That is a transition. Another type of transition is a modal view controller that slides from the bottom of the screen up to fill the screen temporarily. On the iPad, modal screens appear in the center of the screen and dim the rest of the screen usually to point out that they are the main input at that moment.

4.1 Creating a Project with Storyboards

Problem

You want to, in Xcode, create a project that uses Storyboards.

Solution

Choose the Use Storyboard option in the New Project setting dialog:




Figure 4-1. The Use Storyboard option of New Project dialog

Discussion

If you want to create a project that uses storyboards, simply follow these steps:

1. In Xcode, select the File menu and then New→New Project...
2. In the New Project dialog, make sure iOS main category is selected and select Application sub-category under iOS. Once that is done, on the right side, select Single View Application and press Next, as shown in [Figure 4-2](#).




Figure 4-2. Creating a new application for to use storyboards

3. Now select a product name and make sure your app is a Universal app. Apple wants developers to start writing universal apps whenever they can in order for iPad users to also enjoy the same apps that iPhone and iPod Touch users can enjoy. In this dialog, make sure you have checked the User Storyboards checkbox, as shown in [Figure 4-3](#). After you are done, press Next.




Figure 4-3. Using storyboards for a new project

4. You will now be asked to save your project in a folder. Once you are done, press the Create button (see [Figure 4-4](#)) and now you have a project that uses storyboards.




Figure 4-4. Saving the storyboard app on disk

Now if you have a look at the files that Xcode has created for you (see [Figure 4-5](#)), you'll notice two files whose names end with *.storyboard*. Xcode, because this is a universal app, created a storyboard for iPhone and another storyboard for iPad so we can dictate how we want our app to look like on both device families.




Figure 4-5. Two storyboard files in a universal app

See Also

XXX

4.2 Adding a Navigation Controller to a Storyboard

Problem

You want to be able to manage multiple view controllers inside a storyboard-based application.

Solution

Set a navigation controller as the initial view controller of your storyboard file.

Discussion

If you have followed the instructions in [Recipe 4.1](#) and are now running your app on the iPhone Simulator, you'll notice that there is no navigation bar on top of the screen and you are simply just looking at a white screen. The reason behind this is that the initial view controller of our storyboard file is a view controller, as opposed to a navi-

gation controller. In order to add a navigation controller to your storyboard-based app, simply follow these steps:

1. Click on the iPhone storyboard that Xcode created for you. I have named my project *Adding a Navigation Bar to a Storyboard* so my iPhone storyboard file is *MainStoryboard_iPhone.storyboard*. Once you click on this file, Interface Builder will display the contents of this file automatically.
2. Once the storyboard file is open in IB (Interface Builder), simply double-click on an empty space on the storyboard's canvas and you will see the content shrink in size and give you more free space to play with, as you can see in [Figure 4-6](#).




Figure 4-6. The zoomed out view of an iPhone storyboard

3. Under the View menu, select Utilities→Show Object Library.
4. In the Object Library, find the Navigation Controller object (see [Figure 4-7](#)) and drag and drop it into the storyboard, to the *left* side of your existing view controller ([Figure 4-6](#)). Now you will see something similar to that shown in [Figure 4-8](#).



Figure 4-7. The Navigation Controller object in the Object Library




Figure 4-8. A navigation controller comes with its own root view controller

1. As you can see in [Figure 4-8](#), the navigation controller now has added another view controller to our UI. What we need to do is to simply delete this view controller by selecting it first and then pressing the Delete button on the keyboard. Now we are left with the navigation controller and our original view controller, as you can see in [Figure 4-9](#).




Figure 4-9. Removing the root view controller that comes with the navigation controller object

2. Now click once on the navigation controller object on the storyboard. Once the navigation controller object is selected, *hold down the Control key on your keyboard and the left button on your mouse* and drag your mouse over to the view controller (on the right) that we had on our storyboard originally. This will draw a line from the navigation controller all the way to the view controller, as you can see in [Figure 4-10](#).




Figure 4-10. Connecting the navigation controller to the initial view controller

3. Now release your mouse button at which point you will be presented with a dialog asking you what type of connection you want to create between the navigation and the view controller. Select the `rootViewController` item from the list by simply clicking on it (see Figure 4-11).




Figure 4-11. Setting a view controller as the root of a navigation controller

4. After this is done, the storyboard will show that your navigation controller is now connected to the original view controller, as you can see in Figure 4-12.




Figure 4-12. The navigation controller is connected to the initial view controller

5. Last step but perhaps *the most important step* is to make our navigation controller the initial/root view controller. If we don't do this, the storyboard will use the view controller that we initially had as the initial view controller. Have another look at [Figure 4-12](#). Can you see that the view controller on the right side has a border around it. That indicates an initial view controller. To make our navigation the initial view controller, simply select the Navigation Controller under the Navigation Controller Scene panel in Interface Builder, as you can see in [Figure 4-13](#). Now select the View menu in Xcode and choose View→Show Attributes Inspector. Once the attributes inspector is opened, under the View Controller category, check the Is Initial View Controller checkbox (see [Figure 4-14](#)).




Figure 4-13. Selecting the navigation controller in Interface Builder




Figure 4-14. Selecting a navigation controller as the initial view controller of a storyboard

As you can see, now your navigation controller has a border around it. Now if you run your application, you will notice that the initial view controller has a navigation bar on

top, indicating that this view controller now has a navigation controller. In the next recipes we will see how we can make use of the navigation controller to display new scenes on the screen.




Figure 4-15. The navigation bar on a view controller created with a storyboard

We now have a navigation controller with a view controller inside it but our objective now is to trigger an action and then move from one view controller to another. Alright then; let's place a button on our view controller and push a view controller into the stack once the user presses the button. Sounds good? Alright, let's get started:

1. Go back to your *.storyboard* file.
2. In the Object Library, find the View Controller object (see [Figure 4-16](#)) and drag and drop it onto the storyboard, on the right side of our existing view controller, as shown in [Figure 4-17](#).




Figure 4-16. A view controller object in the Object Library




Figure 4-17. Adding a new view controller to a storyboard

3. In Object Library, find the Button object (see [Figure 4-18](#)) and drag and drop it into the first view controller (see [Figure 4-19](#)). Note that if you are zoomed out, Interface Builder will not allow you to drop a button onto a view controller. You need to double click on an empty space on your storyboard to zoom into it before Interface Builder allows you to drop UI components onto your view controllers.




Figure 4-18. Selecting the Button object in the Object Library




Figure 4-19. Dropping a button on the first view controller in our storyboard

4. Now select the button, hold down the Control key on your keyboard and then hold down the left mouse button and on the button and drag all the way to the second view controller (see [Figure 4-20](#)).




Figure 4-20. Connecting a button to another view controller in a storyboard

5. Now lift your fingers off the mouse button and the Control key on your keyboard. You will now be presented with a dialog similar to that shown in [Figure 4-21](#). Simply click on the `performSegueWithIdentifier:sender:` item.




Figure 4-21. Making a button perform a segue

Now if you have a look at your storyboard, you will see that the first view controller is connected to the second view controller, as shown in [Figure 4-22](#):




Figure 4-22. The first view controller is connected to the second view controller through a segue

Now if you run your app and tap on the button on the first view controller, you'll see that the second view controller will automatically get pushed onto the stack of view controllers. Once the second view controller is presented, you will see a back button on the navigation bar. If you press that button, you will be sent back to the first view controller.

See Also

XXX

4.3 Passing Data From One Screen to Another

Problem

You want to pass data from one scene to another using storyboards.

Solution

Use segue objects.

Discussion

A segue is an object, just like any other object in Objective-C. When a transition is happening from one scene to another, the storyboard runtime creates a segue object for that transition. A segue is an instance of class `UIStoryboardSegue`. When a transition happens, the current view controller (that will get pushed out of the screen after the segue) will receive the `prepareForSegue:sender:` message where the `prepareForSegue` parameter will be an object of type `UIStoryboardSegue`. If you want to pass any data from the current view controller to view controller which is about to appear on the screen, you need to do that in the `prepareForSegue:sender:` method.



For this recipe to make sense, you need to have followed the instructions in [Recipe 4.2](#) and created two view controllers inside a navigation controller on your storyboard.

Let's implement the `prepareForSegue:sender:` method in the first view controller:

```
- (void) prepareForSegue:(UIStoryboardSegue *)segue sender:(id)sender{  
  
    NSLog(@"Source Controller = %@", [segue sourceViewController]);  
    NSLog(@"Destination Controller = %@", [segue destinationViewController]);  
    NSLog(@"Segue Identifier = %@", [segue identifier]);  
  
}
```

If you run this app now, you will see the results in the console window. However, if you noted, the identifier is `nil`. Each segue has an identifier which can uniquely identify that segue. Since one scene can have more than one segue associated with it, it is good to give your segues identifiers that you can then detect in your view controllers and take action accordingly.

A segue object in Interface Builder is the connection between two scenes. Here is the segue between my first view controller and the second:




Figure 4-23. Selecting a segue object in Interface Builder

Follow these steps to give your segue an identifier:

1. Select your segue object in Interface Builder by clicking on it.
2. From the View menu, select Utilities→Show Attributes Inspector.
3. In the Attributes Inspector, in the Identifier text field, simply write the identifier that you would like this segue to carry with itself.

You can see that when the storyboard runtime calls the `prepareForSegue:sender:` method in the current view controller to prepare it for the segue, the destination view controller has already been initialized in the segue object. Now this is your chance to pass any required data to the destination view controller. You can either set the data directly into a property of the destination view controller or pass your data by calling a method on that view controller; it is really up to you. In this code, my second view controller is of class `SecondViewController` and I've given my segue the identifier of `SimpleSegueToSecondViewController`:

```
- (void) prepareForSegue:(UIStoryboardSegue *)segue sender:(id)sender{
    NSLog(@"Source Controller = %@", [segue sourceViewController]);
    NSLog(@"Destination Controller = %@", [segue destinationViewController]);
    NSLog(@"Segue Identifier = %@", [segue identifier]);

    if ([[segue identifier]
        isEqualToString:@"SimpleSegueToSecondViewController"]){

        SecondViewController *viewController = [segue destinationViewController];
        viewController.dataModel = ...
    }
}
```

```
}  
  
}
```

See Also

XXX

4.4 Adding a Storyboard to an Existing Project

Problem

You have already coded your app without storyboards and now you would like to start using storyboards instead handling the flow of your app manually.

Solution

Simply follow these steps to allow your non-storyboard apps to take advantage of storyboards:

1. From the File menu, choose New→New File...
2. In the New File dialog, make sure you have selected the Resource sub-category of the iOS category on the left and then choose Storyboard item on the right and press Next (see [Figure 4-24](#)).




Figure 4-24. Adding a storyboard to an existing application

3. In this screen, pick the Device Family for which you want to create your storyboard. If your app is an iPhone or iPad only app, then pick the appropriate device family. If your app is a universal app, you will need to select one device family now, create the storyboard file and then come back and create another one for your other device family. Once you are done, press the Next button.
4. Now select where to save your storyboard.

I had a universal app based on the Single View Application template so I have now created two storyboard files under the names *StoryboardiPhone.storyboard* and *StoryboardiPad.storyboard*.

5. In your project structure, find the *Info.plist* file. Note that this *.plist* file might have been stored under a different name. For instance, I have named my project *Adding a Storyboard to an Existing Project* and my *Info.plist* is stored under the name *Adding a Storyboard to an Existing Project-Info.plist*. Once you click on this file, the property list editor will open automatically.
6. If you have any of these keys, delete them from the *.plist* file:
 - `NSMainNibFile` (might appear as *Main nib file base name*).
 - `NSMainNibFile~ipad` (might appear as *Main nib file base name (iPad)*).

7. If you have an iPhone or iPad only app, then create a new key called `UIMainStoryboardFile` for iPhone or `UIMainStoryboardFile~ipad` for iPad. If you have a universal app, create both these keys.
8. For the value of these keys, provide the filename of the storyboards that you created *without* the `.storyboard` extension.
9. Make sure to save the `.plist` file.
10. Last but perhaps the most important part is to remove the `application:didFinishLaunchingWithOptions:` method from your app delegate's implementation. Depending on how your app is set up, this method might be setting up different view controllers and windows and etc. With storyboards, you will no longer need this.

Discussion

When creating apps on older versions of Xcode or using the new versions but not using storyboards, the structure of our apps will be different from apps that use storyboards. For once, the storyboard-based apps no longer use a main nib file for their windows. This needs to be removed from the `.plist` of our app. The other thing to do will be, as we saw in the Solution section, to make our app understand what our storyboard files are by setting them in the `.plist`.

Once all that is done, we need to make sure that our app delegate is not messing with how we are intending to load our storyboards. Every project is different and you just need to make sure that the app delegate is *not* assigning any object to the `rootViewController` property of the window. If it does, your storyboards will not be displayed and you will spend hours and hours trying to find out what the issue is. The easiest solution would be to simply comment out the entire `application:didFinishLaunchingWithOptions:` method and consider putting your initialization (for instance, initializing any data models) in other places in your app. An alternative is to simply leave this method as it is but comment out any lines that might be changing the window's root view controller object.

See Also

Concurrency

5.0 Introduction

Concurrency is achieved when two or more tasks are executed at the same time. Modern operating systems have the ability to run tasks concurrently even on one CPU. They achieve this by giving every task a certain time slice from the CPU. For instance, if there are 10 tasks to be executed in one second all with the same priority, the operating system will divide 1000 milliseconds (there are 1000 milliseconds per second) by 10 (tasks) and will give each task 100 milliseconds of the CPU time. That means all these tasks will then be executed in the same second and they will appear to have been executed concurrently.

However, with advances in technology, now we have CPUs that have more than one core. This means that the CPU is truly capable of executing tasks at the same time. The operating system will dispatch the tasks to the CPU and will wait until they are done. That simple!

Grand Central Dispatch, or GCD for short, is a low-level C API that works with block objects. The real use for GCD is to dispatch tasks to multiple cores without making you, the programmer, worry about which core is executing which task. On Mac OS X, multicore devices, including laptops, have been available to users for quite some time. With the introduction of multicore devices such as the iPad 2, programmers can write amazing multicore-aware multithreaded apps for iOS.

At the heart of GCD are dispatch queues. Dispatch queues, as we will see soon, are pools of threads managed by GCD on the host operating system, whether it is iOS or Mac OS X. You will not be working with these threads directly. You will just work with dispatch queues, dispatching *tasks* to these queues and asking the queues to invoke your tasks. GCD offers several options for running tasks: synchronously, asynchronously, after a certain delay, etc.

To start using GCD in your apps, you don't have to import any special library into your project. Apple has already incorporated GCD into various frameworks, including Core Foundation and Cocoa/Cocoa Touch. All methods and data types available in GCD

start with a *dispatch_* keyword. For instance, `dispatch_async` allows you to dispatch a task on a queue for asynchronous execution, whereas `dispatch_after` allows you to run a block of code after a given delay.

Traditionally, programmers had to create their own threads to perform tasks in parallel. For instance, an iOS developer would create a thread similar to this to perform an operation 1000 times:

```
- (void) doCalculation{
    /* Do your calculation here */
}

- (void) calculationThreadEntry{

    @autoreleasepool {
        NSUInteger counter = 0;
        while ([[NSThread currentThread] isCancelled] == NO){
            [self doCalculation];
            counter++;
            if (counter >= 1000){
                break;
            }
        }
    }
}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    /* Start the thread */
    [NSThread detachNewThreadSelector:@selector(calculationThreadEntry)
        toTarget:self
        withObject:nil];

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

The programmer has to start the thread manually and then create the required structure for the thread (entry point, autorelease pool, and thread's main loop). When we write the same code with GCD, we really won't have to do much:

```
dispatch_queue_t queue =
    dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

size_t numberOfIterations = 1000;

dispatch_async(queue, ^(void) {
    dispatch_apply(numberOfIterations, queue, ^(size_t iteration){
        /* Perform the operation here */
    })
})
```



```
});  
});
```

In this chapter, you will learn all there is to know about GCD and how to use it to write modern multithreaded apps for iOS and Mac OS X that will achieve blazing performance on multicore devices such as the iPad 2.

We will be working with dispatch queues a lot, so please make sure that you fully understand the concept behind them. There are three types of dispatch queues:

Main Queue

This queue performs all its tasks on the main thread, which is where Cocoa and Cocoa Touch require programmers to call all UI-related methods. Use the `dispatch_get_main_queue` function to retrieve the handle to the main queue.

Concurrent Queues

These are queues that you can retrieve from GCD in order to execute asynchronous or synchronous tasks. Multiple concurrent queues can be executing multiple tasks in parallel, without breaking a sweat. No more thread management, yippee! Use the `dispatch_get_global_queue` function to retrieve the handle to a concurrent queue.

Serial Queues

These are queues that, no matter whether you submit synchronous or asynchronous tasks to them, will always execute their tasks in a first-in-first-out (FIFO) fashion, meaning that they can only execute one block object at a time. However, they do *not* run on the main thread and therefore are perfect for a series of tasks that have to be executed in strict order without blocking the main thread. Use the `dispatch_queue_create` function to create a serial queue. Once you are done with the queue, you must release it using the `dispatch_release` function.

At any moment during the lifetime of your application, you can use multiple dispatch queues at the same time. Your system has only one main queue, but you can create as many serial dispatch queues as you want, within reason, of course, for whatever functionality you require for your app. You can also retrieve multiple concurrent queues and dispatch your tasks to them. Tasks can be handed to dispatch queues in two forms: block objects or C functions, as we will see in [Recipe 5.4](#).

Block objects are *packages* of code that usually appear in the form of methods in Objective-C. Block objects, together with Grand Central Dispatch (GCD), create a harmonious environment in which you can deliver high-performance multithreaded apps in iOS and Mac OS X. What's so special about block objects and GCD, you might ask? It's simple: no more threads! All you have to do is to put your code in block objects and ask GCD to take care of the execution of that code for you.

Block objects in Objective-C are what the programming field calls *first-class objects*. This means you can build code dynamically, pass a block object to a method as a parameter, and return a block object from a method. All of these things make it easier to choose what you want to do at runtime and change the activity of a program. In

particular, block objects can be run in individual threads by GCD. Being Objective-C objects, block objects can be treated like any other object.



Block objects are sometimes referred to as *closures*.

Constructing block objects is similar to constructing traditional C functions, as we will see in [Recipe 5.1](#). Block objects can have return values and can accept parameters. Block objects can be defined inline or treated as a separate block of code, similar to a C function. When created inline, the scope of variables accessible to block objects is considerably different from when a block object is implemented as a separate block of code.

GCD works with block objects. When performing tasks with GCD, you can pass a block object whose code can get executed synchronously or asynchronously, depending on which methods you use in GCD. Thus, you can create a block object that is responsible for downloading a URL passed to it as a parameter. That single block object can then be used in various places in your app synchronously or asynchronously, depending on how you would like to run it. You don't have to make the block object synchronous or asynchronous per se; you will simply call it with synchronous or asynchronous GCD methods and the block object will *just work*.

Block objects are quite new to programmers writing iOS and OS X apps. In fact, block objects are not as popular as threads yet, perhaps because their syntax is a bit different from pure Objective-C methods and more complicated. Nonetheless, block objects are enormously powerful and Apple is making a big push toward incorporating them into Apple libraries. You can already see these additions in classes such as `NSMutableArray`, where programmers can sort the array using a block object.

This chapter is dedicated entirely to constructing and using block objects in iOS and Mac OS X apps, using GCD for dispatching tasks to the operating system, threads and timers. I would like to stress that the only way to get used to block objects' syntax is to write a few of them for yourself. Have a look at the sample code in this chapter and try implementing your own block objects.

Here, you will learn the basics of block objects, followed by some more advanced subjects such as Grand Central Dispatch, Threads, Timers, Operations and Operation Queues. You will understand everything you need to know about block objects before moving to the Grand Central Dispatch material. From my experience, the best way to learn block objects is through examples, so you will see a lot of them in this chapter. Make sure you try the examples for yourself in Xcode to really *get* the syntax of block objects.

Operations can be configured to run a block of code synchronously or asynchronously. You can manage operations manually or place them on *operation queues*, which facilitate concurrency so that you do not need to think about the underlying thread management. In this chapter, you will see how to use operations and operation queues, as well as basic threads and timers, to synchronously and asynchronously execute tasks in applications.

Cocoa provides three different types of operations:

Block operations

These facilitate the execution of one or more block objects.

Invocation operations

These allow you to invoke a method in another, currently existing object.

Plain operations

These are plain operation classes that need to be subclassed. The code to be executed will be written inside the `main` method of the operation object.

Operations, as mentioned before, can be managed with operation queues, which have the data type `NSOperationQueue`. After instantiating any of the aforementioned operation types (block, invocation, or plain operation), you can add them to an operation queue and have the queue manage the operation.

An operation object can have dependencies on other operation objects and be instructed to wait for the completion of one or more operations before executing the task associated with it. Unless you add a dependency, you have no control over the order in which operations run. For instance, adding them to a queue in a certain order does not guarantee that they will execute in that order, despite the use of the term *queue*.

There are a few important things to bear in mind while working with operation queues and operations:

- Operations, by default, run on the thread that starts them, using their `start` instance method. If you want the operations to work asynchronously, you will have to use either an operation queue or a subclass `NSOperation` and detach a new thread on the `main` instance method of the operation.
- An operation can wait for the execution of another operation to finish before it starts its execution. Be careful not to create interdependent operations, a common mistake known as a *race condition*. In other words, do not tell operation A to depend on operation B if B already depends on A; this will cause both to wait forever, taking up memory and possibly hanging your application.
- Operations can be cancelled. So, if you have subclassed `NSOperation` to create custom operation objects, you have to make sure to use the `isCancelled` instance method to check whether the operation has been cancelled before executing the task associated with the operation. For instance, if your operation's task is to check for the availability of an Internet connection every 20 seconds, it must call the `isCancelled` instance method at the beginning of each run to make sure it has not

been cancelled before attempting to check for an Internet connection again. If the operation takes more than a few seconds (such as when you download a file), you should also check `isCancelled` periodically while running the task.

- Operation objects are key-value observing (KVO) compliant on various key paths such as `isFinished`, `isReady`, and `isExecuting`. We will be discussing Key Value Coding and Key Value Observing in a later chapter.
- If you plan to subclass `NSOperation` and provide a custom implementation for the operation, you must create your own autorelease pool in the `main` method of the operation, which gets called from the `start` method. We will discuss this in detail later in this chapter.
- Always keep a reference to the operation objects you create. The concurrent nature of operation queues might make it impossible for you to retrieve a reference to an operation after it has been added to the queue.

Threads and timers are objects, subclassing `NSObject`. Threads are more low-level than timers. When an application runs under iOS, the operating system creates at least one thread for that application, called the main thread. Every thread and timer must be added to a run loop. A run loop, as its name implies, is a loop during which different events can occur, such as a timer firing or a thread running. Discussion of run loops is beyond the scope of this chapter, but we will refer to them here and there in recipes.

Think of a run loop as a kind of loop that has a starting point, a condition for finishing, and a series of events to process during its lifetime. A thread or timer is attached to a run loop and in fact requires a run loop to function.

The main thread of an application is the thread that handles the UI events. If you perform a long-running task on the main thread, you will notice that the UI of your application will become unresponsive or slow to respond. To avoid this, you can create separate threads and/or timers, each of which performs its own task (even if it is a long-running task) but will not block the main thread.

5.1 Constructing Block Objects

Problem

You want to be able to write your own block objects or use block objects with iOS SDK classes.

Solution

You just need to understand the basic differences between the syntax of block objects and classic C functions. These differences are explained in the Discussion section.

Discussion

Block objects can either be inline or coded as independent blocks of code. Let's start with the latter type. Suppose you have a method in Objective-C that accepts two integer values of type `NSInteger` and returns the difference of the two values, by subtracting one from the other, as an `NSInteger`:

```
- (NSInteger) subtract:(NSInteger)paramValue
               from:(NSInteger)paramFrom{

    return paramFrom - paramValue;

}
```

That was very simple, wasn't it? Now let's translate this Objective-C code to a pure C function that provides the same functionality to get one step closer to learning the syntax of block objects:

```
NSInteger subtract(NSInteger paramValue, NSInteger paramFrom){

    return paramFrom - paramValue;

}
```

You can see that the C function is quite different in syntax from its Objective-C counterpart. Now let's have a look at how we could code the same function as a block object:

```
NSInteger (^subtract)(NSInteger, NSInteger) =
    ^(NSInteger paramValue, NSInteger paramFrom){

        return paramFrom - paramValue;

    };
```

Before I go into details about the syntax of block objects, let me show you a few more examples. Suppose we have a function in C that takes a parameter of type `NSUInteger` (an unsigned integer) and returns it as a string of type `NSString`. Here is how we implement this in C:

```
NSString* intToString (NSUInteger paramInteger){

    return [NSString stringWithFormat:@"%lu",
        (unsigned long)paramInteger];

}
```



To learn about formatting strings with system-independent format specifiers in Objective-C, please refer to [String Programming Guide, iOS Developer Library](#) on Apple's website.

The block object equivalent of this C function is shown in [Example 5-1](#).

Example 5-1. Example block object defined as function

```
NSString* (^intToString)(NSInteger) = ^(NSInteger paramInteger){
    NSString *result = [NSString stringWithFormat:@"%lu",
                        (unsigned long)paramInteger];

    return result;
};
```

The simplest form of an independent block object would be a block object that returns void and does not take any parameters in:

```
void (^simpleBlock)(void) = ^{
    /* Implement the block object here */
};
```

Block objects can be invoked in the exact same way as C functions. If they have any parameters, you pass the parameters to them like a C function and any return value can be retrieved exactly as you would retrieve a C function's return value. Here is an example:

```
NSString* (^intToString)(NSInteger) = ^(NSInteger paramInteger){
    NSString *result = [NSString stringWithFormat:@"%lu",
                        (unsigned long)paramInteger];

    return result;
};

- (void) callIntToString{

    NSString *string = intToString(10);
    NSLog(@"string = %@", string);

}
```

The `callIntToString` Objective-C method is calling the `intToString` block object by passing the value 10 as the only parameter to this block object and placing the return value of this block object in the `string` local variable.

Now that we know how to write block objects as independent blocks of code, let's have a look at passing block objects as parameters to Objective-C methods. We will have to think a bit abstractly to understand the goal of the following example.

Suppose we have an Objective-C method that accepts an integer and performs some kind of transformation on it, which may change depending on what else is happening in our program. We know that we'll have an integer as input and a string as output, but we'll leave the exact transformation up to a block object that can be different each time our method runs. This method, therefore, will accept as parameters both the integer to be transformed and the block that will transform it.

For our block object, we'll use the same `intToString` block object that we implemented earlier in [Example 5-1](#). Now we need an Objective-C method that will accept an unsigned integer parameter and a block object as its parameter. The unsigned integer parameter is easy, but how do we tell our method that it has to accept a block object

of the same type as the `intToString` block object? First we `typedef` the signature of the `intToString` block object, which tells the compiler what parameters our block object should accept:

```
typedef NSString* (^IntToStringConverter)(NSUInteger paramInteger);
```

This `typedef` just tells the compiler that block objects that accept an integer parameter and return a string can simply be represented by an identifier named `IntToStringConverter`. Now let's go ahead and write our Objective-C method that accepts both an integer and a block object of type `IntToStringConverter`:

```
- (NSString *) convertIntToString:(NSUInteger)paramInteger
    usingBlockObject:(IntToStringConverter)paramBlockObject{

    return paramBlockObject(paramInteger);

}
```

All we have to do now is call the `convertIntToString:` method with our block object of choice ([Example 5-2](#)).

Example 5-2. Calling the block object in another method

```
- (void) doTheConversion{

    NSString *result = [self convertIntToString:123
                          usingBlockObject:intToString];

    NSLog(@"result = %@", result);

}
```

Now that we know something about independent block objects, let's turn to inline block objects. In the `doTheConversion` method we just saw, we passed the `intToString` block object as the parameter to the `convertIntToString:usingBlockObject:` method. What if we didn't have a block object ready to be passed to this method? Well, that wouldn't be a problem. As mentioned before, block objects are first-class functions and can be constructed at runtime. Let's have a look at an alternative implementation of the `doTheConversion` method ([Example 5-3](#)).

Example 5-3. Example block object defined as function

```
- (void) doTheConversion{

    IntToStringConverter inlineConverter = ^(NSUInteger paramInteger){
        NSString *result = [NSString stringWithFormat:@"%lu",
                          (unsigned long)paramInteger];

        return result;
    };

    NSString *result = [self convertIntToString:123
                          usingBlockObject:inlineConverter];

}
```

```

    NSLog(@"result = %@", result);
}

```

Compare [Example 5-3](#) to the earlier [Example 5-1](#). I have removed the initial code that provided the block object's signature, which consisted of a name and argument, (^intToString)(NSUInteger). I left all the rest of the block object intact. It is now an anonymous object. But this doesn't mean I have no way to refer to the block object. I assign it using an equal sign to a type and a name: `IntToStringConverter inline Converter`. Now I can use the data type to enforce proper use in methods, and use the name to actually pass the block object.

In addition to constructing block objects inline as just shown, we can construct a block object *while* passing it as a parameter:

```

- (void) doTheConversion{

    NSString *result =
    [self convertIntToString:123
        usingBlockObject:^(NSString *(NSUInteger paramInteger) {

        NSString *result = [NSString stringWithFormat:@"%lu",
            (unsigned long)paramInteger];

        return result;

    }]];

    NSLog(@"result = %@", result);

}

```

Compare this example with [Example 5-2](#). Both methods use a block object through the `usingBlockObject` syntax. But whereas the earlier version referred to a previously declared block object by name (`intToString`), this one simply creates a block object on the fly. In this code, we constructed an inline block object that gets passed to the `convertIntToString:usingBlockObject:` method as the second parameter.

See Also

XXX

5.2 Accessing Variables in Block Objects

Problem

You want to understand the difference between accessing variables in Objective-C methods and accessing those variables in block objects.

Solution

Here is a brief summary of what you must know about variables in block objects:

- Local variables in block objects work exactly the same as in Objective-C methods.
- For inline block objects, local variables constitute not only variables defined within the block, but also the variables that have been defined in the method that implements that block object. (Examples will come shortly.)
- You *cannot* refer to `self` in independent block objects implemented in an Objective-C class. If you need to access `self`, you must pass that object to the block object as a parameter. We will see an example of this soon.
- You can refer to `self` in an inline block object only if `self` is present in the lexical scope inside which the block object is created.
- For inline block objects, local variables that are defined *inside* the block object's implementation can be read from and written to. In other words, the block object has read-write access to variables defined inside the block object's body.
- For inline block objects, variables local to the Objective-C method that implements that block can only be read from, not written to. There is an exception, though: a block object can write to such variables if they are defined with the `__block` storage type. We will see an example of this as well.
- Suppose you have an object of type `NSObject` and inside that object's implementation you are using a block object in conjunction with GCD. Inside this block object, you will have read-write access to declared properties of that `NSObject` inside which your block is implemented.
- You can access declared properties of your `NSObject` inside independent block objects *only if* you use the setter and getter methods of these properties. You cannot access declared properties of an object using dot notation inside an independent block object.

Discussion

Let's first see how we can use variables that are local to the implementation of two block objects. One is an inline block object and the other an independent block object:

```
void (^independentBlockObject)(void) = ^(void){  
  
    NSInteger localInteger = 10;  
  
    NSLog(@"local integer = %ld", (long)localInteger);  
  
    localInteger = 20;  
  
    NSLog(@"local integer = %ld", (long)localInteger);  
  
};
```

Invoking this block object, the values we assigned are printed to the console window:

```
local integer = 10
local integer = 20
```

So far, so good. Now let's have a look at inline block objects and variables that are local to them:

```
- (void) simpleMethod{

    NSInteger outsideVariable = 10;

    NSMutableArray *array = [[NSMutableArray alloc]
                             initWithObjects:@"obj1",
                             @"obj2", nil];

    [array sortUsingComparator:^(NSComparisonResult(id obj1, id obj2) {
        NSInteger insideVariable = 20;

        NSLog(@"Outside variable = %lu", (unsigned long)outsideVariable);
        NSLog(@"Inside variable = %lu", (unsigned long)insideVariable);

        /* Return value for our block object */
        return NSOrderedSame;
    })];
}
```



The `sortUsingComparator:` instance method of `NSMutableArray` attempts to sort a mutable array. The goal of this example code is just to demonstrate the use of local variables, so you don't have to know what this method actually does.

The block object can read and write its own `insideVariable` local variable. However, the block object has read-only access to the `outsideVariable` variable by default. In order to allow the block object to write to `outsideVariable`, we must prefix `outsideVariable` with the `__block` storage type:

```
- (void) simpleMethod{

    __block NSInteger outsideVariable = 10;

    NSMutableArray *array = [[NSMutableArray alloc]
                             initWithObjects:@"obj1",
                             @"obj2", nil];

    [array sortUsingComparator:^(NSComparisonResult(id obj1, id obj2) {

        NSInteger insideVariable = 20;
        outsideVariable = 30;

    })];
}
```

```

        NSLog(@"Outside variable = %lu", (unsigned long)outsideVariable);
        NSLog(@"Inside variable = %lu", (unsigned long)insideVariable);

        /* Return value for our block object */
        return NSOrderedSame;

    }];

}

```

Accessing `self` in inline block objects is fine as long as `self` is defined in the lexical scope inside which the inline block object is created. For instance, in this example, the block object will be able to access `self`, since `simpleMethod` is an instance method of an Objective-C class:

```

- (void) simpleMethod{

    NSMutableArray *array = [[NSMutableArray alloc]
                             initWithObjects:@"obj1",
                             @"obj2", nil];

    [array sortUsingComparator:^(NSComparisonResult(id obj1, id obj2) {

        NSLog(@"self = %@", self);

        /* Return value for our block object */
        return NSOrderedSame;

    })];

}

```

You cannot, without a change in your block object's implementation, access `self` in an independent block object. Attempting to compile this code will give you a compile-time error:

```

void (^incorrectBlockObject)(void) = ^{
    NSLog(@"self = %@", self); /* self is undefined here */
};

```

If you want to access `self` in an independent block object, simply pass the object that `self` represents as a parameter to your block object:

```

void (^correctBlockObject)(id) = ^(id self){

    NSLog(@"self = %@", self);

};

- (void) callCorrectBlockObject{

    correctBlockObject(self);

}

```



You don't have to assign the name `self` to this parameter. You can simply call this parameter anything else. However, if you call this parameter `self`, you can simply grab your block object's code later and place it in an Objective-C method's implementation without having to change every instance of your variable's name to `self` for it to be understood by the compiler.

Let's have a look at declared properties and how block objects can access them. For inline block objects, you can use dot notation to read from or write to declared properties of `self`. For instance, let's say we have a declared property of type `NSString` called `stringProperty` in our class:

```
#import <UIKit/UIKit.h>

@interface GCDAppDelegate : NSObject <UIApplicationDelegate>

@property (nonatomic, strong) NSString *stringProperty;

@end
```

Now we can simply access this property in an inline block object like so:

```
#import "GCDAppDelegate.h"

@implementation GCDAppDelegate

@synthesize stringProperty;

- (void) simpleMethod{

    NSMutableArray *array = [[NSMutableArray alloc]
                             initWithObjects:@"obj1",
                             @"obj2", nil];

    [array sortUsingComparator:^(NSComparisonResult(id obj1, id obj2) {

        NSLog(@"self = %@", self);

        self.stringProperty = @"Block Objects";

        NSLog(@"String property = %@", self.stringProperty);

        /* Return value for our block object */
        return NSOrderedSame;

    })];

}

@end
```

In an independent block object, however, you cannot use dot notation to read from or write to a declared property:

```

void (^correctBlockObject)(id) = ^(id self){

    NSLog(@"self = %@", self);

    /* Should use setter method instead of this */
    self.stringProperty = @"Block Objects"; /* Compile-time Error */

    /* Should use getter method instead of this */
    NSLog(@"self.stringProperty = %@",
          self.stringProperty); /* Compile-time Error */

};

```

Instead of dot notation in this scenario, use the getter and the setter methods of this synthesized property:

```

void (^correctBlockObject)(id) = ^(id self){

    NSLog(@"self = %@", self);

    /* This will work fine */
    [self setStringProperty:@"Block Objects"];

    /* This will work fine as well */
    NSLog(@"self.stringProperty = %@",
          [self stringProperty]);

};

```

When it comes to inline block objects, there is one *very* important rule that you have to remember: inline block objects copy the value for the variables in their lexical scope. If you don't understand what that means, don't worry. Let's have a look at an example:

```

typedef void (^BlockWithNoParams)(void);

- (void) scopeTest{

    NSUInteger integerValue = 10;

    /***** Definition of internal block object *****/
    BlockWithNoParams myBlock = ^{
        NSLog(@"Integer value inside the block = %lu",
              (unsigned long)integerValue);
    };
    /***** End definition of internal block object *****/

    integerValue = 20;

    /* Call the block here after changing the
       value of the integerValue variable */
    myBlock();

    NSLog(@"Integer value outside the block = %lu",
          (unsigned long)integerValue);

}

```

We are declaring an integer local variable and initially assigning the value of 10 to it. We then implement our block object but *don't call the block object yet*. After the block object is *implemented*, we simply change the value of the local variable that the block object will later try to read when we call it. Right after changing the local variable's value to 20, we call the block object. You would expect the block object to print the value 20 for the variable, but it won't. It will print 10, as you can see here:

```
Integer value inside the block = 10
Integer value outside the block = 20
```

What's happening here is that the block object is keeping a read-only copy of the `integerValue` variable for itself right where the block is implemented. You might be thinking: why is the block object capturing a *read-only* value of the local variable `integerValue`? The answer is simple, and we've already learned it in this section. Unless prefixed with storage type `__block`, local variables in the lexical scope of a block object are just passed to the block object as read-only variables. Therefore, to change this behavior, we could change the implementation of our `scopeTest` method to prefix the `integerValue` variable with `__block` storage type, like so:

```
- (void) scopeTest{

    __block NSUInteger integerValue = 10;

    /***** Definition of internal block object *****/
    BlockWithNoParams myBlock = ^{
        NSLog(@"Integer value inside the block = %lu",
              (unsigned long)integerValue);
    };
    /***** End definition of internal block object *****/

    integerValue = 20;

    /* Call the block here after changing the
       value of the integerValue variable */
    myBlock();

    NSLog(@"Integer value outside the block = %lu",
          (unsigned long)integerValue);

}
```

Now if we get the results from the console window after the `scopeTest` method is called, we will see this:

```
Integer value inside the block = 20
Integer value outside the block = 20
```

This section should have given you sufficient information about using variables with block objects. I suggest that you write a few block objects and use variables inside them, assigning to them and reading from them, to get a better understanding of how block objects use variables. Keep coming back to this section if you forget the rules that govern variable access in block objects.

See Also

XXX

5.3 Invoking Block Objects

Problem

You've learned how to construct block objects and now you want to execute your block objects to get results.

Solution

Execute your block objects the same way you execute a C function, as shown in the Discussion section.

Discussion

We've seen examples of invoking block objects in [Recipe 5.1](#) and [Recipe 5.2](#). This section contains more concrete examples.

If you have an independent block object, you can simply invoke it just like you would invoke a C function:

```
void (^simpleBlock)(NSString *) = ^(NSString *paramString){
    /* Implement the block object here and use the
       paramString parameter */
};

- (void) callSimpleBlock{

    simpleBlock(@"O'Reilly");

}
```

If you want to invoke an independent block object within another independent block object, follow the same instructions by invoking the new block object just as you would invoke a C method:

```
/****** Definition of first block object *****/
NSString *(^trimString)(NSString *) = ^(NSString *inputString){

    NSString *result = [inputString stringByTrimmingCharactersInSet:
                        [NSCharacterSet whitespaceCharacterSet]];

    return result;

};
/****** End definition of first block object *****/

/****** Definition of second block object *****/
NSString *(^trimWithOtherBlock)(NSString *) = ^(NSString *inputString){
    return trimString(inputString);
}
```

```
};
/***** End definition of second block object *****/

- (void) callTrimBlock{

    NSString *trimmedString = trimWithOtherBlock(@"    O'Reilly    ");
    NSLog(@"Trimmed string = %@", trimmedString);

}
```

In this example, go ahead and invoke the `callTrimBlock` Objective-C method:

```
[self callTrimBlock];
```

The `callTrimBlock` method will call the `trimWithOtherBlock` block object, and the `trimWithOtherBlock` block object will call the `trimString` block object in order to trim the given string. Trimming a string is an easy thing to do and can be done in one line of code, but this example code shows how you can call block objects within block objects.

See Also

XXX

5.4 Dispatching Tasks to Grand Central Dispatch

Problem

Solution

There are two ways to submit tasks to dispatch queues:

- Block Objects (see [Recipe 5.1](#))
- C functions

Discussion

Block objects are the best way of utilizing GCD and its enormous power. Some GCD functions have been extended to allow programmers to use C functions instead of block objects. However, the truth is that only a limited set of GCD functions allow programmers to use C functions, so please do read the recipe about block objects ([Recipe 5.1](#)) before proceeding any further.

C functions that have to be supplied to various GCD functions should be of type `dispatch_function_t`, which is defined as follows in the Apple libraries:

```
typedef void (*dispatch_function_t)(void *);
```

So if we want to create a function named, for instance, `myGCDFunction`, we would have to implement it in this way:


```
void myGCDFunction(void * paraContext){
    /* Do the work here */
}
```



The `paraContext` parameter refers to the context that GCD allows programmers to pass to their C functions when they dispatch tasks to them. We will learn about this shortly.

Block objects that get passed to GCD functions don't always follow the same structure. Some must accept parameters and some shouldn't, but none of the block objects submitted to GCD return a value.

In the next three sections you will learn how to submit tasks to GCD for execution whether they are in the form of block objects or C functions.

See Also

XXX

5.5 Performing UI-Related Tasks with GCD

Problem

You are using GCD for concurrency and you would like to know what the best way of working with UI-related APIs is.

Solution

Use the `dispatch_get_main_queue` function.

Discussion

UI-related tasks have to be performed on the main thread, so the main queue is the only candidate for UI task execution in GCD. We can use the `dispatch_get_main_queue` function to get the handle to the main dispatch queue.

There are two ways of dispatching tasks to the main queue. Both are asynchronous, letting your program continue even when the task is not yet executed:

dispatch_async function

Executes a block object on a dispatch queue.

dispatch_async_f function

Executes a C function on a dispatch queue.



The `dispatch_sync` method *cannot* be called on the main queue because it will block the thread indefinitely and cause your application to deadlock. All tasks submitted to the main queue through GCD must be submitted asynchronously.

Let's have a look at using the `dispatch_async` function. It accepts two parameters:

Dispatch queue handle

The dispatch queue on which the task has to be executed.

Block object

The block object to be sent to the dispatch queue for asynchronous execution.

Here is an example. This code will display an alert, in iOS, to the user, using the main queue:

```
dispatch_queue_t mainQueue = dispatch_get_main_queue();

dispatch_async(mainQueue, ^(void) {

    [[[UIAlertView alloc] initWithTitle:@"GCD"
                                message:@"GCD is amazing!"
                                delegate:nil
                                cancelButtonTitle:@"OK"
                                otherButtonTitles:nil, nil] show];

});
```



As you've noticed, the `dispatch_async` GCD function has no parameters or return value. The block object that is submitted to this function must gather its own data in order to complete its task. In the code snippet that we just saw, the alert view has all the values that it needs to finish its task. However, this might not always be the case. In such instances, you must make sure the block object submitted to GCD has access in its scope to all the values that it requires.

Running this app in iOS Simulator, the user will get results similar to those shown in [Figure 5-1](#).



Figure 5-1. An alert displayed using asynchronous GCD calls

This might not be that impressive. In fact, it is not impressive at all if you think about it. So what makes the main queue truly interesting? The answer is simple: when you are getting the maximum performance from GCD to do some heavy calculation on concurrent or serial threads, you might want to display the results to your user or move a component on the screen. For that, you *must* use the main queue, because it is UI-related work. The functions shown in this section are the *only* way to get out of a serial or a concurrent queue while still utilizing GCD to update your UI, so you can imagine how important it is.

Instead of submitting a block object for execution on the main queue, you can submit a C function object. Submit all UI-related C functions for execution in GCD to the `dispatch_async_f` function. We can get the same results as we got in [Figure 5-1](#), using C functions instead of block objects, with a few adjustments to our code.

As mentioned before, with the `dispatch_async_f` function, we can submit a pointer to an application-defined context, which can then be used by the C function that gets called. So here is the plan: let's create a structure that holds values such as an alert view's title, message, and cancel-button's title. When our app starts, we will put all the values in this structure and pass it to our C function to display. Here is how we are defining our structure:

```
typedef struct{
    char *title;
    char *message;
    char *cancelButtonText;
} UIAlertViewData;
```

Now let's go and implement a C function that we will later call with GCD. This C function should expect a parameter of type `void *`, which we will then typecast to `UIAlertViewData *`. In other words, we expect the caller of this function to pass us a reference to the data for our alert view, encapsulated inside the `UIAlertViewData` structure:

```
void displayAlertView(void *paramContext){

    UIAlertViewData *alertData = (UIAlertViewData *)paramContext;

    NSString *title =
        [NSString stringWithUTF8String:alertData->title];

    NSString *message =
        [NSString stringWithUTF8String:alertData->message];

    NSString *cancelButtonText =
        [NSString stringWithUTF8String:alertData->cancelButtonText];

    [[[UIAlertView alloc] initWithTitle:title
                                message:message
                                delegate:nil
                                cancelButtonTitle:cancelButtonText
                                otherButtonTitles:nil, nil] show];

    free(alertData);
}
```



The reason we are freeing the context passed to us in here instead of in the caller is that the caller is going to execute this C function asynchronously and cannot know when our C function will finish executing. Therefore, the caller has to `malloc` enough space for the `UIAlertViewData` context and our `displayAlertView` C function has to free that space.

And now let's call the `displayAlertView` function on the main queue and pass the context (the structure that holds the alert view's data) to it:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    dispatch_queue_t mainQueue = dispatch_get_main_queue();

    UIAlertViewData *context = (UIAlertViewData *)
    malloc(sizeof(UIAlertViewData));

    if (context != NULL){
        context->title = "GCD";
        context->message = "GCD is amazing.";
        context->cancelButtonTitle = "OK";

        dispatch_async_f(mainQueue,
                        (void *)context,
                        displayAlertView);
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

If you invoke the `currentThread` class method of the `NSThread` class, you will find out that the block objects or the C functions you dispatch to the main queue are indeed running on the main thread:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    dispatch_queue_t mainQueue = dispatch_get_main_queue();

    dispatch_async(mainQueue, ^(void) {
        NSLog(@"Current thread = %@", [NSThread currentThread]);
        NSLog(@"Main thread = %@", [NSThread mainThread]);
    });

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

The output of this code would be similar to that shown here:

```
Current thread = <NSThread: 0x4b0e4e0>{name = (null), num = 1}
Main thread = <NSThread: 0x4b0e4e0>{name = (null), num = 1}
```

Now that you know how to perform UI-related tasks using GCD, it is time we moved to other subjects, such as performing tasks in parallel using concurrent queues (see [Recipe 5.6](#) and [Recipe 5.7](#)) and mixing our code with UI-related code if need be.

See Also

XXX

5.6 Performing Non-UI-Related Tasks Synchronously with GCD

Problem

You want to perform synchronous tasks that do not involve any UI-related code.

Solution

Use the `dispatch_sync` function.

Discussion

There are times when you want to perform tasks that have nothing to do with the UI or interact with the UI as well as doing other tasks that take up a lot of time. For instance, you might want to download an image and display it to the user after it is downloaded. The downloading process has absolutely nothing to do with the UI.

For any task that doesn't involve the UI, you can use global concurrent queues in GCD. These allow either synchronous or asynchronous execution. But synchronous execution does *not* mean your program waits for the code to finish before continuing. It simply means that the concurrent queue will wait until your task has finished before it continues to the next block of code on the queue. When you put a block object on a concurrent queue, your own program *always* continues right away without waiting for the queue to execute the code. This is because concurrent queues, as their name implies, run their code on threads other than the main thread. (There is one exception to this: when a task is submitted to a concurrent or a serial queue using the `dispatch_sync` function, iOS will, if possible, run the task on the *current* thread, which *might* be the main thread, depending on where the code path is at the moment. This is an optimization that has been programmed on GCD, as we shall soon see.)

If you submit a task to a concurrent queue synchronously, and at the same time submit another synchronous task to *another* concurrent queue, these two synchronous tasks will run asynchronously in relation to each other because they are running two *different concurrent queues*. It's important to understand this because sometimes, as we'll see, you want to make sure task A finishes before task B starts. To ensure that, submit them synchronously to the *same* queue.

You can perform synchronous tasks on a dispatch queue using the `dispatch_sync` function. All you have to do is to provide it with the handle of the queue that has to run the task and a block of code to execute on that queue.

Let's look at an example. It prints the integers 1 to 1000 twice, one complete sequence after the other, without blocking the main thread. We can create a block object that does the counting for us and synchronously call the same block object twice:

```
void (^printFrom1To1000)(void) = ^{

    NSUInteger counter = 0;
    for (counter = 1;
         counter <= 1000;
         counter++){

        NSLog(@"Counter = %lu - Thread = %@",
              (unsigned long)counter,
              [NSThread currentThread]);

    }

};
```

Now let's go and invoke this block object using GCD:

```
dispatch_queue_t concurrentQueue =
    dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

dispatch_sync(concurrentQueue, printFrom1To1000);
dispatch_sync(concurrentQueue, printFrom1To1000);
```

If you run this code, you might notice the counting taking place on the main thread, even though you've asked a concurrent queue to execute the task. It turns out this is an optimization by GCD. The `dispatch_sync` function will use the current thread—the thread you're using when you dispatch the task—whenever possible, as a part of an optimization that has been programmed into GCD. Here is what Apple says about it:

As an optimization, this function invokes the block on the current thread when possible.

—Grand Central Dispatch (GCD) Reference

To execute a C function instead of a block object, synchronously, on a dispatch queue, use the `dispatch_sync_f` function. Let's simply translate the code we've written for the `printFrom1To1000` block object to its equivalent C function, like so:

```
void printFrom1To1000(void *paramContext){

    NSUInteger counter = 0;
    for (counter = 1;
         counter <= 1000;
         counter++){

        NSLog(@"Counter = %lu - Thread = %@",
              (unsigned long)counter,
              [NSThread currentThread]);

    }
```

```

    }
}

```

And now we can use the `dispatch_sync_f` function to execute the `printFrom1To1000` function on a concurrent queue, as demonstrated here:

```

dispatch_queue_t concurrentQueue =
    dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

dispatch_sync_f(concurrentQueue,
                NULL,
                printFrom1To1000);

dispatch_sync_f(concurrentQueue,
                NULL,
                printFrom1To1000);

```

The first parameter of the `dispatch_get_global_queue` function specifies the priority of the concurrent queue that GCD has to retrieve for the programmer. The higher the priority, the more CPU timeslices will be provided to the code getting executed on that queue. You can use any of these values for the first parameter to the `dispatch_get_global_queue` function:

`DISPATCH_QUEUE_PRIORITY_LOW`

Fewer timeslices will be applied to your task than normal tasks.

`DISPATCH_QUEUE_PRIORITY_DEFAULT`

The default system priority for code execution will be applied to your task.

`DISPATCH_QUEUE_PRIORITY_HIGH`

More timeslices will be applied to your task than normal tasks.



The second parameter of the `dispatch_get_global_queue` function is reserved and you should always pass the value 0 to it.

In this section you saw how you can dispatch tasks to concurrent queues for synchronous execution. The next section shows asynchronous execution on concurrent queues, while [Recipe 5.11](#) will show how to execute tasks synchronously and asynchronously on serial queues that you create for your applications.

See Also

XXX

5.7 Performing Non-UI Related Tasks Asynchronously with GCD

Problem

You want to be able to execute non-UI related tasks asynchronously, with the help of GCD.

Solution

This is where GCD can show its true power: executing blocks of code asynchronously on the main, serial, or concurrent queues. I promise that, by the end of this section, you will be completely convinced GCD is the future of multithread applications, completely replacing threads in modern apps.

In order to execute asynchronous tasks on a dispatch queue, you must use one of these functions:

`dispatch_async`

Submits a block object to a dispatch queue (both specified by parameters) for asynchronous execution.

`dispatch_async_f`

Submits a C function to a dispatch queue, along with a context reference (all three specified by parameters), for asynchronous execution.

Discussion

Let's have a look at a real example. We'll write an iOS app that is able to download an image from a URL on the Internet. After the download is finished, the app should display the image to the user. Here is the plan and how we will use what we've learned so far about GCD in order to accomplish it:

1. We are going to launch a block object asynchronously on a concurrent queue.
2. Once in this block, we will launch another block object *synchronously*, using the `dispatch_sync` function, to download the image from a URL. Synchronously downloading a URL from an asynchronous code block holds up just the queue running the synchronous function, not the main thread. The whole operation still is asynchronous when we look at it from the main thread's perspective. All we care about is that we are not blocking the main thread while downloading our image.
3. Right after the image is downloaded, we will synchronously execute a block object on the *main queue* (see [Recipe 5.5](#)) in order to display the image to the user on the UI.

The skeleton for our plan is as simple as this:

```
dispatch_queue_t concurrentQueue =  
    dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);
```

```

dispatch_async(concurrentQueue, ^{
    __block UIImage *image = nil;

    dispatch_sync(concurrentQueue, ^{
        /* Download the image here */
    });

    dispatch_sync(dispatch_get_main_queue(), ^{
        /* Show the image to the user here on the main queue*/
    });
});

```

The second `dispatch_sync` call, which displays the image, will be executed on the queue after the first synchronous call, which downloads our image. That's exactly what we want, because we *have* to wait for the image to be fully downloaded before we can display it to the user. So after the image is downloaded, we execute the second block object, but this time on the main queue.

Let's download the image and display it to the user now. We will do this in the `viewDidAppear:` instance method of a view controller displayed in an iPhone app:

```

- (void) viewDidAppear:(BOOL)paramAnimated{

    dispatch_queue_t concurrentQueue =
    dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

    dispatch_async(concurrentQueue, ^{

        __block UIImage *image = nil;

        dispatch_sync(concurrentQueue, ^{
            /* Download the image here */

            /* iPad's image from Apple's website. Wrap it into two
            lines as the URL is too long to fit into one line */
            NSString *urlAsString = @"http://images.apple.com/mobileme/features"\
            "/images/ipad_findyouripad_20100518.jpgg";

            NSURL *url = [NSURL URLWithString:urlAsString];

            NSURLRequest *urlRequest = [NSURLRequest requestWithURL:url];

            NSError *downloadError = nil;
            NSData *imageData = [NSURLConnection
                                sendSynchronousRequest:urlRequest
                                returningResponse:nil
                                error:&downloadError];

            if (downloadError == nil &&
                imageData != nil){

                image = [UIImage imageData:imageData];
                /* We have the image. We can use it now */
            }
        });
    });
}

```

```

    }
    else if (downloadError != nil){
        NSLog(@"Error happened = %@", downloadError);
    } else {
        NSLog(@"No data could get downloaded from the URL.");
    }
});

dispatch_sync(dispatch_get_main_queue(), ^{
    /* Show the image to the user here on the main queue*/

    if (image != nil){
        /* Create the image view here */
        UIImageView *imageView = [[UIImageView alloc]
                                   initWithFrame:self.view.bounds];

        /* Set the image */
        [imageView setImage:image];

        /* Make sure the image is not scaled incorrectly */
        [imageView setContentMode:UIViewContentModeScaleAspectFit];

        /* Add the image to this view controller's view */
        [self.view addSubview:imageView];

    } else {
        NSLog(@"Image isn't downloaded. Nothing to display.");
    }
});

});

}

```

As you can see in [Figure 5-2](#), we have successfully downloaded our image and also created an image view to display the image to the user on the UI.



Figure 5-2. Downloading and displaying images to users, using GCD

Let's move on to another example. Let's say that we have an array of 10,000 random numbers that have been stored in a file on disk and we want to load this array into memory, sort the numbers in an ascending fashion (with the smallest number appearing first in the list), and then display the list to the user. The control used for the display depends on whether you are coding this for iOS (ideally, you'd use an instance of `UITableView`) or Mac OS X (`NSTableView` would be a good candidate). Since we don't have an array, why don't we create the array first, then load it, and finally display it?

Here are two methods that will help us find the location where we want to save the array of 10,000 random numbers on disk on the device:

```
- (NSString *) fileLocation{

    /* Get the document folder(s) */
    NSArray *folders =
        NSSearchPathForDirectoriesInDomains(NSDocumentDirectory,
                                             NSUserDomainMask,
                                             YES);

    /* Did we find anything? */
    if ([folders count] == 0){
        return nil;
    }

    /* Get the first folder */
    NSString *documentsFolder = [folders objectAtIndex:0];

    /* Append the file name to the end of the documents path */
    return [documentsFolder
            stringByAppendingPathComponent:@"list.txt"];
}

- (BOOL) hasFileAlreadyBeenCreated{

    BOOL result = NO;

    NSFileManager *fileManager = [[NSFileManager alloc] init];
    if ([fileManager fileExistsAtPath:[self fileLocation]]){
        result = YES;
    }

    return result;
}
```

Now the important part: we want to save an array of 10,000 random numbers to disk *if and only if* we have not created this array before on disk. If we have, we will load the array from disk immediately. If we have not created this array before on disk, we will first create it and then move on to loading it from disk. At the end, if the array was successfully read from disk, we will sort the array in an ascending fashion and finally display the results to the user on the UI. I will leave displaying the results to the user up to you:

```
dispatch_queue_t concurrentQueue =
    dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

/* If we have not already saved an array of 10,000
   random numbers to the disk before, generate these numbers now
   and then save them to the disk in an array */
dispatch_async(concurrentQueue, ^{

    NSUInteger numberOfValuesRequired = 10000;
```

```

if ([self hasFileAlreadyBeenCreated] == NO){
    dispatch_sync(concurrentQueue, ^{

        NSMutableArray *arrayOfRandomNumbers =
            [[NSMutableArray alloc] initWithCapacity:numberOfValuesRequired];

        NSUInteger counter = 0;
        for (counter = 0;
             counter < numberOfValuesRequired;
             counter++){
            unsigned int randomNumber =
                arc4random() % ((unsigned int)RAND_MAX + 1);

            [arrayOfRandomNumbers addObject:
             [NSNumber numberWithInt:randomNumber]];
        }

        /* Now let's write the array to disk */
        [arrayOfRandomNumbers writeToDisk:[self fileLocation]
         atomically:YES];

    });
}

__block NSMutableArray *randomNumbers = nil;

/* Read the numbers from disk and sort them in an
ascending fashion */
dispatch_sync(concurrentQueue, ^{

    /* If the file has now been created, we have to read it */
    if ([self hasFileAlreadyBeenCreated]){
        randomNumbers = [[NSMutableArray alloc]
            initWithContentsOfFile:[self fileLocation]];

        /* Now sort the numbers */
        [randomNumbers sortUsingComparator:
         ^NSComparisonResult(id obj1, id obj2) {

            NSNumber *number1 = (NSNumber *)obj1;
            NSNumber *number2 = (NSNumber *)obj2;
            return [number1 compare:number2];

        }
    ]];
    });

dispatch_async(dispatch_get_main_queue(), ^{
    if ([randomNumbers count] > 0){
        /* Refresh the UI here using the numbers in the
        randomNumbers array */
    }
});

```

```
});
```

There is a lot more to GCD than synchronous and asynchronous block or function execution. In [Recipe 5.10](#) you will learn how to group block objects together and prepare them for execution on a dispatch queue. I also suggest that you have a look at [Recipe 5.8](#) and [Recipe 5.9](#) to learn about other functionalities that GCD is capable of providing to programmers.

See Also

XXX

5.8 Performing Tasks After a Delay with GCD

Problem

You want to be able to execute code but after a certain amount of delay, which you would like to specify, using GCD.

Solution

Use the `dispatch_after` and `dispatch_after_f` functions.

Discussion

With Core Foundation, you can invoke a selector in an object after a given period of time, using the `performSelector:withObject:afterDelay:` method of the `NSObject` class. Here is an example:

```
- (void) printString:(NSString *)paramString{
    NSLog(@"%@", paramString);
}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [self performSelector:@selector(printString:)
        withObject:@"Grand Central Dispatch"
        afterDelay:3.0];

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    // Override point for customization after application launch.
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

In this example we are asking the runtime to call the `printString:` method after 3 seconds of delay. We can do the same thing in GCD using the `dispatch_after` and `dispatch_after_f` functions, each of which is described here:

`dispatch_after`

Dispatches a block object to a dispatch queue after a given period of time, specified in nanoseconds. These are the parameters that this function requires:

Delay in nanoseconds

The number of nanoseconds GCD has to wait on a given dispatch queue (specified by the second parameter) before it executes the given block object (specified by the third parameter).

Dispatch queue

The dispatch queue on which the block object (specified by the third parameter) has to be executed after the given delay (specified by the first parameter).

Block object

The block object to be invoked after the specified number of nanoseconds on the given dispatch queue. This block object should have no return value and should accept no parameters (see [Recipe 5.1](#)).

`dispatch_after_f`

Dispatches a C function to GCD for execution after a given period of time, specified in nanoseconds. This function accepts four parameters:

Delay in nanoseconds

The number of nanoseconds GCD has to wait on a given dispatch queue (specified by the second parameter) before it executes the given function (specified by the fourth parameter).

Dispatch queue

The dispatch queue on which the C function (specified by the fourth parameter) has to be executed after the given delay (specified by the first parameter).

Context

The memory address of a value in the heap to be passed to the C function (for an example, see [Recipe 5.5](#)).

C function

The address of the C function that has to be executed after a certain period of time (specified by the first parameter) on the given dispatch queue (specified by the second parameter).



Although the delays are in nanoseconds, it is up to iOS to decide the granularity of dispatch delay, and this delay might not be as precise as what you hope when you specify a value in nanoseconds.

Let's have a look at an example for `dispatch_after` first:


```
double delayInSeconds = 2.0;

dispatch_time_t delayInNanoSeconds =
    dispatch_time(DISPATCH_TIME_NOW, delayInSeconds * NSEC_PER_SEC);

dispatch_queue_t concurrentQueue =
    dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

dispatch_after(delayInNanoSeconds, concurrentQueue, ^(void){
    /* Perform your operations here */
});
```

As you can see, the nanoseconds delay parameter for both the `dispatch_after` and `dispatch_after_f` functions has to be of type `dispatch_time_t`, which is an abstract representation of absolute time. To get the value for this parameter, you can use the `dispatch_time` function as demonstrated in this sample code. Here are the parameters that you can pass to the `dispatch_time` function:

Base time

If this value was denoted with B and the delta parameter was denoted with D , the resulting time from this function would be equal to $B+D$. You can set this parameter's value to `DISPATCH_TIME_NOW` to denote *now* as the base time and then specify the delta from now using the delta parameter.

Delta to add to base time

This parameter is the nanoseconds that will get added to the base time parameter to create the result of this function.

For example, to denote a time 3 seconds from now, you could write your code like so:

```
dispatch_time_t delay =
    dispatch_time(DISPATCH_TIME_NOW, 3.0f * NSEC_PER_SEC);
```

Or to denote half a second from now:

```
dispatch_time_t delay =
    dispatch_time(DISPATCH_TIME_NOW, (1.0 / 2.0f) * NSEC_PER_SEC);
```

Now let's have a look at how we can use the `dispatch_after_f` function:

```
void processSomething(void *paramContext){
    /* Do your processing here */
    NSLog(@"Processing...");
}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    double delayInSeconds = 2.0;

    dispatch_time_t delayInNanoSeconds =
        dispatch_time(DISPATCH_TIME_NOW, delayInSeconds * NSEC_PER_SEC);

    dispatch_queue_t concurrentQueue =
        dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);
```

```

dispatch_after_f(delayInNanoSeconds,
                 concurrentQueue,
                 NULL,
                 processSomething);

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];

// Override point for customization after application launch.
self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

See Also

XXX

5.9 Performing a Task at Most Once with GCD

Problem

You want to make sure a piece of code gets executed only once, during the lifetime of your application, even if it gets called more than once from different places in your code (such as the initializer for a singleton).

Solution

Use the `dispatch_once` function.

Discussion

Allocating and initializing a singleton is one of the tasks that has to happen exactly once during the lifetime of an app. I am sure you know of other scenarios where you had to make sure a piece of code was executed only once during the lifetime of your application.

GCD lets you specify an identifier for a piece of code when you attempt to execute it. If GCD detects that this identifier has been passed to the framework before, it won't execute that block of code again. The function that allows you to do this is `dispatch_once`, which accepts two parameters:

Token

A token of type `dispatch_once_t` that holds the token generated by GCD when the block of code is executed for the first time. If you want a piece of code to be executed at most once, you must specify the same token to this method whenever it is invoked in the app. We will see an example of this soon.

Block object

The block object to get executed at most once. This block object returns no values and accepts no parameters.



`dispatch_once` always executes its task on the current queue being used by the code that issues the call, be it a serial queue, a concurrent queue, or the main queue.

Here is an example:

```
static dispatch_once_t onceToken;

void (^executedOnlyOnce)(void) = ^{

    static NSUInteger numberOfEntries = 0;
    numberOfEntries++;
    NSLog(@"Executed %lu time(s)", (unsigned long)numberOfEntries);

};

- (BOOL)application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    dispatch_queue_t concurrentQueue =
        dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

    dispatch_once(&onceToken, ^{
        dispatch_async(concurrentQueue,
            executedOnlyOnce);
    });

    dispatch_once(&onceToken, ^{
        dispatch_async(concurrentQueue,
            executedOnlyOnce);
    });

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;

}
```

As you can see, although we are attempting to invoke the `executedOnlyOnce` block object twice, using the `dispatch_once` function, in reality GCD is only executing this block object once, since the identifier passed to the `dispatch_once` function is the same both times.

Apple, in its [Cocoa Fundamentals Guide](#), shows programmers how to create a singleton. This source code is quite old and has *not yet been updated* to use GCD and Automatic Reference Counting. We can change this model to make use of GCD and the `dispatch_once` function in order to initialize a shared instance of an object, like so:

```
#import "MySingleton.h"

@implementation MySingleton

- (id) sharedInstance{
    static MySingleton *SharedInstance = nil;
    static dispatch_once_t onceToken;
    dispatch_once(&onceToken, ^{
        SharedInstance = [MySingleton new];
    });
    return SharedInstance;
}

@end
```

See Also

XXX

5.10 Grouping Tasks Together with GCD

Problem

You want to group blocks of code together and ensure that all of them get executed by GCD one by one, as dependencies of one another.

Solution

Use the `dispatch_group_create` function to create groups in GCD.

Discussion

GCD lets us create *groups*, which allow you to place your tasks in one place, run all of them, and get a notification at the end from GCD. This has many valuable applications. For instance, suppose you have a UI-based app and want to reload the components on your UI. You have a table view, a scroll view, and an image view. You want to reload the contents of these components using these methods:

```
- (void) reloadDataView{
    /* Reload the table view here */
    NSLog(@"%s", __FUNCTION__);
}

- (void) reloadDataView{
    /* Do the work here */
```

```

    NSLog(@"%s", __FUNCTION__);
}

- (void) reloadImageView{
    /* Reload the image view here */
    NSLog(@"%s", __FUNCTION__);
}

```

At the moment, these methods are empty, but later you can put the relevant UI code in them. Now we want to call these three methods, one after the other, and we want to know when GCD has finished calling these methods so that we can display a message to the user. For this, we should be using a group. You should know about four functions when working with groups in GCD:

dispatch_group_create

Creates a group handle. Once you are done with this group handle, you should dispose of it using the `dispatch_release` function.

dispatch_group_async

Submits a block of code for execution on a group. You must specify the dispatch queue on which the block of code has to be executed *as well as* the group to which this block of code belongs.

dispatch_group_notify

Allows you to submit a block object that should be executed once all tasks added to the group for execution have finished their work. This function also allows you to specify the dispatch queue on which that block object has to be executed.

dispatch_release

Use this function to dispose of any dispatch groups that you create using the `dispatch_group_create` function.

Let's have a look at an example. As explained, in our example we want to invoke the `reloadTableView`, `reloadScrollView`, and `reloadImageView` methods one after the other and then display a message to the user once we are done. We can utilize GCD's powerful grouping facilities in order to accomplish this:

```

dispatch_group_t taskGroup = dispatch_group_create();
dispatch_queue_t mainQueue = dispatch_get_main_queue();

/* Reload the table view on the main queue */
dispatch_group_async(taskGroup, mainQueue, ^{
    [self reloadTableView];
});

/* Reload the scroll view on the main queue */
dispatch_group_async(taskGroup, mainQueue, ^{
    [self reloadScrollView];
});

/* Reload the image view on the main queue */
dispatch_group_async(taskGroup, mainQueue, ^{
    [self reloadImageView];
});

```

```
});

/* At the end when we are done, dispatch the following block */
dispatch_group_notify(taskGroup, mainQueue, ^{
    /* Do some processing here */
    [[[UIAlertView alloc] initWithTitle:@"Finished"
                                message:@"All tasks are finished"
                                delegate:nil
                                cancelButtonTitle:@"OK"
                                otherButtonTitles:nil, nil] show];

});

/* We are done with the group */
dispatch_release(taskGroup);
```

In addition to `dispatch_group_async`, you can also dispatch asynchronous C functions to a dispatch group using the `dispatch_group_async_f` function.



GCDAppDelegate is simply the name of the class from which this example is taken. We have to use this class name in order to typecast a context object so that the compiler will understand our commands.

Like so:

```
void reloadAllComponents(void *context){

    Grouping_Tasks_Together_with_GCDAppDelegate *self =
        (__bridge Grouping_Tasks_Together_with_GCDAppDelegate *)context;

    [self reloadTableView];
    [self reloadScrollView];
    [self reloadImageView];

}

- (BOOL) application:(UIApplication *)application
  didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    dispatch_group_t taskGroup = dispatch_group_create();
    dispatch_queue_t mainQueue = dispatch_get_main_queue();

    dispatch_group_async_f(taskGroup,
                           mainQueue,
                           (__bridge void *)self,
                           reloadAllComponents);

    /* At the end when we are done, dispatch the following block */
    dispatch_group_notify(taskGroup, mainQueue, ^{
        /* Do some processing here */
        [[[UIAlertView alloc] initWithTitle:@"Finished"
                                    message:@"All tasks are finished"
                                    delegate:nil
```

```

        cancelButtonTitle:@"OK"
        otherButtonTitles:nil, nil] show];

});

/* We are done with the group */
dispatch_release(taskGroup);

self.window = [[UIWindow alloc] initWithFrame:
                [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```



Since the `dispatch_group_async_f` function accepts a C function as the block of code to be executed, the C function must have a reference to `self` to be able to invoke instance methods of the current object in which the C function is implemented. That is the reason behind passing `self` as the context pointer in the `dispatch_group_async_f` function. For more information about contexts and C functions, please refer to [Recipe 5.5](#).

Once all the given tasks are finished, the user will see a result similar to that shown in [Figure 5-3](#).



Figure 5-3. Managing a group of tasks with GCD

See Also

XXX

5.11 Constructing Your Own Dispatch Queues with GCD

Problem

You want to create your own, uniquely-named, dispatch queues.

Solution

Use the `dispatch_queue_create` function.

Discussion

With GCD, you can create your own serial dispatch queues (see [Recipe 5.0](#) for serial queues). Serial dispatch queues run their tasks in a first-in-first-out (FIFO) fashion. The asynchronous tasks on serial queues will *not* be performed on the main thread, however, making serial queues highly desirable for concurrent FIFO tasks.

All synchronous tasks submitted to a serial queue will be executed on the current thread being used by the code that is submitting the task, whenever possible. But asynchronous tasks submitted to a serial queue will always be executed on a thread other than the main thread.

We'll use the `dispatch_queue_create` function to create serial queues. The first parameter in this function is a C string (`char *`) that will uniquely identify that serial queue in the *system*. The reason I am emphasizing *system* is because this identifier is a system-wide identifier, meaning that if your app creates a new serial queue with the identifier of `serialQueue1` and somebody else's app does the same, the results of creating a new serial queue with the same name are undefined by GCD. Because of this, Apple strongly recommends that you use a reverse DNS format for identifiers. Reverse DNS identifiers are usually constructed in this way: `com.COMPANY.PRODUCT.IDENTIFIER`. For instance, I could create two serial queues and assign these names to them:

```
com.pixolity.GCD.serialQueue1
com.pixolity.GCD.serialQueue2
```

After you've created your serial queue, you can start dispatching tasks to it using the various GCD functions you've learned in this book. Once you are done with the serial dispatch queue that you've just created, you *must* dispose of it using the `dispatch_release` function.

Would you like to see an example? I thought so!

```
dispatch_queue_t firstSerialQueue =
dispatch_queue_create("com.pixolity.GCD.serialQueue1", 0);

dispatch_async(firstSerialQueue, ^{
    NSUInteger counter = 0;
    for (counter = 0;
         counter < 5;
         counter++){
        NSLog(@"First iteration, counter = %lu", (unsigned long)counter);
    }
});

dispatch_async(firstSerialQueue, ^{
    NSUInteger counter = 0;
    for (counter = 0;
```

```

        counter < 5;
        counter++){
    NSLog(@"Second iteration, counter = %lu", (unsigned long)counter);
}
});

dispatch_async(firstSerialQueue, ^{
    NSUInteger counter = 0;
    for (counter = 0;
         counter < 5;
         counter++){
        NSLog(@"Third iteration, counter = %lu", (unsigned long)counter);
    }
});

dispatch_release(firstSerialQueue);

```

If you run this code and have a look at the output printed to the console window, you will see results similar to these:

```

First iteration, counter = 0
First iteration, counter = 1
First iteration, counter = 2
First iteration, counter = 3
First iteration, counter = 4
Second iteration, counter = 0
Second iteration, counter = 1
Second iteration, counter = 2
Second iteration, counter = 3
Second iteration, counter = 4
Third iteration, counter = 0
Third iteration, counter = 1
Third iteration, counter = 2
Third iteration, counter = 3
Third iteration, counter = 4

```

It's obvious that although we dispatched our block objects asynchronously to the serial queue, the queue has executed their code in a FIFO fashion. We can modify the same sample code to make use of `dispatch_async_f` function instead of the `dispatch_async` function, like so:

```

void firstIteration(void *paramContext){

    NSUInteger counter = 0;
    for (counter = 0;
         counter < 5;
         counter++){
        NSLog(@"First iteration, counter = %lu", (unsigned long)counter);
    }
}

void secondIteration(void *paramContext){

    NSUInteger counter = 0;
    for (counter = 0;

```

```

        counter < 5;
        counter++){
    NSLog(@"Second iteration, counter = %lu", (unsigned long)counter);
}
}

void thirdIteration(void *paramContext){

    NSUInteger counter = 0;
    for (counter = 0;
        counter < 5;
        counter++){
        NSLog(@"Third iteration, counter = %lu", (unsigned long)counter);
    }
}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    dispatch_queue_t firstSerialQueue =
    dispatch_queue_create("com.pixolity.GCD.serialQueue1", 0);

    dispatch_async_f(firstSerialQueue, NULL, firstIteration);
    dispatch_async_f(firstSerialQueue, NULL, secondIteration);
    dispatch_async_f(firstSerialQueue, NULL, thirdIteration);

    dispatch_release(firstSerialQueue);

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

See Also

XXX

5.12 Running Tasks Synchronously with Operations

Problem

You want to run a series of tasks synchronously.

Solution

Create operations and start them manually:

```

#import <UIKit/UIKit.h>

@interface Running_Tasks_Synchronously_with_OperationsAppDelegate
: UIResponder <UIApplicationDelegate>

```

```

@property (strong, nonatomic) UIWindow *window;
@property (nonatomic, strong) NSInvocationOperation *simpleOperation;

@end

```

The implementation of the application delegate is as follows:

```

- (void) simpleOperationEntry:(id)paramObject{

    NSLog(@"Parameter Object = %@", paramObject);
    NSLog(@"Main Thread = %@", [NSThread mainThread]);
    NSLog(@"Current Thread = %@", [NSThread currentThread]);

}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSNumber *simpleObject = [NSNumber numberWithInt:123];

    self.simpleOperation = [[NSInvocationOperation alloc]
        initWithTarget:self
        selector:@selector(simpleOperationEntry:)
        object:simpleObject];

    [self.simpleOperation start];

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

The output of this program (in the console window) will be similar to this:

```

Parameter Object = 123
Main Thread = <NSThread: 0x6810280>{name = (null), num = 1}
Current Thread = <NSThread: 0x6810280>{name = (null), num = 1}

```

As the name of this class implies (`NSInvocationOperation`), the main responsibility of an object of this type is to invoke a method in an object. This is the most straightforward way to invoke a method inside an object using operations.

Discussion

An invocation operation, as described in this chapter's [Introduction](#), is able to invoke a method inside an object. “What is so special about this?” you might ask. The invocation operation’s power can be demonstrated when it is added to an operation queue. With an operation queue, an invocation operation can invoke a method in a target object asynchronously and in parallel to the thread that started the operation. If you have a look at the output printed to the console (in this recipe’s [Solution](#)), you will notice that the current thread inside the method invoked by the invocation operation

is the same as the main thread since the main thread in the `application:didFinishLaunchingWithOptions:` method started the operation using its `start` method. In [Recipe 5.13](#), we will learn how to take advantage of operation queues to run tasks asynchronously.

In addition to invocation operations, you can use block or plain operations to perform tasks synchronously. Here is an example using a block operation to count numbers from zero to 999 (inside the `.h` file of our application delegate):

```
#import <UIKit/UIKit.h>

@interface Running_Tasks_Synchronously_with_OperationsAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (strong, nonatomic) UIWindow *window;
@property (nonatomic, strong) NSBlockOperation *simpleOperation;

@end
```

Here is the implementation of our application delegate (`.m` file):

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.simpleOperation = [NSBlockOperation blockOperationWithBlock:^(
        NSLog(@"Main Thread = %@", [NSThread mainThread]);
        NSLog(@"Current Thread = %@", [NSThread currentThread]);
        NSUInteger counter = 0;
        for (counter = 0;
            counter < 1000;
            counter++){
            NSLog(@"Count = %lu", (unsigned long)counter);
        }
    ]];

    /* Start the operation */
    [self.simpleOperation start];

    /* Print something out just to test if we have to wait
    for the block to execute its code or not */
    NSLog(@"Main thread is here");

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

If we run our application, we will see the values 0 to 999 printed out to the screen followed by the “Main thread is here” message, like this:

```
Main Thread = <NSThread: 0x6810280>{name = (null), num = 1}
Current Thread = <NSThread: 0x6810280>{name = (null), num = 1}
...
```

```
Count = 991
Count = 992
Count = 993
Count = 994
Count = 995
Count = 996
Count = 997
Count = 998
Count = 999
Main thread is here
```

This proves that since the block operation was started in the `application:didFinishLaunchingWithOptions:` method, which itself runs on the main thread, the code inside the block was also running on the main thread. The main point to take from the log messages is that our operation blocked the main thread and the main thread's code continued to be executed after the work for the block operation was done. This is a very bad programming practice. In fact, iOS developers must perform any trick and use any technique that they know of to keep the main thread responsive so that it can do the key job of processing users' input. Here is what Apple has to say about this:

You should be careful what work you perform from the main thread of your application. The main thread is where your application handles touch events and other user input. To ensure that your application is always responsive to the user, you should never use the main thread to perform long-running tasks or to perform tasks with a potentially unbounded end, such as tasks that access the network. Instead, you should always move those tasks onto background threads. The preferred way to do so is to wrap each task in an operation object and add it to an operation queue, but you can also create explicit threads yourself.

To read more about this subject, browse through the “Tuning for Performance and Responsiveness” document in the iOS Reference Library, available at this URL:

<http://developer.apple.com/library/ios/#documentation/iphone/conceptual/iphoneneosprogrammingguide/Performance/Performance.html>

In addition to invocation and block operations, you can also subclass `NSOperation` and perform your task in that class. Before getting started, you must keep a few things in mind while subclassing `NSOperation`:

- If you are not planning on using an operation queue, you have to detach a new thread of your own in the `start` method of the operation. If you do not want to use an operation queue and you do not want your operation to run asynchronously with other operations that you start manually, you can simply call the `main` method of your operation inside the `start` method.
- Two important methods in an instance of `NSOperation` must be overridden by your own implementation of the operation: `isExecuting` and `isFinished`. These can be called from any other object. In these methods, you must return a thread-safe value that you can manipulate from inside the operation. As soon as your operation starts, you must, through KVO, inform any listeners that you are changing the

values that these two methods return. We will see how this works in the example code.

- You must provide your own autorelease pool inside the `main` method of the operation in case your operation will be added to an operation queue at some point in the future. You must make sure your operations work in both ways: whether you start them manually or they get started by an operation queue.
- You must have an initialization method for your operations. There must be only one designated initializer method per operation. All other initializer methods, including the default `init` method of an operation, must call the designated initializer that has the most number of parameters. Other initializer methods must make sure they pass appropriate parameters (if any) to the designated initializer.

Here is the declaration of our operation object (.h file):

```
#import <Foundation/Foundation.h>

@interface CountingOperation : NSOperation

/* Designated Initializer */
- (id) initWithStartingCount:(NSUInteger)paramStartingCount
    endingCount:(NSUInteger)paramEndingCount;

@end
```

The implementation (.m file) of the operation might be a bit long, but hopefully it's easy to understand:

```
#import "CountingOperation.h"

@implementation CountingOperation

NSUInteger    startingCount;
NSUInteger    endingCount;
BOOL         finished;
BOOL         executing;

- (id) init {
    return([self initWithStartingCount:0
                                endingCount:1000]);
}

- (id) initWithStartingCount:(NSUInteger)paramStartingCount
    endingCount:(NSUInteger)paramEndingCount{

    self = [super init];

    if (self != nil){

        /* Keep these values for the main method */
        startingCount = paramStartingCount;
        endingCount = paramEndingCount;

    }

}
```

```

        return(self);
    }

    - (void) start {

        /* If we are cancelled before starting, then
         we have to return immediately and generate the
         required KVO notifications */
        if ([self isCancelled]){
            /* If this operation *is* cancelled */
            /* KVO compliance */
            [self willChangeValueForKey:@"isFinished"];
            finished = YES;
            [self didChangeValueForKey:@"isFinished"];
            return;

        } else {
            /* If this operation is *not* cancelled */
            /* KVO compliance */
            [self willChangeValueForKey:@"isExecuting"];
            executing = YES;
            /* Call the main method from inside the start method */
            [self main];
            [self didChangeValueForKey:@"isExecuting"];

        }

    }

}

- (void) main {

    @try {
        /* Here is our autorelease pool */
        @autoreleasepool {
            /* Keep a local variable here that must get set to YES
             whenever we are done with the task */
            BOOL taskIsFinished = NO;

            /* Create a while loop here that only exists
             if the taskIsFinished variable is set to YES or
             the operation has been cancelled */
            while (taskIsFinished == NO &&
                [self isCancelled] == NO){

                /* Perform the task here */
                NSLog(@"Main Thread = %@", [NSThread mainThread]);
                NSLog(@"Current Thread = %@", [NSThread currentThread]);
                NSUInteger counter = startingCount;
                for (counter = startingCount;
                    counter < endingCount;
                    counter++){
                    NSLog(@"Count = %lu", (unsigned long)counter);
                }

            }

        }

    } @catch (NSException *) {
        // Handle exception
    }
}

```



```

        /* Very important. This way we can get out of the
        loop and we are still complying with the cancellation
        rules of operations */
        taskIsFinished = YES;
    }

    /* KVO compliance. Generate the
    required KVO notifications */
    [self willChangeValueForKey:@"isFinished"];
    [self willChangeValueForKey:@"isExecuting"];
    finished = YES;
    executing = NO;
    [self didChangeValueForKey:@"isFinished"];
    [self didChangeValueForKey:@"isExecuting"];
}
}
@catch (NSException * e) {
    NSLog(@"Exception %@", e);
}
}

- (BOOL) isFinished{
    /* Simply return the value */
    return(finished);
}

- (BOOL) isExecuting{
    /* Simply return the value */
    return(executing);
}

@end

```

We can start this operation like so:

```

#import "Running_Tasks_Synchronously_with_OperationsAppDelegate.h"
#import "CountingOperation.h"

@implementation Running_Tasks_Synchronously_with_OperationsAppDelegate

@synthesize window = _window;
@synthesize simpleOperation;

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.simpleOperation = [[CountingOperation alloc] initWithStartingCount:0
                                                                    endingCount:1000];

    [self.simpleOperation start];

    NSLog(@"Main thread is here");

    self.window = [[UIWindow alloc] initWithFrame:

```

```

        [[UIScreen mainScreen] bounds]];
self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

@end

```

If we run our code, we will see the following results in the console window, just as we did when we used a block operation:

```

Main Thread = <NSThread: 0x6810260>{name = (null), num = 1}
Current Thread = <NSThread: 0x6810260>{name = (null), num = 1}
...
Count = 993
Count = 994
Count = 995
Count = 996
Count = 997
Count = 998
Count = 999
Main thread is here

```

See Also

XXX

5.13 Running Tasks Asynchronously with Operations

Problem

You want to execute operations concurrently.

Solution

Use operation queues. Alternatively, subclass `NSOperation` and detach a new thread on the `main` method.

Discussion

As mentioned in [Recipe 5.12](#), operations, by default, run on the thread that calls the `start` method. Usually we start operations on the main thread, but at the same time we expect our operations to run on their own threads and not take the main thread's time slice. The best solution for us would be to use operation queues. However, if you want to manage your operations manually, which I do not recommend, you can subclass `NSOperation` and detach a new thread on the `main` method. Please refer to [Recipe 5.16](#) for more information about detached threads.

Let's go ahead and use an operation queue and add two simple invocation operations to it. (For more information about invocation operations, please refer to this chapter's

[Introduction](#). For additional example code on invocation operations, please refer to [Recipe 5.12](#).) Here is the declaration (.h file) of our application delegate that utilizes an operation queue and two invocation operations:

```
#import <UIKit/UIKit.h>

@interface Running_Tasks_Asynchronously_with_OperationsAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) NSOperationQueue *operationQueue;
@property (nonatomic, strong) NSInvocationOperation *firstOperation;
@property (nonatomic, strong) NSInvocationOperation *secondOperation;

@end
```

The implementation (.m file) of the application delegate is as follows:

```
#import "Running_Tasks_Asynchronously_with_OperationsAppDelegate.h"

@implementation Running_Tasks_Asynchronously_with_OperationsAppDelegate

@synthesize window = _window;
@synthesize firstOperation;
@synthesize secondOperation;
@synthesize operationQueue;

- (void) firstOperationEntry:(id)paramObject{

    NSLog(@"%s", __FUNCTION__);
    NSLog(@"Parameter Object = %@", paramObject);
    NSLog(@"Main Thread = %@", [NSThread mainThread]);
    NSLog(@"Current Thread = %@", [NSThread currentThread]);

}

- (void) secondOperationEntry:(id)paramObject{

    NSLog(@"%s", __FUNCTION__);
    NSLog(@"Parameter Object = %@", paramObject);
    NSLog(@"Main Thread = %@", [NSThread mainThread]);
    NSLog(@"Current Thread = %@", [NSThread currentThread]);

}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSNumber *firstNumber = [NSNumber numberWithInt:111];
    NSNumber *secondNumber = [NSNumber numberWithInt:222];

    self.firstOperation = [[NSInvocationOperation alloc]
                           initWithTarget:self
                           selector:@selector(firstOperationEntry:)
                           object:firstNumber];
```

```

self.secondOperation = [[NSInvocationOperation alloc]
                        initWithTarget:self
                        selector:@selector(secondOperationEntry:)
                        object:secondNumber];

self.operationQueue = [[NSOperationQueue alloc] init];

/* Add the operations to the queue */
[self.operationQueue addOperation:self.firstOperation];
[self.operationQueue addOperation:self.secondOperation];

NSLog(@"Main thread is here");

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];
self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

@end

```

Here is what is happening in the implementation of our code:

- We have two methods: `firstOperationEntry:` and `secondOperationEntry:`. Each method accepts an object as a parameter and prints out the current thread, the main thread, and the parameter to the console window. These are the entry methods of our invocation operations that will be added to an operation queue.
- We initialize two objects of type `NSInvocationOperation` and set the target selector to each operation entry point described previously.
- We then initialize an object of type `NSOperationQueue`. (It could also be created before the entry methods.) The queue object will be responsible for managing the concurrency in the operation objects.
- We invoke the `addOperation:` instance method of `NSOperationQueue` to add each invocation operation to the operation queue. At this point, the operation queue may or may not immediately start the invocation operations through their `start` methods. However, it is very important to bear in mind that after adding operations to an operation queue, you must not start the operations manually. You must leave this to the operation queue.

Now let's run the example code once and see the results in the console window:

```

[Running_Tasks_Asynchronously_with_OperationsAppDelegate firstOperationEntry:]
Main thread is here
Parameter Object = 111
[Running_Tasks_Asynchronously_with_OperationsAppDelegate secondOperationEntry:]
Main Thread = <NSThread: 0x6810260>{name = (null), num = 1}
Parameter Object = 222
Current Thread = <NSThread: 0x6805c20>{name = (null), num = 3}
Main Thread = <NSThread: 0x6810260>{name = (null), num = 1}
Current Thread = <NSThread: 0x6b2d1d0>{name = (null), num = 4}

```

Brilliant! This proves that our invocation operations are running on their own threads in parallel to the main thread without blocking the main thread at all. Now let's run the same code a couple more times and observe the output in the console window. If you do this, chances are that you will get a result that is completely different, such as this:

```
Main thread is here
[Running_Tasks_Asynchronously_with_OperationsAppDelegate firstOperationEntry:]
[Running_Tasks_Asynchronously_with_OperationsAppDelegate secondOperationEntry:]
Parameter Object = 111
Main Thread = <NSThread: 0x6810260>{name = (null), num = 1}
Current Thread = <NSThread: 0x68247c0>{name = (null), num = 3}
Parameter Object = 222
Main Thread = <NSThread: 0x6810260>{name = (null), num = 1}
Current Thread = <NSThread: 0x6819b00>{name = (null), num = 4}
```

You can clearly observe that the main thread is not blocked and that both invocation operations are running in parallel with the main thread. This just proves the concurrency in the operation queue when two nonconcurrent operations are added to it. The operation queue manages the threads required to run the operations.

If we were to subclass `NSOperation` and add the instances of the new class to an operation queue, we would do things slightly differently. Keep a few things in mind:

- Plain operations that subclass `NSOperation`, when added to an operation queue, will run asynchronously. For this reason, you must override the `isConcurrent` instance method of `NSOperation` and return the value `YES`.
- You must prepare your operation for cancellation by checking the value of the `isCancelled` method periodically while performing the main task of the operation and in the `start` method before you even run the operation. The `start` method will get called by the operation queue in this case after the operation is added to the queue. In this method, check whether the operation is cancelled using the `isCancelled` method. If the operation is cancelled, simply return from the `start` method. If not, call the `main` method from inside the `start` method.
- Override the `main` method with your own implementation of the main task that is to be carried out by the operation. Make sure to allocate and initialize your own autorelease pool in this method and to release the pool just before returning.
- Override the `isFinished` and `isExecuting` methods of your operation and return appropriate `BOOL` values to reveal whether the operation is finished or is executing at the time.

Here is the declaration (*.h* file) of our operation:

```
#import <Foundation/Foundation.h>

@interface SimpleOperation : NSOperation

/* Designated Initializer */
- (id) initWithObject:(NSObject *)paramObject;
```

```
@end
```

The implementation of the operation is as follows:

```
#import "SimpleOperation.h"

@implementation SimpleOperation

NSObject      *givenObject;
BOOL          finished;
BOOL          executing;

- (id) init {
    NSNumber *dummyObject = [NSNumber numberWithInt:123];
    return([self initWithObject:dummyObject]);
}

- (id) initWithObject:(NSObject *)paramObject{
    self = [super init];
    if (self != nil){
        /* Keep these values for the main method */
        givenObject = paramObject;
    }
    return(self);
}

- (void) start {

    /* If we are cancelled before starting, then
     we have to return immediately and generate the
     required KVO notifications */
    if ([self isCancelled]){
        /* If this operation *is* cancelled */
        /* KVO compliance */
        [self willChangeValueForKey:@"isFinished"];
        finished = YES;
        [self didChangeValueForKey:@"isFinished"];
        return;
    } else {
        /* If this operation is *not* cancelled */
        /* KVO compliance */
        [self willChangeValueForKey:@"isExecuting"];
        executing = YES;
        /* Call the main method from inside the start method */
        [self main];
        [self didChangeValueForKey:@"isExecuting"];
    }
}

- (void) main {

    @try {
```

```

@autoreleasepool {
    /* Keep a local variable here that must get set to YES
       whenever we are done with the task */
    BOOL taskIsFinished = NO;

    /* Create a while loop here that only exists
       if the taskIsFinished variable is set to YES or
       the operation has been cancelled */
    while (taskIsFinished == NO &&
           [self isCancelled] == NO){

        /* Perform the task here */
        NSLog(@"%s", __FUNCTION__);
        NSLog(@"Parameter Object = %@", givenObject);
        NSLog(@"Main Thread = %@", [NSThread mainThread]);
        NSLog(@"Current Thread = %@", [NSThread currentThread]);

        /* Very important. This way we can get out of the
           loop and we are still complying with the cancellation
           rules of operations */
        taskIsFinished = YES;

    }

    /* KVO compliance. Generate the
       required KVO notifications */
    [self willChangeValueForKey:@"isFinished"];
    [self willChangeValueForKey:@"isExecuting"];
    finished = YES;
    executing = NO;
    [self didChangeValueForKey:@"isFinished"];
    [self didChangeValueForKey:@"isExecuting"];
}
}

@catch (NSException * e) {
    NSLog(@"Exception %@", e);
}

}

- (BOOL) isConcurrent{
    return YES;
}

- (BOOL) isFinished{
    /* Simply return the value */
    return finished;
}

- (BOOL) isExecuting{
    /* Simply return the value */
    return executing;
}

@end

```

You can now use this operation class in any other class, such as your application delegate. Here is the declaration of our application delegate to utilize this new operation class and add it in an operation queue:

```
#import <UIKit/UIKit.h>

@class SimpleOperation;

@interface Running_Tasks_Asynchronously_with_OperationsAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) NSOperationQueue *operationQueue;
@property (nonatomic, strong) SimpleOperation *firstOperation;
@property (nonatomic, strong) SimpleOperation *secondOperation;

@end
```

The implementation of our application delegate is as follows:

```
#import "Running_Tasks_Asynchronously_with_OperationsAppDelegate.h"
#import "SimpleOperation.h"

@implementation Running_Tasks_Asynchronously_with_OperationsAppDelegate

@synthesize window = _window;
@synthesize firstOperation;
@synthesize secondOperation;
@synthesize operationQueue;

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSNumber *firstNumber = [NSNumber numberWithInt:111];
    NSNumber *secondNumber = [NSNumber numberWithInt:222];

    self.firstOperation = [[SimpleOperation alloc]
                           initWithObject:firstNumber];
    self.secondOperation = [[SimpleOperation alloc]
                           initWithObject:secondNumber];

    self.operationQueue = [[NSOperationQueue alloc] init];

    /* Add the operations to the queue */
    [self.operationQueue addOperation:self.firstOperation];
    [self.operationQueue addOperation:self.secondOperation];

    NSLog(@"Main thread is here");

    self.window = [[UIWindow alloc] initWithFrame:
                   [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```


@end

The results printed to the console window will be similar to what we saw earlier when we used concurrent invocation operations:

```
Main thread is here
-[SimpleOperation main]
-[SimpleOperation main]
Parameter Object = 222
Parameter Object = 222
Main Thread = <NSThread: 0x6810260>{name = (null), num = 1}
Main Thread = <NSThread: 0x6810260>{name = (null), num = 1}
Current Thread = <NSThread: 0x6a10b90>{name = (null), num = 3}
Current Thread = <NSThread: 0x6a13f50>{name = (null), num = 4}
```

5.14 Creating Dependency Between Operations

Problem

You want to start a certain task only after another task has finished executing.

Solution

If operation B has to wait for operation A before it can run the task associated with it, operation B has to add operation A as its dependency using the `addDependency:` instance method of `NSOperation`, as shown here:

```
[self.firstOperation addDependency:self.secondOperation];
```

Both the `firstOperation` and the `secondOperation` properties are of type `NSInvocationOperation`, as we will see in this recipe's [Discussion](#). In this example code, the first operation will not be executed by the operation queue until after the second operation's task is finished.

Discussion

An operation will not start executing until all the operations on which it depends have successfully finished executing the tasks associated with them. By default, an operation, after initialization, has no dependency on other operations.

If we want to introduce dependencies to the example code described in [Recipe 5.13](#), we can slightly modify our application delegate's implementation and use the `addDependency:` instance method to have the first operation wait for the second operation:

```
#import "Creating_Dependency_Between_OperationsAppDelegate.h"

@implementation Creating_Dependency_Between_OperationsAppDelegate

@synthesize window = _window;
```

```

@synthesize firstOperation;
@synthesize secondOperation;
@synthesize operationQueue;

- (void) firstOperationEntry:(id)paramObject{

    NSLog(@"First Operation - Parameter Object = %@",
          paramObject);

    NSLog(@"First Operation - Main Thread = %@",
          [NSThread mainThread]);

    NSLog(@"First Operation - Current Thread = %@",
          [NSThread currentThread]);

}

- (void) secondOperationEntry:(id)paramObject{

    NSLog(@"Second Operation - Parameter Object = %@",
          paramObject);

    NSLog(@"Second Operation - Main Thread = %@",
          [NSThread mainThread]);

    NSLog(@"Second Operation - Current Thread = %@",
          [NSThread currentThread]);

}

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSNumber *firstNumber = [NSNumber numberWithInt:111];
    NSNumber *secondNumber = [NSNumber numberWithInt:222];

    self.firstOperation = [[NSInvocationOperation alloc]
                           initWithTarget:self
                           selector:@selector(firstOperationEntry:)
                           object:firstNumber];

    self.secondOperation = [[NSInvocationOperation alloc]
                           initWithTarget:self
                           selector:@selector(secondOperationEntry:)
                           object:secondNumber];

    [self.firstOperation addDependency:self.secondOperation];

    self.operationQueue = [[NSOperationQueue alloc] init];

    /* Add the operations to the queue */
    [self.operationQueue addOperation:self.firstOperation];
    [self.operationQueue addOperation:self.secondOperation];

    NSLog(@"Main thread is here");

```

```

self.window = [[UIWindow alloc] initWithFrame:
                [[UIScreen mainScreen] bounds]];
self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

@end

```

Now if you execute the program, you will see a result similar to this in the console window:

```

Second Operation - Parameter Object = 222
Main thread is here
Second Operation - Main Thread = <NSThread: 0x6810250>{name = (null), num = 1}
Second Operation - Current Thread = <NSThread: 0x6836ab0>{name = (null), num = 3}
First Operation - Parameter Object = 111
First Operation - Main Thread = <NSThread: 0x6810250>{name = (null), num = 1}
First Operation - Current Thread = <NSThread: 0x6836ab0>{name = (null), num = 3}

```

It's quite obvious that although the operation queue attempted to run both operations in parallel, the first operation had a dependency on the second operation, and therefore the second operation had to finish before the first operation could be run.

If, at any time, you want to break the dependency between two operations, you can use the `removeDependency:` instance method of an operation object.

See Also

XXX

5.15 Creating Concurrency with Timers

Problem

You would like to perform a specific task repeatedly with a certain delay. For instance, you want to update a view on your screen every second for as long as your application is running.

Solution

Use a timer:

```

- (void) paint:(NSTimer *)paramTimer{
    /* Do something here */
    NSLog(@"Painting");
}

- (void) startPainting{

    self.paintingTimer = [NSTimer

```

```

        scheduledTimerWithTimeInterval:1.0
        target:self
        selector:@selector(paint:)
        userInfo:nil
        repeats:YES];
    }

    - (void) stopPainting{
        if (self.paintingTimer != nil){
            [self.paintingTimer invalidate];
        }
    }

    - (void)applicationWillResignActive:(UIApplication *)application{
        [self stopPainting];
    }

    - (void)applicationDidBecomeActive:(UIApplication *)application{
        [self startPainting];
    }
}

```

The `invalidate` method will also release the timer so that we don't have to do that manually. As you can see, we have defined a property called `paintingTimer` that is declared in this way in our header file (*.h* file):

```

#import <UIKit/UIKit.h>

@interface Creating_Concurrency_with_TimersAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) NSTimer *paintingTimer;

@end

```

Discussion

A timer is an object that fires an event at specified intervals. A timer must be scheduled in a run loop. Defining an `NSTimer` object creates a nonscheduled timer that does nothing but is available to the program when you want to schedule it. Once you issue a call such as `scheduledTimerWithTimeInterval:target:selector:userInfo:repeats:`, the time becomes a scheduled timer and will fire the event you request. A scheduled timer is a timer that is added to a run loop. To get any timer to fire its target event, we must schedule that timer on a run loop. This is demonstrated in a later example where we create a nonscheduled timer and then schedule it on the main run loop of the application manually.

Once a timer is created and added to a run loop either explicitly or implicitly, the timer will start calling a method in its target object, specified by the programmer, every n seconds, where n is specified by the programmer as well. Because n is floating-point, you can specify a fraction of a second.

There are various ways to create, initialize, and schedule timers. One of the easiest ways is through the `scheduledTimerWithTimeInterval:target:selector:userInfo:repeats:` class method of `NSTimer`. Here are the different parameters of this method:

`scheduledTimerWithTimeInterval`

This is the number of seconds the timer has to wait before it fires an event. For example, if you want the timer to call a method in its target object twice per second, you have to set this parameter to 0.5 (1 second divided by 2); if you want the target method to be called four times per second, this parameter should be set to 0.25 (1 second divided by 4).

`target`

This is the object that will receive the event.

`selector`

This is the method signature in the target object that will receive the event.

`userInfo`

This is the object that will be retained in the timer for later reference (in the target method of the target object).

`repeats`

This specifies whether the timer must call its target method repeatedly (in which case this parameter has to be set to YES), or just once and then stop (in which case this parameter has to be set to NO).



Once a timer is created and added to a run loop, you can stop and release that timer using the `invalidate` instance method of the `NSTimer` class. This not only will release the timer, but also will release the object, if any, that was passed for the timer to retain during its lifetime (e.g., the object passed to the `userInfo` parameter of the `scheduledTimerWithTimeInterval:target:selector:userInfo:repeats:` class method of `NSTimer`). If you pass NO to the `repeats` parameter, the timer will invalidate itself after the first pass and subsequently will release the object it had retained (if any).

There are other methods you can use to create a scheduled timer. One of them is the `scheduledTimerWithTimeInterval:invocation:repeats:` class method of `NSTimer`:

```
- (void) paint:(NSTimer *)paramTimer{
    /* Do something here */
    NSLog(@"Painting");
}

- (void) startPainting{

    /* Here is the selector that we want to call */
    SEL selectorToCall = @selector(paint:);

    /* Here we compose a method signature out of the selector. We
```

```

    know that the selector is in the current class so it is easy
    to construct the method signature */
    NSStringSignature *methodSignature =
        [[self class] instanceMethodSignatureForSelector:selectorToCall];

    /* Now base our invocation on the method signature. We need this
    invocation to schedule a timer */
    NSInvocation *invocation =
        [NSInvocation invocationWithMethodSignature:methodSignature];
    [invocation setTarget:self];
    [invocation setSelector:selectorToCall];

    /* Start a scheduled timer now */
    self.paintingTimer = [NSTimer scheduledTimerWithTimeInterval:1.0
                                                    invocation:invocation
                                                    repeats:YES];
}

- (void) stopPainting{
    if (self.paintingTimer != nil){
        [self.paintingTimer invalidate];
    }
}

- (void)applicationWillResignActive:(UIApplication *)application{
    [self stopPainting];
}

- (void)applicationDidBecomeActive:(UIApplication *)application{
    [self startPainting];
}

```

Scheduling a timer can be compared to starting a car's engine. A scheduled timer is a running car engine. A nonscheduled timer is a car engine that is ready to be started but is not running yet. We can schedule and unschedule timers whenever we want in our application, just like we might need the engine of a car to be on or off depending on what situation we are in. If you want to schedule a timer manually at a certain time in your application, you can use the `timerWithTimeInterval:target:selector:userInfo:repeats:` class method of `NSTimer`, and when you are ready you can add the timer to your run loop of choice:

```

- (void) startPainting{

    self.paintingTimer = [NSTimer timerWithTimeInterval:1.0
                                                    target:self
                                                    selector:@selector(paint:)
                                                    userInfo:nil
                                                    repeats:YES];

    /* Do your processing here and whenever you are ready,
    use the addTimer:forMode instance method of the NSRunLoop class
    in order to schedule the timer on that run loop */
}

```

```

[[NSRunLoop currentRunLoop] addTimer:self.paintingTimer
                             forMode:NSDefaultRunLoopMode];

}

```



The `currentRunLoop` and `mainRunLoop` class methods of `NSRunLoop` return the current and main run loops of the application, respectively, as their names imply.

Just like you can use the `scheduledTimerWithTimeInterval:invocation:repeats:` variant of creating scheduled timers using invocations, you can also use the `timerWithTimeInterval:invocation:repeats:` class method of `NSTimer` to create an unscheduled timer using an invocation:

```

- (void) paint:(NSTimer *)paramTimer{
    /* Do something here */
    NSLog(@"Painting");
}

- (void) startPainting{

    /* Here is the selector that we want to call */
    SEL selectorToCall = @selector(paint:);

    /* Here we compose a method signature out of the selector. We
       know that the selector is in the current class so it is easy
       to construct the method signature */
    NSString *methodSignature =
    [[self class] instanceMethodSignatureForSelector:selectorToCall];

    /* Now base our invocation on the method signature. We need this
       invocation to schedule a timer */
    NSInvocation *invocation =
    [NSInvocation invocationWithMethodSignature:methodSignature];

    [invocation setTarget:self];
    [invocation setSelector:selectorToCall];

    self.paintingTimer = [NSTimer timerWithTimeInterval:1.0
                                       invocation:invocation
                                       repeats:YES];

    /* Do your processing here and whenever you are ready,
       use the addTimer:forMode instance method of the NSRunLoop class
       in order to schedule the timer on that run loop */

    [[NSRunLoop currentRunLoop] addTimer:self.paintingTimer
                                     forMode:NSDefaultRunLoopMode];

}

- (void) stopPainting{

```

```

        if (self.paintingTimer != nil){
            [self.paintingTimer invalidate];
        }
    }

    - (void)applicationWillResignActive:(UIApplication *)application{
        [self stopPainting];
    }

    - (void)applicationDidBecomeActive:(UIApplication *)application{
        [self startPainting];
    }

```

The target method of a timer receives the instance of the timer that calls it as its parameter. For instance, the `paint:` method introduced initially in this recipe demonstrates how the timer gets passed to its target method, by default, as the target method's one and only parameter:

```

- (void) paint:(NSTimer *)paramTimer{
    /* Do something here */
    NSLog(@"Painting");
}

```

This parameter provides you with a reference to the timer that is firing this method. You can, for instance, prevent the timer from running again using the `invalidate` method, if needed. You can also invoke the `userInfo` method of the `NSTimer` instance in order to retrieve the object being retained by the timer (if any). This object is just an object passed to the initialization methods of `NSTimer`, and it gets directly passed to the timer for future reference.

See Also

XXX

5.16 Creating Concurrency with Threads

Problem

You would like to have maximum control over how separate tasks run in your application. For instance, you would like to run a long calculation requested by the user while freeing the main UI thread to interact with the user and do other things.

Solution

Utilize threads in your application:

```

- (void) downloadNewFile:(id)paramObject{

    @autoreleasepool {
        NSString *fileURL = (NSString *)paramObject;
    }
}

```



```

NSURL      *url = [NSURL URLWithString:fileURL];

NSURLRequest *request = [NSURLRequest requestWithURL:url];

NSURLResponse *response = nil;
NSError        *error = nil;

NSData *downloadedData =
[NSURLConnection sendSynchronousRequest:request
                  returningResponse:&response
                  error:&error];

if ([downloadedData length] > 0){
    /* Fully downloaded */
} else {
    /* Nothing was downloaded. Check the Error value */
}
}

- (void)viewDidLoad {
    [super viewDidLoad];

    NSString *fileToDownload = @"http://www.OReilly.com";

    [NSThread detachNewThreadSelector:@selector(downloadNewFile:)
              toTarget:self
              withObject:fileToDownload];
}

```

Discussion

Any iOS application is made out of one or more threads. In iOS 5, a normal application with one view controller could initially have up to four or five threads created by the system libraries to which the application is linked. At least one thread will be created for your application whether you use multiple threads or not. It is called the “main UI thread” attached to the main run loop.

To understand how useful threads are, let’s do an experiment. Suppose we have three loops:

```

- (void) firstCounter{

    NSUInteger counter = 0;
    for (counter = 0;
         counter < 1000;
         counter++){
        NSLog(@"First Counter = %lu", (unsigned long)counter);
    }
}

```

```

- (void) secondCounter{

    NSUInteger counter = 0;
    for (counter = 0;
        counter < 1000;
        counter++){
        NSLog(@"Second Counter = %lu", (unsigned long)counter);
    }

}

- (void) thirdCounter{

    NSUInteger counter = 0;
    for (counter = 0;
        counter < 1000;
        counter++){
        NSLog(@"Third Counter = %lu", (unsigned long)counter);
    }

}

```

Very simple, aren't they? All they do is go from zero to 1,000, printing their counter numbers. Now suppose you want to run these counters as we would normally do:

```

- (void) viewDidLoad{
    [super viewDidLoad];
    [self firstCounter];
    [self secondCounter];
    [self thirdCounter];
}

```



This code does not necessarily have to be in a view controller's `viewDidLoad` method.

Now open the console window and run this application. You will see the first counter's complete run, followed by the second counter and then the third counter. This means these loops are being run on the same thread. Each one blocks the rest of the thread's code from being executed until it finishes its loop.

What if we wanted all these counters to run at the same time? Of course, we would have to create separate threads for each one. But wait a minute! We already learned that our application creates threads for us when it loads and that whatever code we have been writing so far in our application, wherever it was, was being executed in a thread. So, we just have to create two threads for the first and second counters and leave the third counter to do its job in the main thread:

```

- (void) firstCounter{

    @autoreleasepool {

```

```

        NSInteger counter = 0;
        for (counter = 0;
             counter < 1000;
             counter++){
            NSLog(@"First Counter = %lu", (unsigned long)counter);
        }
    }

- (void) secondCounter{

    @autoreleasepool {
        NSInteger counter = 0;
        for (counter = 0;
             counter < 1000;
             counter++){
            NSLog(@"Second Counter = %lu", (unsigned long)counter);
        }
    }

}

- (void) thirdCounter{

    NSInteger counter = 0;
    for (counter = 0;
         counter < 1000;
         counter++){
        NSLog(@"Third Counter = %lu", (unsigned long)counter);
    }

}

- (void)viewDidLoad {

    [super viewDidLoad];

    [NSThread detachNewThreadSelector:@selector(firstCounter)
                toTarget:self
                withObject:nil];

    [NSThread detachNewThreadSelector:@selector(secondCounter)
                toTarget:self
                withObject:nil];

    /* Run this on the main thread */
    [self thirdCounter];

}

```



The `thirdCounter` method does not have an autorelease pool since it is not run in a new detached thread. This method will be run in the application's main thread, which has an autorelease pool created for it automatically at the startup of every Cocoa Touch application. Also bear in mind that since we are detaching our threads in the `viewDidLoad` method of a view controller, we must handle the deallocation of these threads, if necessary, in the `viewDidUnload` method of the same view controller. The view runs `viewDidUnload` whenever the system sends it a low-memory warning, and failing to deallocate detached threads in that method will lead to a memory leak if those threads were created in the `viewDidLoad` method. For this you will need a reference to the `NSThread` object you have allocated and initialized. Please use the `initWithTarget:selector:object:` instance method of `NSThread` to initialize an object of type `NSThread`. This way, you will get a reference to this thread and you can start it manually using its `start` instance method.

The calls to `detachNewThreadSelector` near the end of the code run the first and second counters as separate threads. Now if you run the application, you will notice output such as the following, in the console window:

```
Second Counter = 921
Third Counter = 301
Second Counter = 922
Second Counter = 923
Second Counter = 924
First Counter = 956
Second Counter = 925
Counter = 957
Second Counter = 926
First Counter = 958
Third Counter = 302
Second Counter = 927
Third Counter = 303
Second Counter = 928
```

In other words, all three counters run at once, and interleave their output randomly.

Every thread must create an autorelease pool. An autorelease pool internally keeps a reference to objects that are being autoreleased before the pool itself is released. This is a very important mechanism in a reference-counted memory management environment such as Cocoa Touch where objects can be autoreleased. Whenever we allocate instances of objects, the retain count of the objects gets set to 1. If we mark the objects as autorelease, the retain count remains at 1, but when the autorelease pool in which the object was created is released, the autorelease object is also sent a `release` message. If its retain count is still 1 at that point, the object gets deallocated.

Every thread requires an autorelease pool to be created for it as the first object that is allocated in that thread. If you don't do this, any object that you allocate in your thread

will leak when the thread exists. To understand this better, let's have a look at the following code:

```
- (void) autoreleaseThread:(id)paramSender{

    NSBundle *mainBundle = [NSBundle mainBundle];
    NSString *filePath = [mainBundle pathForResource:@"AnImage"
                                              ofType:@"png"];

    UIImage *image = [UIImage imageWithContentsOfFile:filePath];

    /* Do something with the image */
    NSLog(@"Image = %@", image);

}

- (void)viewDidLoad {

    [super viewDidLoad];

    [NSThread detachNewThreadSelector:@selector(autoreleaseThread:)
                               toTarget:self
                               withObject:self];

}
```

If you run this code and keep an eye on the console window, you will receive a message similar to this:

```
*** __NSAutoreleaseNoPool(): Object 0x5b2c990 of
class NSCFString autoreleased with no pool in place - just leaking
*** __NSAutoreleaseNoPool(): Object 0x5b2ca30 of
class NSPathStore2 autoreleased with no pool in place - just leaking
*** __NSAutoreleaseNoPool(): Object 0x5b205c0 of
class NSPathStore2 autoreleased with no pool in place - just leaking
*** __NSAutoreleaseNoPool(): Object 0x5b2d650 of
class UIImage autoreleased with no pool in place - just leaking
```

This shows that the autorelease UIImage instance we created is creating a memory leak—and in addition, so is the NSString instance called filePath and other objects that would normally “magically” get deallocated. This is because in our thread, we forgot to allocate and initialize an autorelease pool as the first thing we did. The following is the correct code, which you can test for yourself to make sure it doesn't leak:

```
- (void) autoreleaseThread:(id)paramSender{

    @autoreleasepool {
        NSBundle *mainBundle = [NSBundle mainBundle];
        NSString *filePath = [mainBundle pathForResource:@"AnImage"
                                              ofType:@"png"];

        UIImage *image = [UIImage imageWithContentsOfFile:filePath];

        /* Do something with the image */
        NSLog(@"Image = %@", image);
    }
}
```

```

    }
}

```

5.17 Invoking Background Methods

Problem

You want to know an easy way to create threads, without having to deal with threads directly.

Solution

Use the `performSelectorInBackground:withObject:` instance method of `NSObject`:

```

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [self performSelectorInBackground:@selector(firstCounter)
        withObject:nil];

    [self performSelectorInBackground:@selector(secondCounter)
        withObject:nil];

    [self performSelectorInBackground:@selector(thirdCounter)
        withObject:nil];

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

The counter methods are implemented in this way:

```

- (void) firstCounter{

    @autoreleasepool {
        NSUInteger counter = 0;
        for (counter = 0;
            counter < 1000;
            counter++){
            NSLog(@"First Counter = %lu", (unsigned long)counter);
        }
    }

}

- (void) secondCounter{

    @autoreleasepool {
        NSUInteger counter = 0;
        for (counter = 0;

```

```

        counter < 1000;
        counter++){
    NSLog(@"Second Counter = %lu", (unsigned long)counter);
    }
}

- (void) thirdCounter{

    @autoreleasepool {
        NSUInteger counter = 0;
        for (counter = 0;
            counter < 1000;
            counter++){
            NSLog(@"Third Counter = %lu", (unsigned long)counter);
        }
    }
}

```

Discussion

The `performSelectorInBackground:withObject:` method creates a new thread in the background for us. This is equivalent to our creating a new thread for our selectors. The most important thing that we have to keep in mind is that since this method creates a thread on the given selector, the selector must have an autorelease pool just like any other thread in a reference-counted memory environment.

5.18 Exiting Threads and Timers

Problem

You would like to stop a thread or a timer, or prevent one from firing again.

Solution

For timers, use the `invalidate` instance method of `NSTimer`. For threads, use the `cancel` method. Avoid using the `exit` method of threads, as it does not give the thread a chance to clean up after itself and your application will end up leaking resources:

```

NSThread *thread = /* Get the reference to your thread here */;
[thread cancel];

NSTimer *timer = /* Get the reference to your timer here */;
[timer invalidate];

```

Discussion

Exiting a timer is quite straightforward; you can simply call the timer's `invalidate` instance method. After you call that method, the timer will not fire any more events to its target object.

However, threads are a bit more complicated to exit. When a thread is sleeping and its `cancel` method is called, the thread's loop will still perform its task fully before exiting. Let me demonstrate this for you:

```
- (void) threadEntryPoint{

    @autoreleasepool {
        NSLog(@"Thread Entry Point");
        while ([[NSThread currentThread] isCancelled] == NO){
            [NSThread sleepForTimeInterval:0.2];
            NSLog(@"Thread Loop");
        }
        NSLog(@"Thread Finished");
    }
}

- (void) stopThread{

    NSLog(@"Cancelling the Thread");
    [self.myThread cancel];
    NSLog(@"Releasing the thread");
    self.myThread = nil;
}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.myThread = [[NSThread alloc]
                    initWithTarget:self
                    selector:@selector(threadEntryPoint)
                    object:nil];

    [self performSelector:@selector(stopThread)
     withObject:nil
     afterDelay:3.0f];

    [self.myThread start];

    self.window = [[UIWindow alloc] initWithFrame:
                    [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```


This code creates an instance of `NSThread` and starts the thread immediately. Our thread sleeps for four seconds in every loop before performing its task. However, before the thread is started, we are calling the `stopThread` method of our view controller (which we have written) with a three-second delay. This method calls the `cancel` method of our thread in an attempt to make the thread exit its loop. Now let's run the application and see what gets printed to the console screen:

```
...
Thread Entry Point
Cancelling the Thread
Releasing the thread
Thread Loop
Thread Finished
```

You can clearly see that our thread finished its current loop before exiting, even though the request to cancel it was fired in the middle of the loop. This is a very common pitfall that can be avoided simply by checking whether the thread is cancelled before attempting to perform a task with external side effects inside the thread's loop. We can rewrite our example as follows so that the operation with an external effect (writing to the log) checks first to make sure the thread hasn't been cancelled.

```
- (void) threadEntryPoint{

    @autoreleasepool {
        NSLog(@"Thread Entry Point");
        while ([[NSThread currentThread] isCancelled] == NO){
            [NSThread sleepForTimeInterval:0.2];
            if ([[NSThread currentThread] isCancelled] == NO){
                NSLog(@"Thread Loop");
            }
        }
        NSLog(@"Thread Finished");
    }
}

- (void) stopThread{

    NSLog(@"Cancelling the Thread");
    [self.myThread cancel];
    NSLog(@"Releasing the thread");
    self.myThread = nil;
}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.myThread = [[NSThread alloc]
        initWithTarget:self
        selector:@selector(threadEntryPoint)
        object:nil];
```

```
[self performSelector:@selector(stopThread)
      withObject:nil
      afterDelay:3.0f];

[self.myThread start];

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];
self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}
```

Core Location and Maps

6.0 Introduction

The Core Location and Map Kit frameworks can be used to create location-aware and map-based applications. The Core Location framework uses the internal device's hardware to determine the current location of the device. The Map Kit framework enables your application to display maps to your users, put custom annotations on the maps, and so on. The availability of location services depends on the availability of hardware on the device; if the hardware is there, it must be enabled and switched on for the Map Kit framework to work.

To use the Core Location and Map Kit frameworks, you need to first add them to your project and make sure appropriate header files are imported. Follow these steps to add these two frameworks to your project:

1. Click on your project icon in Xcode.
2. Select the target to which you want to add the frameworks to, as shown in [Figure 6-1](#).
3. Now select the Build Phases tab on the top ([Figure 6-1](#)).
4. Expand the Link Binary With Libraries box ([Figure 6-1](#)) and press the + button.




Figure 6-1. Selecting the target to which we want to add the frameworks

5. In the dialog, you will see the list of all available frameworks and static libraries. Find and select both the `CoreLocation.framework` and the `MapKit.framework` and then press Add, as shown in [Figure 6-2](#).




Figure 6-2. Adding the CoreLocation and the MapKit frameworks to a project

After adding these two frameworks, you will need to add two header files to your *.m* or *.h* file (in your *.h* file if you are referring to any entity that is included in either of the two aforementioned frameworks):

```
#import <CoreLocation/CoreLocation.h>
#import <MapKit/MapKit.h>
```

6.1 Creating a Map View

Problem

You want to instantiate and display a map on a view.

Solution

Create an instance of the `MKMapView` class and add it to a view or assign it as a subview of your view controller. Here is the sample *.h* file of a view controller that creates an instance of `MKMapView` and displays it full-screen on its view:

```
#import <UIKit/UIKit.h>
#import <MapKit/MapKit.h>
```

```

@interface Creating_a_Map_ViewViewController : UIViewController

@property (nonatomic, strong) MKMapView *myMapView;

@end

```

This is a simple root view controller with a variable of type `MKMapView`. Later in the implementation of this view controller (*.m* file), we will initialize the map and set its type to `Satellite`, like so:

```

#import "Creating_a_Map_ViewViewController.h"

@implementation Creating_a_Map_ViewViewController

@synthesize myMapView;

- (void)didReceiveMemoryWarning{
    [super didReceiveMemoryWarning];
}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.myMapView = [[MKMapView alloc]
                      initWithFrame:self.view.bounds];
    /* Set the map type to Satellite */
    self.myMapView.mapType = MKMapTypeSatellite;

    self.myMapView.autoresizingMask =
        UIViewAutoresizingFlexibleWidth |
        UIViewAutoresizingFlexibleHeight;

    /* Add it to our view */
    [self.view addSubview:self.myMapView];
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.myMapView = nil;
}

- (BOOL)shouldAutorotateToInterfaceOrientation
    :(UIInterfaceOrientation)interfaceOrientation{
    return YES;
}

@end

```

Discussion

Creating an instance of the `MKMapView` class is quite straightforward. We can simply assign a frame to it using its constructor, and after the map is created, we will add it as a subview of the view on the screen just so that we can see it.



`MKMapView` is a subclass of `UIView`, so you can manipulate any map view the way you manipulate an instance of `UIView`.

If you haven't already noticed, the `MKMapView` class has a property called `mapType` that can be set to `satellite`, `standard`, or `hybrid`. In this example, we are using the `satellite` map type (see [Figure 6-3](#)).



Figure 6-3. A satellite map view

We can change the visual representation type of a map view using the `mapType` property of an instance of `MKMapView`. Here are the different values we can use for this property:

`MKMapTypeStandard`

Use this map type to display a standard map (this is the default).

`MKMapTypeSatellite`

Use this map type to display a satellite image map (as depicted in [Figure 6-3](#)).

`MKMapTypeHybrid`

Use this map type to display a standard map overlaid on a satellite image map.

See Also

XXX

6.2 Handling the Events of a Map View

Problem

You want to handle various events that a map view can send to its delegate.

Solution

Assign a delegate object, which conforms to the `MKMapViewDelegate` protocol, to the `delegate` property of an instance of the `MKMapView` class:

```
/* Create a map as big as our view */
self.myMapView = [[MKMapView alloc]
                  initWithFrame:self.view.bounds];

/* Set the map type to Satellite */
self.myMapView.mapType = MKMapTypeSatellite;

self.myMapView.delegate = self;

self.myMapView.autoresizingMask =
    UIViewAutoresizingFlexibleWidth |
    UIViewAutoresizingFlexibleHeight;

/* Add it to our view */
[self.view addSubview:self.myMapView];
```

This code can easily run in the `viewDidLoad` method of a view controller object that has a property named `MapView` of type `MKMapView`:

```
#import <UIKit/UIKit.h>
#import <MapKit/MapKit.h>

@interface Handling_the_Events_of_a_Map_ViewViewController
    : UIViewController <MKMapViewDelegate>

@property (nonatomic, strong) MKMapView *myMapView;

@end
```

Discussion

The delegate object of an instance of the `MKMapView` class must implement the methods defined in the `MKMapViewDelegate` protocol in order to receive various messages from the map view and, as we will see later, to be able to provide information to the map view. Various methods are defined in the `MKMapViewDelegate` protocol, such as the `mapViewWillStartLoadingMap:` method that will get called in the delegate object when-

ever the map loading process starts. Bear in mind that a delegate for a map view is not a required object, meaning that you can create map views without assigning delegates to them; these views simply won't respond to user manipulation.

Here is a list of some of the methods declared in the `MKMapViewDelegate` protocol and what they are meant to report to the delegate object of an instance of `MKMapView`:

`mapViewWillStartLoadingMap:`

This method is called on the delegate object whenever the map view starts to load the data that visually represents the map to the user.

`mapView:viewForAnnotation:`

This method is called on the delegate object whenever the map view is asking for an instance of `MKAnnotationView` to visually represent an annotation on the map. For more information about this, please refer to [Recipe 6.4](#).

`mapViewWillStartLocatingUser:`

This method, as its name implies, gets called on the delegate object whenever the map view starts to detect the user's location. For information about finding a user's location, please refer to [Recipe 6.3](#).

`mapView:regionDidChangeAnimated:`

This method gets called on the delegate object whenever the region displayed by the map is changed.

6.3 Pinpointing the Location of a Device

Problem

You want to find the latitude and longitude of a device.

Solution

Use the `CLLocationManager` class:

```
if ([CLLocationManager locationServicesEnabled]){
    self.myLocationManager = [[CLLocationManager alloc] init];
    self.myLocationManager.delegate = self;

    self.myLocationManager.purpose =
        @"To provide functionality based on user's current location.";

    [self.myLocationManager startUpdatingLocation];
} else {
    /* Location services are not enabled.
    Take appropriate action: for instance, prompt the
    user to enable the location services */
    NSLog(@"Location services are not enabled");
}
```

In this code, `myLocationManager` is a property of type `CLLocationManager`. The current class is also the delegate of the location manager in this sample code.

Discussion

The Core Location framework in the SDK provides functionality for programmers to be able to detect the current spatial location of an iOS device. Because in iOS, the user is allowed to disable location services using the Settings, before instantiating an object of type `CLLocationManager`, it is best to first determine whether the location services are enabled on the device.



The delegate object of an instance of `CLLocationManager` must conform to the `CLLocationManagerDelegate` protocol.

This is how we will declare our location manager object in the `.h` file of a view controller (the object creating an instance of `CLLocationManager` does not necessarily have to be a view controller):

```
#import <UIKit/UIKit.h>
#import <CoreLocation/CoreLocation.h>

@interface Pinpointing_the_Location_of_a_DeviceViewController
    : UIViewController <CLLocationManagerDelegate>

@property (nonatomic, strong) CLLocationManager *myLocationManager;

@end
```

The implementation of our view controller is as follows:

```
#import "Pinpointing_the_Location_of_a_DeviceViewController.h"

@implementation Pinpointing_the_Location_of_a_DeviceViewController

@synthesize myLocationManager;

- (void)didReceiveMemoryWarning{
    [super didReceiveMemoryWarning];
}

- (void)locationManager:(CLLocationManager *)manager
    didUpdateToLocation:(CLLocation *)newLocation
    fromLocation:(CLLocation *)oldLocation{

    /* We received the new location */

    NSLog(@"Latitude = %f", newLocation.coordinate.latitude);
    NSLog(@"Longitude = %f", newLocation.coordinate.longitude);
}
```

```

- (void)locationManager:(CLLocationManager *)manager
  didFailWithError:(NSError *)error{

    /* Failed to receive user's location */

}

- (void)viewDidLoad {
    [super viewDidLoad];

    if ([CLLocationManager locationServicesEnabled]){
        self.myLocationManager = [[CLLocationManager alloc] init];
        self.myLocationManager.delegate = self;

        self.myLocationManager.purpose =
            @"To provide functionality based on user's current location.";

        [self.myLocationManager startUpdatingLocation];
    } else {
        /* Location services are not enabled.
        Take appropriate action: for instance, prompt the
        user to enable the location services */
        NSLog(@"Location services are not enabled");
    }

}

- (void) viewDidUnload{
    [super viewDidUnload];
    [self.myLocationManager stopUpdatingLocation];
    self.myLocationManager = nil;
}

- (BOOL)shouldAutorotateToInterfaceOrientation
    :(UIInterfaceOrientation)interfaceOrientation{
    return YES;
}

@end

```

The `startUpdateLocation` instance method of `CLLocationManager` reports the success or failure of retrieving the user's location to its delegate through the `locationManager:didUpdateToLocation:fromLocation:` and `locationManager:didFailWithError:` methods of its delegate object, in that order.



The `locationServicesEnabled` class method of `CLLocationManager` is available in SDK 4.0 and later.

The `CLLocationManager` class implements a property named `purpose`. This property allows us to customize the message that is shown to the users of our application, asking for their permission to allow location services for our application using Core Location functionalities. A good practice is to use localized strings for the value of this property.

6.4 Displaying Pins on a Map View

Problem

You want to point out a specific location on a map to the user.

Solution

Use built-in map view annotations.

Follow these steps:

1. Create a new class and call it `MyAnnotation`.
2. Make sure this class conforms to the `MKAnnotation` protocol.
3. Define a property for this class of type `CLLocationCoordinate2D` and name it `coordinate`. Also make sure you set it as a `readonly` property since the `coordinate` property is defined as `readonly` in the `MKAnnotation` protocol.
4. Optionally, define two properties of type `NSString`, namely `title` and `subtitle`, which will be able to carry the title and the subtitle information for your annotation view. Both of these properties are `readonly` as well.
5. Create an initializer method for your class that will accept a parameter of type `CLLocationCoordinate2D`. In this method, assign the passed location parameter to the property that we defined in step 3. Since this property is `readonly`, it cannot be assigned by code outside the scope of this class. Therefore, the initializer of this class acts as a bridge here and allows us to indirectly assign a value to this property. We will do the same thing for the `title` and the `subtitle` properties.
6. Instantiate the `MyAnnotation` class and add it to your map using the `addAnnotation:` method of the `MKMapView` class.

Discussion

As explained in this recipe's [Solution](#), we must create an object that conforms to the `MKAnnotation` protocol and later instantiate this object and pass it to the map to be displayed. We will write the `.h` file of this object like so:

```
#import <Foundation/Foundation.h>
#import <MapKit/MapKit.h>

@interface MyAnnotation : NSObject <MKAnnotation>

@property (nonatomic, readonly) CLLocationCoordinate2D coordinate;
```

```

@property (nonatomic, copy, readonly) NSString *title;
@property (nonatomic, copy, readonly) NSString *subtitle;

- (id) initWithCoordinates:(CLLocationCoordinate2D)paramCoordinates
    title:(NSString *)paramTitle
    subTitle:(NSString *)paramSubTitle;

@end

```

The *.m* file of the `MyAnnotation` class sets up the class to display location information as follows:

```

#import "MyAnnotation.h"

@implementation MyAnnotation

CLLocationCoordinate2D coordinate;

@synthesize coordinate, title, subtitle;

- (id) initWithCoordinates:(CLLocationCoordinate2D)paramCoordinates
    title:(NSString *)paramTitle
    subTitle:(NSString *)paramSubTitle{

    self = [super init];

    if (self != nil){
        coordinate = paramCoordinates;
        title = paramTitle;
        subtitle = paramSubTitle;
    }

    return(self);
}

@end

```

Later we will instantiate this class and add it to our map, for instance, in the *.m* file of a view controller that creates and displays a map view:

```

#import "Displaying_Pins_on_a_Map_ViewViewController.h"
#import "MyAnnotation.h"

@implementation Displaying_Pins_on_a_Map_ViewViewController

@synthesize myMapView;

- (void)didReceiveMemoryWarning
{
    [super didReceiveMemoryWarning];
    // Release any cached data, images, etc that aren't in use.
}

- (void)viewDidLoad {
    [super viewDidLoad];
}

```

```

/* Create a map as big as our view */
self.myMapView = [[MKMapView alloc]
                  initWithFrame:self.view.bounds];

self.myMapView.delegate = self;

/* Set the map type to Standard */
self.myMapView.mapType = MKMapTypeStandard;

self.myMapView.autoresizingMask =
    UIViewAutoresizingFlexibleWidth |
    UIViewAutoresizingFlexibleHeight;

/* Add it to our view */
[self.view addSubview:self.myMapView];

/* This is just a sample location */
CLLocationCoordinate2D location =
    CLLocationCoordinate2DMake(50.82191692907181, -0.13811767101287842);

/* Create the annotation using the location */
MyAnnotation *annotation =
    [[MyAnnotation alloc] initWithCoordinates:location
                                title:@"My Title"
                                subTitle:@"My Sub Title"];

/* And eventually add it to the map */
[self.myMapView addAnnotation:annotation];
}

- (void) viewDidLoad{
    [super viewDidLoad];
    self.myMapView = nil;
}

- (BOOL)shouldAutorotateToInterfaceOrientation
    :(UIInterfaceOrientation)interfaceOrientation{
    return YES;
}

@end

```

Figure 6-4 depicts the output of the program when run in iPhone Simulator.



Figure 6-4. A built-in pin dropped on a map

See Also

XXX

6.5 Displaying Pins with Different Colors on a Map View

Problem

The default color for pins dropped on a map view is red. You want to be able to display pins in different colors in addition to the default red pin.

Solution

Return instances of `MKPinAnnotationView` to your map view through the `mapView:viewForAnnotation:` delegate method.

Every annotation that is added to an instance of `MKMapView` has a corresponding view that gets displayed on the map view. These views are called *annotation views*. An annotation view is an object of type `MKAnnotationView`, which is a subclass of `UIView`. If the delegate object of a map view implements the `mapView:viewForAnnotation:` delegate method, the delegate object will have to return instances of the `MKAnnotationView` class to represent and, optionally, customize the annotation views to be displayed on a map view.

Discussion

To set up our program so that we can customize the color (choosing from the default SDK pin colors) of the annotation view that gets dropped on a map view, representing an annotation, we must return an instance of the `MKPinAnnotationView` class instead of an instance of `MKAnnotationView` in the `mapView:viewForAnnotation:` delegate method. Bear in mind that the `MKPinAnnotationView` class is a subclass of the `MKAnnotationView` class.

```
- (MKAnnotationView *)mapView:(MKMapView *)mapView
    viewForAnnotation:(id <MKAnnotation>)annotation{

    MKAnnotationView *result = nil;

    if ([annotation isKindOfClass:[MyAnnotation class]] == NO){
        return result;
    }

    if ([mapView isEqual:self.myMapView] == NO){
        /* We want to process this event only for the Map View
           that we have created previously */
        return result;
    }

    /* First typecast the annotation for which the Map View has
       fired this delegate message */
    MyAnnotation *senderAnnotation = (MyAnnotation *)annotation;

    /* Using the class method we have defined in our custom
       annotation class, we will attempt to get a reusable
```

```

        identifier for the pin we are about
        to create */
NSString *pinReusableIdentifier =
[MyAnnotation
 reusableIdentifierforPinColor:senderAnnotation.pinColor];

/* Using the identifier we retrieved above, we will
attempt to reuse a pin in the sender Map View */
MKPinAnnotationView *annotationView = (MKPinAnnotationView *)
[mapView
 dequeueReusableAnnotationViewWithIdentifier:pinReusableIdentifier];

if (annotationView == nil){
    /* If we fail to reuse a pin, then we will create one */
    annotationView = [[MKPinAnnotationView alloc]
                      initWithAnnotation:senderAnnotation
                      reuseIdentifier:pinReusableIdentifier];

    /* Make sure we can see the callouts on top of
    each pin in case we have assigned title and/or
    subtitle to each pin */
    [annotationView setShowCallout:YES];
}

/* Now make sure, whether we have reused a pin or not, that
the color of the pin matches the color of the annotation */
annotationView.pinColor = senderAnnotation.pinColor;

result = annotationView;

return result;
}

```

An annotation view must be reused by giving it an identifier (an `NSString`). By determining which type of pin you would like to display on a map view and setting a unique identifier for each type of pin (e.g., blue pins can be treated as one type of pin and red pins as another), you must reuse the proper type of pin using the `dequeueReusableAnnotationViewWithIdentifier:` instance method of `MKMapView` as demonstrated in the code.

We have set the mechanism of retrieving the unique identifiers of each pin in our custom `MyAnnotation` class. Here is the `.h` file of the `MyAnnotation` class:

```

#import <Foundation/Foundation.h>
#import <MapKit/MapKit.h>

/* These are the standard SDK pin colors. We are setting
unique identifiers per color for each pin so that later we
can reuse the pins that have already been created with the same
color */

#define REUSABLE_PIN_RED    @"Red"
#define REUSABLE_PIN_GREEN @"Green"
#define REUSABLE_PIN_PURPLE @"Purple"

```

```

@interface MyAnnotation : NSObject <MKAnnotation>

@property (nonatomic, unsafe_unretained, readonly)
    CLLocationCoordinate2D coordinate;

@property (nonatomic, copy) NSString *title;
@property (nonatomic, copy) NSString *subtitle;

@property (nonatomic, unsafe_unretained) MKPinAnnotationColor pinColor;

- (id) initWithCoordinates:(CLLocationCoordinate2D)paramCoordinates
    title:(NSString*)paramTitle
    subTitle:(NSString*)paramSubTitle;

+ (NSString *) reusableIdentifierforPinColor
    :(MKPinAnnotationColor)paramColor;

@end

```

Annotations are not the same as annotation views. An annotation is the location that you want to show on a map and an annotation view is the view that represents that annotation on the map. The `MyAnnotation` class is the annotation, not the annotation view. When we create an annotation by instantiating the `MyAnnotation` class, we can assign a color to it using the `pinColor` property that we have defined and implemented. When the time comes for a map view to display an annotation, the map view will call the `mapView:viewForAnnotation:` delegate method and ask its delegate for an annotation view. The `forAnnotation` parameter of this method passes the annotation that needs to be displayed. By getting a reference to the annotation, we can type-cast the annotation to an instance of `MyAnnotation`, retrieve its `pinColor` property, and based on that, create an instance of `MKPinAnnotationView` with the given pin color and return it to the map view.

This is the `.m` file of `MyAnnotation`:

```

#import "MyAnnotation.h"

@implementation MyAnnotation

@synthesize coordinate;
@synthesize title;
@synthesize subtitle;
@synthesize pinColor;

+ (NSString *) reusableIdentifierforPinColor
    :(MKPinAnnotationColor)paramColor{

    NSString *result = nil;

    switch (paramColor){
        case MKPinAnnotationColorRed:{
            result = REUSABLE_PIN_RED;
            break;

```

```

    }
    case MKPinAnnotationColorGreen:{
        result = REUSABLE_PIN_GREEN;
        break;
    }
    case MKPinAnnotationColorPurple:{
        result = REUSABLE_PIN_PURPLE;
        break;
    }
}

return result;
}

- (id) initWithCoordinates:(CLLocationCoordinate2D)paramCoordinates
    title:(NSString*)paramTitle
    subtitle:(NSString*)paramSubTitle{

    self = [super init];

    if (self != nil){
        coordinate = paramCoordinates;
        title = paramTitle;
        subtitle = paramSubTitle;
        pinColor = MKPinAnnotationColorGreen;
    }

    return self;
}

@end

```

After implementing the `MyAnnotation` class, it's time to use it in our application (in this example, we will use it in a view controller). Here is the `.h` file of the view controller:

```

#import <UIKit/UIKit.h>
#import <MapKit/MapKit.h>

@interface Displaying_Pins_with_Different_Colors_on_a_Map_ViewViewController
    : UIViewController <MKMapViewDelegate>

@property (nonatomic, strong) MKMapView *myMapView;

@end

```

The implementation is in the `.m` file like so:

```

#import "Displaying_Pins_with_Different_Colors_on_a_Map_ViewViewController.h"
#import "MyAnnotation.h"

@implementation
    Displaying_Pins_with_Different_Colors_on_a_Map_ViewViewController

    @synthesize myMapView;

```

```

- (void)didReceiveMemoryWarning{
    [super didReceiveMemoryWarning];
}

- (MKAnnotationView *)mapView:(MKMapView *)mapView
    viewForAnnotation:(id <MKAnnotation>)annotation{

    MKAnnotationView *result = nil;

    if ([annotation isKindOfClass:[MyAnnotation class]] == NO){
        return result;
    }

    if ([mapView isEqual:self.myMapView] == NO){
        /* We want to process this event only for the Map View
           that we have created previously */
        return result;
    }

    /* First typecast the annotation for which the Map View has
       fired this delegate message */
    MyAnnotation *senderAnnotation = (MyAnnotation *)annotation;

    /* Using the class method we have defined in our custom
       annotation class, we will attempt to get a reusable
       identifier for the pin we are about
       to create */
    NSString *pinReusableIdentifier =
    [MyAnnotation
     reusableIdentifierforPinColor:senderAnnotation.pinColor];

    /* Using the identifier we retrieved above, we will
       attempt to reuse a pin in the sender Map View */
    MKPinAnnotationView *annotationView = (MKPinAnnotationView *)
    [mapView
     dequeueReusableAnnotationViewWithIdentifier:pinReusableIdentifier];

    if (annotationView == nil){
        /* If we fail to reuse a pin, then we will create one */
        annotationView = [[MKPinAnnotationView alloc]
                           initWithAnnotation:senderAnnotation
                           reuseIdentifier:pinReusableIdentifier];

        /* Make sure we can see the callouts on top of
           each pin in case we have assigned title and/or
           subtitle to each pin */
        [annotationView setShowCallout:YES];
    }

    /* Now make sure, whether we have reused a pin or not, that
       the color of the pin matches the color of the annotation */
    annotationView.pinColor = senderAnnotation.pinColor;

    result = annotationView;

```

```

    return result;
}

- (void)viewDidLoad {
    [super viewDidLoad];

    /* Create a map as big as our view */
    self.myMapView = [[MKMapView alloc]
                      initWithFrame:self.view.bounds];

    self.myMapView.delegate = self;

    /* Set the map type to Standard */
    self.myMapView.mapType = MKMapTypeStandard;

    self.myMapView.autoresizingMask =
        UIViewAutoresizingFlexibleWidth |
        UIViewAutoresizingFlexibleHeight;

    /* Add it to our view */
    [self.view addSubview:self.myMapView];

    /* This is just a sample location */
    CLLocationCoordinate2D location;
    location.latitude = 50.82191692907181;
    location.longitude = -0.13811767101287842;

    /* Create the annotation using the location */
    MyAnnotation *annotation =
        [[MyAnnotation alloc] initWithCoordinates:location
                                title:@"My Title"
                                subTitle:@"My Sub Title"];

    annotation.pinColor = MKPinAnnotationColorPurple;

    /* And eventually add it to the map */
    [self.myMapView addAnnotation:annotation];
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.myMapView = nil;
}

- (BOOL)shouldAutorotateToInterfaceOrientation
    :(UIInterfaceOrientation)interfaceOrientation{
    return YES;
}

@end

```

And the results are shown here:




Figure 6-5. A pin with an alternative color displayed on a map view

6.6 Displaying Custom Pins on a Map View

Problem

Instead of the default iOS SDK pins, you would like to display your own images as pins on a map view.

Solution

Load an arbitrary image into an instance of the `UIImage` class and assign it to the `image` property of the `MKAnnotationView` instance that you return to your map view as a pin:

```
- (MKAnnotationView *)mapView:(MKMapView *)mapView
    viewForAnnotation:(id <MKAnnotation>)annotation{

    MKAnnotationView *result = nil;

    if ([annotation isKindOfClass:[MyAnnotation class]] == NO){
        return result;
    }

    if ([mapView isEqual:self.myMapView] == NO){
        /* We want to process this event only for the Map View
           that we have created previously */
        return result;
    }

    /* First typecast the annotation for which the Map View has
       fired this delegate message */
    MyAnnotation *senderAnnotation = (MyAnnotation *)annotation;

    /* Using the class method we have defined in our custom
       annotation class, we will attempt to get a reusable
       identifier for the pin we are about to create */
    NSString *pinReusableIdentifier =
    [MyAnnotation
     reusableIdentifierforPinColor:senderAnnotation.pinColor];

    /* Using the identifier we retrieved above, we will
       attempt to reuse a pin in the sender Map View */
    MKPinAnnotationView *annotationView = (MKPinAnnotationView *)
    [mapView
     dequeueReusableAnnotationViewWithIdentifier:
     pinReusableIdentifier];

    if (annotationView == nil){
        /* If we fail to reuse a pin, then we will create one */
        annotationView =
        [[MKPinAnnotationView alloc] initWithAnnotation:senderAnnotation
                                         reuseIdentifier:pinReusableIdentifier];

        /* Make sure we can see the callouts on top of
           each pin in case we have assigned title and/or
           subtitle to each pin */
        annotationView.canShowCallout = YES;
    }

    /* Now make sure, whether we have reused a pin or not, that
       the color of the pin matches the color of the annotation */
    annotationView.pinColor = senderAnnotation.pinColor;
```



```

    UIImage *pinImage = [UIImage imageNamed:@"BluePin.png"];
    if (pinImage != nil){
        annotationView.image = pinImage;
    }

    result = annotationView;

    return result;
}

```

In this code, we are displaying an image named *BluePin.png* (in our application bundle) for any pin that is dropped on the map. For the definition and the implementation of the `MyAnnotation` class, refer to [Recipe 6.5](#).

Discussion

The delegate object of an instance of the `MKMapView` class must conform to the `MKMapViewDelegate` protocol and implement the `mapView:viewForAnnotation:` method. The return value of this method is an instance of the `MKAnnotationView` class. Any object that subclasses the aforementioned class, by default, inherits a property called `image`. Assigning a value to this property will replace the default image provided by the Map Kit framework, as shown in [Figure 6-6](#).




Figure 6-6. A custom image displayed on a map view

6.7 Converting Longitude and Latitude to a Meaningful Address

Problem

You have the latitude and longitude of a spatial location and you want to retrieve the address of this location.

Solution

The process of retrieving a meaningful address using spatial coordinates, x and y , is called *reverse geocoding*. Create and use an instance of the `CLGeocoder` class and provide a completion block object, making sure that the block object has no return value and accepts two parameters:

1. A placemarks array (of type `NSArray`) which will be set to the locations which matched your search.
2. An error (of type `NSError`) which will get set to a valid error if the reverse geocoding fails.

After instantiating an object of type `CLGeocoder`, we will use its `reverseGeocodeLocation:completionHandler:` method in order to do the reverse geocoding.

The `.h` file of a simple view controller for this purpose is defined like so:

```
#import <UIKit/UIKit.h>
#import <CoreLocation/CoreLocation.h>

@interface
    Converting_Longitude_and_Latitude_to_a_Meaningful_AddressViewController
    : UIViewController

@property (nonatomic, strong) CLGeocoder *myGeocoder;

@end
```

Then we will go ahead and synthesize our `myGeocoder` property:

```
@implementation
    Converting_Longitude_and_Latitude_to_a_Meaningful_AddressViewController

@synthesize myGeocoder;

...
```

The next thing we will do is to do the reverse geocoding when our view loads:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    CLLocation *location = [[CLLocation alloc]
        initWithLatitude:+38.4112810
        longitude:-122.8409780f];

    self.myGeocoder = [[CLGeocoder alloc] init];

    [self.myGeocoder
        reverseGeocodeLocation:location
        completionHandler:^(NSArray *placemarks, NSError *error) {

        if (error == nil &&
            [placemarks count] > 0){
```

```

        CLPlacemark *placemark = [placemarks objectAtIndex:0];
        /* We received the results */
        NSLog(@"Country = %@", placemark.country);
        NSLog(@"Postal Code = %@", placemark.postalCode);
        NSLog(@"Locality = %@", placemark.locality);
    }
    else if (error == nil &&
             [placemarks count] == 0){
        NSLog(@"No results were returned.");
    }
    else if (error != nil){
        NSLog(@"An error occurred = %@", error);
    }
}

});
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.myGeocoder = nil;
}

```

You can see that the `placemarks` parameter is an array. This array, if the operation is successful, will contain objects of type `CLPlacemark` which mark the addresses that match the longitude and latitude we passed to the `reverseGeocodeLocation:completionHandler:` method. So all we have to do is to make sure that that no error happened and also we need to make sure that the array of placemarks contains at least one placemark.

The `NSLog` methods in the preceding code will write the reverse geocoded address to the console window:

```

Country = United States
Postal Code = 95472
Locality = Sebastopol

```

Discussion

Each application has a limit on the amount of reverse geocoding requests that it can make every day. To perform a reverse geocoding request, you must create an instance of the `CLGeocoder` class. This class requires an active network connection in order to process requests successfully. The reverse geocoded values are reported to the completion handler block that is passed to the `reverseGeocodeLocation:completionHandler:` method.

See Also

XXX

6.8 Converting Meaningful Addresses to Longitude and Latitude

Problem

You have an address of a location and you want to find the spatial location (*longitude*, *latitude*) of that address.

Solution

Use the `geocodeAddressString:completionHandler:` method of the `CLGeocoder` class.

Discussion

Reverse geocoding is the process of retrieving a meaningful address, city and country, and so on, using spatial locations (*Longitude*, *Latitude*). *Geocoding*, on the other hand, is the process of finding the spatial locations of a given address. Both geocoding and reverse geocoding facilities are encapsulated into the `CLGeocoder` class in the CoreLocation framework.

We geocode spatial locations by passing the address as `NSString` to the `geocodeAddressString:completionHandler:` method of the `CLGeocoder` class. The `completionHandler` parameter of this method accepts a block object that returns no value and has two parameters:

1. A placemarks array (of type `NSArray`) which will be set to the locations which matched your search.
2. An error (of type `NSError`) which will get set to a valid error if the geocoding fails.

Let's go ahead and declare a property of type `CLGeocoder` first:

```
#import <UIKit/UIKit.h>
#import <CoreLocation/CoreLocation.h>

@interface
    Converting_Meaningful_Addresses_to_Longitude_and_LatitudeViewController
    : UIViewController

@property (nonatomic, strong) CLGeocoder *myGeocoder;

@end
```

Then we need to synthesize this property:

```
@implementation
    Converting_Meaningful_Addresses_to_Longitude_and_LatitudeViewController

@synthesize myGeocoder;

...
```

And now we will go ahead and implement our code to geocode an address:

```
- (void)didReceiveMemoryWarning{
    [super didReceiveMemoryWarning];
    // Release any cached data, images, etc that aren't in use.
}

- (void)viewDidLoad{
    [super viewDidLoad];

    /* We have our address */
    NSString *oreillyAddress =
        @"1005 Gravenstein Highway North, Sebastopol, CA 95472, USA";

    self.myGeocoder = [[CLGeocoder alloc] init];

    [self.myGeocoder
     geocodeAddressString:oreillyAddress
     completionHandler:^(NSArray *placemarks, NSError *error) {

        if ([placemarks count] > 0 &&
            error == nil){
            NSLog(@"Found %lu placemark(s).", (unsigned long)[placemarks count]);
            CLPlacemark *firstPlacemark = [placemarks objectAtIndex:0];
            NSLog(@"Longitude = %f", firstPlacemark.location.coordinate.longitude);
            NSLog(@"Latitude = %f", firstPlacemark.location.coordinate.latitude);
        }
        else if ([placemarks count] == 0 &&
                 error == nil){
            NSLog(@"Found no placemarks.");
        }
        else if (error != nil){
            NSLog(@"An error occurred = %@", error);
        }

    }];
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.myGeocoder = nil;
}
```

Once the program is run, even in the simulator, you will get the following values printed to the console window if you have a working and active network connection:

```
Found 1 placemark(s).
Longitude = -122.841135
Latitude = 38.410373
```

See Also

XXX

Implementing Gesture Recognizers

7.0 Introduction

Gestures are combination of touch events. An example of gestures is in the default iOS Photo application that allows the user to zoom into and out of a photo using two fingers while “pinching” the photo in and out. Some of the most common gesture event detection code is encapsulated into reusable classes built into the iOS SDK. These classes can be used to detect swipe, pinch, pan, tap, drag, long press, and rotation gestures.

Gesture recognizers must be added to instances of the `UIView` class. A single view can have more than one gesture recognizer. Once a view catches the gesture, that view will be responsible for passing down the same gesture to other views in the hierarchy if needed.

Some touch events required by an application might be complicated to process and might require the same event to be detectable in other views in the same application. This introduces the requirements for reusable gesture recognizers. There are six gesture recognizers in iOS SDK 5:

- Swipe
- Rotation
- Pinch
- Pan
- Long press
- Tap

The basic framework for handling a gesture through a built-in gesture recognizer is as follows:

1. Create an object of the right data type for the gesture recognizer you want.
2. Add this object as a gesture recognizer to the view that will receive the gesture.

3. Write a method that is called when the gesture occurs and that takes the action you want.

The method associated as the target method of any gesture recognizer must follow these rules:

- It must return `void`.
- It must either accept no parameters, or accept a single parameter of type `UIGestureRecognizer` in which the system will pass the gesture recognizer that calls this method.

Here are two examples:

```
- (void) tapRecognizer:(UITapGestureRecognizer *)paramSender{
    /* */
}

- (void) tapRecognizer{
    /* */
}
```

Gesture recognizers are divided into two categories: *discrete* and *continuous*. Discrete gesture recognizers detect their gesture events and, once detected, call a method in their respective owners. Continuous gesture recognizers keep their owner objects informed of the events as they happen, and will call the method in their target object repeatedly as the event happens and until it ends.

For instance, a double-tap event is discrete. Even though it consists of two taps, the system recognizes that the taps occurred close enough together to be treated as a single event. The double-tap gesture recognizer calls the method in its target object once the double-tap event is detected.

An example of a continuous gesture recognizer is rotation. This gesture starts as soon as the user starts the rotation and only finishes when the user lifts his fingers off the screen. The method provided to the rotation gesture recognizer class gets called at short intervals until the event is finished.

Gesture recognizers can be added to any instance of the `UIView` class using the `addGestureRecognizer:` method of the view, and when needed, they can be removed from the view using the `removeGestureRecognizer:` method.

The `UIGestureRecognizer` class has a property named `state`. The `state` property represents the different states the gesture recognizer can have throughout the recognition process. Discrete and continuous gesture recognizers go through different sets of states.

Discrete gesture recognizers can pass through the following states:

1. `UIGestureRecognizerStatePossible`
2. `UIGestureRecognizerStateRecognized`
3. `UIGestureRecognizerStateFailed`

Depending on the situation, a discrete gesture recognizer might send the `UIGestureRecognizerStateRecognized` state to its target, or it might send the `UIGestureRecognizerStateFailed` state if an error occurs during the recognition process.

Continuous gesture recognizers take a different path in the states they send to their targets:

1. `UIGestureRecognizerStatePossible`
2. `UIGestureRecognizerStateBegan`
3. `UIGestureRecognizerStateChanged`
4. `UIGestureRecognizerStateEnded`
5. `UIGestureRecognizerStateFailed`

Again, if the continuous gesture recognizer stumbles upon a situation that cannot be fixed internally, it will end with the `UIGestureRecognizerStateFailed` state instead of `UIGestureRecognizerStateEnded`.

7.1 Detecting Swipe Gestures

Problem

You want to be able to detect when the user performs a swipe gesture on a view, for instance, swiping a picture out of the window.

Solution

Instantiate an object of type `UISwipeGestureRecognizer` and add it to an instance of `UIView`:

```
- (void)viewDidLoad {
    [super viewDidLoad];

    /* Instantiate our object */
    self.swipeGestureRecognizer = [[UISwipeGestureRecognizer alloc]
                                    initWithTarget:self
                                    action:@selector(handleSwipes:)];

    /* Swipes that are performed from right to
       left are to be detected */
    self.swipeGestureRecognizer.direction =
        UISwipeGestureRecognizerDirectionLeft;

    /* Just one finger needed */
    self.swipeGestureRecognizer.numberOfTouchesRequired = 1;

    /* Add it to the view */
    [self.view addGestureRecognizer:self.swipeGestureRecognizer];
}
```

```

- (void) viewDidLoad{
    [super viewDidLoad];
    self.swipeGestureRecognizer = nil;
}

```

A gesture recognizer could be created as a standalone object, but here, because we are using it just for one view, we have created it as a property of the view controller that will receive the gesture (`self.swipeGestureRecognizer`). This recipe's [Discussion](#) shows the `handleSwipes:` method used in this code as the target for the swipe gesture recognizer.

Discussion

The swipe gesture is one of the most straightforward gestures that can be recognized using built-in iOS SDK gesture recognizers. It is a simple movement of one or more fingers on a view from one direction to another. The `UISwipeGestureRecognizer`, like other gesture recognizers, inherits from the `UIGestureRecognizer` class and adds various functionalities to this class, such as properties that allow us to specify the direction in which the swipe gestures have to be performed in order to be detected, or how many fingers the user has to hold on the screen to be able to perform a swipe gesture. Please bear in mind that swipe gestures are discrete gestures.

The `handleSwipes:` method that we used for our gesture recognizer instance can be implemented in this way:

```

- (void) handleSwipes:(UISwipeGestureRecognizer *)paramSender{

    if (paramSender.direction & UISwipeGestureRecognizerDirectionDown){
        NSLog(@"Swiped Down.");
    }
    if (paramSender.direction & UISwipeGestureRecognizerDirectionLeft){
        NSLog(@"Swiped Left.");
    }
    if (paramSender.direction & UISwipeGestureRecognizerDirectionRight){
        NSLog(@"Swiped Right.");
    }
    if (paramSender.direction & UISwipeGestureRecognizerDirectionUp){
        NSLog(@"Swiped Up.");
    }
}

```



You can combine more than one direction in the `direction` property of an instance of the `UISwipeGestureRecognizer` class by using the bitwise OR operand. In Objective-C, this is done with the pipe (`|`) character. For instance, to detect diagonal swipes to the bottom left of the screen you can combine the `UISwipeGestureRecognizerDirectionLeft` and `UISwipeGestureRecognizerDirectionDown` values using the pipe character when constructing your swipe gesture recognizer. In our example, we are attempting to detect only swipes from the right side to the left.

Although swipe gestures are usually performed with one finger, the number of fingers required for the swipe gesture to be recognized can also be specified using the `numberOfTouchesRequired` property of the `UISwipeGestureRecognizer` class.

7.2 Detecting Rotation Gestures

Problem

You want to detect when a user is attempting to rotate an element on the screen using her fingers.

Solution

Create an instance of the `UIRotationGestureRecognizer` class and attach it to your target view:

```
- (void)viewDidLoad {
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.helloWorldLabel = [[UILabel alloc] initWithFrame:CGRectMake(0, 0, 300, 100)];
    self.helloWorldLabel.text = @"Hello, World!";
    self.helloWorldLabel.font = [UIFont systemFontOfSize:16.0f];
    [self.helloWorldLabel sizeToFit];
    self.helloWorldLabel.center = self.view.center;
    [self.view addSubview:self.helloWorldLabel];

    self.rotationGestureRecognizer = [[UIRotationGestureRecognizer alloc]
                                      initWithTarget:self
                                      action:@selector(handleRotations:)];

    [self.view addGestureRecognizer:self.rotationGestureRecognizer];
}

- (void) viewDidLoad{
    [super viewDidLoad];
    self.helloWorldLabel = nil;
}
```

```

        self.rotationGestureRecognizer = nil;
    }

```

Discussion

The `UIRotationGestureRecognizer`, as its name implies, is the perfect candidate among gesture recognizers to detect rotation gestures and to help you build more intuitive graphical user interfaces. For instance, when the user encounters an image on the screen in your application in full-screen mode, it is quite intuitive for her to attempt to correct the orientation by rotating the image.

The `UIRotationGestureRecognizer` class implements a property named `rotation` that specifies the total amount and direction of rotation requested by the user's gesture, in radians. The rotation is determined from the fingers' initial position (`UIGestureRecognizerStateBegan`) and final position (`UIGestureRecognizerStateEnded`).

To rotate UI elements that inherit from `UIView` class, you can pass the `rotation` property of the rotation gesture recognizer to the `CGAffineTransformMakeRotation` function to make an affine transform, as shown in the example.

The code in this recipe's [Solution](#) passes the current object, in this case a view controller, to the target of the rotation gesture recognizer. The target selector is specified as `handleRotations:`, a method we have to implement. But before we do that, let's have a look at the header file of our view controller:

```

#import <UIKit/UIKit.h>

@interface Detecting_Rotation_GesturesViewController : UIViewController

@property (nonatomic, strong)
    UIRotationGestureRecognizer *rotationGestureRecognizer;

@property (nonatomic, strong)
    UILabel *helloWorldLabel;

@property (nonatomic, unsafe_unretained)
    CGFloat rotationAngleInRadians;

@end

```

Before we carry on, let's have a look at what each one of these properties does and why they are declared:

helloWorldLabel

This is a label that we must create on the view of our view controller. Then we will write the code that will rotate this label whenever the user attempts to perform rotation gestures on the view that owns this label, in this case the view of the view controller.

`rotationGestureRecognizer`

This is the instance of the rotation gesture recognizer that we will later allocate and initialize.

`rotationAngleInRadians`

This is the value we will query as the exact rotation angle of our label. Initially we will set this to zero. Since the rotation angles reported by a rotation gesture recognizer are reset every time the rotation gesture is started again, we can keep the value of the rotation gesture recognizer whenever it goes into the `UIGestureRecognizerStateEnded` state. The next time the gesture is started, we will add the previous value to the new value to get an overall rotation angle.

does not matter much. Even the position of the label isn't that important, as we will only attempt to rotate the label around its center, no matter where on our view the label is positioned. The only important thing to remember is that in universal applications, the position of a label on a view controller used in different targets (devices) must be calculated dynamically using the size of its parent view. Otherwise, on different devices such as the iPad or the iPhone, it might appear in different places on the screen.

Using the `center` property of our label, and setting that center location to the center of the containing view, we will center-align the contents of our label. The rotation transformation that we will apply to this label rotates the label around its center, and left-aligned or right-aligned labels whose actual frame is bigger than the minimum frame that is required to hold their contents without truncation will appear to be rotating in an unnatural way and not on the center. If you are curious, just go ahead and left- or right-align the contents of the label and see what happens.

Now let's go and synthesize our properties:

```
#import "Detecting_Rotation_GesturesViewController.h"

@implementation Detecting_Rotation_GesturesViewController

@synthesize rotationGestureRecognizer;
@synthesize helloWorldLabel;
@synthesize rotationAngleInRadians;

...
```

As we saw in this recipe's [Solution](#), the rotation gesture recognizer that we created will send its events to a method called `handleRotations:`. Here is the implementation for this method:

```
- (void) handleRotations:(UIRotationGestureRecognizer *)paramSender{

    if (self.helloWorldLabel == nil){
        return;
    }

    /* Take the previous rotation and add the current rotation to it */
    self.helloWorldLabel.transform =
```

```
CGAffineTransformMakeRotation(self.rotationAngleInRadians +
                              paramSender.rotation);

/* At the end of the rotation, keep the angle for later use */
if (paramSender.state == UIGestureRecognizerStateEnded){
    self.rotationAngleInRadians += paramSender.rotation;
}

}
```

The way a rotation gesture recognizer sends us the rotation angles is very interesting. This gesture recognizer is continuous, which means it starts finding the angles as soon as the user begins her rotation gesture, and sends updates to the handler method at frequent intervals until the user finishes the gesture. Each message treats the starting angle as zero and reports the difference between the messages' starting point (which is the angle where the previous message left off) and its ending point. Thus, the complete effect of the gesture can be discovered only by summing the angles reported by the different events. Clockwise movement produces a positive angular value, whereas counterclockwise movement produces a negative value.



If you are using iPhone Simulator instead of a real device, you can still simulate the rotation gesture by holding down the Option key in the simulator. You will see two circles appearing on the simulator at the same distance from the center of the screen, representing two fingers. If you want to shift these fingers from the center to another location while holding down the Alt key, press the Shift key and point to somewhere else on the screen. Where you leave off your pointer will become the new center for these two fingers.

Now we will simply assign this angle to the rotation angle of our label. But can you imagine what will happen once the rotation is finished and another one starts? The second rotation gesture's angle will replace that of the first rotation in the `rotation` value reported to our handler. For this reason, whenever a rotation gesture is finished, we must keep the current rotation of our label. The value in each rotation gesture's angle must be added in turn, and we must assign the result to the label's rotation transformation as we saw before.

As we saw earlier, we used the `CGAffineTransformMakeRotation` function to create an affine transformation. Functions in the iOS SDK that start with "CG" refer to the Core Graphics framework. For programs that use Core Graphics to compile and link successfully, you must make sure the Core Graphics framework is added to the list of frameworks. New versions of Xcode link a default project against the CoreGraphics framework by default so you don't really have to worry about that.

Now that we are sure Core Graphics is added to our target, we can compile and run our app.

See Also

[Recipe 7.6](#)

7.3 Detecting Panning and Dragging Gestures

Problem

You want the users of your application to be able to move GUI elements around using their fingers.

Solution

Use the `UIPanGestureRecognizer` class:

```
- (void)viewDidLoad {
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    /* Let's first create a label */
    CGRect labelFrame = CGRectMake(0.0f,      /* X */
                                   0.0f,      /* Y */
                                   150.0f,    /* Width */
                                   100.0f); /* Height */

    self.helloWorldLabel = [[UILabel alloc] initWithFrame:labelFrame];
    self.helloWorldLabel.text = @"Hello World";
    self.helloWorldLabel.backgroundColor = [UIColor blackColor];
    self.helloWorldLabel.textColor = [UIColor whiteColor];
    self.helloWorldLabel.textAlignment = NSTextAlignmentCenter;

    /* Make sure to enable user interaction; otherwise, tap events
       won't be caught on this label */
    self.helloWorldLabel.userInteractionEnabled = YES;

    /* And now make sure this label gets displayed on our view */
    [self.view addSubview:self.helloWorldLabel];

    /* Create the Pan Gesture Recognizer */
    self.panGestureRecognizer = [[UIPanGestureRecognizer alloc]
                                  initWithTarget:self
                                  action:@selector(handlePanGestures:)];

    /* At least and at most we need only one finger to activate
       the pan gesture recognizer */
    self.panGestureRecognizer.minimumNumberOfTouches = 1;
    self.panGestureRecognizer.maximumNumberOfTouches = 1;

    /* Add it to our view */
    [self.helloWorldLabel addGestureRecognizer:self.panGestureRecognizer];
}
```

```

- (void) viewDidLoad{
    [super viewDidLoad];
    self.panGestureRecognizer = nil;
    self.helloWorldLabel = nil;
}

```

The pan gesture recognizer will call the `handlePanGestures:` method as its target method. This method is described in this recipe's [Discussion](#).

Discussion

The `UIPanGestureRecognizer`, as its name implies, can detect *pan gestures*. Pan gestures are continuous movements of fingers on the screen; recall that swipe gestures were discrete gestures. This means the method set as the target method of a pan gesture recognizer gets called repeatedly from the beginning to the end of the recognition process. The pan gesture recognizer will go through the following states while recognizing the pan gesture:

1. `UIGestureRecognizerStateBegan`
2. `UIGestureRecognizerStateChanged`
3. `UIGestureRecognizerStateEnded`

We can implement our gesture recognizer target method as follows. The code will move the center of the label along with the user's finger continuously as `UIGestureRecognizerStateChanged` events are reported.

```

- (void) handlePanGestures:(UIPanGestureRecognizer*)paramSender{
    if (paramSender.state != UIGestureRecognizerStateEnded &&
        paramSender.state != UIGestureRecognizerStateFailed){
        CGPoint location = [paramSender locationInView:paramSender.view.superview];
        paramSender.view.center = location;
    }
}

```



To be able to move the label on the view of our view controller, we need the position of the finger on the view, not the label. For this reason, we are calling the `locationInView:` method of the pan gesture recognizer and passing the superview of our label as the target view.

Use the `locationInView:` method of the pan gesture recognizer to find the point of the current panning finger(s). To detect the location of multiple fingers, use the `locationOfTouch:inView:` method. Using the `minimumNumberOfTouches` and `maximumNumberOfTouches` properties of the `UIPanGestureRecognizer`, you can detect more than one panning touch at a time. In our example, for the sake of simplicity, we are trying to detect only one finger.



During the `UIGestureRecognizerStateEnded` state, the reported x and y values might not be a number; in other words, they could be equal to `NAN`. That is why we need to avoid using the reported values during this particular state.

7.4 Detecting Long Press Gestures

Problem

You want to be able to detect when the user taps and holds his finger on a view for a certain period of time.

Solution

Create an instance of the `UILongPressGestureRecognizer` class and add it to the view that has to detect long tap gestures. The `.h` file of our view controller is defined in this way:

```
#import <UIKit/UIKit.h>

@interface Detecting_Long_Press_GesturesViewController : UIViewController

@property (nonatomic, strong)
    UILongPressGestureRecognizer *longPressGestureRecognizer;

@property (nonatomic, strong) UIButton *dummyButton;

@end
```

Here is the `viewDidLoad` instance method of our view controller that uses the long press gesture recognizer that we defined in the `.m` file:

```
- (void)viewDidLoad {
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.dummyButton = [UIButton buttonWithType:UIButtonTypeRoundedRect];
    self.dummyButton.frame = CGRectMake(0.0f,
                                         0.0f,
                                         72.0f,
                                         37.0f);
    self.dummyButton.center = self.view.center;
    [self.view addSubview:self.dummyButton];

    /* First create the gesture recognizer */
    self.longPressGestureRecognizer =
    [[UILongPressGestureRecognizer alloc]
     initWithTarget:self
     action:@selector(handleLongPressGestures:)];
```

```

/* The number of fingers that must be present on the screen */
self.longPressGestureRecognizer.numberOfTouchesRequired = 2;

/* Maximum 100 pixels of movement allowed before the gesture
is recognized */
self.longPressGestureRecognizer.allowableMovement = 100.0f;

/* The user must press 2 fingers (numberOfTouchesRequired) for
at least 1 second for the gesture to be recognized */
self.longPressGestureRecognizer.minimumPressDuration = 1.0;

/* Add this gesture recognizer to our view */
[self.view addGestureRecognizer:self.longPressGestureRecognizer];
}

- (void) viewDidLoad{
    [super viewDidLoad];
    self.longPressGestureRecognizer = nil;
    self.dummyButton = nil;
}

```



Our code runs on a view controller with a property named `longPressGestureRecognizer` of type `UILongPressGestureRecognizer`. For more information, refer to this recipe's [Discussion](#).

Discussion

The iOS SDK comes with a long tap gesture recognizer class named `UILongTapGestureRecognizer`. A long tap gesture is triggered when the user presses one or more fingers (configurable by the programmer) on a `UIView` and holds the finger(s) for a specific amount of time. Furthermore, you can narrow the detection of gestures down to only those long tap gestures that are performed after a certain number of fingers are tapped on a view for a certain number of times and are then kept on the view for a specified number of seconds. Bear in mind that long taps are continuous events.

Four important properties can change the way the long tap gesture recognizer performs. These are:

`numberOfTapsRequired`

This is the number of taps the user has to perform on the target view, before the gesture can be triggered. Bear in mind that a tap is *not* a mere finger positioned on a screen. A tap is the movement of putting a finger down on the screen and lifting the finger off. The default value of this property is 0.

`numberOfTouchesRequired`

This property specifies the number of fingers that are required to be touching the screen before the gesture can be recognized. You must specify the same number of

fingers to detect the taps, if the `numberOfTapsRequired` property is set to a value larger than 0.

`allowableMovement`

This is the maximum number of pixels that the fingers on the screen can be moved before the gesture recognition is aborted.

`minimumPressDuration`

This property dictates how long, measured in seconds, the user must press her finger(s) on the screen before the gesture event can be detected.

In our example, these properties are set as follows:

- `numberOfTapsRequired`: default (we are not changing this value)
- `numberOfTouchesRequired`: 2
- `allowableMovement`: 100
- `minimumPressDuration`: 1

With these values, the long tap gesture will be recognized only if the user presses on the screen and holds both fingers for one second (`minimumPressDuration`) without moving her fingers more than 100 pixels around (`allowableMovement`).

Now when the gesture is recognized, it will call our `handleLongPressGestures:` method, which we can implement in this way:

```
- (void) handleLongPressGestures:(UILongPressGestureRecognizer *)paramSender{

    /* Here we want to find the mid point of the two fingers
    that caused the long press gesture to be recognized. We configured
    this number using the numberOfTouchesRequired property of the
    UILongPressGestureRecognizer that we instantiated in the
    viewDidLoad instance method of this View Controller. If we
    find that another long press gesture recognizer is using this
    method as its target, we will ignore it */

    if ([paramSender isEqual:self.longPressGestureRecognizer]){

        if (paramSender.numberOfTouchesRequired == 2){

            CGPoint touchPoint1 =
            [paramSender locationOfTouch:0
             inView:paramSender.view];

            CGPoint touchPoint2 =
            [paramSender locationOfTouch:1
             inView:paramSender.view];

            CGFloat midPointX = (touchPoint1.x + touchPoint2.x) / 2.0f;
            CGFloat midPointY = (touchPoint1.y + touchPoint2.y) / 2.0f;

            CGPoint midPoint = CGPointMake(midPointX, midPointY);

            self.dummyButton.center = midPoint;
```

```

    } else {
        /* This is a long press gesture recognizer with more
           or less than 2 fingers */
    }
}
}

```



One of the applications in iOS that uses long tap gesture recognizers is the Maps application. In this application, when you are looking at different locations, press your finger on a specific location and hold it for a while without lifting it off the screen. This will drop a pin on that specific location.

7.5 Detecting Tap Gestures

Problem

You want to be able to detect when users tap on a view.

Solution

Create an instance of the `UITapGestureRecognizer` class and add it to the target view, using the `addGestureRecognizer:` instance method of the `UIView` class. Let's have a look at the definition of our view controller (the `.h` file):

```

#import <UIKit/UIKit.h>

@interface Detecting_Tap_GesturesViewController : UIViewController

@property (nonatomic, strong)
    UITapGestureRecognizer *tapGestureRecognizer;

@end

```

The implementation of the `viewDidLoad` instance method of our view controller is as follows:

```

- (void)viewDidLoad {
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    /* Create the Tap Gesture Recognizer */
    self.tapGestureRecognizer = [[UITapGestureRecognizer alloc]
                                  initWithTarget:self
                                  action:@selector(handleTaps)];

    /* The number of fingers that must be on the screen */
}

```

```

self.tapGestureRecognizer.numberOfTouchesRequired = 2;

/* The total number of taps to be performed before the
gesture is recognized */
self.tapGestureRecognizer.numberOfTapsRequired = 3;

/* Add this gesture recognizer to our view */
[self.view addGestureRecognizer:self.tapGestureRecognizer];
}

- (void) viewDidLoad{
    [super viewDidLoad];
    self.tapGestureRecognizer = nil;
}

```

Discussion

The tap gesture recognizer is the best candidate among gesture recognizers to detect plain tap gestures. A tap event is the event triggered by the user touching and lifting his finger(s) off the screen. A tap gesture is a discrete gesture.

The `locationInView:` method of the `UITapGestureRecognizer` class can be used to detect the location of the tap event. If the tap gesture requires more than one touch, the `locationOfTouch:inView:` method of the `UITapGestureRecognizer` class can be called to determine individual touch points. In our code, we have set the `numberOfTouchesRequired` property of our tap gesture recognizer to 2. With this value set, our gesture recognizer will require two fingers to be on the screen on each tap event. The number of taps that are required for the gesture recognizer to recognize this gesture is set to 3 using the `numberOfTapsRequired` property. We have provided the `handleTaps:` method as the target method of our tap gesture recognizer:

```

- (void) handleTaps:(UITapGestureRecognizer*)paramSender{

    NSInteger touchCounter = 0;
    for (touchCounter = 0;
         touchCounter < paramSender.numberOfTouchesRequired;
         touchCounter++){
        CGPoint touchPoint =
            [paramSender locationOfTouch:touchCounter
                               inView:paramSender.view];
        NSLog(@"Touch #%lu: %@",
              (unsigned long)touchCounter+1,
              NSStringFromCGPoint(touchPoint));
    }
}

```

In this code, we are going through the number of touches that our tap gesture recognizer was asked to look for. Based on that number, we are finding the location of each tap. Depending on where you tap on the view on your simulator, you will get results similar to this in the console window:

Touch #1: {107, 186}
Touch #2: {213, 254}



If you are using the simulator, you can simulate two touches at the same time by holding down the Option key and moving your mouse on the simulator's screen. You will now have two concentric touch points on the screen.

One function that is worth noting is the `NSStringFromCGPoint` method, which, as its name implies, can convert a `CGPoint` structure to `NSString`. We use this function to convert the `CGPoint` of each touch on the screen to an `NSString` so that we can log it to the console window using `NSLog`. You can bring up the console window using `Run→Console`.

7.6 Detecting Pinch Gestures

Problem

You want your users to be able to perform a pinch gesture on a view.

Solution

Create an instance of the `UIPinchGestureRecognizer` class and add it to your target view, using the `addGestureRecognizer:` instance method of the `UIView` class:

```
- (void)viewDidLoad {
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    CGRect labelRect = CGRectMake(0.0f,      /* X */
                                  0.0f,      /* Y */
                                  200.0f,    /* Width */
                                  200.0f);   /* Height */

    self.myBlackLabel = [[UILabel alloc] initWithFrame:labelRect];
    self.myBlackLabel.center = self.view.center;
    self.myBlackLabel.backgroundColor = [UIColor blackColor];

    /* Without this line, our pinch gesture recognizer
       will not work */
    self.myBlackLabel.userInteractionEnabled = YES;
    [self.view addSubview:self.myBlackLabel];

    /* Create the Pinch Gesture Recognizer */
    self.pinchGestureRecognizer = [[UIPinchGestureRecognizer alloc]
                                    initWithTarget:self
                                    action:@selector(handlePinches:)];
```

```

/* Add this gesture recognizer to our view */
[self.myBlackLabel
 addGestureRecognizer:self.pinchGestureRecognizer];

}

- (void) viewDidLoad{
    [super viewDidLoad];
    self.myBlackLabel = nil;
    self.pinchGestureRecognizer = nil;
}

```

The *.h* file of our view controller is defined in this way:

```

#import <UIKit/UIKit.h>

@interface Detecting_Pinch_GesturesViewController : UIViewController

@property (nonatomic, strong)
    UIPinchGestureRecognizer *pinchGestureRecognizer;

@property (nonatomic, strong) UILabel *myBlackLabel;

@property (nonatomic, unsafe_unretained) CGFloat currentScale;

@end

```

Discussion

Pinching allows users to scale GUI elements up and down easily. For instance, the Safari web browser on iOS allows users to pinch on a web page in order to zoom into the contents being displayed. Pinching works in two ways: scaling up and scaling down. It is a continuous gesture that must always be performed using two fingers on the screen.

The state of this gesture recognizer changes in this order:

1. `UIGestureRecognizerStateBegan`
2. `UIGestureRecognizerStateChanged`
3. `UIGestureRecognizerStateEnded`

Once the pinch gesture is recognized, the action method in the target object will be called and will continue to be called until the pinch gesture is ended. Inside the action method you can access two very important properties of the pinch gesture recognizer: **scale** and **velocity**. **scale** is the factor by which you should scale the x- and y-axes of a GUI element to reflect the size of the user's gesture. **velocity** is the velocity of the pinch in pixels per second. The velocity is a negative value if the touch points are getting closer to each other and a positive value if they are getting farther away from each other.

The value of the **scale** property can be provided to the `CGAffineTransformMakeScale` Core Graphics function in order to retrieve an affine transformation. This affine transformation can be applied to the transform property of any instance of the `UIView` class in order to change its transformation. We are using this function in this way:

```

- (void) handlePinches:(UIPinchGestureRecognizer*)paramSender{

    if (paramSender.state == UIGestureRecognizerStateEnded){
        self.currentScale = paramSender.scale;
    } else if (paramSender.state == UIGestureRecognizerStateBegan &&
               self.currentScale != 0.0f){
        paramSender.scale = self.currentScale;
    }

    if (paramSender.scale != NAN &&
        paramSender.scale != 0.0){
        paramSender.view.transform =
            CGAffineTransformMakeScale(paramSender.scale,
                                       paramSender.scale);
    }
}

```

Since the `scale` property of a pinch gesture recognizer is reset every time a new pinch gesture is recognized, we are storing the last value of this property in an instance property of our view controller called `currentScale`. The next time a new gesture is recognized, we start the scale factor from the previously reported scale factor, as demonstrated in the code.

Networking, JSON, XML and Twitter

8.0 Introduction

iOS apps, when connected to the internet, become more lively. That is just a given! Let me give you an example. Let's imagine an app that brings high quality wallpapers to its users. The user can pick from a big list of wallpapers and then assign any of those images as her iOS background. Now compare this app with an app that does the same thing but adds to its list of wallpapers, every day or every week or month. The user comes back to the app and voila! Tens of new wallpapers are dynamically added to the app. That is the magic of web services, internet and some creativity on the app developer side and this can easily be achieved with basic knowledge of networking, XML, JSON and Twitter connectivity.

iOS SDK allows us to connect to the internet and retrieve and send data using the `NSURLConnection` class. Our JSON serialization and deserialization will all be done using the `NSJSONSerialization` class. XML parsing will be done using the `NSXMLParser` and the Twitter connectivity will be done using the Twitter framework.

8.1 Downloading Asynchronously with `NSURLConnection`

Problem

You want to download a file from a URL, asynchronously.

Solution

Use the `NSURLConnection` class with an asynchronous request.

Discussion

There are two ways of using the `NSURLConnection` class. One is asynchronous and the other is synchronous. Asynchronous connection will create a new thread and does its

downloading process on the new thread. Synchronous connection will block the *calling thread* while downloading content and doing its communication.

Many developers think that a synchronous connection blocks the *main thread* but that is incorrect. A synchronous connection will always block the thread from which it is fired. If you fire a synchronous connection from the main thread, yes, the main thread will be blocked. But if you fire a synchronous connection from a thread other than the main thread, it will be like an asynchronous connection, in that, it won't block your main thread. In fact, the only difference between a synchronous and an asynchronous connection is that the runtime will create a thread for the asynchronous connection while it won't do such thing for a synchronous connection.

In order to create an asynchronous connection, we need to:

1. Have our URL in an instance of `NSString`.
2. Convert our string to an instance of `NSURL`.
3. Place our URL in a URL Request of type `NSURLRequest`, or in case of mutable URLs, in an instance of `NSMutableURLRequest`.
4. Create an instance of `NSURLConnection` and pass the URL request to it.

We can create an asynchronous url connection using the `sendAsynchronousRequest:queue:completionHandler:` class method of `NSURLConnection`. The parameters to this method are:

`sendAsynchronousRequest`

A request of type `NSURLRequest`, as we already discussed.

`queue`

An operation queue. We can simply allocate and initialize a new operation queue and pass it to this method if we wish.

`completionHandler`

A block object to be executed when the asynchronous connection finishes its work either successfully or unsuccessfully. This block object should accept three parameters:

1. An object of type `NSURLResponse` which encapsulates the response that the server sent us, if any.
2. Data of type `NSData` if any. This data will be the data that the connection fetched from the URL.
3. Error of type `NSError` if an error occurs.



The `sendAsynchronousRequest:queue:completionHandler:` method doesn't get called on the main thread so make sure if you want to perform a UI related task, that you are back on the main thread.

Enough talk and let's have a look at an example. In this example, we will try to fetch the HTML contents of Apple's website's homepage and then print the contents as string to the console window:

```
/* 1 */
NSString *urlAsString = @"http://www.apple.com";
NSURL *url = [NSURL URLWithString:urlAsString];
NSURLRequest *urlRequest = [NSURLRequest requestWithURL:url];
NSOperationQueue *queue = [[NSOperationQueue alloc] init];

[NSURLConnection
 sendAsynchronousRequest:urlRequest
 queue:queue
 completionHandler:^(NSURLResponse *response,
                      NSData *data,
                      NSError *error) {

    if ([data length] >0 &&
        error == nil){
        NSString *html = [[NSString alloc] initWithData:data
                                                    encoding:NSUTF8StringEncoding];
        NSLog(@"HTML = %@", html);
    }
    else if ([data length] == 0 &&
             error == nil){
        NSLog(@"Nothing was downloaded.");
    }
    else if (error != nil){
        NSLog(@"Error happened = %@", error);
    }

}];
```

As simple as that. If you wanted to save the data that the connection downloaded for us to the disk, you could simply do so using the appropriate methods of the `NSData` that we get from the completion block:

```
NSString *urlAsString = @"http://www.apple.com";
NSURL *url = [NSURL URLWithString:urlAsString];
NSURLRequest *urlRequest = [NSURLRequest requestWithURL:url];
NSOperationQueue *queue = [[NSOperationQueue alloc] init];

[NSURLConnection
 sendAsynchronousRequest:urlRequest
 queue:queue
 completionHandler:^(NSURLResponse *response,
                      NSData *data,
                      NSError *error) {

    if ([data length] >0 &&
        error == nil){

        /* Get the documents directory */
        NSString *documentsDir =
            [NSSearchPathForDirectoriesInDomains(NSDocumentDirectory,
```

```

                                NSUserDomainMask,
                                YES) objectAtIndex:0];

    /* Append the file name to the documents directory */
    NSString *filePath = [documentsDir
                          stringByAppendingPathComponent:@"apple.html"];

    /* Write the data to the file */
    [data writeToFile:filePath
      atomically:YES];

    NSLog(@"Successfully saved the file to %@", filePath);

}
else if ([data length] == 0 &&
         error == nil){
    NSLog(@"Nothing was downloaded.");
}
else if (error != nil){
    NSLog(@"Error happened = %@", error);
}
}

}];

```

It's that simple really. In older versions of iOS SDK, url connections were using the delegation model but now it's all simply block based and you don't have to worry about implementing delegate methods anymore.

See Also

XXX

8.2 Handling Timeouts in Asynchronous Connections

Problem

You want to set a wait-limit on your asynchronous connection, a timeout, in other words.

Solution

Set the timeout on your URL request which you pass to the `NSURLConnection` class.

Discussion

When instantiating an object of type `NSURLRequest` to pass to your url connection, you can use its `requestWithURL:cachePolicy:timeoutInterval:` class method and pass the desired number of seconds of your timeout, to the `timeoutInterval` parameter.

For instance, if you want to wait a maximum of 30 seconds to download the contents of Apple's homepage using a synchronous connection, you would create your URL request like so:

```
NSString *urlAsString = @"http://www.apple.com";
NSURL *url = [NSURL URLWithString:urlAsString];

NSURLRequest *urlRequest =
[NSURLRequest
 requestWithURL:url
 cachePolicy:NSURLRequestReloadIgnoringLocalAndRemoteCacheData
 timeoutInterval:30.0f];

NSOperationQueue *queue = [[NSOperationQueue alloc] init];

[NSURLConnection
 sendAsynchronousRequest:urlRequest
 queue:queue
 completionHandler:^(NSURLResponse *response,
                      NSData *data,
                      NSError *error) {

    if ([data length] > 0 &&
        error == nil){
        NSString *html = [[NSString alloc] initWithData:data
                                                    encoding:NSUTF8StringEncoding];
        NSLog(@"HTML = %@", html);
    }
    else if ([data length] == 0 &&
             error == nil){
        NSLog(@"Nothing was downloaded.");
    }
    else if (error != nil){
        NSLog(@"Error happened = %@", error);
    }

}];
```

What will happen here is that the runtime will try to retrieve the contents of the provided URL. If this can be done before 30 seconds and the connection can and will be established before the timeout occurs, then fine. If not, the runtime will provide you with a timeout error in the error parameter of the completion block.

See Also

XXX

8.3 Downloading Synchronously with NSURLConnection

Problem

You want to download the contents of a URL, synchronously.

Solution

Use the `sendSynchronousRequest:returningResponse:error:` class method of `NSURLConnection`. The return value of this method is data of type `NSData`.

Discussion

Using the `sendSynchronousRequest:returningResponse:error:` class method of `NSURLConnection`, we can send a synchronous request to a URL. Now remember! Synchronous connection does *not* necessarily block the main thread. Synchronous connections block the *current thread* and if the current thread is the main thread, then the main thread will be blocked. If you go on a global concurrent queue with GCD and then initiate a synchronous connection, then you are *not* blocking the main thread.

Let's go ahead and initiate our first synchronous connection and see what happens. In this example, we will try to retrieve the home page of Yahoo!'s US website:

```
- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSLog(@"We are here...");

    NSString *urlAsString = @"http://www.yahoo.com";
    NSURL *url = [NSURL URLWithString:urlAsString];

    NSURLRequest *urlRequest = [NSURLRequest requestWithURL:url];

    NSURLResponse *response = nil;
    NSError *error = nil;

    NSLog(@"Firing synchronous url connection...");
    NSData *data = [NSURLConnection sendSynchronousRequest:urlRequest
                                   returningResponse:&response
                                   error:&error];

    if ([data length] > 0 &&
        error == nil){
        NSLog(@"%lu bytes of data was returned.", (unsigned long)[data length]);
    }
    else if ([data length] == 0 &&
             error == nil){
        NSLog(@"No data was returned.");
    }
    else if (error != nil){
        NSLog(@"Error happened = %@", error);
    }

    NSLog(@"We are done.");

    self.window = [[UIWindow alloc] initWithFrame:
                  [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
```

```

        [self.window makeKeyAndVisible];
        return YES;
    }

```

If you run this app and then look at the console window, you will see something similar to this printed out:

```

We are here...
Firing synchronous url connection...
194472 bytes of data was returned.
We are done.

```

So it's obvious that the current thread printed the string *We are here...* to the console window, waited for the connection to finish (as it was a synchronous connection which blocks the current thread), and then printed the *We are done.* text to the console window. Now let's do an experiment. Let's place the same exact synchronous connection inside a global concurrent queue in GCD, which guarantees concurrency, and see what happens:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSLog(@"We are here...");

    NSString *urlAsString = @"http://www.yahoo.com";

    NSLog(@"Firing synchronous url connection...");

    dispatch_queue_t dispatchQueue =
        dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

    dispatch_async(dispatchQueue, ^(void) {

        NSURL *url = [NSURL URLWithString:urlAsString];
        NSURLRequest *urlRequest = [NSURLRequest requestWithURL:url];
        NSURLResponse *response = nil;
        NSError *error = nil;

        NSData *data = [NSURLConnection sendSynchronousRequest:urlRequest
                                         returningResponse:&response
                                         error:&error];

        if ([data length] > 0 &&
            error == nil){
            NSLog(@"%lu bytes of data was returned.", (unsigned long)[data length]);
        }
        else if ([data length] == 0 &&
                 error == nil){
            NSLog(@"No data was returned.");
        }
        else if (error != nil){
            NSLog(@"Error happened = %@", error);
        }
    });
}

```

```

    NSLog(@"We are done.");

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

And the output will be similar to this:

```

We are here...
Firing synchronous url connection...
We are done.
194326 bytes of data was returned.

```

So in this example, the current thread carried on to print the *We are done.* text to the console window without having to wait for the synchronous connection to finish reading from its URL. That is interesting, isn't it? So this proves that a synchronous url connection won't necessarily block the main thread, if managed properly. Synchronous connections are guaranteed to block the *current thread* though.

See Also

XXX

8.4 Modifying a URL Request with NSMutableURLRequest

Problem

You want to be able to adjust various HTTP headers and settings of a URL request before passing it to a url connection.

Solution

Use NSMutableURLRequest instead of NSURLRequest.

Discussion

A URL request can be mutable and immutable. A mutable URL request is a URL request that can be changed after it has been allocated and initialized. An immutable URL request cannot be modified after it has been allocated and initialized. Mutable URL request is target of this recipe. You can create mutable URL requests using the NSMutableURLRequest class.

Let's have a look at an example where we will change the timeout interval of a URL request *after* we have allocated and initialized it:


```
NSString *urlAsString = @"http://www.apple.com";
NSURL *url = [NSURL URLWithString:urlAsString];
NSMutableURLRequest *urlRequest = [NSMutableURLRequest requestWithURL:url];
[urlRequest setTimeoutInterval:30.0f];
```

Now let's have a look at another example where we set the URL and the timeout of a URL request after it has been allocated and initialized:

```
NSString *urlAsString = @"http://www.apple.com";
NSURL *url = [NSURL URLWithString:urlAsString];
NSMutableURLRequest *urlRequest = [NSMutableURLRequest new];
[urlRequest setTimeoutInterval:30.0f];
[urlRequest setURL:url];
```

In other recipes in this chapter, we will have a look at some of the really neat tricks that we can perform using mutable URL requests. If not for these tricks, we would be better off just using immutable URL requests.

See Also

XXX

8.5 Sending HTTP GET Requests with NSURLConnection

Problem

You want to send a GET request over the HTTP protocol and perhaps want to also pass parameters along your request to the receiver.

Solution

Use query string parameters if the specifications of the URL you are retrieving tell you to do so.

Discussion

A GET request is a request to a web server to retrieve data. A GET request usually carries some parameters. Parameters in a GET request are sent in the query string (as part of the URL)

I have prepared a simple GET web service at the following address: <http://pixonity.com/get.php>

If you open this URL in your browser, you will see something similar to what is shown in [Figure 8-1](#):




Figure 8-1. The example GET web service opened in a web browser

So our web browser is able to open this URL just fine and you can see that the web service is able to detect query string parameters and GET parameters. Now if you go ahead and open the following URL (<http://pixolity.com/get.php?param1=First¶m2=Second>) in your browser, you will see results similar to that shown in Figure 8-2:




Figure 8-2. Query string parameters sent to the GET web service

Obviously, if you want to simulate sending query string parameters in a GET request to the same web service using `NSURLConnection`, you would do so by using a mutable URL request and explicitly specifying your HTTP method to GET using the `setHTTPMe`

thod: method of NSMutableURLRequest and put your parameters as part of the URL, like so:

```
/* URL = http://pixolity.com/get.php?param1=First&param2=Second */
NSString *urlAsString = @"http://pixolity.com/get.php";
urlAsString = [urlAsString stringByAppendingString:@"?param1=First"];
urlAsString = [urlAsString stringByAppendingString:@"&param2=Second"];

NSURL *url = [NSURL URLWithString:urlAsString];

NSMutableURLRequest *urlRequest = [NSMutableURLRequest requestWithURL:url];
[urlRequest setTimeoutInterval:30.0f];
[urlRequest setHTTPMethod:@"GET"];

NSOperationQueue *queue = [[NSOperationQueue alloc] init];

[NSURLConnection
 sendAsynchronousRequest:urlRequest
 queue:queue
 completionHandler:^(NSURLResponse *response,
                      NSData *data,
                      NSError *error) {

    if ([data length] > 0 &&
        error == nil){
        NSString *html = [[NSString alloc] initWithData:data
                                                encoding:NSUTF8StringEncoding];
        NSLog(@"HTML = %@", html);
    }
    else if ([data length] == 0 &&
             error == nil){
        NSLog(@"Nothing was downloaded.");
    }
    else if (error != nil){
        NSLog(@"Error happened = %@", error);
    }

}];
```

What gets printed to the console window now is the data that comes back from the web service:

```
TML =
<html>
  <head>
    <title>iOS 5 Programming Cookbook GET Example</title>
  </head>
  <body>

<b>HTTP Method</b> = GET<br/><br/><b>Query String</b> = Array
(
  [param1] => First
  [param2] => Second
)
```

```
</body>  
</html>
```

The only thing that you have to bear in mind is that the first parameter is prefixed with a question mark and any subsequent parameter is prefixed with an ampersand. That's really about it! Now you are using the HTTP GET method and you know how to send parameters as query string.

See Also

XXX

8.6 Sending HTTP POST Requests with `NSURLConnection`

Problem

You want to be able to call a web service using HTTP POST method and perhaps pass parameters as part of the HTTP body or in the query string, to the web service.

Solution

Just like the GET method, we can use the POST method using `NSURLConnection`. We must explicitly set our URL's method to POST.

Discussion

I have set up a dummy web service at the following address: <http://pixolity.com/post.php>. If you open this URL in your browser, you will see something similar to that shown in [Figure 8-3](#):




Figure 8-3. The POST web service opened in a web browser

This web service expects POST requests and is able to print out parameters which are sent as part of the query string and as part of the HTTP body so you can send both, if you want to. Let's write a simple app that can create an asynchronous connection and send a few parameters as query string and a few parameters in the HTTP body to the aforementioned URL:

```
NSString *urlAsString = @"http://pixolity.com/post.php";
urlAsString = [urlAsString stringByAppendingString:@"?param1=First"];
urlAsString = [urlAsString stringByAppendingString:@"&param2=Second"];

NSURL *url = [NSURL URLWithString:urlAsString];

NSMutableURLRequest *urlRequest = [NSMutableURLRequest requestWithURL:url];
[urlRequest setTimeoutInterval:30.0f];
[urlRequest setHTTPMethod:@"POST"];

NSString *body = @"bodyParam1=BodyValue1&bodyParam2=BodyValue2";
[urlRequest setHTTPBody:[body dataUsingEncoding:NSUTF8StringEncoding]];

NSOperationQueue *queue = [[NSOperationQueue alloc] init];

[NSURLConnection
 sendAsynchronousRequest:urlRequest
 queue:queue
 completionHandler:^(NSURLResponse *response,
                      NSData *data,
                      NSError *error) {
```

```

    if ([data length] > 0 &&
        error == nil){
        NSString *html = [[NSString alloc] initWithData:data
                                                            encoding:NSUTF8StringEncoding];
        NSLog(@"HTML = %@", html);
    }
    else if ([data length] == 0 &&
             error == nil){
        NSLog(@"Nothing was downloaded.");
    }
    else if (error != nil){
        NSLog(@"Error happened = %@", error);
    }
}

}];

```



The first parameter sent in the HTTP body does not have to be prefixed with an ampersand, unlike the first parameter in a query string.

And if you now look at the output printed to the console window, you will see something similar to this:

```

HTML =
<html>
  <head>
    <title>iOS 5 Programming Cookbook POST Example</title>
  </head>
  <body>

    <b>HTTP Method</b> = POST<br/><br/><b>Query String</b> = Array
    (
      [param1] => First
      [param2] => Second
    )
    <br/><br/><b>Body Parameters</b> = Array
    (
      [bodyParam1] => BodyValue1
      [bodyParam2] => BodyValue2
    )

  </body>
</html>

```

See Also

XXX

8.7 Sending HTTP DELETE Requests with NSURLConnection

Problem

You want to be able to call a web service using HTTP DELETE method to delete a resource from a URL, and perhaps you would like to pass parameters as part of the HTTP body or in the query string, to the web service.

Solution

Just like the GET and POST methods, we can use the DELETE method using NSURLConnection. We must explicitly set our URL's method to DELETE.

Discussion

I have set up a dummy web service at the following address: <http://pixolity.com/delete.php>. If you open this URL in your browser, you will see something similar to that shown in Figure 8-4:




Figure 8-4. The DELETE web service opened in a web browser

This web service expects DELETE requests and is able to print out parameters which are sent as part of the query string and as part of the HTTP body so you can send both, if you want to. Let's write a simple app that can create an asynchronous connection and send a few parameters as query string and a few parameters in the HTTP body to the aforementioned URL using the DELETE HTTP method:

```

NSString *urlAsString = @"http://pixolity.com/delete.php";
urlAsString = [urlAsString stringByAppendingString:@"?param1=First"];
urlAsString = [urlAsString stringByAppendingString:@"&param2=Second"];

NSURL *url = [NSURL URLWithString:urlAsString];

NSMutableURLRequest *urlRequest = [NSMutableURLRequest requestWithURL:url];
[urlRequest setTimeoutInterval:30.0f];
[urlRequest setHTTPMethod:@"DELETE"];

NSString *body = @"bodyParam1=BodyValue1&bodyParam2=BodyValue2";
[urlRequest setHTTPBody:[body dataUsingEncoding:NSUTF8StringEncoding]];

NSOperationQueue *queue = [[NSOperationQueue alloc] init];

[NSURLConnection
sendAsynchronousRequest:urlRequest
queue:queue
completionHandler:^(NSURLResponse *response,
                    NSData *data,
                    NSError *error) {

    if ([data length] > 0 &&
        error == nil){
        NSString *html = [[NSString alloc] initWithData:data
                                                    encoding:NSUTF8StringEncoding];
        NSLog(@"HTML = %@", html);
    }
    else if ([data length] == 0 &&
             error == nil){
        NSLog(@"Nothing was downloaded.");
    }
    else if (error != nil){
        NSLog(@"Error happened = %@", error);
    }
}];

```



The first parameter sent in the HTTP body does not have to be prefixed with an ampersand, unlike the first parameter in a query string.

And if you now look at the output printed to the console window, you will see something similar to this:

```

HTML =
<html>
  <head>
    <title>iOS 5 Programming Cookbook DELETE Example</title>
  </head>
  <body>

<b>HTTP Method</b> = DELETE<br/><br/><b>Query String</b> = Array

```



```

(
    [param1] => First
    [param2] => Second
)
<br/><br/><b>Body Parameters</b> = Array
(
    [bodyParam1] => BodyValue1
    [bodyParam2] => BodyValue2
)

</body>
</html>

```

See Also

XXX

8.8 Sending HTTP PUT Requests with NSURLConnection

Problem

You want to be able to call a web service using HTTP PUT method to place a resource into web server, and perhaps you would like to pass parameters as part of the HTTP body or in the query string, to the web service.

Solution

Just like the GET and POST and DELETE methods, we can use the PUT method using NSURLConnection. We must explicitly set our URL's method to PUT.

Discussion

I have set up a dummy web service at the following address: <http://pixolity.com/put.php>. If you open this URL in your browser, you will see something similar to that shown in [Figure 8-5](#):




Figure 8-5. The PUT web service opened in a web browser

This web service expects PUT requests and is able to print out parameters which are sent as part of the query string and as part of the HTTP body so you can send both, if you want to. Let's write a simple app that can create an asynchronous connection and send a few parameters as query string and a few parameters in the HTTP body to the aforementioned URL using the DELETE PUT method:

```
NSString *urlAsString = @"http://pixolity.com/put.php";
urlAsString = [urlAsString stringByAppendingString:@"?param1=First"];
urlAsString = [urlAsString stringByAppendingString:@"&param2=Second"];

NSURL *url = [NSURL URLWithString:urlAsString];

NSMutableURLRequest *urlRequest = [NSMutableURLRequest requestWithURL:url];
[urlRequest setTimeoutInterval:30.0f];
[urlRequest setHTTPMethod:@"PUT"];

NSString *body = @"bodyParam1=BodyValue1&bodyParam2=BodyValue2";
[urlRequest setHTTPBody:[body dataUsingEncoding:NSUTF8StringEncoding]];

NSOperationQueue *queue = [[NSOperationQueue alloc] init];

[NSURLConnection
 sendAsynchronousRequest:urlRequest
 queue:queue
 completionHandler:^(NSURLResponse *response,
                      NSData *data,
                      NSError *error) {
```

```

    if ([data length] > 0 &&
        error == nil){
        NSString *html = [[NSString alloc] initWithData:data
                                                            encoding:NSUTF8StringEncoding];
        NSLog(@"HTML = %@", html);
    }
    else if ([data length] == 0 &&
             error == nil){
        NSLog(@"Nothing was downloaded.");
    }
    else if (error != nil){
        NSLog(@"Error happened = %@", error);
    }
}

}];

```



The first parameter sent in the HTTP body does not have to be prefixed with an ampersand, unlike the first parameter in a query string.

And if you now look at the output printed to the console window, you will see something similar to this:

```

HTML =
<html>
  <head>
    <title>iOS 5 Programming Cookbook PUT Example</title>
  </head>
  <body>

    <b>HTTP Method</b> = PUT<br/><br/><b>Query String</b> = Array
    (
      [param1] => First
      [param2] => Second
    )
    <br/><br/><b>Body Parameters</b> = Array
    (
      [bodyParam1] => BodyValue1
      [bodyParam2] => BodyValue2
    )

  </body>
</html>

```

See Also

XXX

8.9 Serializing Arrays and Dictionaries into JSON

Problem

You want to serialize a dictionary or an array into a JSON object that you can transfer over the network or simply save to disk.

Solution

Use the `dataWithJSONObject:options:error:` method of the `NSJSONSerialization` class.

Discussion

The `dataWithJSONObject:options:error:` method of the `NSJSONSerialization` class can serialize dictionaries and arrays which contain only instances of `NSString`, `NSNumber`, `NSArray`, `NSDictionary` or `NSNull` for nil values. As mentioned, the object that you pass to this method should either be an array or a dictionary.

Now let's go ahead and create a simple dictionary with a few keys and values:

```
NSMutableDictionary *dictionary = [[NSMutableDictionary alloc] init];

[dictionary setValue:@"Anthony"
                 forKey:@"First Name"];

[dictionary setValue:@"Robbins"
                 forKey:@"Last Name"];

[dictionary setValue:[NSNumber numberWithInt:51]
                 forKey:@"Age"];

NSArray *arrayOfAnthonysChildren = [[NSArray alloc]
                                     initWithObjects:
                                     @"Anthony's Son 1",
                                     @"Anthony's Daughter 1",
                                     @"Anthony's Son 2",
                                     @"Anthony's Son 3",
                                     @"Anthony's Daughter 2",
                                     nil];

[dictionary setValue:arrayOfAnthonysChildren
                 forKey:@"children"];
```

As you can see, this dictionary contains the first name, last name and age of Anthony Robbins. A key in the dictionary named *children* contains the name of Anthony's children. This is an array of strings with each string representing one child. So by this time, the `dictionary` variable contains all the values that we want it to contain. It is now time to serialize it into a JSON object:

```
NSError *error = nil;
NSData *jsonData = [NSJSONSerialization
                   dataWithJSONObject:dictionary
```

```

        options:NSJSONWritingPrettyPrinted
        error:&error];

if ([jsonData length] > 0 &&
    error == nil){

    NSLog(@"Successfully serialized the dictionary into data = %@", jsonData);

}
else if ([jsonData length] == 0 &&
    error == nil){

    NSLog(@"No data was returned after serialization.");

}
else if (error != nil){

    NSLog(@"An error happened = %@", error);

}

```

The return value of the `dataWithJSONObject:options:error:` method is data of type `NSData`. However, you can simply turn this data into a string and print it to the console using the `initWithData:encoding:` initializer of `NSString`. Here is the complete example that serializes a dictionary into a JSON object and will then convert that object into a string and prints the string out to the console window:

```

NSMutableDictionary *dictionary = [[NSMutableDictionary alloc] init];

[dictionary setValue:@"Anthony"
    forKey:@"First Name"];

[dictionary setValue:@"Robbins"
    forKey:@"Last Name"];

[dictionary setValue:[NSNumber numberWithInt:51]
    forKey:@"Age"];

NSArray *arrayOfAnthonysChildren = [[NSArray alloc]
    initWithObjects:
        @"Anthony's Son 1",
        @"Anthony's Daughter 1",
        @"Anthony's Son 2",
        @"Anthony's Son 3",
        @"Anthony's Daughter 2",
        nil];

[dictionary setValue:arrayOfAnthonysChildren
    forKey:@"children"];

NSError *error = nil;
NSData *jsonData = [NSJSONSerialization
    dataWithJSONObject:dictionary
    options:NSJSONWritingPrettyPrinted
    error:&error];

```

```

if ([jsonData length] > 0 &&
    error == nil){

    NSLog(@"Successfully serialized the dictionary into data.");
    NSString *jsonString = [[NSString alloc] initWithData:jsonData
                                                    encoding:NSUTF8StringEncoding];

    NSLog(@"JSON String = %@", jsonString);

}
else if ([jsonData length] == 0 &&
    error == nil){

    NSLog(@"No data was returned after serialization.");

}
else if (error != nil){

    NSLog(@"An error happened = %@", error);

}

```

When you run this app, the following results will get printed to the console window:

```

Successfully serialized the dictionary into data.
JSON String = {
    "Last Name" : "Robbins",
    "First Name" : "Anthony",
    "children" : [
        "Anthony's Son 1",
        "Anthony's Daughter 1",
        "Anthony's Son 2",
        "Anthony's Son 3",
        "Anthony's Daughter 2"
    ],
    "Age" : 51
}

```

See Also

XXX

8.10 Deserializing JSON into Arrays and Dictionaries

Problem

You have JSON data and you want to deserialize it into a dictionary or an array.

Solution

Use the `JSONObjectWithData:options:error:` method of the `NSJSONSerialization` class.

Discussion

If you already have serialized your dictionary or array into a JSON object (encapsulated inside an instance of `NSData`, see [Recipe 8.9](#)), then you should be able to deserialize them back into a dictionary or an array, using the `JSONObjectWithData:options:error:` method of the `NSJSONSerialization` class. The object that is returned back by this method will either be a dictionary or an array, depending on the data that we pass to it. Here is an example:

```
/* Now try to deserialize the JSON object into a dictionary */
error = nil;
id jsonObject = [NSJSONSerialization
                 JSONObjectWithData:jsonData
                 options:NSJSONReadingAllowFragments
                 error:&error];

if (jsonObject != nil &&
    error == nil){

    NSLog(@"Successfully deserialized...");

    if ([jsonObject isKindOfClass:[NSDictionary class]]){

        NSDictionary *deserializedDictionary = (NSDictionary *)jsonObject;
        NSLog(@"Deserialized JSON Dictionary = %@", deserializedDictionary);

    }
    else if ([jsonObject isKindOfClass:[NSArray class]]){

        NSArray *deserializedArray = (NSArray *)jsonObject;
        NSLog(@"Deserialized JSON Array = %@", deserializedArray);

    }
    else {
        /* Some other object was returned. We don't know how to deal
        with this situation as the deserializer only returns dictionaries
        or arrays */
    }

}
else if (error != nil){
    NSLog(@"An error happened while deserializing the JSON data.");
}
```

If now we mix this code with the code from [Recipe 8.9](#), we can first serialize our dictionary into a JSON object and then deserialize that JSON object back into a dictionary and print out the results to make sure things went fine:

```
NSMutableDictionary *dictionary = [[NSMutableDictionary alloc] init];

[dictionary setValue:@"Anthony"
                  forKey:@"First Name"];

[dictionary setValue:@"Robbins"
```

```

        forKey:@"Last Name"];

[dictionary setValue:[NSNumber numberWithInt:51]
 forKey:@"Age"];

NSArray *arrayOfAnthonysChildren = [[NSArray alloc]
    initWithObjects:
        @"Anthony's Son 1",
        @"Anthony's Daughter 1",
        @"Anthony's Son 2",
        @"Anthony's Son 3",
        @"Anthony's Daughter 2",
        nil];

[dictionary setValue:arrayOfAnthonysChildren
 forKey:@"children"];

NSError *error = nil;
NSData *jsonData = [NSJSONSerialization
    dataWithJSONObject:dictionary
    options:NSJSONWritingPrettyPrinted
    error:&error];

if ([jsonData length] > 0 &&
    error == nil){

    NSLog(@"Successfully serialized the dictionary into data.");

    /* Now try to deserialize the JSON object into a dictionary */
    error = nil;
    id jsonObject = [NSJSONSerialization
        JSONObjectWithData:jsonData
        options:NSJSONReadingAllowFragments
        error:&error];

    if (jsonObject != nil &&
        error == nil){

        NSLog(@"Successfully deserialized...");

        if ([jsonObject isKindOfClass:[NSDictionary class]]){

            NSDictionary *deserializedDictionary = (NSDictionary *)jsonObject;
            NSLog(@"Dersialized JSON Dictionary = %@", deserializedDictionary);

        }
        else if ([jsonObject isKindOfClass:[NSArray class]]){

            NSArray *deserializedArray = (NSArray *)jsonObject;
            NSLog(@"Dersialized JSON Array = %@", deserializedArray);

        }
        else {
            /* Some other object was returned. We don't know how to deal
            with this situation as the deserializer only returns dictionaries

```



```

        or arrays */
    }

    }
    else if (error != nil){
        NSLog(@"An error happened while deserializing the JSON data.");
    }

    }
    else if ([jsonData length] == 0 &&
             error == nil){

        NSLog(@"No data was returned after serialization.");

    }
    else if (error != nil){

        NSLog(@"An error happened = %@", error);

    }
}

```

The `options` parameter of the `JSONObjectWithData:options:error:` method accepts one or a mixture of the following values:

`NSJSONReadingMutableContainers`

The dictionary or the array returned by the `JSONObjectWithData:options:error:` method will be mutable. In other words, this method will return either an instance of `NSMutableArray` or `NSMutableDictionary`, as opposed to immutable array or dictionary.

`NSJSONReadingMutableLeaves`

Leaf values will be encapsulated into instances of `NSMutableString`.

`NSJSONReadingAllowFragments`

This option will allow the deserialization of JSON data whose root top level object is not an array or a dictionary.

See Also

XXX

8.11 Integrating Twitter Functionality Into Your Apps

Problem

You want to integrate Twitter functionality into your iOS apps.

Solution

Use the Twitter framework.

Discussion

To be able to integrate Twitter functionality into our iOS apps, we need to use the Twitter framework but first, we need to add this framework to our app. Follow these steps to add the Twitter framework to your app:

1. Click on your project icon in Xcode.
2. Select the target to which you want to add the Twitter framework.
3. On the top, select Build Phases.
4. Expand the Link Binary with Libraries box to see all the frameworks that are currently linked to your target.
5. Click on the little + button at the bottom left corner of the Link Binary with Libraries box.
6. Select Twitter.framework from the list and then press the Add button.

Good! Now we have the Twitter framework linked to our app. The next thing that we need to do is to go ahead and import the appropriate header file into our view controller's header file:

```
#import <UIKit/UIKit.h>
#import <Twitter/Twitter.h>

@interface Integrating_Twitter_Functionality_Into_Your_AppsViewController
    : UIViewController

@end
```

The next step is to instantiate an object of type `TWTweetComposeViewController` which will take care of *Twitting* for us. This is just a view controller which you can display on top of your view controller. I have defined a property for our view controller for this:

```
#import <UIKit/UIKit.h>
#import <Twitter/Twitter.h>

@interface Integrating_Twitter_Functionality_Into_Your_AppsViewController
    : UIViewController

@property (nonatomic, strong) TWTweetComposeViewController *twitterController;

@end
```

Let's go ahead and synthesize our property:

```
#import "Integrating_Twitter_Functionality_Into_Your_AppsViewController.h"

@implementation
    Integrating_Twitter_Functionality_Into_Your_AppsViewController

@synthesize twitterController;

...
```

Then let's go ahead and in the `viewDidLoad` method of our view controller, initialize our Twitter composer controller. You can then use the `setInitialText:` method of `TWTweetComposeViewController` to set the text that will appear in the Twitter composer controller initially, before the user enters anything:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.twitterController = [[TWTweetComposeViewController alloc] init];
    [self.twitterController setInitialText:@"Your Tweet Goes Here"];
    [self.navigationController presentViewController:self.twitterController
                                             animated:YES];
}
```

Now if you open your app in the simulator, you will notice that the Twitter composer will get displayed for a second (see [Figure 8-6](#)) and then you will probably just see the Twitter credentials screen in the Settings app, as shown in [Figure 8-7](#).



Figure 8-6. Twitter composer shown as a modal controller



Figure 8-7. The Twitter login screen is displayed if the user has not yet logged into Twitter

The reason for the Twitter login screen being displayed is because the user has not yet logged into Twitter on that iOS device. Now go ahead and enter your Twitter credentials in the login screen (see [Figure 8-7](#)). Once you enter your credentials and press the Sign In button, you will be presented with a dialog asking you whether you want the Twitter app on your device or not. Press *Later*. We don't want to be bothered with installing that app at the moment; I've also noticed that trying to install the Twitter app on the simulator is problematic and you will get an icon on your simulator saying *Waiting* and the wait will never be over. So we are better off without the Twitter app on the simulator. On a real device though, this works just fine. [Figure 8-8](#):



Figure 8-8. Installing the Twitter app

After the user has entered her Twitter credentials, launching your app again will simply display the Twitter composer (see [Figure 8-6](#)).

Aside from the main text that you add to the composer controller, you can also add images using the `addImage:` method of the composer controller. Also you can attach a URL to your tweets using the `addURL:` method of the composer controller. Here is an example:

```
- (void)viewDidLoad{
    [super viewDidLoad];
```

```

self.twitterController = [[TWTweetComposeViewController alloc] init];

NSString *text =
@"Anthony Robbins at Unleash the Power Within (UPW) in London";

[self.twitterController setInitialText:text];

UIImage *anthonyRobbins = [UIImage imageNamed:@"Anthony Robbins.jpg"];
[self.twitterController addImage:anthonyRobbins];

NSURL *url = [NSURL URLWithString:@"http://www.tonyrobbins.com"];
[self.twitterController addURL:url];

[self.navigationController presentViewController:self.twitterController
                                           animated:YES];

}

```



The URL that you add to a Tweet will *not* be displayed as part of your Tweet in the Twitter controller although it will be sent as part of your Tweet to your Twitter timeline.

The results that your users will now see on their devices will be similar to that shown in [Figure 8-9](#):



Figure 8-9. A simple tweet with image and URL

The Twitter composer controller does *not* work with delegates. It works with completion handler blocks, as all modern components in the iOS SDK. So if you want to get updates from this controller after you have displayed it to the user, then add a completion handler block object to the composer, using its `setCompletionHandler:` method. This method requires a block object that should have not return value and must accept a parameter of type `TWTweetComposeViewControllerResult` that lists these values:

TWTweetComposeViewControllerResultCancelled

This is the result that gets sent to our completion block when the user cancels the Twitter composer controller. In this case, we must dismiss the Twitter composer controller.

TWTweetComposeViewControllerResultDone

This is the result that gets sent to our completion block when the Twitter composer controller has successfully sent the tweet onto the user's timeline. If you get this result, then you don't have to dismiss the controller as it gets dismissed in this state automatically.

And here is an example:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.twitterController = [[TWTweetComposeViewController alloc] init];

    __weak
    Integrating_Twitter_Functionality_Into_Your_AppsViewController
    *weakSelf = self;

    [self.twitterController setCompletionHandler:
    ^(TWTweetComposeViewControllerResult result){

        Integrating_Twitter_Functionality_Into_Your_AppsViewController
        *strongSelf = weakSelf;

        switch (result){
            case TWTweetComposeViewControllerResultDone:{
                /* The Tweet was submitted successfully.
                Will be dismissed automatically */
                break;
            }
            case TWTweetComposeViewControllerResultCancelled:{
                if (strongSelf != nil){
                    [strongSelf.twitterController
                     dismissModalViewControllerAnimated:YES];
                }
                break;
            }
        }
    }

    }

}

NSString *text =
@"Anthony Robbins at Unleash the Power Within (UPW) in London";

[self.twitterController setInitialText:text];

UIImage *anthonyRobbins = [UIImage imageNamed:@"Anthony Robbins.jpg"];
[self.twitterController addImage:anthonyRobbins];

NSURL *url = [NSURL URLWithString:@"http://www.tonyrobbins.com"];
```

```

[self.twitterController addURL:url];

[self.navigationController presentViewController:self.twitterController
                                         animated:YES];

}

```

See Also

XXX

8.12 Parsing XML with NSXMLParser

Problem

You want to be able to parse XML.

Solution

Use the `NSXMLParser` class.

Discussion

The `NSXMLParser` uses a delegate model to parse XML content. Let's go ahead and create a simple XML file that contains the following data (save this file as *MyXML.xml* in your project):

```

<?xml version="1.0" encoding="UTF-8"?>
<root>

  <person id="1">
    <firstName>Anthony</firstName>
    <lastName>Robbins</lastName>
    <age>51</age>
  </person>

  <person id="2">
    <firstName>Richard</firstName>
    <lastName>Branson</lastName>
    <age>61</age>
  </person>

</root>

```

Now let's go ahead and define a property of type `NSXMLParser`:

```

#import <UIKit/UIKit.h>

@interface Parsing_XML_with_NSXMLParserAppDelegate
    : UIResponder <UIApplicationDelegate, NSXMLParserDelegate>

@property (nonatomic, strong) UIWindow *window;

```

```
@property (nonatomic, strong) NSXMLParser *xmlParser;

@end
```

You can also see that I have defined my app delegate as an XML parser delegate, by conforming to the `NSXMLParserDelegate` protocol, which is required for a delegate object of an XML parser of type `NSXMLParser`. Let's continue to synthesize our XML parser:

```
#import "Parsing_XML_with_NSXMLParserAppDelegate.h"

@implementation Parsing_XML_with_NSXMLParserAppDelegate

@synthesize window = _window;
@synthesize xmlParser;

...
```

Now let's go on to reading the *MyXML.xml* from the disk and passing it to our XML parser:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSString *xmlFilePath = [[NSBundle mainBundle] pathForResource:@"MyXML"
                                                                    ofType:@"xml"];

    NSData *xml = [[NSData alloc] initWithContentsOfFile:xmlFilePath];

    self.xmlParser = [[NSXMLParser alloc] initWithData:xml];
    self.xmlParser.delegate = self;
    if ([self.xmlParser parse]){
        NSLog(@"The XML is parsed.");
    } else{
        NSLog(@"Failed to parse the XML");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

We first read the contents of our file into an instance of `NSData` and then we initialize our XML parser with the `initWithData:`, using the data that we read from the XML file. We then call the `parse` method of the XML parser to start the parsing process. This method will block the current thread until the parsing process is finished. If you have big XML files to parse, it is highly recommended that you use a global dispatch queue to do the parsing.

To know how to parse the XML file, we need to know the delegate methods defined in the `NSXMLParserDelegate` protocol and their responsibilities:

`parserDidStartDocument:`

Gets called when the parsing starts.

`parserDidEndDocument:`

Gets called when the parsing ends.

`parser:didStartElement:namespaceURI:qualifiedName:attributes:`

Gets called when the parser encounters and parses a new element in the XML document.

`parser:didEndElement:namespaceURI:qualifiedName:`

Gets called when the parser has finished parsing the current element.

`parser:foundCharacters:`

When the parser parses string contents of elements.

Using these delegate methods, we can go ahead and define an object model for our XML objects. Let's first define an object to represent an XML element, into a class called `XMLElement`:

```
#import <Foundation/Foundation.h>

@interface XMLElement : NSObject

@property (nonatomic, strong) NSString *name;
@property (nonatomic, strong) NSString *text;
@property (nonatomic, strong) NSDictionary *attributes;
@property (nonatomic, strong) NSMutableArray *subElements;
@property (nonatomic, weak) XMLElement *parent;

@end
```

Now let's implement our `XMLElement` class:

```
#import "XMLElement.h"

@implementation XMLElement

@synthesize name;
@synthesize text;
@synthesize attributes;
@synthesize subElements;
@synthesize parent;

- (NSMutableArray *) subElements{
    if (subElements == nil){
        subElements = [[NSMutableArray alloc] init];
    }
    return subElements;
}

@end
```

We want the `subElements` mutable array to be created only if it is nil when it is accessed, hence, we place our allocation and initialization code for this property in its own getter

method. If an XML element doesn't have sub elements and we never use that property, then there is no point allocating and initializing a mutable array for that element. This technique is known as lazy allocation.

So now let's go ahead and define an instance of `XMLElement` and call it *rootElement*. Our plan is to start the parsing process and drill down the XML file as we parse it with our delegate methods, until we have successfully parsed the whole file:

```
#import <UIKit/UIKit.h>

@class XMLElement;

@interface Parsing_XML_with_NSXMLParserAppDelegate
    : UIResponder <UIApplicationDelegate, NSXMLParserDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) NSXMLParser *xmlParser;
@property (nonatomic, strong) XMLElement *rootElement;
@property (nonatomic, strong) XMLElement *currentElementPointer;

@end
```

The `currentElementPointer` will be the XML element that we are parsing at the moment, in our XML structure so it can move up and down the structure as we parse the file. It's a simple pointer, whereas, the `rootElement` will always be the root element of our XML. Next we will synthesize our new properties:

```
#import "Parsing_XML_with_NSXMLParserAppDelegate.h"
#import "XMLElement.h"

@implementation Parsing_XML_with_NSXMLParserAppDelegate

@synthesize window = _window;
@synthesize xmlParser;
@synthesize rootElement;
@synthesize currentElementPointer;

...
```

And let's start the parsing process. The first method we want to take care of is the `parserDidStartDocument:` method. In this method, we will simply reset everything:

```
- (void)parserDidStartDocument:(NSXMLParser *)parser{
    self.rootElement = nil;
    self.currentElementPointer = nil;
}
```

The next method would be the `parser:didStartElement:namespaceURI:qualifiedName:attributes:` method. In this method, we will create the root element if it is not created already and if any new element is getting parsed, we will calculate where in the structure of the XML we are and then add a new element to our current element:

```
- (void) parser:(NSXMLParser *)parser
    didStartElement:(NSString *)elementName
```

```

        namespaceURI:(NSString *)namespaceURI
        qualifiedName:(NSString *)qName
        attributes:(NSDictionary *)attributeDict{

    if (self.rootElement == nil){
        /* We don't have a root element. Create it and point to it */
        self.rootElement = [[XMLElement alloc] init];
        self.currentElementPointer = self.rootElement;
    } else {
        /* Already have root. Create new element and add it as one of
        the subelements of the current element */
        XMLElement *newElement = [[XMLElement alloc] init];
        newElement.parent = self.currentElementPointer;
        [self.currentElementPointer.subElements addObject:newElement];
        self.currentElementPointer = newElement;
    }

    self.currentElementPointer.name = elementName;
    self.currentElementPointer.attributes = attributeDict;

}

```

Next up, is the `parser:foundCharacters:` method. This method can get called multiple times for the current element so we need to make sure we are ready for multiple entry into this method. For instance, if the text of an element is 4000 characters long, the parser might parse maximum of 1000 characters in the first go, then the next 1000 and so on and call our `parser:foundCharacters:` method for the current element, 4 times:

```

- (void)        parser:(NSXMLParser *)parser
    foundCharacters:(NSString *)string{

    if ([self.currentElementPointer.text length] > 0){
        self.currentElementPointer.text =
            [self.currentElementPointer.text stringByAppendingString:string];
    } else {
        self.currentElementPointer.text = string;
    }

}

```

The next method to take care of would be the `parser:didEndElement:namespaceURI:qualifiedName:` method which gets called when the parser encounters the end of an element. In here, we just need to point our XML element pointer back one level to the parent of the current element, as simple as that:

```

- (void)        parser:(NSXMLParser *)parser
    didEndElement:(NSString *)elementName
    namespaceURI:(NSString *)namespaceURI
    qualifiedName:(NSString *)qName{

    self.currentElementPointer = self.currentElementPointer.parent;

}

```

Last but not least, we need to handle the `parserDidEndDocument:` method and dispose of our `currentElementPointer` property:

```
- (void)parserDidEndDocument:(NSXMLParser *)parser{
    self.currentElementPointer = nil;
}
```

That is all. Now let's go ahead and parse our document:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSString *xmlFilePath = [[NSBundle mainBundle] pathForResource:@"MyXML"
                                                                ofType:@"xml"];

    NSData *xml = [[NSData alloc] initWithContentsOfFile:xmlFilePath];

    self.xmlParser = [[NSXMLParser alloc] initWithData:xml];
    self.xmlParser.delegate = self;
    if ([self.xmlParser parse]){
        NSLog(@"The XML is parsed.");

        /* self.rootElement is now the root element in the XML */

    } else{
        NSLog(@"Failed to parse the XML");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

Now you can use the `rootElement` property to traverse the structure of our XML.

See Also

XXX

Audio and Video

9.0 Introduction

The AVFoundation framework in the iOS SDK allows developers to play and/or record audio and video with ease. In addition, the Media Player framework allows developers to play audio and video files.

Before you can run the code in this chapter, you must add the AVFoundation.framework and MediaPlayer.framework frameworks to your Xcode project. You can do this by following these steps:

1. In Xcode, click on your project's icon (a blue icon).
2. Select the target to which you want to add the framework.
3. On the top, select Build Phases.
4. Select the + button in the bottom left of the Link Binaries with Libraries box.
5. Hold down the Command key and choose AVFoundation.framework and MediaPlayer.framework from the list.
6. Select Add.

9.1 Playing Audio Files

Problem

You want to be able to play an audio file in your application.

Solution

Use the AV Foundation (Audio and Video Foundation) framework's `AVAudioPlayer` class.

Discussion

The `AVAudioPlayer` class in the AV Foundation framework can play back all audio formats supported by iOS. The `delegate` property of an instance of `AVAudioPlayer` allows you to get notified by events, such as whenever the audio playback is interrupted or if an error occurs as a result of playing an audio file. Let's have a look at a simple example that demonstrates how we can play an audio file that is in our application's bundle:

```
- (void)viewDidLoad {
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    dispatch_queue_t dispatchQueue =
        dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

    dispatch_async(dispatchQueue, ^(void) {
        NSBundle *mainBundle = [NSBundle mainBundle];

        NSString *filePath = [mainBundle pathForResource:@"MySong"
                                                         ofType:@"mp3"];

        NSData *fileData = [NSData dataWithContentsOfFile:filePath];

        NSError *error = nil;

        /* Start the audio player */
        self.audioPlayer = [[AVAudioPlayer alloc] initWithData:fileData
                                                         error:&error];

        /* Did we get an instance of AVAudioPlayer? */
        if (self.audioPlayer != nil){
            /* Set the delegate and start playing */
            self.audioPlayer.delegate = self;
            if ([self.audioPlayer prepareToPlay] &&
                [self.audioPlayer play]){
                /* Successfully started playing */
            } else {
                /* Failed to play */
            }
        } else {
            /* Failed to instantiate AVAudioPlayer */
        }
    });
}
```

As you can see, the file's data is loaded into an instance of `NSData` and then passed on to `AVAudioPlayer`'s `initWithData:error:` method. Because we need the actual, absolute path of the MP3 file to extract the data from that file, we invoke the `mainBundle` class method of `NSBundle` to retrieve the information from our application's configuration. The `pathForResource:ofType:` instance method of `NSBundle` can then be used to retrieve the absolute path to a resource of a specific type, as demonstrated in the example code.

In the `viewDidLoad` method, we are using GCD to asynchronously load the song's data into an instance of `NSData` and use that as a feed to our audio player. We are doing this because loading the data of an audio file, depending on the length of the audio file, can take a long time and if we do this on the main thread, we are running the risk of stalling the UI experience. Because of this, we are using a global concurrent queue to ensure that our code does *not* run on the main thread.

Since we are assigning the instance of `AVAudioPlayer` to a property named `audioPlayer`, we must also see how this property is defined:

```
#import <UIKit/UIKit.h>
#import <AVFoundation/AVFoundation.h>

@interface Playing_Audio_FilesViewController
    : UIViewController <AVAudioPlayerDelegate>

@property (nonatomic, strong) AVAudioPlayer *audioPlayer;

@end
```

As you can see, we have made our view controller the delegate of the audio player. This way, we can receive messages from the system whenever our audio player, for instance, is interrupted or has finished playing the song. With this information in hand, we can make appropriate decisions in our application, such as starting to play another audio file.

See Also

[Recipe 9.2](#); [Recipe 9.5](#)

9.2 Handling Interruptions While Playing Audio

Problem

You want your `AVAudioPlayer` instance to resume playing after an interruption on an iOS device, such as an incoming call.

Solution

Implement the `audioPlayerBeginInterruption:` and `audioPlayerEndInterruption:withFlags:` methods of the `AVAudioPlayerDelegate` protocol in the delegate object of your `AVAudioPlayer` instance:

```
- (void)audioPlayerBeginInterruption:(AVAudioPlayer *)player{

    /* Audio Session is interrupted. The player will be paused here */

}

- (void)audioPlayerEndInterruption:(AVAudioPlayer *)player
```

```

        withFlags:(NSUInteger)flags{

            if (flags == AVAudioSessionInterruptionFlags_ShouldResume &&
                player != nil){
                [player play];
            }
        }
    }
}

```

Discussion

On an iOS device, such as an iPhone, a phone call could interrupt the execution of the foreground application. The audio session(s) associated with the application will be deactivated in that case and audio files will not be played until after the interruption is ended. In the beginning and the end of an interruption, we receive delegate messages from the `AVAudioPlayer` informing us of the different states the audio session is passing through. After the end of an interruption, we can simply resume the playback of audio.



Incoming phone calls cannot be simulated with iPhone Simulator. You must always test your applications on a real device.

When an interruption occurs, the `audioPlayerBeginInterruption:` delegate method of an `AVAudioPlayer` instance will be called. Here, your audio session has been deactivated. In case of a phone call, the user can just hear her ring tone. When the interruption ends (the phone call is finished or the user rejects the call), the `audioPlayerEndInterruption:withFlags:` delegate method of your `AVAudioPlayer` will be invoked. If the `withFlags` parameter contains the value `AVAudioSessionInterruptionFlags_ShouldResume`, you can immediately resume the playback of your audio player using the `play` instance method of `AVAudioPlayer`.



The playback of audio files using `AVAudioPlayer` might show memory leaks in Instruments when the application is being run on iPhone Simulator. Testing the same application on an iOS device proves that the memory leaks are unique to the simulator, not the device. I strongly suggest that you run, test, debug, and optimize your applications on real devices before releasing them on the App Store.

9.3 Recording Audio

Problem

You want to be able to record audio files on an iOS device.

Solution

Make sure you have added the `CoreAudio.framework` framework to your target file, and use the `AVAudioRecorder` class in the AV Foundation framework:

```
NSError *error = nil;

NSString *pathAsString = [self audioRecordingPath];

NSURL *audioRecordingURL = [NSURL fileURLWithPath:pathAsString];

self.audioRecorder = [[AVAudioRecorder alloc]
                      initWithURL:audioRecordingURL
                      settings:[self audioRecordingSettings]
                      error:&error];
```

For information about the `audioRecordingSettings` and `audioRecordingPath` methods used in this example, refer to this recipe's [Discussion](#).

Discussion

The `AVAudioRecorder` class in the AV Foundation framework facilitates audio recording in iOS applications. To start a recording, you need to pass various pieces of information to the `initWithURL:settings:error:` instance method of `AVAudioRecorder`:

The URL of the file where the recording should be saved

This is a local URL. The AV Foundation framework will decide which audio format should be used for the recording based on the file extension provided in this URL, so choose the extension carefully.

The settings that must be used before and while recording

Examples include the sampling rate, channels, and other information that will help the audio recorder start the recording. This is a dictionary object.

The address of an instance of NSError where any initialization errors should be saved to

The error information could be valuable later, and you can retrieve it from this instance method in case something goes wrong.

The `settings` parameter of the `initWithURL:settings:error:` method is particularly interesting. There are many keys that could be saved in the `settings` dictionary, but we will discuss only some of the most important ones in this recipe:

AVFormatIDKey

The format of the recorded audio. Some of the values that can be specified for this key are:

- `kAudioFormatLinearPCM`
- `kAudioFormatAppleLossless`

AVSampleRateKey

The sample rate that needs to be used for the recording.

AVNumberOfChannelsKey

The number of channels that must be used for the recording.

AVEncoderAudioQualityKey

The quality with which the recording must be made. Some of the values that can be specified for this key are:

- AVAudioQualityMin
- AVAudioQualityLow
- AVAudioQualityMedium
- AVAudioQualityHigh
- AVAudioQualityMax

With all this information in hand, we can go on and write an application that can record audio input into a file and then play it using `AVAudioPlayer`. What we want to do, specifically, is:

1. Start recording audio in Apple Lossless format.
2. Save the recording into a file named *Recording.m4a* in our application's *Documents* directory.
3. Five seconds after the recording starts, finish the recording process and immediately start playing the file into which we recorded the audio input.

We will start by declaring the required properties in the *.h* file of a simple view controller:

```
#import <UIKit/UIKit.h>
#import <CoreAudio/CoreAudioTypes.h>
#import <AVFoundation/AVFoundation.h>

@interface Recording_AudioViewController : UIViewController
    <AVAudioPlayerDelegate, AVAudioRecorderDelegate>

@property (nonatomic, strong) AVAudioRecorder *audioRecorder;
@property (nonatomic, strong) AVAudioPlayer *audioPlayer;

- (NSString *)      audioRecordingPath;
- (NSDictionary *)  audioRecordingSettings;

@end
```

When the view inside our view controller is loaded for the first time, we will attempt to start the recording process and then stop the process, if successfully started, after five seconds:

```
- (void)viewDidLoad {
    [super viewDidLoad];

    NSError *error = nil;

    NSString *pathAsString = [self audioRecordingPath];
```

```

NSURL *audioRecordingURL = [NSURL fileURLWithPath:pathAsString];

self.audioRecorder = [[AVAudioRecorder alloc]
                      initWithURL:audioRecordingURL
                      settings:[self audioRecordingSettings]
                      error:&error];

if (self.audioRecorder != nil){

    self.audioRecorder.delegate = self;
    /* Prepare the recorder and then start the recording */

    if ([self.audioRecorder prepareToRecord] &&
        [self.audioRecorder record]){
        NSLog(@"Successfully started to record.");

        /* After 5 seconds, let's stop the recording process */
        [self performSelector:@selector(stopRecordingOnAudioRecorder:)
            withObject:self.audioRecorder
            afterDelay:5.0f];

    } else {
        NSLog(@"Failed to record.");
        self.audioRecorder = nil;
    }

} else {
    NSLog(@"Failed to create an instance of the audio recorder.");
}

}

- (void) viewDidLoad{
    [super viewDidLoad];

    if ([self.audioRecorder isRecording]){
        [self.audioRecorder stop];
    }
    self.audioRecorder = nil;

    if ([self.audioPlayer isPlaying]){
        [self.audioPlayer stop];
    }
    self.audioPlayer = nil;

}

```

In the `viewDidLoad` method of our view controller, we attempt to instantiate an object of type `AVAudioRecorder` and assign it to the `audioRecorder` property that we declared in the `.h` file of the same view controller earlier.

We are using an instance method called `audioRecordingPath` to determine the `NSString` representation of the local URL where we want to store our recording. This method is implemented like so:

```
- (NSString *) audioRecordingPath{

    NSString *result = nil;

    NSArray *folders =
    NSSearchPathForDirectoriesInDomains(NSDocumentDirectory,
                                        NSUserDomainMask,
                                        YES);

    NSString *documentsFolder = [folders objectAtIndex:0];

    result = [documentsFolder
              stringByAppendingPathComponent:@"Recording.m4a"];

    return result;
}
```

The return value of this function is the document path of your application with the name of the destination file appended to it. For instance, if the document path of your application is:

```
/var/mobile/Applications/ApplicationID/Documents/
```

the destination audio recording path will be:

```
/var/mobile/Applications/ApplicationID/Documents/Recording.m4a
```

When instantiating our `AVAudioRecorder`, we are using a dictionary for the settings parameter of the initialization method of the audio recorder, as explained before. This dictionary is constructed using our `audioRecordingSettings` instance method, implemented in this way:

```
- (NSDictionary *) audioRecordingSettings{

    NSDictionary *result = nil;

    /* Let's prepare the audio recorder options in the dictionary.
       Later we will use this dictionary to instantiate an audio
       recorder of type AVAudioRecorder */

    NSMutableDictionary *settings = [[NSMutableDictionary alloc] init];

    [settings
     setValue:[NSNumber numberWithInt:kAudioFormatAppleLossless]
     forKey:AVFormatIDKey];

    [settings
     setValue:[NSNumber numberWithFloat:44100.0f]
     forKey:AVSampleRateKey];
}
```



```

[settings
 setValue:[NSNumber numberWithInt:1]
 forKey:AVNumberOfChannelsKey];

[settings
 setValue:[NSNumber numberWithInt:AVAudioQualityLow]
 forKey:AVEncoderAudioQualityKey];

result = [NSDictionary dictionaryWithDictionary:settings];

return result;
}

```

You can see that five seconds after the recording starts successfully in the `viewDidLoad` method of the view controller, we are calling the `stopRecordingOnAudioRecorder` method, implemented like so:

```

- (void) stopRecordingOnAudioRecorder
    :(AVAudioRecorder *)paramRecorder{

    /* Just stop the audio recorder here */
    [paramRecorder stop];

}

```

Now that we have asked our audio recorder to stop recording, we will wait for its delegate messages to tell us when the recording has actually stopped. It's good not to assume that the `stop` instance method of `AVAudioRecorder` instantly stops the recording. Instead, I recommend that you wait for the `audioRecorderDidFinishRecording:successfully:` delegate method (declared in the `AVAudioRecorderDelegate` protocol) before proceeding.

When the audio recording has actually stopped, we will attempt to play what was recorded:

```

- (void)audioRecorderDidFinishRecording:(AVAudioRecorder *)recorder
    successfully:(BOOL)flag{

    if (flag){

        NSLog(@"Successfully stopped the audio recording process.");

        /* Let's try to retrieve the data for the recorded file */
        NSError *playbackError = nil;

        NSError *readingError = nil;
        NSData *fileData =
            [NSData dataWithContentsOfFile:[self audioRecordingPath]
             options:NSDataReadingMapped
             error:&readingError];

        /* Form an audio player and make it play the recorded data */
        self.audioPlayer = [[AVAudioPlayer alloc] initWithData:fileData
                                                                error:&playbackError];
    }
}

```

```

/* Could we instantiate the audio player? */
if (self.audioPlayer != nil){
    self.audioPlayer.delegate = self;

    /* Prepare to play and start playing */
    if ([self.audioPlayer prepareToPlay] &&
        [self.audioPlayer play]){
        NSLog(@"Started playing the recorded audio.");
    } else {
        NSLog(@"Could not play the audio.");
    }

} else {
    NSLog(@"Failed to create an audio player.");
}

} else {
    NSLog(@"Stopping the audio recording failed.");
}

/* Here we don't need the audio recorder anymore */
self.audioRecorder = nil;
}

```

After the audio player is finished playing the song (if it does so successfully), the `audioPlayerDidFinishPlaying:successfully:` delegate method will be called in the delegate object of our audio player. We will implement this method like so (this method is defined in the `AVAudioPlayerDelegate` protocol):

```

- (void)audioPlayerDidFinishPlaying:(AVAudioPlayer *)player
    successfully:(BOOL)flag{
    if (flag){
        NSLog(@"Audio player stopped correctly.");
    } else {
        NSLog(@"Audio player did not stop correctly.");
    }

    if ([player isEqual:self.audioPlayer]){
        self.audioPlayer = nil;
    } else {
        /* This is not our player */
    }

}

```

As explained in [Recipe 9.2](#), when playing audio files using `AVAudioPlayer`, we also need to handle interruptions, such as incoming phone calls, when deploying our application on an iOS device and before releasing the application on the App Store:

```

- (void)audioPlayerBeginInterruption:(AVAudioPlayer *)player{

    /* The audio session has been deactivated here */
}

```

```

    }

    - (void)audioPlayerEndInterruption:(AVAudioPlayer *)player
      withFlags:(NSUInteger)flags{

        if (flags == AVAudioSessionInterruptionFlags_ShouldResume){
            [player play];
        }

    }

```

Instances of `AVAudioRecorder` must also handle interruptions, just like instances of `AVAudioPlayer`. These interruptions can be handled as explained in [Recipe 9.4](#).

See Also

[Recipe 9.2](#); [Recipe 9.4](#)

9.4 Handling Interruptions While Recording Audio

Problem

You want your `AVAudioRecorder` instance to be able to resume recording after an interruption, such as an incoming phone call.

Solution

Implement the `audioRecorderBeginInterruption:` and `audioRecorderEndInterruption:withFlags:` methods of the `AVAudioRecorderDelegate` protocol in the delegate object of your audio recorder, and resume the recording process by invoking the `record` instance method of your `AVAudioRecorder` when the interruption has ended:

```

    - (void)audioRecorderBeginInterruption:(AVAudioRecorder *)recorder{

        NSLog(@"Recording process is interrupted");

    }

    - (void)audioRecorderEndInterruption:(AVAudioRecorder *)recorder
      withFlags:(NSUInteger)flags{

        if (flags == AVAudioSessionInterruptionFlags_ShouldResume){
            NSLog(@"Resuming the recording...");
            [recorder record];
        }

    }

```

Discussion

Just like audio players (instances of `AVAudioPlayer`), audio recorders of type `AVAudioRecorder` also receive delegate messages whenever the audio session associated with them is deactivated because of an interruption. The two methods mentioned in this recipe's [Solution](#) are the best places to handle such interruptions. In the case of an interruption to the audio recorder, you can invoke the `record` instance method of `AVAudioRecorder` after the interruption to continue the recording process. However, the recording will overwrite the previous recording and all data that was recorded before the interruption will be lost.



It is very important to bear in mind that when the delegate of your audio recorder receives the `audioRecorderBeginInterruption:` method, the audio session has already been deactivated, and invoking the `resume` instance method will not work on your audio recorder. After the interruption is ended, you must invoke the `record` instance method of your `AVAudioRecorder` to resume recording.

9.5 Playing Audio over Other Active Sounds

Problem

You either want to put other applications in silent mode while you play audio or play audio on top of other applications' audio playback (if any).

Solution

Use audio sessions to set the type of audio category your application uses.

Discussion

The `AVAudioSession` class was introduced in the AV Foundation framework. Every iOS application has one audio session. This audio session can be accessed using the `sharedInstance` class method of the `AVAudioSession` class, like so:

```
AVAudioSession *audioSession = [AVAudioSession sharedInstance];
```

After retrieving an instance of the `AVAudioSession` class, you can invoke the `setCategory:error:` instance method of the audio session object to choose among the different categories available to iOS applications. Different values that can be set as the audio session category of an application are listed here:

`AVAudioSessionCategorySoloAmbient`

This category is exactly like the `AVAudioSessionCategoryAmbient` category, except that this category will stop the audio playback of all other applications, such as the iPod. When the device is put into silent mode, your audio playback will be paused.

This also happens when the screen is locked. This is the default category that iOS chooses for an application.

AVAudioSessionCategoryRecord

This stops other applications' audio (e.g., the iPod) and also will not allow your application to initiate an audio playback (e.g., using `AVAudioPlayer`). You can only record audio in this mode. Using this category, calling the `prepareToPlay` instance method of `AVAudioPlayer` will return `YES` and the `play` instance method will return `NO`. The main UI interface will function as usual. The recording of your application will continue even if the iOS device's screen is locked by the user.

AVAudioSessionCategoryPlayback

This category will silence other applications' audio playback (such as the audio playback of iPod applications). You can then use the `prepareToPlay` and `play` instance methods of `AVAudioPlayer` to play a sound in your application. The main UI thread will function as normal. The audio playback will continue even if the screen is locked by the user and even if the device is in silent mode.

AVAudioSessionCategoryPlayAndRecord

This category allows audio to be played and recorded at the same time in your application. This will stop the audio playback of other applications when your audio recording or playback begins. The main UI thread of your application will function as normal. The playback and the recording will continue even if the screen is locked or the device is in silent mode.

AVAudioSessionCategoryAudioProcessing

This category can be used for applications that do audio processing, but not audio playback or recording. By setting this category, you cannot play or record any audio in your application. Calling the `prepareToPlay` and `play` instance methods of `AVAudioPlayer` will return `NO`. Audio playback of other applications, such as the iPod, will also stop if this category is set.

AVAudioSessionCategoryAmbient

This category will not stop the audio from other applications, but it will allow you to play audio over the audio being played by other applications, such as the iPod. The main UI thread of your application will function normally. The `prepareToPlay` and `play` instance methods of `AVAudioPlayer` will return with the value `YES`. The audio being played by your application will stop when the user locks the screen. The silent mode silences the audio playback of your application only if your application is the only application playing an audio file. If you start playing audio while the iPod is playing a song, putting the device in silent mode does not stop your audio playback.

To give you an example of using `AVAudioSession`, let's start an audio player that will play its audio file over other applications' audio playback. We will begin with the `.h` file of a view controller:

```
#import <UIKit/UIKit.h>
#import <AVFoundation/AVFoundation.h>
```

```

@interface Playing_Audio_over_Other_Active_SoundsViewController
    : UIViewController <AVAudioPlayerDelegate>

@property (nonatomic, strong) AVAudioPlayer *audioPlayer;

@end

```

Here is how we will alter our audio session and how we will then load a song into the memory and into an audio player for playing. We will do this in the `viewDidLoad` method of our view controller:

```

- (void)viewDidLoad {
    [super viewDidLoad];

    NSError *audioSessionError = nil;
    AVAudioSession *audioSession = [AVAudioSession sharedInstance];
    if ([audioSession setCategory:AVAudioSessionCategoryAmbient
                            error:&audioSessionError]){
        NSLog(@"Successfully set the audio session.");
    } else {
        NSLog(@"Could not set the audio session");
    }

    dispatch_queue_t dispatchQueue =
        dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

    dispatch_async(dispatchQueue, ^(void) {
        NSBundle *mainBundle = [NSBundle mainBundle];

        NSString *filePath = [mainBundle pathForResource:@"MySong"
                                                         ofType:@"mp3"];

        NSData *fileData = [NSData dataWithContentsOfFile:filePath];

        NSError *audioPlayerError = nil;

        self.audioPlayer = [[AVAudioPlayer alloc] initWithData:fileData
                                                            error:&audioPlayerError];

        if (self.audioPlayer != nil){
            self.audioPlayer.delegate = self;

            if ([self.audioPlayer prepareToPlay] &&
                [self.audioPlayer play]){
                NSLog(@"Successfully started playing.");
            } else {
                NSLog(@"Failed to play the audio file.");
                self.audioPlayer = nil;
            }
        } else {
            NSLog(@"Could not instantiate the audio player.");
        }
    });
}

```

```

    }
  });
}

- (void) viewDidLoad{
  [super viewDidLoad];

  if ([self.audioPlayer isPlaying]){
    [self.audioPlayer stop];
  }
  self.audioPlayer = nil;
}

```

And then we will move on to handling the `AVAudioPlayerDelegate` protocol's methods:

```

- (void)audioPlayerBeginInterruption:(AVAudioPlayer *)player{
  /* The audio session has been deactivated here */
}

- (void)audioPlayerEndInterruption:(AVAudioPlayer *)player
    withFlags:(NSUInteger)flags{
  if (flags == AVAudioSessionInterruptionFlags_ShouldResume){
    [player play];
  }
}

- (void)audioPlayerDidFinishPlaying:(AVAudioPlayer *)player
    successfully:(BOOL)flag{

  if (flag){
    NSLog(@"Audio player stopped correctly.");
  } else {
    NSLog(@"Audio player did not stop correctly.");
  }

  if ([player isEqual:self.audioPlayer]){
    self.audioPlayer = nil;
  } else {
    /* This is not our audio player */
  }
}

```

You can see that we are using the shared instance of the `AVAudioSession` class in the `viewDidLoad` instance method of our view controller to set the audio category of our application to `AVAudioSessionCategoryAmbient` in order to allow our application to play audio files over other applications' audio playback.

9.6 Playing Video Files

Problem

You would like to be able to play video files in your iOS application.

Solution

Use an instance of the `MPMoviePlayerController` class.



If you simply want to display a full-screen movie player, you can use the `MPMoviePlayerViewController` class and push your movie player view controller into the stack of view controllers of a navigation controller (for instance), or simply present your movie player view controller as a modal controller on another view controller using the `presentMoviePlayerViewControllerAnimated:` instance method of `UIViewController`. In this recipe, we will use `MPMoviePlayerController` instead of `MPMoviePlayerViewController` in order to get full access to various settings that a movie player view controller does not offer, such as windowed-mode video playback (not full-screen).

Discussion

The Media Player framework in the iOS SDK allows programmers to play audio and video files, among other interesting things. To be able to play a video file, we will instantiate an object of type `MPMoviePlayerController` like so:

```
self.moviePlayer = [[MPMoviePlayerController alloc] initWithContentURL:url];
```

In this code, `moviePlayer` is a property of type `MPMoviePlayerController` defined and synthesized for the current view controller. In older iOS SDKs, programmers had very little control over how movies were played using the Media Player framework. With the introduction of the iPad, the whole framework changed drastically to give more control to programmers and allow them to present their contents with more flexibility than before.

An instance of `MPMoviePlayerController` has a property called `view`. This view is of type `UIView` and is the view in which the media, such as video, will be played. As a programmer, you are responsible for inserting this view into your application's view hierarchy to present your users with the content being played. Since you get a reference to an object of type `UIView`, you can shape this view however you want. For instance, you can simply change the background color of this view to a custom color.

Many multimedia operations depend on the notification system. For instance, `MPMoviePlayerController` does not work with delegates; instead, it relies on notifications. This allows for a very flexible decoupling between the system libraries and the applications that iOS programmers write. For classes such as `MPMoviePlayerController`, we start

listening for notifications that get sent by instances of that class. We use the default notification center and add ourselves as an observer for a notification.

To be able to test our recipe, we need a sample *.mov* file to play with the movie player. You can download an Apple-provided sample file from <http://support.apple.com/kb/HT1425>. Make sure you download the H.264 file format. If this file is zipped, unzip it and rename it to *Sample.m4v*. Now drag and drop this file into your application bundle in Xcode.

After doing this, we can go ahead and write a simple program that attempts to play the video file for us. Here is our *.h* file:

```
#import <UIKit/UIKit.h>
#import <MediaPlayer/MediaPlayer.h>

@interface Playing_Video_FilesViewController : UIViewController

@property (nonatomic, strong) MPMoviePlayerController *moviePlayer;
@property (nonatomic, strong) UIButton *playButton;

@end
```

Here is the implementation of the `startPlayingVideo:` method that we defined in our *.h* file:

```
- (void) startPlayingVideo:(id)paramSender{

    /* First let's construct the URL of the file in our application bundle
       that needs to get played by the movie player */
    NSBundle *mainBundle = [NSBundle mainBundle];

    NSString *urlAsString = [mainBundle pathForResource:@"Sample"
                                                         ofType:@"m4v"];

    NSURL *url = [NSURL URLWithString:urlAsString];

    /* If we have already created a movie player before,
       let's try to stop it */
    if (self.moviePlayer != nil){
        [self stopPlayingVideo:nil];
    }

    /* Now create a new movie player using the URL */
    self.moviePlayer = [[MPMoviePlayerController alloc] initWithContentURL:url];

    if (self.moviePlayer != nil){

        /* Listen for the notification that the movie player sends us
           whenever it finishes playing an audio file */
        [[NSNotificationCenter defaultCenter]
         addObserver:self
         selector:@selector(videoHasFinishedPlaying:)
         name:MPMoviePlayerPlaybackDidFinishNotification
         object:self.moviePlayer];
    }
}
```

```

        NSLog(@"Successfully instantiated the movie player.");

        /* Scale the movie player to fit the aspect ratio */
        self.moviePlayer.scalingMode = MPMovieScalingModeAspectFit;

        /* Let's start playing the video in full screen mode */
        [self.moviePlayer play];

        [self.view addSubview:self.moviePlayer.view];

        [self.moviePlayer setFullscreen:YES
                               animated:YES];

    } else {
        NSLog(@"Failed to instantiate the movie player.");
    }
}

```

As you can see, we manage the movie player's view ourselves. If we add the view of the movie player to our view controller's view, we have to remove the view manually. This view will not get removed from our view controller's view even if we release the movie player. The following method stops the video and then removes the associated view:

```

- (void) stopPlayingVideo:(id)paramSender {

    if (self.moviePlayer != nil){

        [[NSNotificationCenter defaultCenter]
         removeObserver:self
         name:MPMoviePlayerPlaybackDidFinishNotification
         object:self.moviePlayer];

        [self.moviePlayer stop];

        if ([self.moviePlayer.view.superview isEqual:self.view]){
            [self.moviePlayer.view removeFromSuperview];
        }
    }
}

```



Please be extra careful when using the `superview` property of your movie player's view. In cases such as when your view is unloaded because of low-memory warnings, you must not use the `view` property of your view controller in any way after it is set to `nil`. Doing so will cause the iOS SDK to throw out warnings in the console window.

Here is our implementation of the `viewDidUnload` method:

```

- (void) viewDidUnload{
    self.playButton = nil;
    [self stopPlayingVideo:nil];
}

```

```

        self.moviePlayer = nil;
        [super viewDidLoad];
    }

```

In the `startPlayingVideo:` instance method of our view controller we are listening for the `MPMoviePlayerPlaybackDidFinishNotification` notification that `MKMoviePlayerView Controller` will send to the default notification center. We listen to this notification on the `videoHasFinishedPlaying:` instance method of our view controller. Here we can get notified when the movie playback has finished and perhaps dispose of our movie player object:

```

- (void) videoHasFinishedPlaying:(NSNotification *)paramNotification{

    /* Find out what the reason was for the player to stop */
    NSNumber *reason =
    [paramNotification.userInfo
     valueForKey:MPMoviePlayerPlaybackDidFinishReasonUserInfoKey];

    if (reason != nil){
        NSInteger reasonAsInteger = [reason integerValue];

        switch (reasonAsInteger){
            case MPMovieFinishReasonPlaybackEnded:{
                /* The movie ended normally */
                break;
            }
            case MPMovieFinishReasonPlaybackError:{
                /* An error happened and the movie ended */
                break;
            }
            case MPMovieFinishReasonUserExited:{
                /* The user exited the player */
                break;
            }
        }

        NSLog(@"Finish Reason = %ld", (long)reasonAsInteger);
        [self stopPlayingVideo:nil];
    } /* if (reason != nil){ */

}

```

You might have already noticed that we are invoking the `stopPlayingVideo:` instance method that we've implemented in the `videoHasFinishedPlaying:` notification handler. We do this because the `stopPlayingVideo:` instance method takes care of unregistering our object from the notifications received by the media player and removes the media player from the superview. In other words, when the video stops playing, it does not necessarily mean the resources we allocated for that player have been deallocated. We need to take care of that manually. Bear in mind that the `MPMoviePlayerController` class does not work in iPhone Simulator. You need to run this code on a real device and check the results for yourself.

See Also

[Recipe 9.7](#)

9.7 Capturing Thumbnails from a Video File

Problem

You are playing a video file using an instance of the `MPMoviePlayerController` class and would like to capture a screenshot from the movie at a certain time.

Solution

Use the `requestThumbnailImagesAtTimes:timeOption:` instance method of `MPMoviePlayerController` like so:

```
/* Capture the frame at the third second into the movie */
NSNumber *thirdSecondThumbnail = [NSNumber numberWithFloat:3.0f];

/* We can ask to capture as many frames as we
   want. But for now, we are just asking to capture one frame */
NSArray *requestedThumbnails =
[NSArray arrayWithObject:thirdSecondThumbnail];

/* Ask the movie player to capture this frame for us */
[self.moviePlayer
 requestThumbnailImagesAtTimes:requestedThumbnails
 timeOption:MPMovieTimeOptionExact];
```

Discussion

An instance of `MPMoviePlayerController` is able to capture thumbnails from the currently playing movie, synchronously and asynchronously. In this recipe, we are going to focus on asynchronous image capture for this class.

We can use the `requestThumbnailImagesAtTimes:timeOption:` instance method of `MPMoviePlayerController` to asynchronously access thumbnails. When I say “asynchronously,” I mean that during the time the thumbnail is being captured and reported to your designated object (as we will soon see), the movie player will continue its work and will not block the playback. We must observe the `MPMoviePlayerThumbnailImageRequestDidFinishNotification` notification message the movie player sends to the default notification center in order to find out when our thumbnails are available:

```
- (void) startPlayingVideo:(id)paramSender{

    /* First let's construct the URL of the file in our application bundle
       that needs to get played by the movie player */
    NSBundle *mainBundle = [NSBundle mainBundle];

    NSString *urlAsString = [mainBundle pathForResource:@"Sample"
```

```

ofType:@"m4v"];

NSURL *url = [NSURL fileURLWithPath:urlAsString];

/* If we have already created a movie player before,
let's try to stop it */
if (self.moviePlayer != nil){
    [self stopPlayingVideo:nil];
}

/* Now create a new movie player using the URL */
self.moviePlayer = [[MPMoviePlayerController alloc] initWithContentURL:url];

if (self.moviePlayer != nil){

    /* Listen for the notification that the movie player sends us
    whenever it finishes playing an audio file */
    [[NSNotificationCenter defaultCenter]
    addObserver:self
    selector:@selector(videoHasFinishedPlaying:)
    name:MPMoviePlayerPlaybackDidFinishNotification
    object:self.moviePlayer];

    [[NSNotificationCenter defaultCenter]
    addObserver:self
    selector:@selector(videoThumbnailIsAvailable:)
    name:MPMoviePlayerThumbnailImageRequestDidFinishNotification
    object:self.moviePlayer];

    NSLog(@"Successfully instantiated the movie player.");

    /* Scale the movie player to fit the aspect ratio */
    self.moviePlayer.scalingMode = MPMovieScalingModeAspectFit;

    /* Let's start playing the video in full screen mode */
    [self.moviePlayer play];

    [self.view addSubview:self.moviePlayer.view];

    [self.moviePlayer setFullscreen:YES
    animated:YES];

    /* Capture the frame at the third second into the movie */
    NSNumber *thirdSecondThumbnail = [NSNumber numberWithFloat:3.0f];

    /* We can ask to capture as many frames as we
    want. But for now, we are just asking to capture one frame */
    NSArray *requestedThumbnails =
    [NSArray arrayWithObject:thirdSecondThumbnail];

    /* Ask the movie player to capture this frame for us */
    [self.moviePlayer
    requestThumbnailImagesAtTimes:requestedThumbnails
    timeOption:MPMovieTimeOptionExact];
}

```

```

    } else {
        NSLog(@"Failed to instantiate the movie player.");
    }
}

```

You can see that we are asking the movie player to capture the frame at the third second into the movie. Once this task is completed, the `videoThumbnailIsAvailable:` instance method of our view controller will be called. Here is how we can access the captured image:

```

- (void) videoThumbnailIsAvailable:(NSNotification *)paramNotification{

    MPMoviePlayerController *controller = [paramNotification object];

    if (controller != nil &&
        [controller isEqual:self.moviePlayer]){
        NSLog(@"Thumbnail is available");

        /* Now get the thumbnail out of the user info dictionary */
        UIImage *thumbnail =
            [paramNotification.userInfo
             objectForKey:MPMoviePlayerThumbnailImageKey];

        if (thumbnail != nil){
            /* We got the thumbnail image. You can now use it here */
        }
    }
}

```

Since we started listening to the `MPMoviePlayerThumbnailImageRequestDidFinishNotification` notifications when we instantiated our movie player object in the `startPlayingVideo:` method, we must also stop listening for this notification whenever we stop the movie player (or whenever you believe is appropriate depending on your application architecture):

```

- (void) stopPlayingVideo:(id)paramSender {

    if (self.moviePlayer != nil){

        [[NSNotificationCenter defaultCenter]
         removeObserver:self
         name:MPMoviePlayerPlaybackDidFinishNotification
         object:self.moviePlayer];

        [[NSNotificationCenter defaultCenter]
         removeObserver:self
         name:MPMoviePlayerThumbnailImageRequestDidFinishNotification
         object:self.moviePlayer];

        [self.moviePlayer stop];

        if ([self.moviePlayer.view.superview isEqual:self.view]){
            [self.moviePlayer.view removeFromSuperview];
        }
    }
}

```

```

    }
}

}

```

When calling the `requestThumbnailImagesAtTimes:timeOption:` instance method of `MPMoviePlayerController`, we can specify one of two values for `timeOption`: `MPMovieTimeOptionExact` or `MPMovieTimeOptionNearestKeyFrame`. The former gives us the frame playing at the exact point we requested in the timeline of our video, whereas the latter is less exact, but also uses fewer system resources and offers an overall better performance when capturing thumbnails from a video. `MPMovieTimeOptionNearestKeyFrame` is usually adequate in terms of precision because it is just a couple of frames off.

9.8 Accessing the Music Library

Problem

You want to access an item that your user picks from her music library.

Solution

Use the `MPMediaPickerController` class:

```

MPMediaPickerController *mediaPicker = [[MPMediaPickerController alloc]
                                         initWithMediaTypes:MPMediaTypeAny];

```

Discussion

`MPMediaPickerController` is a view controller that the iPod application displays to the user. By instantiating `MPMediaPickerController`, you can present a standard view controller to your users to allow them to select whatever item they want from their library and then transfer the control to your application. This is particularly useful in games, for instance, where the user plays the game and can have your application play his favorite tracks in the background.

You can get information from the media picker controller by becoming its delegate (conforming to `MPMediaPickerControllerDelegate`):

```

#import <UIKit/UIKit.h>
#import <MediaPlayer/MediaPlayer.h>

@interface Accessing_the_Music_LibraryViewController
    : UIViewController <MPMediaPickerControllerDelegate>

@end

```

Inside your `displayMediaPlayer:` selector, implement the code required to display an instance of the media picker controller and present it to the user as a modal view controller:

```

- (void) displayMediaPlayer{

    MPMediaPickerController *mediaPicker = [[MPMediaPickerController alloc]
                                              initWithMediaTypes:MPMediaTypeAny];

    if (mediaPicker != nil){

        NSLog(@"Successfully instantiated a media picker.");
        mediaPicker.delegate = self;
        mediaPicker.allowsPickingMultipleItems = NO;

        [self.navigationController presentViewController:mediaPicker
                                                  animated:YES];

    } else {
        NSLog(@"Could not instantiate a media picker.");
    }

}

```

The `allowsPickingMultipleItems` property of the media picker controller lets you specify whether users can pick more than one item from their library before dismissing the media picker controller. This takes a `BOOL` value, so for now we just set it to `NO`; we will later see what this looks like. Now let's implement the various delegate messages defined in the `MPMediaPickerControllerDelegate` protocol:

```

- (void) mediaPicker:(MPMediaPickerController *)mediaPicker
    didPickMediaItems:(MPMediaItemCollection *)mediaItemCollection{

    NSLog(@"Media Picker returned");

    for (MPMediaItem *thisItem in mediaItemCollection.items){

        NSURL      *itemURL =
        [thisItem valueForKeyProperty:MPMediaItemPropertyAssetURL];

        NSString   *itemTitle =
        [thisItem valueForKeyProperty:MPMediaItemPropertyTitle];

        NSString   *itemArtist =
        [thisItem valueForKeyProperty:MPMediaItemPropertyArtist];

        MPMediaItemArtwork *itemArtwork =
        [thisItem valueForKeyProperty:MPMediaItemPropertyArtwork];

        NSLog(@"Item URL = %@", itemURL);
        NSLog(@"Item Title = %@", itemTitle);
        NSLog(@"Item Artist = %@", itemArtist);
        NSLog(@"Item Artwork = %@", itemArtwork);
    }

    [mediaPicker dismissModalViewControllerAnimated:YES];

}

```


You can access different properties of each selected item using the `valueForProperty:` instance method of `MPMediaItem`. Instances of this class will be returned to your application through the `mediaItemCollection` parameter of the `mediaPicker:didPickMediaItems:` delegate message.

Now let's write a program with a very simple GUI that allows us to ask the user to pick one music item from his iPod library. After he picks the music file, we will attempt to play it using an `MPMusicPlayerController` instance. Our GUI has two simple buttons: Pick and Play, and Stop Playing. The first button will ask the user to pick an item from his iPod library for us to play, and the second button will stop the audio playback (if we are already playing the song). We will start with the design of the UI of our application. Let's create it in a simple way, as shown in [Figure 9-1](#).




Figure 9-1. A very simple UI for our media picker and AV Audio Player

Now let's go ahead and define these two buttons in the *.h* of our view controller:

```
@interface Accessing_the_Music_LibraryViewController : UIViewController
    <MPMediaPickerControllerDelegate, AVAudioPlayerDelegate>

    @property (nonatomic, strong) MPMusicPlayerController *myMusicPlayer;
    @property (nonatomic, strong) UIButton *buttonPickAndPlay;
    @property (nonatomic, strong) UIButton *buttonStopPlaying;

@end
```

When our view loads up, we will then instantiate these two buttons and place them on our view:

```
- (void)viewDidLoad {
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];

    self.buttonPickAndPlay = [UIButton buttonWithType:UIButtonTypeRoundedRect];
    self.buttonPickAndPlay.frame = CGRectMake(0.0f,
                                              0.0f,
                                              200,
                                              37.0f);
    self.buttonPickAndPlay.center = CGPointMake(self.view.center.x,
                                              self.view.center.y - 50);
    [self.buttonPickAndPlay setTitle:@"Pick and Play"
      forState:UIControlStateNormal];
    [self.buttonPickAndPlay addTarget:self
      action:@selector(displayMediaPickerAndPlayItem)
      forControlEvents:UIControlEventTouchUpInside];
    [self.view addSubview:self.buttonPickAndPlay];

    self.buttonStopPlaying = [UIButton buttonWithType:UIButtonTypeRoundedRect];
    self.buttonStopPlaying.frame = CGRectMake(0.0f,
                                              0.0f,
                                              200,
                                              37.0f);
    self.buttonStopPlaying.center = CGPointMake(self.view.center.x,
                                              self.view.center.y + 50);
    [self.buttonStopPlaying setTitle:@"Stop Playing"
      forState:UIControlStateNormal];
    [self.buttonStopPlaying addTarget:self
      action:@selector(stopPlayingAudio)
      forControlEvents:UIControlEventTouchUpInside];
    [self.view addSubview:self.buttonStopPlaying];

    [self.navigationController setNavigationBarHidden:YES
      animated:NO];
}
```

The two most important methods in our view controller are the `displayMediaPickerAndPlayItem` and `stopPlayingAudio`:

```
- (void) stopPlayingAudio{

    if (self.myMusicPlayer != nil){

        [[NSNotificationCenter defaultCenter]
         removeObserver:self
         name:MPMusicPlayerControllerPlaybackStateDidChangeNotification
         object:self.myMusicPlayer];

        [[NSNotificationCenter defaultCenter]
         removeObserver:self
         name:MPMusicPlayerControllerNowPlayingItemDidChangeNotification
         object:self.myMusicPlayer];
    }
}
```

```

        [[NSNotificationCenter defaultCenter]
         removeObserver:self
         name:MPMusicPlayerControllerVolumeDidChangeNotification
         object:self.myMusicPlayer];

        [self.myMusicPlayer stop];
    }
}

- (void) displayMediaPlayerAndPlayItem{

    MPMediaPickerController *mediaPicker =
    [[MPMediaPickerController alloc]
     initWithMediaTypes:MPMediaTypeMusic];

    if (mediaPicker != nil){

        NSLog(@"Successfully instantiated a media picker.");
        mediaPicker.delegate = self;
        mediaPicker.allowsPickingMultipleItems = YES;

        [self.navigationController presentViewController:mediaPicker
         animated:YES];

    } else {
        NSLog(@"Could not instantiate a media picker.");
    }

}

```

When our media picker controller succeeds, the `mediaPicker:didPickMediaItems` message will be called in the delegate object (in this case, our view controller). On the other hand, if the user cancels the media player, we'll get the `mediaPicker:mediaPickerDidCancel` message. The following code implements the method that will be called in each case:

```

- (void) mediaPicker:(MPMediaPickerController *)mediaPicker
  didPickMediaItems:(MPMediaItemCollection *)mediaItemCollection{

    NSLog(@"Media Picker returned");

    /* First, if we have already created a music player, let's
       deallocate it */
    self.myMusicPlayer = nil;

    self.myMusicPlayer = [[MPMusicPlayerController alloc] init];

    [self.myMusicPlayer beginGeneratingPlaybackNotifications];

    /* Get notified when the state of the playback changes */
    [[NSNotificationCenter defaultCenter]
     addObserver:self
     selector:@selector(musicPlayerStateChanged:)

```

```

        name:MPMusicPlayerControllerPlaybackStateDidChangeNotification
        object:self.myMusicPlayer];

/* Get notified when the playback moves from one item
to the other. In this recipe, we are only going to allow
our user to pick one music file */
[[NSNotificationCenter defaultCenter]
 addObserver:self
 selector:@selector(nowPlayingItemIsChanged:)
 name:MPMusicPlayerControllerNowPlayingItemDidChangeNotification
 object:self.myMusicPlayer];

/* And also get notified when the volume of the
music player is changed */
[[NSNotificationCenter defaultCenter]
 addObserver:self
 selector:@selector(volumeIsChanged:)
 name:MPMusicPlayerControllerVolumeDidChangeNotification
 object:self.myMusicPlayer];

/* Start playing the items in the collection */
[self.myMusicPlayer setQueueWithItemCollection:mediaItemCollection];
[self.myMusicPlayer play];

/* Finally dismiss the media picker controller */
[mediaPicker dismissModalViewControllerAnimated:YES];
}

- (void) mediaPickerDidCancel:(MPMediaPickerController *)mediaPicker{

/* The media picker was cancelled */
NSLog(@"Media Picker was cancelled");
[mediaPicker dismissModalViewControllerAnimated:YES];

}

```

We are listening for the events our music player generates through the notifications that it sends. Here are the three methods that are going to be responsible for handling the notifications we are listening to for the music player:

```

- (void) musicPlayerStateChanged:(NSNotification *)paramNotification{

    NSLog(@"Player State Changed");

    /* Let's get the state of the player */
    NSNumber *stateAsObject =
    [paramNotification.userInfo
     objectForKey:@"MPMusicPlayerControllerPlaybackStateKey"];

    NSInteger state = [stateAsObject integerValue];

    /* Make your decision based on the state of the player */
    switch (state){
        case MPMusicPlaybackStateStopped:{

```

```

        /* Here the media player has stopped playing the queue. */
        break;
    }
    case MPMusicPlaybackStatePlaying:{
        /* The media player is playing the queue. Perhaps you
           can reduce some processing that your application
           that is using to give more processing power
           to the media player */
        break;
    }
    case MPMusicPlaybackStatePaused:{
        /* The media playback is paused here. You might want
           to indicate by showing graphics to the user */
        break;
    }
    case MPMusicPlaybackStateInterrupted:{
        /* An interruption stopped the playback of the media queue */
        break;
    }
    case MPMusicPlaybackStateSeekingForward:{
        /* The user is seeking forward in the queue */
        break;
    }
    case MPMusicPlaybackStateSeekingBackward:{
        /* The user is seeking backward in the queue */
        break;
    }
    } /* switch (State){ */
}

- (void) nowPlayingItemIsChanged:(NSNotification *)paramNotification{

    NSLog(@"Playing Item Is Changed");

    NSString *persistentID =
    [paramNotification.userInfo
     objectForKey:@"MPMusicPlayerControllerNowPlayingItemPersistentIDKey"];

    /* Do something with Persistent ID */
    NSLog(@"Persistent ID = %@", persistentID);

}

- (void) volumeIsChanged:(NSNotification *)paramNotification{
    NSLog(@"Volume Is Changed");
    /* The userInfo dictionary of this notification is normally empty */
}

```

We will also implement the `viewDidUnload` method of our view controller to make sure we won't leave any memory leaking:

```

- (void) viewDidUnload{
    [super viewDidUnload];

    [self stopPlayingAudio];
}

```

```
        self.myMusicPlayer = nil;  
    }
```

By running our application and pressing the Pick and Play button on our view controller, we will be presented with the media picker controller. Once the picker view controller is displayed, the same iPod UI will be presented to our user. After the user picks an item (or cancels the whole dialog), we will get appropriate delegate messages called in our view controller (since our view controller is the delegate of our media picker). After the items are picked (we only allow one item in this recipe, though), we will start our music player and start playing the whole collection.

If you want to allow your users to pick more than one item at a time, simply set the `allowsPickingMultipleItems` property of your media picker controller to YES:

```
mediaPicker.allowsPickingMultipleItems = YES;
```



Sometimes when working with the media picker controller (`MPMediaPickerController`), the “`MPMediaPicker: Lost connection to iPod library`” message will be printed out to the console screen. This is because the media picker has been interrupted by an event such as syncing with iTunes while the picker was being displayed to the user. Immediately, your `mediaPickerDidCancel:` delegate message will be called as well.

Address Book

10.0 Introduction

On an iOS device, the Contacts application allows users to add to, remove from, and manipulate their address book. The address book can be a collection of people and groups. Each person can have properties such as first name, last name, phone number, and email address assigned to her. Some properties can have a single value and some can have multiple values. For instance, the first name of a person is one value but the phone number can be multiple values (e.g., if the user has two home phone numbers).

The `AddressBook.framework` framework in the iOS SDK allows us to interact with the address book database on the device. We can get the array of all entities in the user's address book, insert and change values, and much more.

To use the address-book-related functions in your application, follow these steps to first add `AddressBook.framework` to your application:

1. Click on your project's icon in Xcode.
2. Select the target to which you want to add the `AddressBook` framework.
3. On the top of the screen, select the Build Phases tab.
4. In the Build Phases tab, find and expand the Link Binary with Libraries box and press the + button, located at the bottom left corner of that box.
5. In the list that gets displayed, select the `AddressBook.framework` and press the Add button (see [Figure 10-1](#)).




Figure 10-1. Adding the AddressBook framework to our app

After you've added the framework to your application, whenever you want to use address-book-related functions you must include the main header file of the framework in your header (.h) or implementation (.m) file, like so:

```
#import <UIKit/UIKit.h>
#import <AddressBook/AddressBook.h>

@interface RootViewController : UIViewController

@end
```



You can use the Address Book framework on iOS Simulator, but the Contacts database on the simulator is empty by default. If you want to run the examples in this chapter on iOS Simulator, first populate your address book (on the simulator) using the Contacts application.

I have populated my iOS Simulator's contacts database with three entries, as shown in [Figure 10-2](#).




Figure 10-2. Contacts added to iOS Simulator

I also suggest that you populate the address book of your iOS Simulator with as many values as possible: multiple phone numbers for work and home, different addresses, and so forth. Only through such diversity can you correctly test the Address Book framework's functions.

10.1 Getting a Reference to Address Book

Problem

You would like to get a reference to the user's address book database.

Solution

Use the `ABAddressBookCreate` function in the Address Book framework:

```
- (BOOL)      application:(UIApplication *)application
  didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    ABAddressBookRef addressBook = ABAddressBookCreate();

    if (addressBook != nil){
        NSLog(@"Successfully accessed the address book.");

        /* Work with the address book here */

        /* Let's see if we have made any changes to the
           address book or not, before attempting to save it */

        if (ABAddressBookHasUnsavedChanges(addressBook)){
            /* Now decide if you want to save the changes to
               the address book */
            NSLog(@"Changes were found in the address book.");

            BOOL doYouWantToSaveChanges = YES;

            /* We can make a decision to save or revert the
               address book back to how it was before */
            if (doYouWantToSaveChanges){

                CFErrorRef saveError = NULL;

                if (ABAddressBookSave(addressBook, &saveError)){
                    /* We successfully saved our changes to the
                       address book */
                } else {
                    /* We failed to save the changes. You can now
                       access the [saveError] variable to find out
                       what the error is */
                }

            } else {

                /* We did NOT want to save the changes to the address
                   book so let's revert it to how it was before */
                ABAddressBookRevert(addressBook);

            }

        } else {
```

```

        /* We have not made any changes to the address book */
        NSLog(@"No changes to the address book.");
    }

    CFRelease(addressBook);

} else {
    NSLog(@"Could not access the address book.");
}

self.window = [[UIWindow alloc] initWithFrame:
                [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```



I created the `doYouWantToSaveChanges` local variable and set it to YES just to demonstrate that we can, if we need to, revert an address book whose contents have been changed (reversion is done through the `ABAddressBookRevert` procedure). You can add code, for instance, asking the user if he wants the changes to be saved or not, and if not, you can revert the address book to its original state.

For more information about importing the Address Book framework into your application, please refer to this chapter's [Introduction](#).

Discussion

To get a reference to the user's address book database, we must use the `ABAddressBookCreate` function. This function returns a value of type `ABAddressBookRef` that will be `nil` if the address book cannot be accessed. You must check for `nil` values before accessing the address book reference returned by this function. Attempting to modify a `nil` address book will terminate your application with a runtime error.

After retrieving a reference to the user's address book, you can start making changes to the contacts, reading the entries, and so on. If you have made any changes to the address book, the `ABAddressBookHasUnsavedChanges` function will tell you by returning the value YES.



An instance of the address book database returned by the `ABAddressBookCreate` function must be released when you are finished working with it, using the `CFRelease` Core Foundation method, as demonstrated in our example code.

After determining whether changes were made to the address book database, you can either save or discard these changes using the `ABAddressBookSave` or `ABAddressBookRevert` procedure, respectively.

10.2 Retrieving All the People in the Address Book

Problem

You want to retrieve all contacts in the user's address book.

Solution

Use the `ABAddressBookCopyArrayOfAllPeople` function to retrieve an array of all contacts:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    ABAddressBookRef addressBook = ABAddressBookCreate();

    if (addressBook != nil){
        NSLog(@"Successfully accessed the address book.");

        NSArray *arrayOfAllPeople = (__bridge_transfer NSArray *)
            ABAddressBookCopyArrayOfAllPeople(addressBook);

        NSUInteger peopleCounter = 0;
        for (peopleCounter = 0;
             peopleCounter < [arrayOfAllPeople count];
             peopleCounter++){

            ABRecordRef thisPerson =
                (__bridge ABRecordRef)[arrayOfAllPeople objectAtIndex:peopleCounter];

            NSLog(@"%@", thisPerson);

            /* Use the [thisPerson] address book record */

        }

        CFRelease(addressBook);
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

Discussion

After accessing the user's address book database, we can call the `ABAddressBookCopyArrayOfAllPeople` function to retrieve an array of all the contacts in that address book. The return value of this function is an immutable array of type `CFArrayRef`. We cannot work with this type of array the way we work with instances of `NSArray`, but here are a few functions that will let us traverse an array of type `CFArrayRef`:

`CFArrayGetCount`

Call this function to get the number of items in an instance of `CFArrayRef`. This is similar to the `count` instance method of an `NSArray`.

`CFArrayGetValueAtIndex`

Call this function to retrieve an item at a specific location of an instance of `CFArrayRef`. This is similar to the `objectAtIndex:` instance method of an `NSArray`.

The `CFArrayRef` Core Foundation object is one of the objects that supports Toll-Free Bridging to its NS counterpart, `NSArray`. This means that we can simply bridge this Core Foundation array and type-cast it to an instance of `NSArray`. This works perfectly under ARC using the `__bridge_transfer` keyword which will decrease the reference count on the Core Foundation object, since our local array is a strong variable by default, and will retain its contents without us having to do anything extra.

The items that are put in an array of all people, retrieved by calling the `ABAddressBookCopyArrayOfAllPeople` function, are of type `ABRecordRef`. In [Recipe 10.3](#), you will see how to access different properties of the entries, such as a person's entry, in the address book database.

See Also

[Recipe 10.1](#)

10.3 Retrieving Properties of Address Book Entries

Problem

You have retrieved a reference to an item in the address book, such as a person's entry, and you want to retrieve that person's properties, such as first and last names.

Solution

Use the `ABRecordCopyValue` function on the person's Address Book record.

Discussion

The records in the address book database are of type `ABRecordRef`. Each record could be either a group or a person. We have not discussed groups yet, so let's focus on people.

Each person could have various types of information assigned to him, such as his first name, last name, email address, and so on. Bear in mind that many of these values are optional, and at the time of creating a new contact in the address book database, the user can simply leave out fields such as phone number, middle name, email address, URL, and so forth.

`ABRecordCopyValue` accepts an address book record and the property that has to be retrieved as its two parameters. The second parameter is the property of the record that we want to retrieve. Here are some of the common properties (all of these properties are defined as constant values in the *ABPerson.h* header file):

`kABPersonFirstNameProperty`

This value will retrieve the first name of the given person. The return value is of type `CFStringRef`, which can be cast to `NSString` easily.

`kABPersonLastNameProperty`

This value will retrieve the last name of the given person. Like the first name property, the return value will be of type `CFStringRef`, which again can be cast to `NSString` with a bridge cast.

`kABPersonMiddleNameProperty`

This value will retrieve the middle name of the given person. Like the first name and the last name, the return value will be of type `CFStringRef`, which can be cast to `NSString` with a bridge cast.

`kABPersonEmailProperty`

This will retrieve the given person's email address. The return value in this case will be of type `ABMultiValueRef`. This is a data type that can contain multiple values inside it, like an array, but *not exactly* like an array. This type of data will be discussed next.

Some of the values that we retrieve from the `ABRecordCopyValue` function are straightforward, generic types, such as `CFStringRef`. This function can return complicated values, such as the email of a contact. The email could be further broken down into home email, work email, and so on. These values are called *multivalues* in the Address Book framework. Various functions allow us to work with multiple values (which are of type `ABMultiValueRef`):

`ABMultiValueGetCount`

Returns the number of value/label pairs that are inside the multivalue.

`ABMultiValueCopyLabelAtIndex`

Returns the label associated with a multivalue item at a specific index. For instance, if the user has three emails, such as work, home, and test emails, the index of the work email in the email multivalue would be 1. This function will then retrieve the label associated with that email (in this example, *work*). Please bear in mind that multivalues do not necessarily have to have labels. Make sure you check for `NULL` values.

ABMultiValueCopyValueAtIndex

Returns the string value associated with a multivalued item at a specific index. I know this sounds complicated, but imagine the user has work, home, and test emails. If we provide the index 0 to this function, it will retrieve the given contact's work email.

Now let's first go ahead and write a simple app that can retrieve all the people in the address book and print out their first name, last name and email address objects:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    ABAddressBookRef addressBook = ABAddressBookCreate();

    if (addressBook != nil){
        NSLog(@"Successfully accessed the address book.");

        NSArray *allPeople = (__bridge_transfer NSArray *)
            ABAddressBookCopyArrayOfAllPeople(addressBook);

        NSUInteger peopleCounter = 0;
        for (peopleCounter = 0;
             peopleCounter < [allPeople count];
             peopleCounter++){

            ABRecordRef thisPerson = (__bridge ABRecordRef)
                [allPeople objectAtIndex:peopleCounter];

            NSString *firstName = (__bridge_transfer NSString *)
                ABRecordCopyValue(thisPerson, kABPersonFirstNameProperty);

            NSString *lastName = (__bridge_transfer NSString *)
                ABRecordCopyValue(thisPerson, kABPersonLastNameProperty);

            NSString *email = (__bridge_transfer NSString *)
                ABRecordCopyValue(thisPerson, kABPersonEmailProperty);

            NSLog(@"First Name = %@", firstName);
            NSLog(@"Last Name = %@", lastName);
            NSLog(@"Address = %@", email);

        }

        CFRelease(addressBook);
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

If I run this app, with the 3 contacts that I've added to my Address Book, I will get the following printed to the console window:

```
Successfully accessed the address book.
First Name = Vandad
Last Name = Nahavandipoor
Address = ABMultiValueRef 0x684ad50 with 2 value(s)
    0: _$!<Home>!$_ (0x684af00) - vandad.np@gmail.com (0x684af20)
    1: _$!<Work>!$_ (0x684aee0) - iosandosx@gmail.com (0x684af90)
First Name = Brian
Last Name = Jepson
Address = ABMultiValueRef 0x684ac00 with 1 value(s)
    0: _$!<Home>!$_ (0x684adf0) - brian@oreilly.com (0x684ae10)
First Name = Andy
Last Name = Oram
Address = ABMultiValueRef 0x684a710 with 1 value(s)
    0: _$!<Home>!$_ (0x684ace0) - andy@oreilly.com (0x684ad00)
```

It's immediately visible that the multi-value field, email, cannot be read as a plain string object. So let's go ahead, using the functions that we just learnt, implement a method that accepts an object of type `ABRecordRef` and correctly reads that record's multi-value email field and prints the values out to the console:

```
- (void) logPersonEmails:(ABRecordRef)paramPerson{

    if (paramPerson == NULL){
        NSLog(@"The given person is NULL.");
        return;
    }

    ABMultiValueRef emails =
        ABRecordCopyValue(paramPerson, kABPersonEmailProperty);

    if (emails == NULL){
        NSLog(@"This contact does not have any emails.");
        return;
    }

    /* Go through all the emails */
    NSUInteger emailCounter = 0;

    for (emailCounter = 0;
         emailCounter < ABMultiValueGetCount(emails);
         emailCounter++){

        /* Get the label of the email (if any) */
        NSString *emailLabel = (__bridge_transfer NSString *)
            ABMultiValueCopyLabelAtIndex(emails, emailCounter);

        NSString *localizedEmailLabel = (__bridge_transfer NSString *)
            ABAddressBookCopyLocalizedLabel((__bridge CFStringRef)emailLabel);

        /* And then get the email address itself */
        NSString *email = (__bridge_transfer NSString *)
            ABMultiValueCopyValueAtIndex(emails, emailCounter);
```

```

        NSLog(@"Label = %@, Localized Label = %@, Email = %@",
              emailLabel,
              localizedEmailLabel,
              email);
    }

    CFRelease(emails);
}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    ABAddressBookRef addressBook = ABAddressBookCreate();

    if (addressBook != nil){
        NSLog(@"Successfully accessed the address book.");

        NSArray *allPeople = (__bridge_transfer NSArray *)
            ABAddressBookCopyArrayOfAllPeople(addressBook);

        NSUInteger peopleCounter = 0;
        for (peopleCounter = 0;
             peopleCounter < [allPeople count];
             peopleCounter++){

            ABRecordRef thisPerson =
                (__bridge ABRecordRef)[allPeople objectAtIndex:peopleCounter];

            NSString *firstName = (__bridge_transfer NSString *)
                ABRecordCopyValue(thisPerson, kABPersonFirstNameProperty);

            NSString *lastName = (__bridge_transfer NSString *)
                ABRecordCopyValue(thisPerson, kABPersonLastNameProperty);

            NSLog(@"First Name = %@", firstName);
            NSLog(@"Last Name = %@", lastName);

            [self logPersonEmails:thisPerson];
        }

        CFRelease(addressBook);
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```



Calling the `CFRelease` procedure on a `NULL` value will crash your application. Make sure you check for `NULL` values before calling this Core Foundation procedure.

Label values returned by the `ABMultiValueCopyLabelAtIndex` function are rather cryptic and hard to read. Examples are “_<Other>!\$” and “_<Home>!\$” that might be set for email addresses with labels of Other and Home. However, if you want to retrieve a plain and readable version of these labels, you can first copy the label using the `ABMultiValueCopyLabelAtIndex` function and pass the returned value of this function to the `ABAddressBookCopyLocalizedLabel` function.

See Also

[Recipe 10.1](#); [Recipe 10.2](#)

10.4 Inserting a Person Entry into the Address Book

Problem

You want to create a new person contact and insert it into the user’s address book.

Solution

Use the `ABPersonCreate` function to create a new person. Set the person’s properties using the `ABRecordSetValue` function and add the person to the address book using the `ABAddressBookAddRecord` function.

Discussion

After accessing the address book database using the `ABAddressBookCreate` function, you can start inserting new group and person records into the database. In this recipe, we will concentrate on inserting new person records. For information about inserting new groups into the address book, please refer to [Recipe 10.5](#).

We must use the `ABPersonCreate` function in order to create a new person record. Bear in mind that calling this function is not enough to add the person record to the address book. You must save the address book for your record to appear in the database.

By calling the `ABPersonCreate` function, you get a Core Foundation reference to a value of type `ABRecordRef`. Now you can call the `ABRecordSetValue` function to set the various properties of a new person entry. Once you are done, you must add the new person record to the database. You can do this using the `ABAddressBookAddRecord` function. After doing this, you must also save any unsaved changes to the address book database in order to truly save your new person record. Do this by using the `ABAddressBookSave` function.

So let's utilize all this into implementing a method that allows us to insert a new person entry into the address book:

```
- (ABRecordRef) newPersonWithFirstName:(NSString *)paramFirstName
                           lastName:(NSString *)paramLastName
                           inAddressBook:(ABAddressBookRef)paramAddressBook{

    ABRecordRef result = NULL;

    if (paramAddressBook == NULL){
        NSLog(@"The address book is NULL.");
        return NULL;
    }

    if ([paramFirstName length] == 0 &&
        [paramLastName length] == 0){
        NSLog(@"First name and last name are both empty.");
        return NULL;
    }

    result = ABPersonCreate();

    if (result == NULL){
        NSLog(@"Failed to create a new person.");
        return NULL;
    }

    BOOL couldSetFirstName = NO;
    BOOL couldSetLastName = NO;
    CFErrorRef setFirstNameError = NULL;
    CFErrorRef setLastNameError = NULL;

    couldSetFirstName = ABRecordSetValue(result,
                                           kABPersonFirstNameProperty,
                                           (__bridge CFTypeRef)paramFirstName,
                                           &setFirstNameError);

    couldSetLastName = ABRecordSetValue(result,
                                           kABPersonLastNameProperty,
                                           (__bridge CFTypeRef)paramLastName,
                                           &setLastNameError);

    CFErrorRef couldAddPersonError = NULL;
    BOOL couldAddPerson = ABAddressBookAddRecord(paramAddressBook,
                                                  result,
                                                  &couldAddPersonError);

    if (couldAddPerson){
        NSLog(@"Successfully added the person.");
    } else {
        NSLog(@"Failed to add the person.");
        CFRelease(result);
        result = NULL;
        return result;
    }
}
```

```

if (ABAddressBookHasUnsavedChanges(paramAddressBook)){

    CFErrorRef couldSaveAddressBookError = NULL;
    BOOL couldSaveAddressBook = ABAddressBookSave(paramAddressBook,
                                                    &couldSaveAddressBookError);

    if (couldSaveAddressBook){
        NSLog(@"Successfully saved the address book.");
    } else {
        NSLog(@"Failed to save the address book.");
    }
}

if (couldSetFirstName &&
    couldSetLastName){
    NSLog(@"Successfully set the first name and the last name of the person.");
} else {
    NSLog(@"Failed to set the first name and/or last name of the person.");
}

return result;
}

```

And now in our app delegate, let's invoke this method and pass it an address book object:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    ABAddressBookRef addressBook = ABAddressBookCreate();

    if (addressBook != NULL){

        ABRecordRef anthonyRobbins = [self newPersonWithFirstName:@"Anthony"
                                                                lastName:@"Robbins"
                                                                inAddressBook:addressBook];

        if (anthonyRobbins != NULL){
            NSLog(@"Anthony Robbins' record is inserted into the Address Book.");
            CFRelease(anthonyRobbins);
        }

        CFRelease(addressBook);
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];
    // Override point for customization after application launch.
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

The `newPersonWithFirstName:lastName:inAddressBook:` method that we implemented creates a new person entry in the address book database. After invoking this function, you will see the results, as shown in Figure 10-3, in the Contacts application on iPhone Simulator.




Figure 10-3. A new person record is added to the address book



Memory management on Core Foundation is quite different from what you might be used to when writing applications for Cocoa Touch. As this topic is beyond the scope of this book, please make sure you read the “Memory Management Programming Guide for Core Foundation” documentation on Apple’s website:

<http://developer.apple.com/iphone/library/documentation/corefoundation/Conceptual/CFMemoryMgmt/CFMemoryMgmt.html>

10.5 Inserting a Group Entry into the Address Book

Problem

You want to categorize your contacts into groups.

Solution

Use the `ABGroupCreate` function.

Bear in mind that, as mentioned before, Core Foundation memory management is more complex than what Xcode's static analyzer could process. Therefore, attempting to compile Core Foundation code with the LLVM compiler with static analysis turned on might give you a lot of warnings. You can ignore these warnings and test the code with Instruments to make sure your code does not leak. I encourage you to familiarize yourself with memory management in Core Foundation by reading Apple's "Memory Management Programming Guide for Core Foundation" document, as mentioned in a previous note.

Discussion

After retrieving the reference to the address book database, you can call the `ABGroupCreate` function to create a new group entry. However, you must perform a few more operations before you can insert this group into the address book operation. The first thing you have to do is to set the name of this group using the `ABRecordSetValue` function with the `kABGroupNameProperty` property, as shown in the example code.

After the name of the group is set, you need to add it to the address book database just like you add a new person's entry, using the `ABAddressBookAddRecord` function. For more information about adding a new person's entry to the address book database, please read [Recipe 10.4](#).



Inserting a new group with a name that already exists in the address book database will create a new group with the same name but with no group members. In later recipes, we will learn how to avoid doing this by first finding the groups in the database and making sure a group with that name doesn't already exist.

After adding the group to the address book, you also need to save the address book's contents using the `ABAddressBookSave` function.

So, with all this in mind, let's go ahead and implement a method that allows us to create a new group with any name in the Address Book database:

```
- (ABRecordRef) newGroupWithName:(NSString *)paramGroupName  
    inAddressBook:(ABAddressBookRef)paramAddressBook{
```



```

ABRecordRef result = NULL;

if (paramAddressBook == NULL){
    NSLog(@"The address book is nil.");
    return NULL;
}

result = ABGroupCreate();

if (result == NULL){
    NSLog(@"Failed to create a new group.");
    return NULL;
}

BOOL couldSetGroupName = NO;
NSErrorRef error = NULL;

couldSetGroupName = ABRecordSetValue(result,
                                     kABGroupNameProperty,
                                     (__bridge CTypeRef)paramGroupName,
                                     &error);

if (couldSetGroupName){

    BOOL couldAddRecord = NO;
    NSErrorRef couldAddRecordError = NULL;

    couldAddRecord = ABAddressBookAddRecord(paramAddressBook,
                                             result,
                                             &couldAddRecordError);

    if (couldAddRecord){

        NSLog(@"Successfully added the new group.");

        if (ABAddressBookHasUnsavedChanges(paramAddressBook)){
            BOOL couldSaveAddressBook = NO;
            NSErrorRef couldSaveAddressBookError = NULL;
            couldSaveAddressBook = ABAddressBookSave(paramAddressBook,
                                                       &couldSaveAddressBookError);

            if (couldSaveAddressBook){
                NSLog(@"Successfully saved the address book.");
            } else {
                CFRelease(result);
                result = NULL;
                NSLog(@"Failed to save the address book.");
            }
        } else {
            CFRelease(result);
            result = NULL;
            NSLog(@"No unsaved changes.");
        }
    } else {
        CFRelease(result);
        result = NULL;
    }
}

```

```

        NSLog(@"Could not add a new group.");
    }
} else {
    CFRelease(result);
    result = NULL;
    NSLog(@"Failed to set the name of the group.");
}

return result;
}

```

All we have to do now is to call this method to make sure that it works as expected:

```

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    ABAddressBookRef addressBook = ABAddressBookCreate();

    if (addressBook != nil){
        NSLog(@"Successfully accessed the address book.");

        ABRecordRef personalCoachesGroup =
        [self newGroupWithName:@"Personal Coaches"
            inAddressBook:addressBook];

        if (personalCoachesGroup != NULL){
            NSLog(@"Successfully created the group.");
            CFRelease(personalCoachesGroup);
        } else {
            NSLog(@"Could not create the group.");
        }

        CFRelease(addressBook);
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

After running your code, you will see the results shown in [Figure 10-4](#) (you might have created other groups before, so your address book might not look exactly like that shown in the figure).



Figure 10-4. A new group created in the address book database

10.6 Adding Persons to Groups

Problem

You want to assign a person entry in the address book to a group.

Solution

Use the `ABGroupAddMember` function.

Discussion

We learned to insert into the address book database both person entries (in [Recipe 10.4](#)) and group entries (in [Recipe 10.5](#)). We implemented two custom methods named `newPersonWithFirstName:lastName:inAddressBook:` and `newGroupWithName:inAddressBook:` in the two aforementioned recipes. Now we want to add the person entry to the group we created and save the information to the address book database. Combining these three recipes, we can use the following code to achieve our goal:

```
- (BOOL) addPerson:(ABRecordRef)paramPerson
        toGroup:(ABRecordRef)paramGroup
        saveToAddressBook:(ABAddressBookRef)paramAddressBook{

    BOOL result = NO;

    if (paramPerson == NULL ||
        paramGroup == NULL ||
        paramAddressBook == NULL){
        NSLog(@"Invalid parameters are given.");
        return NO;
    }

    CFErrorRef error = NULL;

    /* Now attempt to add the person entry to the group */
    result = ABGroupAddMember(paramGroup,
                              paramPerson,
                              &error);

    if (result == NO){
        NSLog(@"Could not add the person to the group.");
        return result;
    }

    /* Make sure we save any unsaved changes */
    if (ABAddressBookHasUnsavedChanges(paramAddressBook)){
        BOOL couldSaveAddressBook = NO;
        CFErrorRef couldSaveAddressBookError = NULL;
        couldSaveAddressBook = ABAddressBookSave(paramAddressBook,
                                                  &couldSaveAddressBookError);

        if (couldSaveAddressBook){
            NSLog(@"Successfully added the person to the group.");
            result = YES;
        } else {
            NSLog(@"Failed to save the address book.");
        }
    } else {
        NSLog(@"No changes were saved.");
    }
}
```

```

    return result;
}

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    ABAddressBookRef addressBook = ABAddressBookCreate();

    if (addressBook != nil){

        ABRecordRef richardBranson = [self newPersonWithFirstName:@"Richard"
                                                                    lastName:@"Branson"
                                                                    inAddressBook:addressBook];

        if (richardBranson != NULL){

            ABRecordRef entrepreneursGroup = [self newGroupWithName:@"Entrepreneurs"
                                                                    inAddressBook:addressBook];

            if (entrepreneursGroup != NULL){

                if ([self addPerson:richardBranson
                                toGroup:entrepreneursGroup
                                saveToAddressBook:addressBook]){

                    NSLog(@"Successfully added Richard Branson \
                        to the Entrepreneurs Group");

                } else {
                    NSLog(@"Failed to add Richard Branson to the Entrepreneurs group.");
                }

                CFRelease(entrepreneursGroup);
            } else {
                NSLog(@"Failed to create the Entrepreneurs group.");
            }

            CFRelease(richardBranson);
        } else {
            NSLog(@"Failed to create an entity for Richard Branson.");
        }

        CFRelease(addressBook);
    } else {
        NSLog(@"Address book is nil.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

We can see that the person entry we added to the “Entrepreneurs” group and to the database is, in fact, now inside this group in the address book, as shown in [Figure 10-5](#).



Figure 10-5. Adding a person to a group

See Also

[Recipe 10.5](#)

10.7 Searching the Address Book

Problem

You want to be able to find a specific person or group in the address book database.

Solution

Use the `ABAddressBookCopyArrayOfAllPeople` and `ABAddressBookCopyArrayOfAllGroups` functions to find all people and groups in the address book. Traverse the returned arrays to find the information you are looking for. Alternatively, you can use the `ABAddressBookCopyPeopleWithName` function to find person entries with a given name.

Discussion

Up to this point, we have been inserting group and person entries into the address book without checking if such a group or person already exists. We can use the `ABAddressBookCopyArrayOfAllPeople` and `ABAddressBookCopyArrayOfAllGroups` functions to get the array of all people and groups in the address book and search in the array to see if the person or group entries we are about to insert into the address book already exist. Here are two methods that will make use of these functions and that can also be used in other recipes:

```
- (BOOL) doesPersonExistWithFirstName:(NSString *)paramFirstName
                           lastName:(NSString *)paramLastName
                   inAddressBook:(ABRecordRef)paramAddressBook{

    BOOL result = NO;

    if (paramAddressBook == NULL){
        NSLog(@"The address book is null.");
        return NO;
    }

    NSArray *allPeople = (__bridge_transfer NSArray *)
        ABAddressBookCopyArrayOfAllPeople(paramAddressBook);

    NSUInteger peopleCounter = 0;
    for (peopleCounter = 0;
         peopleCounter < [allPeople count];
         peopleCounter++){

        ABRecordRef person = (__bridge ABRecordRef)
            [allPeople objectAtIndex:peopleCounter];

        NSString *firstName = (__bridge_transfer NSString *)
            ABRecordCopyValue(person, kABPersonFirstNameProperty);

        NSString *lastName = (__bridge_transfer NSString *)
            ABRecordCopyValue(person, kABPersonLastNameProperty);
```

```

    BOOL firstNameIsEqual = NO;
    BOOL lastNameIsEqual = NO;

    if ([firstName length] == 0 &&
        [paramFirstName length] == 0){
        firstNameIsEqual = YES;
    }
    else if ([firstName isEqualToString:paramFirstName]){
        firstNameIsEqual = YES;
    }

    if ([lastName length] == 0 &&
        [paramLastName length] == 0){
        lastNameIsEqual = YES;
    }
    else if ([lastName isEqualToString:paramLastName]){
        lastNameIsEqual = YES;
    }

    if (firstNameIsEqual &&
        lastNameIsEqual){
        return YES;
    }
}

return result;
}

```

Similarly, we can check the existence of a group by first retrieving the array of all the groups in the address book database, using the `ABAddressBookCopyArrayOfAllGroups` function:

```

- (BOOL) doesGroupExistWithGroupName:(NSString *)paramGroupName
    inAddressBook:(ABAddressBookRef)paramAddressBook{

    BOOL result = NO;

    if (paramAddressBook == NULL){
        NSLog(@"The address book is null.");
        return NO;
    }

    NSArray *allGroups = (__bridge_transfer NSArray *)
        ABAddressBookCopyArrayOfAllGroups(paramAddressBook);

    NSUInteger groupCounter = 0;
    for (groupCounter = 0;
         groupCounter < [allGroups count];
         groupCounter++){

        ABRecordRef group = (__bridge ABRecordRef)
            [allGroups objectAtIndex:index:groupCounter];
    }
}

```



```

NSString *groupName = (__bridge_transfer NSString *)
    ABRecordCopyValue(group, kABGroupNameProperty);

if ([groupName length] == 0 &&
    [paramGroupName length] == 0){
    return YES;
}

else if ([groupName isEqualToString:paramGroupName]){
    return YES;
}

}

return result;
}

```



Attempting to create a group with the name equal to @, (an empty string) or nil or NULL will create a new group with the name “Contacts” in the address book database. Please try to avoid creating groups with empty names or names equal to nil or NULL.

We can use the `doesGroupExistWithGroupName:inAddressBook:` method in this way:

```

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    ABAddressBookRef addressBook = ABAddressBookCreate();

    if (addressBook != NULL){

        if ([self doesGroupExistWithGroupName:@"O'Reilly"
            inAddressBook:addressBook]){
            NSLog(@"The O'Reilly group already exists in the address book.");
        } else {

            ABRecordRef oreillyGroup = [self newGroupWithName:@"O'Reilly"
                inAddressBook:addressBook];

            if (oreillyGroup != NULL){
                NSLog(@"Successfully created a group for O'Reilly.");
                CFRelease(oreillyGroup);
            } else {
                NSLog(@"Failed to create a group for O'Reilly.");
            }
        }
    }

    CFRelease(addressBook);
}

self.window = [[UIWindow alloc] initWithFrame:

```

```

        [[[UIScreen mainScreen] bounds]]];

        self.window.backgroundColor = [UIColor whiteColor];
        [self.window makeKeyAndVisible];
        return YES;
    }

```

For the implementation of the `createNewGroupWithName:inAddressBook:` method, please refer to [Recipe 10.5](#).

As we saw earlier, we have two ways of finding a person in the address book database:

- Retrieving the array of all people in the address book, using the `ABAddressBookCopyArrayOfAllPeople` function. We then get each record inside the array and compare the first and last name properties of each person with the strings we are looking for. This function helps you find the exact match you are looking for. You can search in any of the properties assigned to that person in the address book, including first name, last name, email, phone number, and so on.
- Asking the Address Book framework to perform the search based on a composite name for us. This is done using the `ABAddressBookCopyPeopleWithName` function.

Here is an example of using the `ABAddressBookCopyPeopleWithName` function to search for a contact with a specific name:

```

- (BOOL) doesPersonExistWithFullName:(NSString *)paramFullName
    inAddressBook:(ABAddressBookRef)paramAddressBook{

    BOOL result = NO;

    if (paramAddressBook == NULL){
        NSLog(@"Address book is null.");
        return NO;
    }

    NSArray *allPeopleWithThisName = (__bridge_transfer NSArray *)
    ABAddressBookCopyPeopleWithName(paramAddressBook,
        (__bridge CFStringRef)paramFullName);

    if ([allPeopleWithThisName count] > 0){
        result = YES;
    }

    return result;
}

```

Here is how we can use this method that we just implemented:

```

- (BOOL) application:(UIApplication *)application
    didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    ABAddressBookRef addressBook = ABAddressBookCreate();

    if (addressBook != NULL){

```

```

if ([self doesPersonExistWithFullName:@"Anthony Robbins"
    inAddressBook:addressBook]){
    NSLog(@"Anthony Robbins exists in the address book.");
} else {
    NSLog(@"Anthony Robbins does not exist in the address book.");

    ABRecordRef anthonyRobbins = [self newPersonWithFirstName:@"Anthony"
        lastName:@"Robbins"
        inAddressBook:addressBook];

    if (anthonyRobbins != NULL){
        NSLog(@"Successfully created a record for Anthony Robbins");
        CFRelease(anthonyRobbins);
    } else {
        NSLog(@"Failed to create a record for Anthony Robbins");
    }
}

CFRelease(addressBook);
}

self.window = [[UIWindow alloc] initWithFrame:
    [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

Using this function, we won't have to know the full name to be able to find a contact in the address book. We can just pass a part of the name—for instance, just the first name—in order to find all the contacts with that specific first name.



The search performed by the `ABAddressBookCopyPeopleWithName` function is case-insensitive.

10.8 Retrieving and Setting a Person's Address Book Image

Problem

You want to be able to retrieve and set the images of address book people entries.

Solution

Use one of the following functions:

ABPersonHasImageData

Use this function to find out if an address book entry has an image set.

ABPersonCopyImageData

Use this function to retrieve the image data (if any).

ABPersonSetImageData

Use this function to set the image data for an entry.

Discussion

As mentioned in this recipe's [Solution](#), we can use the `ABPersonCopyImageData` function to retrieve the data associated with an image of a person entry in the address book. We can use this function in a method of our own to make it more convenient to use:

```
- (UIImage *) getPersonImage:(ABRecordRef)paramPerson{

    UIImage *result = nil;

    if (paramPerson == NULL){
        NSLog(@"The person is nil.");
        return NULL;
    }

    NSData *imageData = (__bridge_transfer NSData *)
        ABPersonCopyImageData(paramPerson);

    if (imageData != nil){
        UIImage *image = [UIImage imageWithData:imageData];
        result = image;
    }

    return result;
}
```

The `ABPersonSetImageData` function sets the image data for a person entry in the address book. Since this function uses data, not the image itself, we need to get `NSData` from `UIImage`. If we want the data pertaining to a PNG image, we can use the `UIImagePNGRepresentation` function to retrieve the PNG `NSData` representation of the image of type `UIImage`. To retrieve JPEG image data from an instance of `UIImage`, use the `UIImageJPEGRepresentation` function. Here is the method that will allow you to set the image of a person entry in the address book database:

```
- (BOOL) setPersonImage:(ABRecordRef)paramPerson
    inAddressBook:(ABAddressBookRef)paramAddressBook
    withImageData:(NSData *)paramImageData{

    BOOL result = NO;

    if (paramAddressBook == NULL){
        NSLog(@"The address book is nil.");
        return NO;
    }
}
```

```

if (paramPerson == NULL){
    NSLog(@"The person is nil.");
    return NO;
}

NSErrorRef couldSetPersonImageError = NULL;

BOOL couldSetPersonImage =
ABPersonSetImageData(paramPerson,
    (__bridge CFDataRef)paramImageData,
    &couldSetPersonImageError);

if (couldSetPersonImage){
    NSLog(@"Successfully set the person's image. Saving...");
    if (ABAddressBookHasUnsavedChanges(paramAddressBook)){
        BOOL couldSaveAddressBook = NO;
        NSErrorRef couldSaveAddressBookError = NULL;
        couldSaveAddressBook = ABAddressBookSave(paramAddressBook,
            &couldSaveAddressBookError);

        if (couldSaveAddressBook){
            NSLog(@"Successfully saved the address book.");
            result = YES;
        } else {
            NSLog(@"Failed to save the address book.");
        }
    } else {
        NSLog(@"There are no changes to be saved!");
    }
} else {
    NSLog(@"Failed to set the person's image.");
}

return result;
}

```

Now let's write a simple application to demonstrate use of these methods. In this example code, we want to achieve the following:

- Create a simple view controller with two labels and two image views.
- Attempt to retrieve a contact with the first name “Anthony” and the last name “Robbins” from our address book. If this contact doesn't exist, we will create it.
- Retrieve the previous image (if any) of the contact and display it in the first image view (the top image view).
- Set a new image for the contact, retrieved from our application bundle, and display the new image in the second image view (the bottom image view).

Let's get started. Here is the *.h* file of our view controller:

```

#import <UIKit/UIKit.h>
#import <AddressBook/AddressBook.h>

```

```

@interface Retrieving_and_Setting_a_Person_s_Address_Book_ImageViewController
    : UIViewController

@property (nonatomic, strong) UILabel *labelOldImage;
@property (nonatomic, strong) UIImageView *imageViewOld;

@property (nonatomic, strong) UILabel *labelNewImage;
@property (nonatomic, strong) UIImageView *imageViewNew;

@end

```

Now let's go ahead and synthesize our properties:

```

#import "Retrieving_and_Setting_a_Person_s_Address_Book_ImageViewController.h"

@implementation
    Retrieving_and_Setting_a_Person_s_Address_Book_ImageViewController

@synthesize labelOldImage;
@synthesize imageViewOld;
@synthesize labelNewImage;
@synthesize imageViewNew;

...

```

Next stop is the `viewDidLoad` method of our view controller where we will instantiate our labels and image views and place them on our view controller's view:

```

- (void) changeYPositionOfView:(UIView *)paramView
    to:(CGFloat)paramY{

    CGRect viewFrame = paramView.frame;
    viewFrame.origin.y = paramY;
    paramView.frame = viewFrame;

}

- (void) createLabelAndImageViewForOldImage{

    self.labelOldImage = [[UILabel alloc] initWithFrame:CGRectZero];
    self.labelOldImage.text = @"Old Image";
    self.labelOldImage.font = [UIFont systemFontOfSize:16.0f];
    [self.labelOldImage sizeToFit];
    self.labelOldImage.center = self.view.center;
    [self.view addSubview:self.labelOldImage];
    [self changeYPositionOfView:self.labelOldImage
        to:80.0f];

    self.imageViewOld = [[UIImageView alloc] initWithFrame:CGRectMake(0.0f,
                                                                    0.0f,
                                                                    100.0f,
                                                                    100.0f)];

    self.imageViewOld.center = self.view.center;
    self.imageViewOld.contentMode = UIViewContentModeScaleAspectFit;
    [self.view addSubview:self.imageViewOld];
    [self changeYPositionOfView:self.imageViewOld

```

```

        to:105.0f];
    }

    - (void) createLabelAndImageViewForNewImage{

        self.labelNewImage = [[UILabel alloc] initWithFrame:CGRectZero];
        self.labelNewImage.text = @"New Image";
        self.labelNewImage.font = [UIFont systemFontOfSize:16.0f];
        [self.labelNewImage sizeToFit];
        self.labelNewImage.center = self.view.center;
        [self.view addSubview:self.labelNewImage];
        [self changeYPositionOfView:self.labelNewImage
         to:210.0f];

        self.imageViewNew = [[UIImageView alloc] initWithFrame:CGRectMake(0.0f,
                                                                           0.0f,
                                                                           100.0f,
                                                                           100.0f)];

        self.imageViewNew.center = self.view.center;
        self.imageViewNew.contentMode = UIViewContentModeScaleAspectFit;
        [self.view addSubview:self.imageViewNew];
        [self changeYPositionOfView:self.imageViewNew
         to:235.0f];
    }

    - (void)viewDidLoad{
        [super viewDidLoad];

        self.view.backgroundColor = [UIColor whiteColor];
        [self createLabelAndImageViewForOldImage];
        [self createLabelAndImageViewForNewImage];
    }

    - (void)viewDidUnload{
        [super viewDidUnload];
        self.labelOldImage = nil;
        self.imageViewOld = nil;
        self.labelNewImage = nil;
        self.imageViewNew = nil;
    }
}

```

Now we need to modify our `viewDidLoad` method a little bit so that we can read a person's image from the address book and then set his image and display the new one, using the functions we've learnt about in this and other recipes in this chapter:

```

- (ABRecordRef) getPersonWithFirstName:(NSString *)paramFirstName
                                lastName:(NSString *)paramLastName
                                inAddressBook:(ABRecordRef)paramAddressBook{

    ABRecordRef result = NULL;

    if (paramAddressBook == NULL){

```

```

        NSLog(@"The address book is null.");
        return NULL;
    }

    NSArray *allPeople = (__bridge_transfer NSArray *)
    ABAddressBookCopyArrayOfAllPeople(paramAddressBook);

    NSUInteger peopleCounter = 0;
    for (peopleCounter = 0;
         peopleCounter < [allPeople count];
         peopleCounter++){

        ABRecordRef person = (__bridge ABRecordRef)
        [allPeople objectAtIndex:peopleCounter];

        NSString *firstName = (__bridge_transfer NSString *)
        ABRecordCopyValue(person, kABPersonFirstNameProperty);

        NSString *lastName = (__bridge_transfer NSString *)
        ABRecordCopyValue(person, kABPersonLastNameProperty);

        BOOL firstNameIsEqual = NO;
        BOOL lastNameIsEqual = NO;

        if ([firstName length] == 0 &&
            [paramFirstName length] == 0){
            firstNameIsEqual = YES;
        }
        else if ([firstName isEqualToString:paramFirstName]){
            firstNameIsEqual = YES;
        }

        if ([lastName length] == 0 &&
            [paramLastName length] == 0){
            lastNameIsEqual = YES;
        }
        else if ([lastName isEqualToString:paramLastName]){
            lastNameIsEqual = YES;
        }

        if (firstNameIsEqual &&
            lastNameIsEqual){
            return person;
        }
    }

    return result;
}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];
}

```



```

[self createLabelAndImageViewForOldImage];
[self createLabelAndImageViewForNewImage];

ABAddressBookRef addressBook = ABAddressBookCreate();

if (addressBook != NULL){

    ABRecordRef anthonyRobbins = [self getPersonWithFirstName:@"Anthony"
                                                                    lastName:@"Robbins"
                                                                    inAddressBook:addressBook];

    if (anthonyRobbins == NULL){
        NSLog(@"Couldn't find record. Creating one...");
        anthonyRobbins = [self newPersonWithFirstName:@"Anthony"
                                                                    lastName:@"Robbins"
                                                                    inAddressBook:addressBook];

        if (anthonyRobbins == NULL){
            NSLog(@"Failed to create a new record for this person.");
            CFRelease(addressBook);
            return;
        }
    }

    self.imageViewOld.image = [self getPersonImage:anthonyRobbins];

    NSString *newImageFilePath =
    [[NSBundle mainBundle] pathForResource:@"Anthony Robbins"
                                         ofType:@"jpg"];

    UIImage *newImage = [[UIImage alloc]
                          initWithContentsOfFile:newImageFilePath];

    NSData *newImageData = UIImagePNGRepresentation(newImage);

    if ([self setPersonImage:anthonyRobbins
                        inAddressBook:addressBook
                        withImageData:newImageData]){
        NSLog(@"Successfully set this person's new image.");
        self.imageViewNew.image = [self getPersonImage:anthonyRobbins];
    } else {
        NSLog(@"Failed to set this person's new image.");
    }

    CFRelease(anthonyRobbins);
    CFRelease(addressBook);
}
}

```

The results are shown here:




Figure 10-6. The old image for a contact is replaced by a new one

Camera and the Photo Library

11.0 Introduction

Devices running iOS, such as the iPhone, are equipped with cameras—for instance, the iPhone 4 has two cameras and the iPhone 3G and 3GS each have one. Some iOS devices, such as the first generation of the iPad, do not have cameras. The `UIImagePickerController` class allows programmers to display the familiar Camera interface to their users and ask them to take a photo or shoot a video. The photos taken or the videos shot by the user with the `UIImagePickerController` class then become accessible to the programmer.

In this chapter, you will learn how to let users take photos and shoot videos from inside applications, access these photos and videos, and access the photos and videos that are placed inside the Photo Library on an iOS device such as the iPod Touch and iPad.



iOS Simulator does not support the Camera interface. Please test and debug all your applications that require a Camera interface on a real device.

In this chapter, first we will attempt to determine if a camera is available on the iOS device that is running our application. You can also determine whether the camera allows you (the programmer) to capture videos, images, or both. To do this, make sure you have added the `MobileCoreServices.framework` framework to your target by following these steps:

1. Click on your project's icon in Xcode.
2. Select the target to which you want to add the framework.
3. On the top of the screen, select the Build Phases tab.
4. In the Build Phases screen, expand the Link Binary with Libraries box and press the little + button on the bottom left corner of that box.

5. Choose `MobileCoreServices.framework` from the list.
6. Click the Add button.

We will then move to other topics, such as accessing videos and photos from different albums on an iOS device. These are the same albums that are accessible through the Photos application built into iOS.

Accessing photos inside albums is more straightforward than accessing videos, however. For photos, we will be given the address of the photo and we can simply load the data of the image either in an instance of `NSData` or directly into an instance of `UIImage`. For videos, we won't be given a file address on the filesystem from which to load the data of the video. Instead, we will be given an address such as this:

```
assets-library://asset/asset.MOV?id=1000000004&ext=MOV
```

For addresses such as this, we need to use the Assets Library framework. The Assets Library framework allows us to access the contents accessible through the Photos application, such as videos and photos shot by the user. You can also use the Assets Library framework to save images and videos on the device. These photos and videos will then become accessible by the Photo Library as well as other applications that wish to access these contents.

To make sure the recipes in this chapter compile correctly, follow these steps to add the Assets Library framework to your target:

1. Click on your project's icon in Xcode.
2. Select the target to which you want to add the framework.
3. On the top of the screen, select the Build Phases tab.
4. In the Build Phases screen, expand the Link Binary with Libraries box and press the little + button on the bottom left corner of that box.
5. Choose `AssetsLibrary.framework` from the list.
6. Click the Add button.

To access the data of an asset given the URL to the asset, follow these steps:

1. Allocate and initialize an object of type `ALAssetsLibrary`. The Assets Library object facilitates the bridge that you need in order to access the videos and photos accessible by the Photos application.
2. Use the `assetForURL:resultBlock:failureBlock` instance method of the Assets Library object (allocated and initialized in step 1) to access the asset. An asset could be an image, a video, or any other resource available to the Photo Library. This method works with block objects. For more information about block objects and GCD, please refer to [Chapter 5](#).
3. Release the Assets Library object allocated and initialized in step 1.

At this point, you might be wondering: how do I access the data for the asset? The `resultBlock` parameter of the `assetForURL:resultBlock:failureBlock` instance method of the Assets Library object will need to point to a block object that accepts a single parameter of type `ALAsset`. `ALAsset` is a class provided by the Assets Library that encapsulates an asset available to Photos and any other iOS application that wishes to use these assets. For more information about storing photos and videos in the Photo Library, please refer to [Recipe 11.4](#) and [Recipe 11.5](#). If you want to learn more about retrieving photos and videos from the Photo Library and the Assets Library, please refer to [Recipe 11.6](#) and [Recipe 11.7](#).

11.1 Detecting and Probing the Camera

Problem

You want to know whether the iOS device running your application has a camera that you can access. This is an important check to make before attempting to use the camera, unless you are sure your application will never run on a device that lacks one.

Solution

Use the `isSourceTypeAvailable:` class method of `UIImagePickerController` with the `UIImagePickerControllerSourceTypeCamera` value, like so:

```
- (BOOL) isCameraAvailable{

    return [UIImagePickerController isSourceTypeAvailable:
           UIImagePickerControllerSourceTypeCamera];

}

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    if ([self isCameraAvailable]){
        NSLog(@"Camera is available.");
    } else {
        NSLog(@"Camera is not available.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
                   [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

Discussion

Before attempting to display an instance of `UIImagePickerController` to your user for taking photos or shooting videos, you must detect whether the device supports that interface. The `isSourceTypeAvailable:` class method allows you to determine three sources of data:

- The camera, by passing the `UIImagePickerControllerSourceTypeCamera` value to this method.
- The Photo Library, by passing the `UIImagePickerControllerSourceTypePhotoLibrary` value to this method. This browses the root folder of the *Photos* directory on the device.
- The camera roll folder in the *Photos* directory, by passing the `UIImagePickerControllerSourceTypeSavedPhotosAlbum` value to this method.

If you want to check the availability of any of these facilities on an iOS device, you must pass these values to the `isSourceTypeAvailable:` class method of `UIImagePickerController` before attempting to present the interfaces to the user.

Now in the *.h* or the *.m* file of your object(s) (depending on your requirements), import the main header file of the framework we just added. Here I will import these framework into the *.h* file of my app delegate:

```
#import <UIKit/UIKit.h>
#import <AssetsLibrary/AssetsLibrary.h>
#import <MobileCoreServices/MobileCoreServices.h>

@interface Detecting_and_Probing_the_CameraAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (strong, nonatomic) UIWindow *window;

@end
```

Now we can use the `isSourceTypeAvailable:` and `availableMediaTypesForSourceType:` class methods of `UIImagePickerController` to determine first if a media source is available (camera, Photo Library, etc.), and if so, whether media types such as image and video are available on that media source:

```
- (BOOL) cameraSupportsMedia:(NSString *)paramMediaType
    sourceType:(UIImagePickerControllerSourceType)paramSourceType{

    __block BOOL result = NO;

    if ([paramMediaType length] == 0){
        NSLog(@"Media type is empty.");
        return NO;
    }

    NSArray *availableMediaTypes =
        [UIImagePickerController availableMediaTypesForSourceType:paramSourceType];
```

```

[availableMediaTypes enumerateObjectsUsingBlock:
^(id obj, NSUInteger idx, BOOL *stop) {

    NSString *mediaType = (NSString *)obj;
    if ([mediaType isEqualToString:paramMediaType]){
        result = YES;
        *stop= YES;
    }

}];

return result;
}

- (BOOL) doesCameraSupportShootingVideos{

    return [self cameraSupportsMedia:(__bridge NSString *)kUTTypeMovie
        sourceType:UIImagePickerControllerSourceTypeCamera];

}

- (BOOL) doesCameraSupportTakingPhotos{

    return [self cameraSupportsMedia:(__bridge NSString *)kUTTypeImage
        sourceType:UIImagePickerControllerSourceTypeCamera];

}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    if ([self doesCameraSupportTakingPhotos]){
        NSLog(@"The camera supports taking photos.");
    } else {
        NSLog(@"The camera does not support taking photos");
    }

    if ([self doesCameraSupportShootingVideos]){
        NSLog(@"The camera supports shooting videos.");
    } else {
        NSLog(@"The camera does not support shooting videos.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

Some iOS devices could have more than one camera. The two cameras might be called the front and the rear cameras. To determine whether these cameras are available, use the `isCameraDeviceAvailable:` class method of `UIImagePickerController`, like so:

```
- (BOOL) isFrontCameraAvailable{

    return [UIImagePickerController
            isCameraDeviceAvailable:UIImagePickerControllerCameraDeviceFront];

}

- (BOOL) isRearCameraAvailable{

    return [UIImagePickerController
            isCameraDeviceAvailable:UIImagePickerControllerCameraDeviceRear];

}
```

By calling these methods on an older iPhone with no rear camera, you will see that the `isFrontCameraAvailable` method returns `NO` and the `isRearCameraAvailable` method returns `YES`. Running the code on an iPhone with both the front and rear cameras will prove that both methods will return `YES`, as iPhone 4 devices are equipped with both front- and rear-facing cameras.

If detecting which camera is present on a device isn't enough for your application, you can retrieve other settings using the `UIImagePickerController` class. One such setting is whether flash capability is available for a camera on the device. You can use the `isFlashAvailableForCameraDevice:` class method of `UIImagePickerController` to determine the availability of a flash capability on the rear or front camera. Please bear in mind that the `isFlashAvailableForCameraDevice:` class method of `UIImagePickerController` checks the availability of the given camera device first, before checking the availability of a flash capability on that camera. Therefore, you can run the methods we will implement on devices that do not have front or rear cameras without a need to first check if the camera is available.

```
- (BOOL) isFlashAvailableOnFrontCamera{

    return [UIImagePickerController isFlashAvailableForCameraDevice:
            UIImagePickerControllerCameraDeviceFront];

}

- (BOOL) isFlashAvailableOnRearCamera{

    return [UIImagePickerController isFlashAvailableForCameraDevice:
            UIImagePickerControllerCameraDeviceRear];

}
```

Now if we take advantage of all the methods that we wrote in this recipe and test them in your app delegate (for example) we can see the results on different devices:


```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    if ([self isFrontCameraAvailable]){
        NSLog(@"The front camera is available.");
        if ([self isFlashAvailableOnFrontCamera]){
            NSLog(@"The front camera is equipped with a flash");
        } else {
            NSLog(@"The front camera is not equipped with a flash");
        }
    } else {
        NSLog(@"The front camera is not available.");
    }

    if ([self isRearCameraAvailable]){
        NSLog(@"The rear camera is available.");
        if ([self isFlashAvailableOnRearCamera]){
            NSLog(@"The rear camera is equipped with a flash");
        } else {
            NSLog(@"The rear camera is not equipped with a flash");
        }
    } else {
        NSLog(@"The rear camera is not available.");
    }

    if ([self doesCameraSupportTakingPhotos]){
        NSLog(@"The camera supports taking photos.");
    } else {
        NSLog(@"The camera does not support taking photos");
    }

    if ([self doesCameraSupportShootingVideos]){
        NSLog(@"The camera supports shooting videos.");
    } else {
        NSLog(@"The camera does not support shooting videos.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

Here are the results when we run the application on an iPhone 4:

```

The front camera is available.
The front camera is not equipped with a flash
The rear camera is available.
The rear camera is equipped with a flash
The camera supports taking photos.
The camera supports shooting videos.

```

Here is the output of the same code when run on an iPhone 3GS:

```
The front camera is not available.  
The rear camera is available.  
The rear camera is not equipped with a flash  
The camera supports taking photos.  
The camera supports shooting videos.
```

Running the same code on the first generation iPad will result in this output in the console window:

```
The front camera is not available.  
The rear camera is not available.  
The camera does not support taking photos  
The camera does not support shooting videos
```

Running the same code on the iPad 2 will result in this output in the console window:

```
The front camera is available.  
The front camera is not equipped with a flash  
The rear camera is available.  
The rear camera is not equipped with a flash  
The camera supports taking photos.  
The camera supports shooting videos.
```

11.2 Taking Photos with the Camera

Problem

You want to ask the user to take a photo with the camera on his iOS device, and you want to access that photo once the user is done.

Solution

Instantiate an object of type `UIImagePickerController` and present it as a modal view controller on your current view controller. Here is the `.h` file of our view controller:

```
#import <UIKit/UIKit.h>  
#import <AssetsLibrary/AssetsLibrary.h>  
#import <MobileCoreServices/MobileCoreServices.h>  
  
@interface Taking_Photos_with_the_CameraViewController  
    : UIViewController <UINavigationControllerDelegate,  
                        UIImagePickerControllerDelegate>  
  
@end
```

The delegate of an instance of `UIImagePickerController` must conform to the `UINavigationControllerDelegate` and `UIImagePickerControllerDelegate` protocols. If you forget to include them in the `.h` file of your delegate object, you'll get warnings from the compiler when assigning a value to the delegate property of your image picker controller. Please bear in mind that you can still assign an object to the delegate property of an instance of `UIImagePickerController` where that object does not explicitly conform to the `UIImagePickerControllerDelegate` and `UINavigationControllerDelegate`

protocols, but implements the required methods in these protocols. I, however, suggest that you give a hint to the compiler that the delegate object does, in fact, conform to the aforementioned protocols in order to avoid getting compiler warnings.

In the implementation of our view controller (*.m* file), we will attempt to display an image picker controller as a modal view controller, like so:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    if ([self isCameraAvailable] &&
        [self doesCameraSupportTakingPhotos]){

        UIImagePickerController *controller =
            [[UIImagePickerController alloc] init];

        controller.sourceType = UIImagePickerControllerSourceTypeCamera;

        NSString *requiredMediaType = (__bridge NSString *)kUTTypeImage;
        controller.mediaTypes = [[NSArray alloc]
            initWithObjects:requiredMediaType, nil];

        controller.allowsEditing = YES;
        controller.delegate = self;

        [self.navigationController presentViewController:controller
            animated:YES];

    } else {
        NSLog(@"Camera is not available.");
    }
}
```



We are using the `isCameraAvailable` and `doesCameraSupportTakingPhotos` methods in this example. These methods are implemented and explained in [Recipe 11.1](#).

In this example, we are allowing the user to take photos using the image picker. You must have noticed that we are setting the delegate property of the image picker to `self`, which refers to our view controller. For this, we have to make sure we have implemented the methods defined in the `UIImagePickerControllerDelegate` protocol, like so:

```
- (void) imagePickerController:(UIImagePickerController *)picker
didFinishPickingMediaWithInfo:(NSDictionary *)info{

    NSLog(@"Picker returned successfully.");

    NSString *mediaType = [info objectForKey:
        UIImagePickerControllerMediaType];
```

```

if ([mediaType isEqualToString:(__bridge NSString *)kUTTypeMovie]){

    NSURL *urlOfVideo =
    [info objectForKey:UIImagePickerControllerMediaURL];

    NSLog(@"Video URL = %@", urlOfVideo);

}

else if ([mediaType isEqualToString:(__bridge NSString *)kUTTypeImage]){

    /* Let's get the metadata. This is only for
    images. Not videos */

    NSDictionary *metadata =
    [info objectForKey:
    UIImagePickerControllerMediaMetadata];

    UIImage *theImage =
    [info objectForKey:
    UIImagePickerControllerOriginalImage];

    NSLog(@"Image Metadata = %@", metadata);
    NSLog(@"Image = %@", theImage);

}

[picker dismissModalViewControllerAnimated:YES];

}

- (void)imagePickerControllerDidCancel:(UIImagePickerController *)picker{

    NSLog(@"Picker was cancelled");
    [picker dismissModalViewControllerAnimated:YES];

}

```

Discussion

There are a couple of important things that you must keep in mind about the image picker controller's delegate. First, two delegate messages are called on the delegate object of the image picker controller. The `imagePickerController:didFinishPickingMediaWithInfo:` method gets called when the user finishes execution of the image picker (e.g., takes a photo and presses a button at the end), whereas the `imagePickerControllerDidCancel:` method gets called when the image picker's operation is cancelled.

Also, the `imagePickerController:didFinishPickingMediaWithInfo:` delegate method contains information about the item that was captured by the user, be it an image or a video. The `didFinishPickingMediaWithInfo` parameter is a dictionary of values that tell you what the image picker has captured and the metadata of that item, along with other

useful information. The first thing you have to do in this method is to read the value of the `UIImagePickerControllerMediaType` key in this dictionary. The object for this key is an instance of `NSString` that could be one of these values:

`kUTTypeImage`

For a photo that was shot by the camera

`kUTTypeMovie`

For a movie/video that was shot by the camera



The `kUTTypeImage` and `kUTTypeMovie` values are available in the Mobile Core Services framework and are of type `CFStringRef`. You can simply typecast these values to `NSString` if needed.

After determining the type of resource created by the camera (video or photo), you can access that resource's properties using the `didFinishPickingMediaWithInfo` dictionary parameter again.

For images (`kUTTypeImage`), you can access these keys:

`UIImagePickerControllerMediaMetadata`

This key's value is an object of type `NSDictionary`. This dictionary contains a lot of useful information about the image that was shot by the user. A complete discussion of the values inside this dictionary is beyond the scope of this chapter.

`UIImagePickerControllerOriginalImage`

This key's value is an object of type `UIImage` containing the image that was shot by the user.

`UIImagePickerControllerCropRect`

If editing is enabled (using the `allowsEditing` property of `UIImagePickerController`), the object of this key will contain the rectangle of the cropped area.

`UIImagePickerControllerEditedImage`

If editing is enabled (using the `allowsEditing` property of `UIImagePickerController`), this key's value will contain the edited (resized and scaled) image.

For videos (`kUTTypeMovie`) that are shot by the user, you can access the `UIImagePickerControllerMediaURL` key in the `didFinishPickingMediaWithInfo` dictionary parameter of the `imagePickerController:didFinishPickingMediaWithInfo:` method. The value of this key is an object of type `NSURL` containing the URL of the video that was shot by the user.

After you get a reference to the `UIImage` instance that the user took with the camera, you can simply use that instance within your application.



The images that are shot by the image picker controller within your application are not saved to the camera roll by default.

See Also

[Recipe 11.1](#)

11.3 Taking Videos with the Camera

Problem

You want to allow your users to shoot a video using their iOS device, and you would like to be able to use that video from inside your application.

Solution

Use `UIImagePickerController` with the `UIImagePickerControllerSourceTypeCamera` source type and the `kUTTypeMovie` media type:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    if ([self isCameraAvailable] &&
        [self doesCameraSupportTakingPhotos]){

        UIImagePickerController *controller =
            [[UIImagePickerController alloc] init];

        controller.sourceType = UIImagePickerControllerSourceTypeCamera;

        NSString *requiredMediaType = (__bridge NSString *)kUTTypeMovie;
        controller.mediaTypes = [[NSArray alloc]
                                initWithObjects:requiredMediaType, nil];

        controller.allowsEditing = YES;
        controller.delegate = self;

        [self.navigationController presentViewController:controller
                                                animated:YES];

    } else {
        NSLog(@"Camera is not available.");
    }
}
```



The `isCameraAvailable` and `doesCameraSupportShootingVideos` methods used in this sample code are implemented and discussed in [Recipe 11.1](#).

We will implement the delegate methods of our image picker controller like so:

```
- (void) imagePickerController:(UIImagePickerController *)picker
didFinishPickingMediaWithInfo:(NSDictionary *)info{

    NSLog(@"Picker returned successfully.");

    NSLog(@"%@", info);

    NSString *mediaType = [info objectForKey:
                           UIImagePickerControllerMediaType];

    if ([mediaType isEqualToString:(__bridge NSString *)kUTTypeMovie]){

        NSURL *urlOfVideo =
        [info objectForKey:UIImagePickerControllerMediaURL];

        NSLog(@"Video URL = %@", urlOfVideo);

        NSError *dataReadingError = nil;

        NSData *videoData =
        [NSData dataWithContentsOfURL:urlOfVideo
                     options:NSDataReadingMapped
                     error:&dataReadingError];

        if (videoData != nil){
            /* We were able to read the data */
            NSLog(@"Successfully loaded the data.");
        } else {
            /* We failed to read the data. Use the dataReadingError
            variable to determine what the error is */
            NSLog(@"Failed to load the data with error = %@",
                  dataReadingError);
        }
    }

    [picker dismissModalViewControllerAnimated:YES];
}

- (void)imagePickerControllerDidCancel:(UIImagePickerController *)picker{

    NSLog(@"Picker was cancelled");
    [picker dismissModalViewControllerAnimated:YES];
}
```

Discussion

Once you detect that the iOS device your application is running on supports video recording, you can bring up the image picker controller with the `UIImagePickerControllerSourceTypeCamera` source type and `kUTTypeMovie` media type to allow the users of your application to shoot videos. Once they are done, the `imagePickerController:didFinishPickingMediaWithInfo:` delegate method will get called and you can use the `didFinishPickingMediaWithInfo` dictionary parameter to find out more about the captured video (the values that can be placed inside this dictionary are thoroughly explained in [Recipe 11.2](#)).

When the user shoots a video using the image picker controller, the video will be saved in a temporary folder inside your application's bundle, not inside the camera roll. An example of such a URL is:

```
file://localhost/private/var/mobile/Applications          /<APPID>/tmp/capture-
T0x104e20.tmp.TQ9UTr/capturedvideo.MOV
```



The value *APPID* in the URL represents your application's unique identifier, and will clearly be different depending on your application.

As the programmer, not only can you allow your users to shoot videos from inside your application, but also you can modify how the videos are captured. You can change two important properties of the `UIImagePickerController` class in order to modify the default behavior of video recording:

`videoQuality`

This property specifies the quality of the video. You can choose a value such as `UIImagePickerControllerQualityTypeHigh` or `UIImagePickerControllerQualityTypeMedium` for the value of this property.

`videoMaximumDuration`

This property specifies the maximum duration of the video. This value is measured in seconds.

For instance, if we were to allow our users to record high-quality videos for up to 30 seconds, we could simply modify the values of the aforementioned properties of our instance of `UIImagePickerController` like so:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    if ([self isCameraAvailable] &&
        [self doesCameraSupportTakingPhotos]){

        UIImagePickerController *controller =
            [[UIImagePickerController alloc] init];
```



```

        controller.sourceType = UIImagePickerControllerSourceTypeCamera;

        NSString *requiredMediaType = (__bridge NSString *)kUTTypeMovie;
        controller.mediaTypes = [[NSArray alloc]
                                   initWithObjects:requiredMediaType, nil];

        controller.allowsEditing = YES;
        controller.delegate = self;

        /* Record in high quality */
        controller.videoQuality = UIImagePickerControllerQualityTypeHigh;

        /* Only allow 30 seconds of recording */
        controller.videoMaximumDuration = 30.0f;

        [self.navigationController presentViewController:controller
                                                  animated:YES];

    } else {
        NSLog(@"Camera is not available.");
    }
}

```

See Also

[Recipe 11.1](#)

11.4 Storing Photos in the Photo Library

Problem

You want to be able to store a photo in the user's photo library.

Solution

Use the `UIImageWriteToSavedPhotosAlbum` procedure:

```

- (void) imageWasSavedSuccessfully:(UIImage *)paramImage
    didFinishSavingWithError:(NSError *)paramError
    contextInfo:(void *)paramContextInfo{

    if (paramError == nil){
        NSLog(@"Image was saved successfully.");
    } else {
        NSLog(@"An error happened while saving the image.");
        NSLog(@"Error = %@", paramError);
    }

}

- (void) UIImagePickerController:(UIImagePickerController *)picker

```

```

didFinishPickingMediaWithInfo:(NSDictionary *)info{

    NSLog(@"Picker returned successfully.");

    NSLog(@"%@", info);

    NSString *mediaType = [info objectForKey:
                           UIImagePickerControllerMediaType];

    if ([mediaType isEqualToString:(__bridge NSString *)kUTTypeImage]){

        UIImage *theImage = nil;

        if ([picker allowsEditing]){
            theImage = [info objectForKey:UIImagePickerControllerEditedImage];
        } else {
            theImage = [info objectForKey:UIImagePickerControllerOriginalImage];
        }

        SEL selectorToCall =
            @selector(imageWasSavedSuccessfully:didFinishSavingWithError:contextInfo:);

        UIImageWriteToSavedPhotosAlbum(theImage,
                                       self,
                                       selectorToCall,
                                       NULL);

    }

    [picker dismissModalViewControllerAnimated:YES];
}

- (void)imagePickerControllerDidCancel:(UIImagePickerController *)picker{

    NSLog(@"Picker was cancelled");
    [picker dismissModalViewControllerAnimated:YES];
}

- (void)viewDidLoad{
    [super viewDidLoad];

    if ([self isCameraAvailable] &&
        [self doesCameraSupportTakingPhotos]){

        UIImagePickerController *controller =
            [[UIImagePickerController alloc] init];

        controller.sourceType = UIImagePickerControllerSourceTypeCamera;

        NSString *requiredMediaType = (__bridge NSString *)kUTTypeImage;
        controller.mediaTypes = [[NSArray alloc]
                                initWithObjects:requiredMediaType, nil];
    }
}

```

```

controller.allowsEditing = YES;
controller.delegate = self;

[self.navigationController presentViewController:controller
                                     animated:YES];

} else {
    NSLog(@"Camera is not available.");
}

}

```



The `isCameraAvailable` and `doesCameraSupportTakingPhotos` methods used in this example are thoroughly explained in [Recipe 11.1](#).

Discussion

Usually after a user is done taking a photo with her iOS device, she expects the photo to be saved into her photo library. However, applications that are not originally shipped with iOS can ask the user to take a photo, using the `UIImagePickerController` class, and then process that image. In this case, the user will understand that the application provided by us might not save the photo to her photo library and might simply use it internally. For instance, if an instant messaging application allows users to transfer their photos to each other's devices, the user will understand that a photo she takes inside the application will not be saved to her photo library, but will instead be transferred over the Internet to the other user.

However, if you decide you want to store an instance of `UIImage` to the photo library on the user's device, you can use the `UIImageWriteToSavedPhotosAlbum` function. This function accepts four parameters:

1. The image
2. The object that will get notified whenever the image is fully saved
3. A parameter that specifies the selector that has to be called on the target object (specified by the second parameter) when the save operation finishes
4. A context value that will get passed to the specified selector once the operation is done

Providing the second, third, and fourth parameters to this procedure is optional. If you do provide the second and third parameters, the fourth parameter still remains optional. For instance, this is the selector we have chosen in our example:

```

- (void) imageWasSavedSuccessfully:(UIImage *)paramImage
    didFinishSavingWithError:(NSError *)paramError
    contextInfo:(void *)paramContextInfo{

    if (paramError == nil){

```

```

        NSLog(@"Image was saved successfully.");
    } else {
        NSLog(@"An error happened while saving the image.");
        NSLog(@"Error = %@", paramError);
    }
}

```



If the `error` parameter that you receive in this selector is equal to `nil`, that means the image was saved in the user's photo library successfully. Otherwise, you can retrieve the value of this parameter to determine what the issue was.

11.5 Storing Videos in the Photo Library

Problem

You want to store a video accessible through a URL, such as a video in your application bundle, to the Photo Library.

Solution

Use the `writeVideoAtPathToSavedPhotosAlbum:completionBlock:` instance method of `ALAssetsLibrary`:

```

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.assetsLibrary = [[ALAssetsLibrary alloc] init];

    NSURL *videoURL = [[NSBundle mainBundle] URLForResource:@"MyVideo"
                                                             withExtension:@"MOV"];

    if (videoURL != nil){
        [self.assetsLibrary
         writeVideoAtPathToSavedPhotosAlbum:videoURL
         completionBlock:^(NSURL *assetURL, NSError *error) {

            if (error == nil){
                NSLog(@"no errors happened");
            } else {
                NSLog(@"Error happened while saving the video.");
                NSLog(@"The error is = %@", error);
            }
        }];
    } else {
        NSLog(@"Could not find the video in the app bundle.");
    }

    self.window = [[UIWindow alloc] initWithFrame:

```

```

        [[[UIScreen mainScreen] bounds]]];

        self.window.backgroundColor = [UIColor whiteColor];
        [self.window makeKeyAndVisible];
        return YES;
    }

```

In our example, `assetsLibrary` is a property of type `ALAssetsLibrary`. Although this example allocates and initializes this property in the app delegate, you do not necessarily have to use Assets Library objects in your app delegate. You can allocate, initialize, and use them anywhere in your application that you find most appropriate.

Discussion

The Assets Library framework is a convenient bridge between developers and the Photo Library. As mentioned in [Recipe 11.6](#), the iOS SDK provides you with built-in GUI components that you can use to access the contents of the Photo Library. However, you might sometimes require direct access to these contents. In such instances, you can use the Assets Library framework.

After allocating and initializing the Assets Library object of type `ALAssetsLibrary`, you can use the `writeVideoAtPathToSavedPhotosAlbum:completionBlock:` instance method of this object to write a video from a URL to the Photo Library. All you have to do is provide the URL of the video in `NSURL` form and a block object whose code will be called when the video is saved. The block object must accept two parameters of type `NSURL` and `NSError`, respectively.

If the `error` parameter is `nil`, the save process went well and you don't have to worry about anything. One of the common errors that iOS could return to you is similar to this:

```

Error Domain=ALAssetsLibraryErrorDomain Code=-3302 "Invalid data"
UserInfo=0x7923590 {NSLocalizedFailureReason=
There was a problem writing this asset because
the data is invalid and cannot be viewed or played.,
NSLocalizedRecoverySuggestion=Try with different data,
NSLocalizedDescription=Invalid data}

```

You will get this error message if you attempt to pass a URL that is not inside your application bundle. If you are testing your application on iPhone Simulator, occasionally you might also get this error message:

```

Error Domain=ALAssetsLibraryErrorDomain Code=-3310 "Data unavailable"
UserInfo=0x6456810 {NSLocalizedRecoverySuggestion=
Launch the Photos application, NSLocalizedDescription=Data unavailable}

```

If so, please open the Photos application in iOS Simulator once, and then launch your application again.

The first parameter passed to the block object provided to the `writeVideoAtPathToSavedPhotosAlbum:completionBlock:` method will point to the Assets Library URL of the stored video. A sample URL of this kind will look like this:

```
assets-library://asset/asset.MOV?id=1000000002&ext=MOV
```

In [Recipe 11.7](#), we will learn how to use such a URL to load the data for the video file into memory.

11.6 Retrieving Photos and Videos from the Photo Library

Problem

You want users to be able to pick a photo or a video from their photo library and use it in your application.

Solution

Use the `UIImagePickerControllerSourceTypePhotoLibrary` value for the source type of your `UIImagePickerController` and the `kUTTypeImage` or `kUTTypeMovie` value, or both, for the media type, like so:

```
- (BOOL) isPhotoLibraryAvailable{

    return [UIImagePickerController isSourceTypeAvailable:
        UIImagePickerControllerSourceTypePhotoLibrary];

}

- (BOOL) canUserPickVideosFromPhotoLibrary{

    return [self
        cameraSupportsMedia:(__bridge NSString *)kUTTypeMovie
        sourceType:UIImagePickerControllerSourceTypePhotoLibrary];

}

- (BOOL) canUserPickPhotosFromPhotoLibrary{

    return [self
        cameraSupportsMedia:(__bridge NSString *)kUTTypeImage
        sourceType:UIImagePickerControllerSourceTypePhotoLibrary];

}

- (void)viewDidLoad{
    [super viewDidLoad];

    if ([self isPhotoLibraryAvailable]){

        UIImagePickerController *controller =
            [[UIImagePickerController alloc] init];

        controller.sourceType = UIImagePickerControllerSourceTypePhotoLibrary;

        NSMutableArray *mediaTypes = [[NSMutableArray alloc] init];
```

```

        if ([self canUserPickPhotosFromPhotoLibrary]){
            [mediaTypes addObject:(__bridge NSString *)kUTTypeImage];
        }

        if ([self canUserPickVideosFromPhotoLibrary]){
            [mediaTypes addObject:(__bridge NSString *)kUTTypeMovie];
        }

        controller.mediaTypes = mediaTypes;

        controller.delegate = self;

        [self.navigationController presentViewController:controller
                                                animated:YES];
    }
}

```

For the implementation of the `cameraSupportsMedia:sourceType:` method we are using in this example, please refer to [Recipe 11.1](#).

Discussion

To allow your users to pick photos or videos from their photo library, you must set the `sourceType` property of an instance of `UIImagePickerController` to `UIImagePickerControllerSourceTypePhotoLibrary` before presenting the image picker to them. In addition, if you want to filter the videos or photos out of the items presented to your users once the image picker is shown, exclude the `kUTTypeMovie` or `kUTTypeImage` value from the array of media types of the image picker (in the `mediaTypes` property), respectively.

Bear in mind that setting the `mediaTypes` property of an image picker controller to `nil` or an empty array will result in a runtime error.

After the user is done picking the image, you will get the usual delegate messages through the `UIImagePickerControllerDelegate` protocol. For more information on how you can implement the methods defined in this protocol for processing images, please refer to [Recipe 11.2](#).

See Also

[Recipe 11.7](#)

11.7 Retrieving Assets from the Assets Library

Problem

You want to directly retrieve photos or videos from the Photo Library without the help of any built-in GUI components.

Solution

Use the Assets Library framework. Follow these steps:

1. Allocate and initialize an object of type `ALAssetsLibrary`.
2. Provide two block objects to the `enumerateGroupsWithTypes:usingBlock:failureBlock:` instance method of the Assets Library object. The first block will retrieve all the groups associated with the type that we passed to this method. The groups will be of type `ALAssetsGroup`. The second block returns an error in case of failure.
3. Use the `enumerateAssetsUsingBlock:` instance method of each group object to enumerate the assets available in each group. This method takes a single parameter, a block that retrieves information on a single asset. The block that you pass as a parameter must accept three parameters, of which the first must be of type `ALAsset`.
4. After retrieving the `ALAsset` objects available in each group, you can retrieve various properties of each asset, such as their type, available URLs, and so on. Retrieve these properties using the `valueForProperty:` instance method of each asset of type `ALAsset`. The return value of this method, depending on the property passed to it, could be `NSDictionary`, `NSString`, or any other object type. We will see a few common properties that we can retrieve from each asset soon.
5. Invoke the `defaultRepresentation` instance method of each object of type `ALAsset` to retrieve its representation object of type `ALAssetRepresentation`. Each asset in the Assets Library can have more than one representation. For instance, a photo might have a PNG representation by default, but a JPEG representation as well. Using the `defaultRepresentation` method of each asset of type `ALAsset`, you can retrieve the `ALAssetRepresentation` object, and then use that to retrieve different representations (if available) of each asset.
6. Use the size and the `getBytes:fromOffset:length:error:` instance methods of each asset representation to load the asset's representation data. You can then write the read bytes into an `NSData` object or do whatever else you need to do in your application. Additionally, for photos, you can use the `fullResolutionImage`, `fullScreenImage`, and `CGImageWithOptions:` instance methods of each representation to retrieve images of type `CGImageRef`. You can then construct a `UIImage` from `CGImageRef` using the `imageWithCGImage:` class method of `UIImage`.

```
- (void)viewDidLoad{
    [super viewDidLoad];
    self.assetsLibrary = [[ALAssetsLibrary alloc] init];

    [self.assetsLibrary
     enumerateGroupsWithTypes:ALAssetsGroupAll
     usingBlock:^(ALAssetsGroup *group, BOOL *stop) {
         [group enumerateAssetsUsingBlock:^(ALAsset *result,
                                           NSUInteger index,
                                           BOOL *stop) {

             /* Get the asset type */
```



```

        NSString *assetType = [result valueForKeyProperty:ALAssetPropertyType];

        if ([assetType isEqualToString:ALAssetTypePhoto]){
            NSLog(@"This is a photo asset");
        }

        else if ([assetType isEqualToString:ALAssetTypeVideo]){
            NSLog(@"This is a video asset");
        }

        else if ([assetType isEqualToString:ALAssetTypeUnknown]){
            NSLog(@"This is an unknown asset");
        }

        /* Get the URLs for the asset */
        NSDictionary *assetURLs = [result valueForKeyProperty:ALAssetPropertyURLs];

        NSUInteger    assetCounter = 0;
        for (NSString *assetURLKey in assetURLs){
            assetCounter++;
            NSLog(@"Asset URL %lu = %@",
                (unsigned long)assetCounter,
                [assetURLs valueForKey:assetURLKey]);
        }

        /* Get the asset's representation object */
        ALAssetRepresentation *assetRepresentation =
            [result defaultRepresentation];

        NSLog(@"Representation Size = %lld", [assetRepresentation size]);

    }
}

failureBlock:^(NSError *error) {
    NSLog(@"Failed to enumerate the asset groups.");
};

}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.assetsLibrary = nil;
}

```

Discussion

The Assets Library is broken down into groups. Each group contains assets and each asset has properties such as URLs and representation objects.

You can retrieve all assets of all types from the Assets Library using the `ALAssetsGroupAll` constant passed to the `enumerateGroupsWithTypes` parameter of the `enumerateGroupsWithTypes:usingBlock:failureBlock:` instance method of the Assets Library object. Here is a list of values you can pass to this parameter to enumerate different groups of assets:

`ALAssetsGroupAlbum`

Groups representing albums that have been stored on an iOS device through iTunes.

`ALAssetsGroupFaces`

Groups representing albums that contain face assets that were stored on an iOS device through iTunes.

`ALAssetsGroupSavedPhotos`

Groups representing the saved photos in the Photo Library. These are accessible to an iOS device through the Photos application as well.

`ALAssetsGroupAll`

All available groups in the Assets Library.

Now let's go ahead and write a simple application that retrieves the data for the first image found in the Assets Library, creates a `UIImageView` out of it, and adds the image view to the view of the current view controller. This way, we will learn how to read the contents of an asset using its representation.

Let's start with the declaration of our view controller and define an image view in there, which we will use to display the first image that we can find in the assets library:

```
#import <UIKit/UIKit.h>
#import <AssetsLibrary/AssetsLibrary.h>
#import <MobileCoreServices/MobileCoreServices.h>

@interface Retrieving_Assets_from_the_Assets_LibraryViewController
    : UIViewController <UIImagePickerControllerDelegate,
                        UINavigationControllerDelegate>

@property (nonatomic, strong) ALAssetsLibrary *assetsLibrary;
@property (nonatomic, strong) UIImageView *imageView;

@end
```

Let's go ahead and synthesize our asset library and image view properties:

```
#import "Retrieving_Assets_from_the_Assets_LibraryViewController.h"

@implementation Retrieving_Assets_from_the_Assets_LibraryViewController

@synthesize assetsLibrary;
@synthesize imageView;

...
```

Now when our view controller loads its view, we will initialize our assets library object and then start enumerating the assets library until we find the first photo. At that time, we will use the representation of that asset (photo) in order to display the photo on the image view:

```
- (void)viewDidLoad{
    [super viewDidLoad];
```

```

self.view.backgroundColor = [UIColor whiteColor];
self.assetsLibrary = [[ALAssetsLibrary alloc] init];

dispatch_queue_t dispatchQueue =
    dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

dispatch_async(dispatchQueue, ^(void) {

    [self.assetsLibrary
     enumerateGroupsWithTypes:ALAssetsGroupAll
     usingBlock:^(ALAssetsGroup *group, BOOL *stop) {

        [group enumerateAssetsUsingBlock:^(ALAsset *result,
                                           NSUInteger index,
                                           BOOL *stop) {

            __block BOOL foundThePhoto = NO;

            if (foundThePhoto){
                *stop = YES;
            }

            /* Get the asset type */
            NSString *assetType = [result valueForKey:ALAssetPropertyType];

            if ([assetType isEqualToString:ALAssetTypePhoto]){
                NSLog(@"This is a photo asset");

                foundThePhoto = YES;
                *stop = YES;

                /* Get the asset's representation object */
                ALAssetRepresentation *assetRepresentation =
                    [result defaultRepresentation];

                /* We need the scale and orientation to be able to construct a
                 properly oriented and scaled UIImage out of the
                 representation object */
                CGFloat imageScale = [assetRepresentation scale];

                UIImageOrientation imageOrientation =
                    (UIImageOrientation)[assetRepresentation orientation];

                dispatch_async(dispatch_get_main_queue(), ^(void) {

                    CGImageRef imageReference =
                        [assetRepresentation fullResolutionImage];

                    /* Construct the image now */
                    UIImage *image =
                        [[UIImage alloc] initWithCGImage:imageReference
                                                         scale:imageScale
                                                         orientation:imageOrientation];

```

```

        if (image != nil){
            self.imageView = [[UIImageView alloc]
                               initWithFrame:self.view.bounds];
            self.imageView.contentMode = UIViewContentModeScaleAspectFit;
            self.imageView.image = image;
            [self.view addSubview:self.imageView];

        } else {
            NSLog(@"Failed to create the image.");
        }
    });

}

});
}
failureBlock:^(NSError *error) {
    NSLog(@"Failed to enumerate the asset groups.");
}];

});

}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.assetLibrary = nil;
    self.imageView = nil;
}

```

We enumerate the groups and every asset in the groups. Then we find the first photo asset and retrieve its representation. Using the representation, we construct a `UIImage`, and from the `UIImage`, we construct a `UIImageView` to display that image on our view. Quite simple, isn't it?

For video files, we are dealing with a slightly different issue as the `ALAssetRepresentation` class does not have any methods that could return an object that encapsulates our video files. For this reason, we have to read the contents of a video asset into a buffer and perhaps save it to our *Documents* folder where it is easier for us to access later. Of course, the requirements depend on your application, but in this example code, we will go ahead and find the first video in the Assets Library and store it in our application's *Documents* folder under the name *Temp.MOV*:

```

- (void)viewDidLoad{
    [super viewDidLoad];

    self.view.backgroundColor = [UIColor whiteColor];
    self.assetLibrary = [[ALAssetsLibrary alloc] init];

    dispatch_queue_t dispatchQueue =
    dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

    dispatch_async(dispatchQueue, ^(void) {

```

```

[self.assetsLibrary
enumerateGroupsWithTypes:ALAssetsGroupAll
usingBlock:^(ALAssetsGroup *group, BOOL *stop) {

    __block BOOL foundTheVideo = NO;

    [group enumerateAssetsUsingBlock:^(ALAsset *result,
                                       NSUInteger index,
                                       BOOL *stop) {

        /* Get the asset type */
        NSString *assetType = [result valueForKeyProperty:ALAssetPropertyType];

        if ([assetType isEqualToString:ALAssetTypeVideo]){
            NSLog(@"This is a video asset");

            foundTheVideo = YES;
            *stop = YES;

            /* Get the asset's representation object */
            ALAssetRepresentation *assetRepresentation =
                [result defaultRepresentation];

            const NSUInteger BufferSize = 1024;
            uint8_t buffer[BufferSize];
            NSUInteger bytesRead = 0;
            long long currentOffset = 0;
            NSError *readingError = nil;

            /* Find the documents folder (an array) */
            NSArray *documents =
                NSSearchPathForDirectoriesInDomains(NSDocumentDirectory,
                                                    NSUserDomainMask,
                                                    YES);

            /* Retrieve the one documents folder that we need */
            NSString *documentsFolder = [documents objectAtIndex:0];

            /* Construct the path where the video has to be saved */
            NSString *videoPath = [documentsFolder
                                   stringByAppendingPathComponent:@"Temp.MOV"];

            NSFileManager *fileManager = [[NSFileManager alloc] init];

            /* Create the file if it doesn't exist already */
            if ([fileManager fileExistsAtPath:videoPath] == NO){
                [fileManager createFileAtPath:videoPath
                                     contents:nil
                                     attributes:nil];
            }

            /* We will use this file handle to write the contents
            of the media assets to the disk */
            NSFileHandle *fileHandle = [NSFileHandle
                                         fileHandleForWritingAtPath:videoPath];

```

```

do{

    /* Read as many bytes as we can put in the buffer */
    bytesRead = [assetRepresentation getBytes:(uint8_t *)&buffer
                                           fromOffset:currentOffset
                                           length:BufferSize
                                           error:&readingError];

    /* If we couldn't read anything, we will exit this loop */
    if (bytesRead == 0){
        break;
    }

    /* Keep the offset up to date */
    currentOffset += bytesRead;

    /* Put the buffer into an NSData */
    NSData *readData = [[NSData alloc]
                        initWithBytes:(const void *)&buffer
                        length:bytesRead];

    /* And write the data to file */
    [fileHandle writeData:readData];

} while (bytesRead > 0);

NSLog(@"Finished reading and storing the \
      video in the documents folder");

}

}];

if (foundTheVideo){
    *stop = YES;
}

}
failureBlock:^(NSError *error) {
    NSLog(@"Failed to enumerate the asset groups.");
}];

});

}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.assetsLibrary = nil;
}

```

This is what's happening in our sample code:

- We get the default representation of the first video asset that we find in the Assets Library.
- We create a file called *Temp.MOV* in our application's *Documents* folder to save the contents of the video asset.
- We create a loop that runs so long as there is still data in the asset representation waiting to be read. The `getBytes:fromOffset:length:error:` instance method of our asset representation object reads as many bytes as we can fit into our buffer for as many times as necessary until we get to the end of the representation data.
- After reading the data into our buffer, we encapsulate the data into an object of type `NSData` using the `initWithBytes:length:` initialization method of `NSData`. We then write this data to the file we created previously using the `writeData:` instance method of `NSFileHandle`.

11.8 Editing Videos on an iOS Device

Problem

You want the user of your application to be able to edit videos straight from your application.

Solution

Use the `UINavigationController` class. In this example, we will use this class in conjunction with an image picker controller. First we will ask the user to pick a video from her photo library. After she does, we will display an instance of the video editor controller and allow the user to edit the video she picked.

Discussion

The `UINavigationController` in the iOS SDK allows programmers to display a video editor interface to the users of their applications. All you have to do is to provide the URL of the video that needs to be edited and then present the video editor controller as a modal view. You should not overlay the view of this controller with any other views and you should not modify this view.



Calling the `presentModalViewController:animated:` method immediately after calling the `dismissModalViewControllerAnimated:` method of a view controller will terminate your application with a runtime error. You must wait for the first view controller to be dismissed and then present the second view controller. You can take advantage of the `viewDidAppear:` instance method of your view controllers to detect when your view is displayed. You know at this point that any modal view controllers must have disappeared.

So let's go ahead and declare our view controller and any necessary properties:

```
#import <UIKit/UIKit.h>
#import <AssetsLibrary/AssetsLibrary.h>
#import <MobileCoreServices/MobileCoreServices.h>

@interface Editing_Videos_on_an_iOS_DeviceViewController
    : UIViewController <UINavigationControllerDelegate,
                        UIVideoEditorControllerDelegate,
                        UIImagePickerControllerDelegate>

@property (nonatomic, strong) NSURL *videoURLToEdit;

@end
```



The `UIVideoEditorController` is not designed to work in landscape mode. Even if the view controller that displays an instance of the video editor supports all orientations, the video editor will be shown in portrait mode only.

Now let's go ahead and synthesize our video URL property:

```
#import "Editing_Videos_on_an_iOS_DeviceViewController.h"

@implementation Editing_Videos_on_an_iOS_DeviceViewController

@synthesize videoURLToEdit;

...
```

The next thing to do is to handle different video editor delegate messages in our view controller:

```
- (void)videoEditorController:(UIVideoEditorController *)editor
    didSaveEditedVideoToPath:(NSString *)editedVideoPath{
    NSLog(@"The video editor finished saving video");
    NSLog(@"The edited video path is at = %@", editedVideoPath);
    [editor dismissModalViewControllerAnimated:YES];
}

- (void)videoEditorController:(UIVideoEditorController *)editor
    didFailWithError:(NSError *)error{
    NSLog(@"Video editor error occurred = %@", error);
    [editor dismissModalViewControllerAnimated:YES];
}

- (void)videoEditorControllerDidCancel:(UIVideoEditorController *)editor{
    NSLog(@"The video editor was cancelled");
    [editor dismissModalViewControllerAnimated:YES];
}
```


When our view loads, we need to display a video picker to the user. She will then be able to pick a video from her library and we will then proceed to allow her to edit that video:

```
- (BOOL) cameraSupportsMedia:(NSString *)paramMediaType
    sourceType:(UIImagePickerControllerSourceType)paramSourceType{

    __block BOOL result = NO;

    if ([paramMediaType length] == 0){
        NSLog(@"Media type is empty.");
        return NO;
    }

    NSArray *availableMediaTypes =
    [UIImagePickerController availableMediaTypesForSourceType:paramSourceType];

    [availableMediaTypes enumerateObjectsUsingBlock:
    ^(id obj, NSUInteger idx, BOOL *stop) {

        NSString *mediaType = (NSString *)obj;
        if ([mediaType isEqualToString:paramMediaType]){
            result = YES;
            *stop= YES;
        }

    }];

    return result;
}

- (BOOL) canUserPickVideosFromPhotoLibrary{

    return [self cameraSupportsMedia:(__bridge NSString *)kUTTypeMovie
        sourceType:UIUIImagePickerControllerSourceTypePhotoLibrary];

}

- (BOOL) isPhotoLibraryAvailable{

    return [UIImagePickerController
        isSourceTypeAvailable:
        UIImagePickerControllerSourceTypePhotoLibrary];

}

- (void)viewDidLoad {
    [super viewDidLoad];

    if ([self isPhotoLibraryAvailable] &&
        [self canUserPickVideosFromPhotoLibrary]){

        UIImagePickerController *imagePicker =
        [[UIImagePickerController alloc] init];
```

```

/* Set the source type to photo library */
imagePicker.sourceType = UIImagePickerControllerSourceTypePhotoLibrary;

/* And we want our user to be able to pick movies from the library */
NSArray *mediaTypes = [[NSArray alloc] initWithObjects:
    (__bridge NSString *)kUTTypeMovie, nil];

imagePicker.mediaTypes = mediaTypes;

/* Set the delegate to the current view controller */
imagePicker.delegate = self;

/* Present our image picker */
[self.navigationController presentViewController:imagePicker
    animated:YES];

}

}

```

We now need to know when the user is done picking a video so let's handle various delegate methods of our image picker control:

```

- (void) imagePickerController:(UIImagePickerController *)picker
    didFinishPickingMediaWithInfo:(NSDictionary *)info{

    NSLog(@"Picker returned successfully.");

    NSString *mediaType = [info objectForKey:
        UIImagePickerControllerMediaType];

    if ([mediaType isEqualToString:(NSString *)kUTTypeMovie]){
        self.videoURLToEdit = [info objectForKey:UIImagePickerControllerMediaURL];
    }

    [picker dismissModalViewControllerAnimated:YES];

}

- (void) imagePickerControllerDidCancel:(UIImagePickerController *)picker{

    NSLog(@"Picker was cancelled");
    self.videoURLToEdit = nil;
    [picker dismissModalViewControllerAnimated:YES];

}

```

And when our view appears to the user after she has selected a video from the assets library on her device, we can proceed to display the video editor:

```

- (void) viewWillAppear:(BOOL)animated{
    [super viewWillAppear:animated];

    if (self.videoURLToEdit != nil){

```

```

NSString *videoPath = [self.videoURLToEdit path];

/* First let's make sure the video editor is able to edit the
video at the path in our documents folder */
if ([UIVideoEditorController canEditVideoAtPath:videoPath]){

    /* Instantiate the video editor */
    UIVideoEditorController *videoEditor =
    [[UIVideoEditorController alloc] init];

    /* We become the delegate of the video editor */
    videoEditor.delegate = self;

    /* Make sure to set the path of the video */
    videoEditor.videoPath = videoPath;

    /* And present the video editor */
    [self.navigationController presentViewController:videoEditor
                                             animated:YES];

    self.videoURLToEdit = nil;

} else {
    NSLog(@"Cannot edit the video at this path");
}

}

}

```

In our example, the user is allowed to pick any video from the photo library. Once she does, we will display the video editor controller by providing the path of the video that the video picker passes to us in a delegate method.

The video editor controller's delegate gets important messages about the state of the video editor. This delegate object must conform to the `UIVideoEditorControllerDelegate` and `UINavigationControllerDelegate` protocols. In our example, we chose our view controller to become the delegate of our video editor. Once the editing is done, the delegate object receives the `videoEditorController:didSaveEditedVideoToPath:` delegate method from the video editor controller. The path of the edited video will be passed through the `didSaveEditedVideoToPath` parameter.

Before attempting to display the interface of the video editor to your users, you must call the `canEditVideoAtPath:` class method of `UIVideoEditorController` to make sure the path you are trying to edit is editable by the controller. If the return value of this class method is `YES`, proceed to configuring and displaying the video editor's interface. If not, take a separate path, perhaps displaying an alert to your user.

See Also

[Recipe 11.6](#); [Recipe 11.7](#)

Multitasking

12.0 Introduction

Multitasking enables *background execution*, which means the application can keep working as usual—running tasks, spawning new threads, listening for notifications, and reacting to events—but simply does not display anything on the screen or have any way to interact with the user. When the user presses the Home button on the device, which in previous versions of the iPhone and iPad would terminate the application, the application is now sent into the background.

An application running on an iOS version that supports multitasking is, by default, opted into background execution. If you link your application against iOS SDK 4.0 and later, you can opt out of background execution, as you will see in [Recipe 12.10](#). If you do, your application will be terminated when the user presses the Home button, as before.

When our application moves to the background (such as when the user presses the Home button) and then back to the foreground (when the user selects the application again), various messages are sent by the system and are expected to be received by an object we designate as our application delegate. For instance, when our application is sent to the background, our application delegate will receive the `applicationDidEnterBackground:` method, and as the application comes back to the foreground by the user, the application delegate will receive the `applicationWillEnterForeground:` delegate message.

In addition to these delegate messages, iOS also sends notifications to the running application when it transitions the application to the background and from the background to the foreground. The notification that gets sent when the application is moved to the background is `UIApplicationDidEnterBackgroundNotification`, and the notification that gets sent when an application transitions from the background to the foreground is `UIApplicationWillEnterForegroundNotification`. You can use the default notification center to register for these notifications.

12.1 Detecting the Availability of Multitasking

Problem

You want to find out whether the iOS device running your application supports multitasking.

Solution

Call the `isMultitaskingSupported` instance method of `UIDevice`, like so:

```
- (BOOL) isMultitaskingSupported{

    BOOL result = NO;
    if ([[UIDevice currentDevice]
        respondsToSelector:@selector(isMultitaskingSupported)]){
        result = [[UIDevice currentDevice] isMultitaskingSupported];
    }
    return result;
}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    if ([self isMultitaskingSupported]){
        NSLog(@"Multitasking is supported.");
    } else {
        NSLog(@"Multitasking is not supported.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

Discussion

Your application, depending on the iOS devices it targets, can be run and executed on a variety of devices on different operating systems. For instance, if you compile your application with iOS SDK 5.0 and your deployment target OS is 4.0, your application can be run on the iPhone 3G, iPhone 3GS, iPhone 4, and iPod Touch (second and third generations), provided that the iOS on these devices has been updated to iOS 4.0 or iOS 5. Furthermore, a device could have iOS 5.0 or later installed on it, but the underlying hardware might not be strong enough for multitasking to be supported. Because of this, your application must be aware of whether multitasking is enabled on that specific hardware and on that specific iOS before attempting to act like a multitasking application.

12.2 Completing a Long-Running Task in the Background

Problem

You want to borrow some time from iOS to complete a long-running task when your application is being sent to the background.

Solution

Use the `beginBackgroundTaskWithExpirationHandler:` instance method of `UIApplication`. After you have finished the task, call the `endBackgroundTask:` instance method of `UIApplication`.

Discussion

When an iOS application is sent to the background, its main thread is paused. The threads you create within your application using the `detachNewThreadSelector:toTarget:withObject:` class method of `NSThread` are also suspended. If you are attempting to finish a long-running task when your application is being sent to the background, you must call the `beginBackgroundTaskWithExpirationHandler:` instance method of `UIApplication` to borrow some time from iOS. The `backgroundTimeRemaining` property of `UIApplication` contains the number of seconds the application has to finish its job. If the application doesn't finish the long-running task before this time expires, iOS will terminate the application. Every call to the `beginBackgroundTaskWithExpirationHandler:` method must have a corresponding call to `endBackgroundTask:` (another instance method of `UIApplication`). In other words, if you ask for more time from iOS to complete a task, you must tell iOS when you are done with that task. Once this is done and no more tasks are requested to be running in the background, your application will be fully put into the background with all threads paused.

When your application is in the foreground, the `backgroundTimeRemaining` property of `UIApplication` is equal to the `DBL_MAX` constant, which is the largest value a value of type `double` can contain (the integer equivalent of this value is normally equal to -1 in this case). After iOS is asked for more time before the application is fully suspended, this property will indicate the number of seconds the application has before it finishes running its task(s).

You can call the `beginBackgroundTaskWithExpirationHandler:` method as many times as you wish inside your application. The important thing to keep in mind is that whenever iOS returns a token or a task identifier to your application with this method, you must call the `endBackgroundTask:` method to mark the end of that task once you are finished running the task. Failing to do so might cause iOS to terminate your application.

While in the background, applications are not supposed to be fully functioning and processing heavy data. They are indeed only supposed to *finish* a long-running task.

An example could be an application that is calling a web service API and has not yet received the response of that API from the server. During this time, if the application is sent to the background, the application can request more time until it receives a response from the server. Once the response is received, the application must save its state and mark that task as finished by calling the `endBackgroundTask:` instance method of `UIApplication`.

Let's have a look at an example. I will start by defining a property of type `UIBackgroundTaskIdentifier` in the app delegate. Also, let's define a timer of type `NSTimer` which we will use to print a message to the console window every 1 second when our app is sent to the background:

```
#import <UIKit/UIKit.h>

@interface Completing_a_Long_Running_Task_in_the_BackgroundAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;

@property (nonatomic, unsafe_unretained)
    UIBackgroundTaskIdentifier backgroundTaskIdentifier;

@property (nonatomic, strong) NSTimer *myTimer;

@end
```

And then we will continue on to synthesize our properties:

```
#import "Completing_a_Long_Running_Task_in_the_BackgroundAppDelegate.h"

@implementation Completing_a_Long_Running_Task_in_the_BackgroundAppDelegate

@synthesize window = _window;
@synthesize backgroundTaskIdentifier;
@synthesize myTimer;

...
```

Now let's move on to creating and scheduling our timer when the app gets sent to the background:

```
- (BOOL) isMultitaskingSupported{

    BOOL result = NO;
    if ([[UIDevice currentDevice]
        respondsToSelector:@selector(isMultitaskingSupported)]){
        result = [[UIDevice currentDevice] isMultitaskingSupported];
    }
    return result;
}

- (void) timerMethod:(NSTimer *)paramSender{
```



```

NSTimeInterval backgroundTimeRemaining =
    [[UIApplication sharedApplication] backgroundTimeRemaining];

if (backgroundTimeRemaining == DBL_MAX){
    NSLog(@"Background Time Remaining = Undetermined");
} else {
    NSLog(@"Background Time Remaining = %.02f Seconds",
        backgroundTimeRemaining);
}
}

- (void)applicationDidEnterBackground:(UIApplication *)application{

    if ([self isMultitaskingSupported] == NO){
        return;
    }

    self.myTimer =
    [NSTimer scheduledTimerWithTimeInterval:1.0f
                                     target:self
                               selector:@selector(timerMethod:)
                               userInfo:nil
                               repeats:YES];

    self.backgroundTaskIdentifier =
    [application beginBackgroundTaskWithExpirationHandler:^(void) {
        [self endBackgroundTask];
    }];
}

```

You can see that in the completion handler for our background task, we are calling the `endBackgroundTask` method of our app delegate. This is a method which we have written and it looks like this:

```

- (void) endBackgroundTask{

    dispatch_queue_t mainQueue = dispatch_get_main_queue();

    __weak Completing_a_Long_Running_Task_in_the_BackgroundAppDelegate
    *weakSelf = self;

    dispatch_async(mainQueue, ^(void) {

        Completing_a_Long_Running_Task_in_the_BackgroundAppDelegate
        *strongSelf = weakSelf;

        if (strongSelf != nil){
            [strongSelf.myTimer invalidate];
            [[UIApplication sharedApplication]
                endBackgroundTask:self.backgroundTaskIdentifier];
            strongSelf.backgroundTaskIdentifier = UIBackgroundTaskInvalid;
        }
    })
}

```

```
});  
}
```

There are a couple of things that we need to do to clear up after a long running task:

1. End any threads or timers, whether they are foundation timers or they are created with GCD.
2. End the background task by calling the `endBackgroundTask:` method of `UIApplication`.
3. Mark our task as ended by assigning the value of `UIBackgroundTaskInvalid` to our task identifiers.

Last but not least, when our app is brought to the foreground, if we still have our background task running, we need to ensure that we are getting rid of it:

```
- (void)applicationWillEnterForeground:(UIApplication *)application{  
    if (self.backgroundTaskIdentifier != UIBackgroundTaskInvalid){  
        [self endBackgroundTask];  
    }  
}
```

In our example, whenever the application is put into the background, we ask for more time to finish a long-running task (in this case, for instance, our timer's code). In our time, we constantly read the value of the `backgroundTimeRemaining` property of `UIApplication`'s instance and print that value out to the console. In the `beginBackgroundTaskWithExpirationHandler:` instance method of `UIApplication`, we provided the code that will be executed just before our application's extra time to execute a long-running task finishes (usually about 5 to 10 seconds before the expiration of the task). In here, we can simply end the task by calling the `endBackgroundTask:` instance method of `UIApplication`.



When an application is sent to the background and the application has requested more execution time from iOS, before the execution time is finished, the application could be revived and brought to the foreground by the user again. If you had previously asked for a long-running task to be executed in the background when the application was being sent to the background, you must end the long-running task using the `endBackgroundTask:` instance method of `UIApplication`.

See Also

[Recipe 12.1](#)

12.3 Receiving Local Notifications in the Background

Problem

You want to present an alert to your user even when your application is not running. You want to create this alert locally inside your application without using push notifications.

Solution

Instantiate an object of type `UILocalNotification` and schedule it using the `scheduleLocalNotification:` instance method of `UIApplication`.

```
- (BOOL) localNotificationWithMessage:(NSString *)paramMessage
        actionButtonTitle:(NSString *)paramActionButtonTitle
        launchImage:(NSString *)paramLaunchImage
        applicationBadge:(NSInteger)paramApplicationBadge
        secondsFromNow:(NSTimeInterval)paramSecondsFromNow
        userInfo:(NSDictionary *)paramUserInfo{

    if ([paramMessage length] == 0){
        return NO;
    }

    UILocalNotification *notification = [[UILocalNotification alloc] init];
    notification.alertBody = paramMessage;
    notification.alertAction = paramActionButtonTitle;

    if ([paramActionButtonTitle length] > 0){
        /* Make sure we have the action button for the user to press
           to open our application */
        notification.hasAction = YES;
    } else {
        notification.hasAction = NO;
    }

    /* Here you have a chance to change the launch image of your application
       when the notification's action is viewed by the user */
    notification.alertLaunchImage = paramLaunchImage;

    /* Change the badge number of the application once the notification is
       presented to the user. Even if the user dismisses the notification,
       the badge number of the application will change */
    notification.applicationIconBadgeNumber = paramApplicationBadge;

    /* This dictionary will get passed to your application
       later if and when the user decides to view this notification */
    notification.userInfo = paramUserInfo;

    /* We need to get the system time zone so that the alert view
       will adjust its fire date if the user's time zone changes */
    NSTimeZone *timeZone = [NSTimeZone systemTimeZone];
    notification.timeZone = timeZone;
```

```

/* Schedule the delivery of this notification 10 seconds from now */
NSDate *today = [NSDate date];

NSDate *fireDate = [today dateByAddingTimeInterval:paramSecondsFromNow];

NSCalendar *calendar = [NSCalendar autoupdatingCurrentCalendar];

NSUInteger dateComponents =
    NSYearCalendarUnit |
    NSMonthCalendarUnit |
    NSDayCalendarUnit |
    NSHourCalendarUnit |
    NSMinuteCalendarUnit |
    NSSecondCalendarUnit;

NSDateComponents *components = [calendar components:dateComponents
                                                fromDate:fireDate];

/* Here you have a chance to change these components. That's why we
   retrieved the components of the date in the first place. */
fireDate = [calendar dateFromComponents:components];

/* Finally set the schedule date for this notification */
notification.fireDate = fireDate;

[[UIApplication sharedApplication] cancelAllLocalNotifications];

[[UIApplication sharedApplication] scheduleLocalNotification:notification];

return YES;
}

```

Discussion

A *local notification* is an alert view (an object of type `UIAlertView`) that gets presented to the user if your application is running in the background or not running at all. You can schedule the delivery of a local notification using the `scheduleLocalNotification:` instance method of `UIApplication`. The `cancelAllLocalNotifications` instance method cancels the delivery of all pending local notifications.

You can ask iOS to deliver a local notification to the user in the future when your application is not even running. These notifications could also be recurring—for instance, every week at a certain time. However, extra care must be taken when you are specifying the *fire date* for your notifications.

For instance, let's say the time is now 13:00 in London, the time zone is GMT+0, and your application is currently running on a user's device. You want to be able to deliver a notification at 14:00 to your user even if your application is not running at that time. Now your user is on a plane at London's Gatwick Airport and plans to fly to Stockholm where the time zone is GMT+1. If the flight takes 30 minutes, the user will be in Stock-

holm at 13:30 GMT+0. However, when he lands, the iOS device will detect the change in the time zone and will change the user's device time to 14:30. Your notification was supposed to occur at 14:00 (GMT+0), so as soon as the time zone is changed, iOS detects that the notification is due to be displayed (30 minutes late, in fact, with the new time zone) and will display your notification.

The issue is that your notification was supposed to be displayed at 14:00 GMT+0 or 15:00 GMT+1, and not 14:30 GMT+1. To deal with occasions such as this (which may be more common than you think, with modern travel habits), when specifying a date and time for your local notifications to be fired, you should also specify the time zone of the date and time you are specifying.

The previous code did not include the alert view that you need to write in order to have something to display to the user. Let's go ahead and add that code in our application and see what happens on iPhone Simulator in different scenarios. Here is the *.h* file of our application delegate:

```
#import <UIKit/UIKit.h>

@interface Receiving_Local_Notifications_in_the_BackgroundAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (nonatomic, strong) UIWindow *window;

@end
```

Perfect! Now we will go to the `application:didReceiveLocalNotification:` method and see if a local notification has woken our app up. If not, we will schedule one:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];

    id scheduledLocalNotification =
    [launchOptions valueForKey:
        UIApplicationLaunchOptionsLocalNotificationKey];

    if (scheduledLocalNotification != nil){

        /* We received a local notification while
        our application wasn't running. You can now typecase the
        ScheduledLocalNotification variable to UILocalNotification and
        use it in your application */

        NSString *message = @"Local Notification Woke Us Up";
        [[[UIAlertView alloc] initWithTitle:@"Notification"
            message:message
            delegate:nil
```

```

        cancelButtonTitle:@"OK"
        otherButtonTitles:nil, nil] show];

    } else {

        NSString *message=@"A new instant message is available. \
        Would you like to read this message?";

        /* If a local notification didn't start our application,
        then we start a new local notification */

        [self localNotificationWithMessage:message
            cancelButtonTitle:@"Yes"
            launchImage:nil
            applicationBadge:1
            secondsFromNow:10.0f
            userInfo:nil];

        message=@"A new Local Notification is set up \
        to be displayed 10 seconds from now";

        [[[UIAlertView alloc] initWithTitle:@"Set Up"
            message:message
            delegate:nil
            cancelButtonTitle:@"OK"
            otherButtonTitles:nil, nil] show];

    }

    return YES;
}

```

Last but not least, we will handle the `application:didReceiveLocalNotification:` method of our `UIApplicationDelegate` in our app delegate to make sure we display a message to the user if she opens our app because of a local notification:

```

- (void) application:(UIApplication *)application
  didReceiveLocalNotification:(UILocalNotification *)notification{

    NSString *message=@"The Local Notification is delivered.";

    [[[UIAlertView alloc] initWithTitle:@"Local Notification"
        message:message
        delegate:nil
        cancelButtonTitle:@"OK"
        otherButtonTitles:nil, nil] show];

}

```

Now let's test the code. Here is our first scenario: the user has just installed our application and will launch it for the first time. [Figure 12-1](#) shows what he will see.



Figure 12-1. An indication of local notifications being set up

The user *taps the OK button and stays in the application*. [Figure 12-2](#) depicts the message that will be shown to the user after the notification is delivered to our application.




Figure 12-2. A local notification delivered while our app is running

When the application is running or even in the background (has not been terminated yet), iOS will call the `application:didReceiveLocalNotification:` method of our application delegate to let our application know a local notification has been delivered to us. If the user is inside the application, iOS will not do anything special and will not display a message automatically. However, iOS does display a notification message automatically when our application is running in the background.

In scenario 2, the user opens our application for the first time, as shown in [Figure 12-1](#), and immediately after pressing the OK button presses the Home button on

his iOS device, sending our application to the background. Now when the notification is delivered, our user will see a message similar to that shown in [Figure 12-3](#).



Figure 12-3. A local notification delivered to an app in the background

Because we set the application badge number property of our local notification to 1 when we created the notification, our application's badge number is immediately set to 1 when the notification is delivered. The user doesn't have to close or accept the notification for the badge number to be changed. Now if the user presses the Yes button, iOS will launch the application associated with this local notification and the user will

see a screen similar to that shown in [Figure 12-2](#). Please note that in this scenario, our application has not been terminated but sent to the background.

Scenario 3 is when our application runs for the first time, as shown in [Figure 12-1](#), and the user sends our application to the background. Then the user terminates our application manually by double-tapping the Home button and closing the application using the Close button that will appear on the application icon when the user presses and holds his finger on the icon for a few seconds, as shown in [Figure 12-4](#).



Figure 12-4. The user attempting to terminate our application before the local notification is delivered

Once our application is terminated, the local notification will be displayed to the user after a few seconds (10 seconds from the time we scheduled the notification). Once the notification is delivered, the user will see a screen similar to that shown in [Figure 12-3](#). After the user presses the Yes button, iOS will relaunch our application and the user will see a screen similar to that shown in [Figure 12-5](#).




Figure 12-5. A local notification waking up the terminated app

So, you can visually see how local notifications work. When our application is running in the foreground or the background, iOS will deliver the local notification through the `application:didReceiveLocalNotification: delegate` method. However, if our

application has been terminated either by the user or by iOS, we will receive the local notification (that is, if the user decides to view it) through the application's `didFinishLaunchingWithOptions:` method. We can retrieve the notification using the `UIApplicationLaunchOptionsLocalNotificationKey` key of the `didFinishLaunchingWithOptions` parameter.

A local notification does not necessarily have to be an action notification. Action notifications have two buttons. You can change the title of one button through the `alertAction` property of `UINotification`. The other button is an OK button that simply dismisses the alert; you cannot change the title or action. If a notification is not an action notification (when the `hasAction` property of `UINotification` is set to `NO`), the notification will simply have an OK button, and pressing this button will *not* relaunch your application.

12.4 Playing Audio in the Background

Problem

You are writing an application that plays audio files (such as a music player) and you would like the audio files to be played even if your application is running in the background.

Solution

Create a new array key in your application's main `.plist` file. Set the name of the key to `UIBackgroundModes`. Add the value `audio` to this new key. Here is an example of the contents of a `.plist` file with the aforementioned key and value added:

```
<dict>
    ...
    ...
    ...
    <key>UIBackgroundModes</key>
    <array>
        <string>audio</string>
    </array>
    ...
    ...
    ...
</dict>
```

Now you can use the AV Foundation to play audio files, and your audio files will be played even if your application is in the background.

Discussion

In iOS, applications can request that their audio files continue playing even if the application is sent to the background. AV Foundation's `AVAudioPlayer` is an

easy-to-use audio player that we will use in this recipe. Our mission is to start an audio player and play a simple song, and while the song is playing, send the application to the background by pressing the Home button. If we have included the `UIBackgroundModes` key in our application's *.plist* file, iOS will continue playing the music the audio player in our application is playing, even in the background. While in the background, we should only play music and provide our music player with the data that is necessary for it to run. We should not be performing any other tasks, such as displaying new screens and such.

Here is the *.h* file of a simple app delegate that starts an `AVAudioPlayer`:

```
#import <UIKit/UIKit.h>
#import <AVFoundation/AVFoundation.h>

@interface Playing_Audio_in_the_BackgroundAppDelegate
    : UIResponder <UIApplicationDelegate, AVAudioPlayerDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) AVAudioPlayer *audioPlayer;

@end
```

When our app opens, we will allocate and initialize our audio player, read the contents of a file named *MySong.mp4* into an instance of `NSData` and use that data in the initialization process of our audio player:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    dispatch_queue_t dispatchQueue =
        dispatch_get_global_queue(DISPATCH_QUEUE_PRIORITY_DEFAULT, 0);

    dispatch_async(dispatchQueue, ^(void) {
        NSError *audioSessionError = nil;
        AVAudioSession *audioSession = [AVAudioSession sharedInstance];
        if ([audioSession setCategory:AVAudioSessionCategoryPlayback
                                error:&audioSessionError]){
            NSLog(@"Successfully set the audio session.");
        } else {
            NSLog(@"Could not set the audio session");
        }

        NSBundle *mainBundle = [NSBundle mainBundle];

        NSString *filePath = [mainBundle pathForResource:@"MySong"
                                                         ofType:@"mp3"];

        NSData *fileData = [NSData dataWithContentsOfFile:filePath];

        NSError *error = nil;

        /* Start the audio player */
        self.audioPlayer = [[AVAudioPlayer alloc] initWithData:fileData
                                                             error:&error];
```

```

/* Did we get an instance of AVAudioPlayer? */
if (self.audioPlayer != nil){
    /* Set the delegate and start playing */

    self.audioPlayer.delegate = self;

    if ([self.audioPlayer prepareToPlay] &&
        [self.audioPlayer play]){
        NSLog(@"Successfully started playing...");
    } else {
        NSLog(@"Failed to play.");
    }

} else {
    /* Failed to instantiate AVAudioPlayer */
}
});

self.window = [[UIWindow alloc] initWithFrame:
                [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];

return YES;
}

```



Please bear in mind that playing audio in the background might not work in iPhone Simulator. You need to test this recipe on a real device. On the simulator, chances are that the audio will stop playing once your application is sent to the background.

In this example code, we are using AV audio sessions to silence music playback from other applications (such as the iPod application) before starting to play the audio. For more information about audio sessions, please refer to [Recipe 9.5](#). When in the background, you are not limited to playing only the current audio file. If the currently playing audio file (in the background) finishes playing, you can start another instance of `AVAudioPlayer` and play a completely new audio file. iOS will adjust the processing required for this, and there is no guarantee your application will be given permission to allocate enough memory while in the background to accommodate for the data of the new sound file that needs to be played.

Another important thing to keep in mind is that while your application is running an audio file in the background, the value returned by the `backgroundTimeRemaining` property of `UIApplication` will not be changed. In other words, an application that requests to play audio files in the background is not implicitly or explicitly asking iOS for extra execution time.

12.5 Handling Location Changes in the Background

Problem

You are writing an application whose main functionality is processing location changes, using Core Location. You want the application to retrieve the iOS device location changes even if the application is sent to the background.

Solution

Add the location value to the `UIBackgroundModes` key of your main application *.plist* file, like so:

```
<dict>
  ...
  ...
  ...
  <key>UIBackgroundModes</key>
  <array>
    <string>location</string>
  </array>
  ...
  ...
  ...
</dict>
```

Discussion

When your application is running in the foreground, you can receive delegate messages from an instance of `CLLocationManager` telling you when iOS detects that the device is at a new location. However, if your application is sent to the background and is no longer active, the location delegate messages will normally not be delivered to your application. They will instead be delivered in a batch when your application becomes the foreground application again.

If you still want to be able to receive changes in the location of the user's device while running in the background, you must add the `location` value to the `UIBackgroundModes` key of your application's main *.plist* file, as shown in this recipe's [Solution](#). Once in the background, your application will continue to receive the changes in the device's location. Let's test this in a simple app with just the app delegate.

What I intend to do in this app is to keep a boolean value in the app delegate, and I will be calling it *executingInBackground*. When the app goes to the background, I will set this value to YES and when the app comes back to the foreground, I will set this value to NO. When we get location updates from CoreLocation, we will check this flag. If this flag is set to YES, then we won't do any heavy calculations or any UI update because, well, our app is in the background and as a responsible programmer we are supposed not to do heavy processing while our app is in the background. If our app is in the foreground however, we have all the device's processing power to do the normal

processing that we wish to do. We also will attempt to get the best location change accuracy when our app is in the foreground and when the app is sent to the background, we will make sure we ask for less accuracy in location updates to ease the strain on the location sensors. So let's go ahead and define our app delegate:

```
#import <UIKit/UIKit.h>
#import <CoreLocation/CoreLocation.h>

@interface Handling_Location_Changes_in_the_BackgroundAppDelegate
    : UIResponder <UIApplicationDelegate, CLLocationManagerDelegate>

@property (nonatomic, strong) UIWindow *window;
@property (nonatomic, strong) CLLocationManager *myLocationManager;
@property (nonatomic, unsafe_unretained, getter=isExecutingInBackground)
    BOOL executingInBackground;

@end
```

And then let's synthesize our properties and write the getter method of the `executingInBackground` property, called `isExecutingInBackground`:

```
#import "Handling_Location_Changes_in_the_BackgroundAppDelegate.h"

@implementation Handling_Location_Changes_in_the_BackgroundAppDelegate

@synthesize window = _window;
@synthesize myLocationManager;
@synthesize executingInBackground;

- (BOOL) isExecutingInBackground{
    return executingInBackground;
}

...
```

Now let's go ahead and create and start our location manager when our app is started:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.myLocationManager = [[CLLocationManager alloc] init];
    self.myLocationManager.desiredAccuracy = kCLLocationAccuracyBest;
    self.myLocationManager.delegate = self;
    [self.myLocationManager startUpdatingLocation];

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];
    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

You can see that we have set the desired accuracy of our location manager to a high level. However, when we go to the background, we want to lower this accuracy to give iOS a bit of a rest:


```
- (void)applicationDidEnterBackground:(UIApplication *)application{
    self.executingInBackground = YES;

    /* Reduce the accuracy to ease the strain on
       iOS while we are in the background */
    self.myLocationManager.desiredAccuracy = kCLLocationAccuracyHundredMeters;
}
```

When our app is awakened from the background, we can change this accuracy back to a high level:

```
- (void)applicationWillEnterForeground:(UIApplication *)application{
    self.executingInBackground = NO;

    /* Now that our app is in the foreground again, let's increase the location
       detection accuracy */
    self.myLocationManager.desiredAccuracy = kCLLocationAccuracyBest;
}
```

Additionally, we would like to avoid doing any intense processing when we get a new location from the location manager, while our app is in the background so we need to handle the `locationManager:didUpdateToLocation:fromLocation:` delegate method of our location manager in this way:

```
- (void)locationManager:(CLLocationManager *)manager
    didUpdateToLocation:(CLLocation *)newLocation
    fromLocation:(CLLocation *)oldLocation{

    if ([self isExecutingInBackground]){
        /* We are in the background. Do not do any heavy processing */
    } else {
        /* We are in the foreground. Do any processing that you wish */
    }

}
```

The simple rule here is that if we are in the background, we should be using the smallest amount of memory and processing power to satisfy our application's needs. So, by decreasing the accuracy of the location manager while in the background, we are decreasing the amount of processing iOS has to do to deliver new locations to our application.



Depending on the version of iOS Simulator that you are testing your applications with and also the settings of your network connection and many other factors which affect this process, background location processing might not work for you. Please test your applications, including the source code in this recipe, on a real device.

12.6 Saving and Loading the State of Multitasking iOS Apps

Problem

You want the state of your iOS app to be saved when it is sent to the background, and for the same state to resume when the application is brought to the foreground.

Solution

Use a combination of the `UIApplicationDelegate` protocol's messages sent to your application delegate and the notifications sent by iOS to preserve the state of your multitasking apps.

Discussion

When an empty iOS application (an application with just one window and no code written for it) is run on an iOS device with support for multitasking for the first time (not from the background), the following `UIApplicationDelegate` messages will be sent to your app delegate, in this order:

1. `application:didFinishLaunchingWithOptions:`
2. `applicationDidBecomeActive:`

If the user presses the Home button on her iOS device, your app delegate will receive these messages, in this order:

1. `applicationWillResignActive:`
2. `applicationDidEnterBackground:`

Once the application is in the background, the user can press the Home button twice and select our application from the list of background applications. Once our application is brought to the foreground again, we will receive these messages in the application delegate, in this order:

1. `applicationWillEnterForeground:`
2. `applicationDidBecomeActive:`

In addition to these messages, we will also receive various notification messages from iOS when our application is sent to the background or brought to the foreground again.

To save and load back the state of your apps, you need to think carefully about the tasks you need to pause when going into the background and then resume after the application is brought to the foreground. Let me give you an example. As mentioned in [Recipe 12.7](#), network connections can be easily resumed by the system itself, so we might not need to do anything special in the case of downloading a file from the network. However, if you are writing a game, for instance, it is best to listen for the notifications that iOS sends when your application is being sent to the background, and to

act accordingly. In such a scenario, you can simply put the game engine into a paused state. You can also put the state of the sound engine into a paused state if necessary.

After an application is sent to the background, it has about 10 seconds to save any unsaved data and prepare itself to be brought to the foreground at any moment by the user. You can optionally ask for extra execution time if required (further information about this is available in [Recipe 12.2](#)).

Let's demonstrate saving your state with an example. Suppose we are writing a game for iOS. When our game is sent to the background, we want to:

1. Put the game engine into a paused state.
2. Save the user's score to disk.
3. Save the current level's data to disk. This includes where the user is in the level, the physical aspects of the level, the camera position, and so on.

When the user opens the application again, bringing the application to the foreground, we want to:

1. Load the user's score from disk.
2. Load the level the user was playing the last time from disk.
3. Resume the game engine.

Now let's say our app delegate is our game engine. Let's define a few methods in the app delegate's header file:

```
#import <UIKit/UIKit.h>

@interface Saving_and>Loading_the_State_of_Multitasking_iOS_AppsAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (strong, nonatomic) UIWindow *window;

/* Saving the state of our app */
- (void) saveUserScore;
- (void) saveLevelToDisk;
- (void) pauseGameEngine;

/* Loading the state of our app */
- (void) loadUserScore;
- (void) loadLevelFromDisk;
- (void) resumeGameEngine;

@end
```

And we will proceed to place stub implementations of these methods in the implementation file of our app delegate:

```
#import "Saving_and>Loading_the_State_of_Multitasking_iOS_AppsAppDelegate.h"

@implementation
    Saving_and>Loading_the_State_of_Multitasking_iOS_AppsAppDelegate
```

```

@synthesize window = _window;

- (void) saveUserScore{
    /* Save the user score here */
}

- (void) saveLevelToDisk{
    /* Save the current level and the user's location on map to disk */
}

- (void) pauseGameEngine{
    /* Pause the game engine here */
}

- (void) loadUserScore{
    /* Load the user's location back to memory */
}

- (void) loadLevelFromDisk{
    /* Load the user's previous location on the map */
}

- (void) resumeGameEngine{
    /* Resume the game engine here */
}

...

```

Now we need to make sure that our app is able to handle interruptions such as incoming calls on an iPhone. On such occasions, our app won't be sent to the background, but it will become inactive. When the user finishes the phone call for instance, iOS will bring our app to the active state. So when our app becomes inactive, we need to make sure we are pausing our game engine and when the app becomes active again, we can resume our game engine. We don't need to save anything to the disk when our app becomes inactive really (at least in this example) because iOS will bring our app to its previous state once it becomes active again:

```

- (void)applicationWillResignActive:(UIApplication *)application{
    [self pauseGameEngine];
}

- (void)applicationDidBecomeActive:(UIApplication *)application{
    [self resumeGameEngine];
}

```

And now, simply, when our app is sent to the background, we will save the state of our game and when our app is back in the foreground, we will load the state back:

```

- (void)applicationDidEnterBackground:(UIApplication *)application{
    [self saveUserScore];
    [self saveLevelToDisk];
    [self pauseGameEngine];
}

```

```

- (void)applicationWillEnterForeground:(UIApplication *)application{
    [self loadUserScore];
    [self loadLevelFromDisk];
    [self resumeGameEngine];
}

```

Not every application is a game. However, you can use this technique to load and save the state of your application in the multitasking environment of iOS.

See Also

[Recipe 12.2](#)

12.7 Handling Network Connections in the Background

Problem

You are using instances of `NSURLConnection` to send and receive data to and from a web server and are wondering how you can allow your application to work in the multitasking environment of iOS without connection failures.

Solution

Make sure you support connection failures in the block objects that you submit to your connection objects.

Discussion

For applications that use `NSURLConnection` but do not borrow extra time from iOS when they are sent to the background, connection handling is truly simple. Let's go through an example to see how an asynchronous connection will act in case the application is sent to the background and brought to the foreground again. For this, let's send an asynchronous connection request to retrieve the contents of a URL; say, Apple's home page:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSString *urlAsString = @"http://www.apple.com";
    NSURL *url = [NSURL URLWithString:urlAsString];
    NSURLRequest *urlRequest = [NSURLRequest requestWithURL:url];
    NSOperationQueue *queue = [[NSOperationQueue alloc] init];

    [NSURLConnection
    sendAsynchronousRequest:urlRequest
    queue:queue
    completionHandler:^(NSURLResponse *response, NSData *data, NSError *error) {

        if ([data length] > 0 &&

```

```

        error != nil){
    /* Date did come back */
}
else if ([data length] == 0 &&
        error != nil){
    /* No data came back */
}
else if (error != nil){
    /* Error happened. Make sure you handle this properly */
}

}];

self.window = [[UIWindow alloc] initWithFrame:
                [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```



I advise you to replace the Apple's homepage URL in this example with the URL to a rather large file on the internet. Reason being is that if your app is downloading a large file, you will have more time to play with the app and send it to the background and bring it to the foreground. Whereas, if you are on a rather fast internet connection and you are just downloading Apple's home page, chances are that the connection is going to retrieve the data for you in a second or two.

In the foreground, our application will continue downloading the file. While downloading, the user can press the Home button and send the application to the background. What you will observe is true magic! iOS will automatically put the download process into a paused state for you. When the user brings your application to the foreground again, the downloading will resume without you writing a single line of code to handle multitasking.

Now let's see what happens with synchronous connections. We are going to download a very big file on the main thread (a very bad exercise, do not do this in a production application!) as soon as our application launches:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    /* Replace this URL with the URL of a file that is rather big in size */
    NSString *urlAsString = @"http://www.apple.com";
    NSURL *url = [NSURL URLWithString:urlAsString];
    NSURLRequest *urlRequest = [NSURLRequest requestWithURL:url];
    NSError *error = nil;

    NSData *connectionData = [NSURLConnection sendSynchronousRequest:urlRequest
                                                returningResponse:nil

```

```

error:&error];

if ([connectionData length] > 0 &&
    error == nil){

}
else if ([connectionData length] == 0 &&
    error == nil){

}
else if (error != nil){

}

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

If you run this application and send it to the background, you will notice that the application's GUI is sent to the background, but the application's core is never sent to the background and the appropriate delegate messages—`applicationWillResignActive:` and `applicationDidEnterBackground:`—will never be received. I have conducted this test on an iPhone.

The problem with this approach is that we are consuming the main thread's time slice by downloading files synchronously. We can fix this by either downloading the files asynchronously on the main thread, as mentioned before, or downloading them synchronously on separate threads.

Take the previous sample code, for example. If we download the same big file synchronously on a global concurrent queue, the connection will be paused when the application is sent to the background and will resume once it is brought to the foreground again:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

dispatch_queue_t dispatchQueue =
    dispatch_get_global_queue(DSPATCH_QUEUE_PRIORITY_DEFAULT, 0);

dispatch_async(dispatchQueue, ^(void) {

    /* Replace this URL with the URL of a file that is rather big in size */
    NSString *urlAsString = @"http://www.apple.com";
    NSURL *url = [NSURL URLWithString:urlAsString];
    NSURLRequest *urlRequest = [NSURLRequest requestWithURL:url];
    NSError *error = nil;

    NSData *connectionData = [NSURLConnection sendSynchronousRequest:urlRequest
                                                                    returningResponse:nil

```

```

error:&error];

    if ([connectionData length] > 0 &&
        error == nil){

    }
    else if ([connectionData length] == 0 &&
             error == nil){

    }
    else if (error != nil){

    }
  });

  self.window = [[UIWindow alloc] initWithFrame:
                 [[UIScreen mainScreen] bounds]];

  self.window.backgroundColor = [UIColor whiteColor];
  [self.window makeKeyAndVisible];
  return YES;
}

```

See Also

[Recipe 12.2](#)

12.8 Handling Notifications Delivered to a Waking App

Problem

When your application is brought to the foreground, you want to be able to get notifications about important system changes such as the user’s locale changes.

Solution

Simply listen to one of the many system notifications that iOS sends to waking applications. Some of these notifications are listed here:

NSCurrentLocaleDidChangeNotification

This notification is delivered to applications when the user changes her locale: for instance, if the user switches her iOS device’s language from English to Spanish in the Settings page of the device.

NSUserDefaultsDidChangeNotification

This notification is fired when the user changes the application’s settings in the Settings page of the iOS device (if any setting is provided to the user).

UIDeviceBatteryStateDidChangeNotification

This notification gets sent whenever the state of the battery of the iOS device is changed. For instance, if the device is plugged into a computer when the applica-

tion is in the foreground and then unplugged when in the background, the application will receive this notification (if the application has registered for this notification). The state can then be read using the `batteryState` property of an instance of `UIDevice`.

`UIDeviceProximityStateDidChangeNotification`

This notification gets sent whenever the state of the proximity sensor changes. The last state is available through the `proximityState` property of an instance of `UIDevice`.

Discussion

When your application is in the background, a lot of things could happen! For instance, the user might suddenly change the locale of her iOS device through the Settings page from English to Spanish. Applications can register themselves for such notifications. These notifications will be coalesced and then delivered to a waking application. Let me explain what I mean by the term *coalesced*. Suppose your application is in the foreground and you have registered for `UIDeviceOrientationDidChangeNotification` notifications. Now the user presses the Home button and your application gets sent to the background. The user then rotates the device from portrait, to landscape right, to portrait, and then to landscape left. When the user brings your application to the foreground, you will receive only one notification of type `UIDeviceOrientationDidChangeNotification`. This is coalescing. All the other orientations that happened along the way before your application opens are not important (since your application isn't on the screen) and the system will not deliver them to your application. However, the system will deliver you at least one notification for each aspect of the system, such as orientation, and you can then detect the most up-to-date orientation of the device.

Here is the implementation of a simple view controller that takes advantage of this technique to determine changes in orientation:

```
#import "Handling_Notifications_Delivered_to_a_Waking_AppViewController.h"

@implementation Handling_Notifications_Delivered_to_a_Waking_AppViewController

- (void) orientationChanged:(NSNotification *)paramNotification{
    NSLog(@"Orientation Changed");
}

- (void) viewDidLoad{
    [super viewDidLoad];

    [[NSNotificationCenter defaultCenter]
     addObserver:self
     selector:@selector(orientationChanged:)
     name:UIDeviceOrientationDidChangeNotification
     object:nil];
}
```

```

- (void)viewDidUnload{
    [super viewDidUnload];

    [[NSNotificationCenter defaultCenter] removeObserver:self];
}

- (BOOL)shouldAutorotateToInterfaceOrientation
    :(UIInterfaceOrientation)interfaceOrientation{
    return YES;
}

@end

```

Run the application on the device now. After the view controller is displayed on the screen, press the Home button to send the application to the background. Now try changing the orientation of the device a couple of times, and then relaunch the application. Observe the results, and you will see that initially when your application opens, at most one notification will be sent to the `orientationChanged:` method. You might get a second call, though, if your view hierarchy supports orientation changes.

12.9 Responding to Changes in App Settings

Problem

Your application exposes a settings bundle to the user. You want to get notified of the changes the user has made to your application's settings (while the application was in the background) as soon as your application is brought to the foreground.

Solution

Register for the `NSUserDefaultsDidChangeNotification` notification.

Discussion

Applications written for iOS can expose a bundle file for their settings. These settings will be available to users through the Settings application on their device. To get a better understanding of how this works, let's create a settings bundle:

1. In Xcode, choose File→New File.
2. Make sure the iOS category is selected on the left.
3. Choose the Resources sub-category.
4. Choose Settings Bundle as the file type and click Next.
5. Set the filename as *Settings.bundle*.
6. Click Save.

Now you have a file in Xcode named *Settings.bundle*. Leave this file as it is, without modifying it. Put the code in this recipe’s [Solution](#) into your root view controller and run the application. Press the Home button on the device and go to the device’s Settings application. If you have named your application “foo” you will see “Foo” in the Settings application, as shown in [Figure 12-6](#) (the name of the sample application I created is “Responding to Changes in App Settings”).



Figure 12-6. Our Settings.bundle displayed in the Settings app on iOS Simulator

Tap on your application’s name to see the settings your application exposes to the user, as shown in [Figure 12-7](#).



Figure 12-7. The contents of the default *Settings.bundle*

Let's go ahead and in our app delegate, start listening for `NSUserDefaultsDidChangeNotification` notifications and when our app terminates, obviously, we will remove our app delegate from the notification chain:

```
#import "Responding_to_Changes_in_App_SettingsAppDelegate.h"

@implementation Responding_to_Changes_in_App_SettingsAppDelegate

@synthesize window = _window;

- (void) settingsChanged:(NSNotification *)paramNotification{
```

```

        NSLog(@"Settings changed");
        NSLog(@"Notification Object = %@", [paramNotification object]);
    }

    - (BOOL) application:(UIApplication *)application
    didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

        [[NSNotificationCenter defaultCenter]
         addObserver:self
         selector:@selector(settingsChanged:)
         name:NSUserDefaultsDidChangeNotification
         object:nil];

        self.window = [[UIWindow alloc] initWithFrame:
                        [[UIScreen mainScreen] bounds]];

        self.window.backgroundColor = [UIColor whiteColor];
        [self.window makeKeyAndVisible];
        return YES;
    }

    - (void)applicationWillTerminate:(UIApplication *)application{
        [[NSNotificationCenter defaultCenter] removeObserver:self];
    }

    @end

```

Now try to change some of these settings while your application is running in the background. After you are done, bring the application to the foreground and you will see that only one `NSUserDefaultsDidChangeNotification` notification will be delivered to your application. The object attached to this notification will be of type `NSUserDefaults` and will contain the contents of your application's settings user defaults.

12.10 Opting Out of Multitasking

Problem

You do not want your application to participate in multitasking.

Solution

Add the `UIApplicationExitsOnSuspend` key to your application's main *.plist* file and set the value to `true`:

```

<dict>
    ...
    ...
    ...
    <key>UIApplicationExitsOnSuspend</key>

```

```
<true/>
...
...
...
</dict>
```

Discussion

In some circumstances, you might require that your iOS applications not be multitasking (although I strongly encourage you to develop your applications to be multitasking-aware). In such cases, you can add the `UIApplicationExitsOnSuspend` key to your application's main *.plist* file. Devices on latest iOS versions that support multitasking understand this value and the OS will terminate an application with this key set to `true` in the application's *.plist* file. On earlier iOS versions without support for multitasking, this value will have no meaning to the operating system and will be ignored.

When such an application runs on latest iOS, the following application delegate messages will be posted to your application:

1. `application:didFinishLaunchingWithOptions:`
2. `applicationDidBecomeActive:`

If the user presses the Home button on the device, the following messages will be sent to your application delegate:

1. `applicationDidEnterBackground:`
2. `applicationWillTerminate:`

13.0 Introduction

Core Data is a powerful framework on the iOS SDK that allows programmers to store and manage data in an object-oriented way. Traditionally, programmers had to store their data on disk using the archiving capabilities of Objective-C or write their data to files and manage them manually. With the introduction of Core Data, programmers can simply interact with its object-oriented interface to manage their data efficiently. In this chapter, you will learn how to use Core Data to create the model of your application (in the Model-View-Controller software architecture).

Core Data interacts with a persistent store at a lower level that is not visible to the programmer. iOS decides how the low-level data management is implemented. All the programmer must know is the high-level API she is provided with. But understanding the structure of Core Data and how it works internally is very important. Let's create a Core Data application to understand this a bit better.

Core Data in an iOS application needs a bit of setting up. Fortunately, with Xcode, this process is very easy. You can simply create a Core Data application and leave the rest up to Xcode.

Follow these instructions to create a project in Xcode that uses Core Data:

1. Open Xcode if it's not open already.
2. From the File menu, select New→New Project...
3. In the New Project dialog, make sure iOS is the main category on the left and Application is the sub-category under it. Then on the right hand side of the dialog, choose Empty Application and press Next, as shown in [Figure 13-1](#).




Figure 13-1. Creating an empty application for Core Data

4. Now for your product name choose Introduction to Core Data and make sure the User Core Data check box is ticked, as shown in [Figure 13-2](#). Once done, press the Next button.




Figure 13-2. Setting up a project to use Core Data

5. Now you must choose where to save your project. Once you are done selecting the destination folder, pres the Create button, as shown in [Figure 13-3](#).




Figure 13-3. Selecting where to save our Core Data project

Now in Xcode, find the file named *Introduction_to_Core_DataAppDelegate.h*. This is the shared delegate of our application, since our application is universal. Both the iPad and iPhone application delegates will use this delegate as their superclass. If you have a look at the contents of this file, you will find that three properties were added to the declaration of the application delegate for you. These properties are:

- `managedObjectContext` (of type `NSManagedObjectContext`)
- `managedObjectModel` (of type `NSManagedObjectModel`)
- `persistentStoreCoordinator` (of type `NSPersistentStoreCoordinator`)

I know this is new and probably confusing to you, but by comparing these new concepts to existing database concepts, it will become easier for you to digest:

Persistent store coordinator

This is the bridge or the connection between the physical file that stores our data and our application. This bridge will be responsible for managing different object contexts.

Managed object model

This is the same concept as a schema in a database. This could represent the tables in a database or the different types of managed objects we can create in our database.

Managed object context

This is the bridge between the programmer and the managed object model. Using the managed object context, you can insert a new row into a new table, read rows from a certain table, and so on. (Actually, Core Data doesn't use the concept of a "table," but I'm using the term here because it's familiar and will help you understand how Core Data works.)

Managed object

This is similar to a row in a table. We insert managed objects into the managed object context and save the context. This way, we create a new row in a table in our database.

In [Recipe 13.1](#), you will learn how to create a Core Data model using Xcode. This is the first step toward creating a database *schema*.

13.1 Creating a Core Data Model with Xcode

Problem

You want to visually design the data model of your iOS application using Xcode.

Solution

Follow the instructions in this chapter's [Introduction](#) to create a Core Data project. Then find the file with the extension of *xcdatamodel* in your application bundle in Xcode and click on it to open the visual data editor, as shown in [Figure 13-4](#).




Figure 13-4. Visual data editor in Xcode

Discussion

Xcode’s visual data editor is a fantastic tool that allows programmers to design the data model of their applications with ease. There are two important definitions you need to learn before you can work with this tool:

Entity

Is the same as a table in a database

Attribute

Defines a column in the entity

Entities will later become objects (managed objects) when we generate the code based on our object model. This is explained in [Recipe 13.2](#). For now, in this recipe, we will concentrate on creating the data model in this tool.

In the editor, find the + button at the bottom. Press and hold your mouse button on this button and then select Add Entity from the menu that will appear, as shown in [Figure 13-5](#):




Figure 13-5. Adding a new entity to our data model

Your new entity will be created and will be in a state whereby you can immediately rename it after creation. Change the name of this entity to Person, as shown in [Figure 13-6](#):




Figure 13-6. Changing the name of the new entity to Person

Select the **Person** entity and create the following three attributes for it, by selecting the plus [+] button in the Attributes pane (see [Figure 13-7](#)):




Figure 13-7. The Attributes box

- firstName (of type String.
- lastName (of type String.
- age (of type Integer 32.




Figure 13-8. Added three attributes to the Person entity

While you are in the data model editor, From the View menu in Xcode, choose Utilities→Show Utilities. The utilities pane will open on the right hand side of Xcode, now on top, choose the Data Model Inspector button and make sure that you have clicked on the Person entity that we just created. At this point, the Data Model inspector will be populated with items relevant to the Person entity, as shown in [Figure 13-9](#):




Figure 13-9. The Data Model Inspector shown on the right side of the Xcode window

Now click on the `firstName`, `lastName`, and the `age` attributes of the `Person` entity and in the Data Model Inspector, make sure the `firstName` and the `lastName` attributes are *not optional* by unticking the `Optional` check box and make sure the `age` field is optional by ticking the `Optional` check box.

Now your data model in the editor must look similar to that depicted in [Figure 13-10](#).




Figure 13-10. The `Person` Entity with three attributes

OK, we are done creating the model. Choose File→Save to make sure your changes are saved. To learn how to generate code based on the managed object you just created, refer to [Recipe 13.2](#).

13.2 Generating Class Files for Core Data Entities

Problem

You followed the instructions in [Recipe 13.1](#) and you want to know how to create code based on your object model.

Solution

Follow these steps:

1. In Xcode, find the file with the *xcdatamodel* extension that was created for your application when you created the application itself in Xcode. Click on the file, and you should see the editor on the righthand side of the Xcode window.
2. Select the Person entity that we created earlier (see [Recipe 13.1](#)).
3. Select File→New File in Xcode.
4. In the New File dialog, make sure you have selected iOS as the main category and Core Data as the sub-category. Then choose the `NSObject subclass` item from the right hand side of the dialog and press Next, as shown in [Figure 13-11](#).




Figure 13-11. Creating a Managed Object subclass in Xcode

5. Now choose where to save your files in your project and press Create, as shown in [Figure 13-12](#).




Figure 13-12. Selecting the destination folder for the Managed Object

Now you will see two new files in your project, called *Person.h* and *Person.m*. Open the contents of the *Person.h* file. It will look like the following:

```
#import <Foundation/Foundation.h>
#import <CoreData/CoreData.h>

@interface Person : NSManagedObject {
@private
}
@property (nonatomic, retain) NSString * firstName;
@property (nonatomic, retain) NSString * lastName;
@property (nonatomic, retain) NSNumber * age;

@end
```

The *Person.m* file is implemented for us in this way:

```
#import "Person.h"
```

```
@implementation Person
@dynamic firstName;
@dynamic lastName;
@dynamic age;

@end
```

There you go! We turned our managed object into a real definition and implementation. In [Recipe 13.3](#), you will learn how to instantiate and save a managed object of type `Person` into the managed object context of your application.

Discussion

When you create your data model using the editor in Xcode, you are creating the relationships, entities, attributes, and so forth. However, to be able to use your model in your app, you must generate the code for your model. If you view the `.h` and `.m` files for your entities, you will realize that all the attributes are being assigned dynamically. You can even see the `@dynamic` directive in the `.m` file of your entities to tell the compiler that you will fulfill the request of each attribute at runtime using dynamic method resolution.

None of the code that Core Data runs on your entities is visible to you, and there is no need for it to be visible to the programmer in the first place. All you have to know is that a `Person` entity has three attributes named `firstName`, `lastName`, and `age`. You can assign values to these attributes (if they are read/write properties) and you can save to and load them from the context, as we'll see in [Recipe 13.3](#).

13.3 Creating and Saving Data Using Core Data

Problem

You have already created a managed object and you want to instantiate it and insert that instance into your app's Core Data context.

Solution

Follow the instructions in [Recipe 13.1](#) and [Recipe 13.2](#). Now you can use the `insertNewObjectForEntityForName:inManagedObjectContext:` class method of `NSManagedObjectContext` to create a new object of a type specified by the first parameter of this method. Once the new entity (the managed object) is created, you can modify it by changing its properties. After you are done, save your managed object context using the `save:` instance method of the managed object context.

Assuming that you have created a universal application in Xcode with the name “Creating and Saving Data Using Core Data” follow these steps to insert a new managed object into the context:

1. Find the file named *Creating_and_Saving_Data_Using_Core_DataAppDelegate.m*.
2. Import the *Person.h* file into the app delegate's implementation file:



Person is the entity we created in [Recipe 13.1](#).

```
#import "Creating_and_Saving_Data_Using_Core_DataAppDelegate.h"
#import "Person.h"

@implementation Creating_and_Saving_Data_Using_Core_DataAppDelegate

@synthesize window = _window;
@synthesize managedObjectContext = __managedObjectContext;
@synthesize managedObjectModel = __managedObjectModel;
@synthesize persistentStoreCoordinator = __persistentStoreCoordinator;

...
```

3. In the `application:didFinishLaunchingWithOptions:` method of your shared application delegate, write this code:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{
    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    Person *newPerson = [NSEntityDescription
        insertNewObjectForEntityForName:@"Person"
        inManagedObjectContext:self.managedObjectContext];

    if (newPerson != nil){

        newPerson.firstName = @"Anthony";
        newPerson.lastName = @"Robbins";
        newPerson.age = [NSNumber numberWithInt:51];

        NSError *savingError = nil;

        if ([self.managedObjectContext save:&savingError]){
            NSLog(@"Successfully saved the context.");
        } else {
            NSLog(@"Failed to save the context. Error = %@", savingError);
        }

    } else {
        NSLog(@"Failed to create the new person.");
    }

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
}
```

```

    return YES;
}

```

Discussion

Previous recipes showed how to create entities and generate code based on them using the editor in Xcode. The next thing we need to do is start using those entities and instantiate them. For this, we use `NSEntityDescription` and call its `insertNewObjectForEntityForName:inManagedObjectContext:` class method. This will look up the given entity (specified by its name as `NSString`) in the given managed object context. If the entity is found, the method will return a new instance of that entity. This is similar to creating a new row (managed object) in a table (entity) in a database (managed object context).



Attempting to insert an unknown entity into a managed object context will raise an exception of type `NSInternalInconsistencyException`.

After inserting a new entity into the context, we must save the context. This will flush all the unsaved data of the context to the persistent store. We can do this using the `save:` instance method of our managed object context. If the `BOOL` return value of this method is `YES`, we can be sure that our context is saved. In [Recipe 13.4](#), you will learn how to read the data back to memory.

13.4 Reading Data from Core Data

Problem

You want to be able to read the contents of your entities (tables) using Core Data.

Solution

Use an instance of `NSFetchRequest`:

```

- (BOOL) createNewPersonWithFirstName:(NSString *)paramFirstName
                                lastName:(NSString *)paramLastName
                                age:(NSInteger)paramAge{

    BOOL result = NO;

    if ([paramFirstName length] == 0 ||
        [paramLastName length] == 0){
        NSLog(@"First and Last names are mandatory.");
        return NO;
    }

    Person *newPerson = [NSEntityDescription
                        insertNewObjectForEntityForName:@"Person"

```

```

        inManagedObjectContext:self.managedObjectContext];

    if (newPerson == nil){
        NSLog(@"Failed to create the new person.");
        return NO;
    }

    newPerson.firstName = paramFirstName;
    newPerson.lastName = paramLastName;
    newPerson.age = [NSNumber numberWithInt:paramAge];

    NSError *savingError = nil;

    if ([self.managedObjectContext save:&savingError]){
        return YES;
    } else {
        NSLog(@"Failed to save the new person. Error = %@", savingError);
    }

    return result;
}

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [self createNewPersonWithFirstName:@"Anthony"
                                lastName:@"Robbins"
                                age:51];

    [self createNewPersonWithFirstName:@"Richard"
                                lastName:@"Branson"
                                age:61];

    /* Create the fetch request first */
    NSFetchRequest *fetchRequest = [[NSFetchRequest alloc] init];

    /* Here is the entity whose contents we want to read */
    NSEntityDescription *entity =
    [NSEntityDescription
    entityForName:@"Person"
    inManagedObjectContext:self.managedObjectContext];

    /* Tell the request that we want to read the
    contents of the Person entity */
    [fetchRequest setEntity:entity];

    NSError *requestError = nil;

    /* And execute the fetch request on the context */
    NSArray *persons =
    [self.managedObjectContext executeFetchRequest:fetchRequest
                                error:&requestError];

```

```

/* Make sure we get the array */
if ([persons count] > 0){

    /* Go through the persons array one by one */
    NSUInteger counter = 1;
    for (Person *thisPerson in persons){

        NSLog(@"Person %lu First Name = %@",
              (unsigned long)counter,
              thisPerson.firstName);

        NSLog(@"Person %lu Last Name = %@",
              (unsigned long)counter,
              thisPerson.lastName);

        NSLog(@"Person %lu Age = %ld",
              (unsigned long)counter,
              (unsigned long)[thisPerson.age integerValue]);

        counter++;
    }

} else {
    NSLog(@"Could not find any Person entities in the context.");
}

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

For more information about fetch requests, please refer to this recipe's [Discussion](#).

Discussion

For those of you who are familiar with database terminology, a *fetch request* is similar to a `SELECT` statement. In the `SELECT` statement, you specify which rows, with which conditions, have to be returned from which table. With a fetch request, we do the same thing. We specify the entity (table) and the managed object context (the database layer). We can also specify sort descriptors for sorting the data we read. But first we'll focus on reading the data to make it simpler.

To be able to read the contents of the `Person` entity (we created this entity in [Recipe 13.1](#) and turned it into code in [Recipe 13.2](#)), we first ask the `NSEntityDescription` class to search in our managed object context for an entity named `Person`. Once it is found, we will tell our fetch request what entity we want to read from. After this, all that's left to do is to execute the fetch request as we saw in this recipe's [Solution](#).

The return value of the `executeFetchRequest:error:` instance method of `NSManagedObjectContext` is either `nil` (in case of an error) or an array of `Person` managed objects. If no results are found for the given entity, the returned array will be empty.

See Also

[Recipe 13.1](#); [Recipe 13.2](#)

13.5 Deleting Data From Core Data

Problem

You want to delete a managed object (a row in a table) from a managed object context (your database).

Solution

Use the `deleteObject:` instance method of `NSManagedObjectContext`:

```
- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [self createNewPersonWithFirstName:@"Anthony"
                                lastName:@"Robbins"
                                age:51];

    [self createNewPersonWithFirstName:@"Richard"
                                lastName:@"Branson"
                                age:61];

    /* Create the fetch request first */
    NSFetchRequest *fetchRequest = [[NSFetchRequest alloc] init];

    /* Here is the entity whose contents we want to read */
    NSEntityDescription *entity =
    [NSEntityDescription entityForName:@"Person"
     inManagedObjectContext:self.managedObjectContext];

    /* Tell the request that we want to read the
    contents of the Person entity */
    [fetchRequest setEntity:entity];

    NSError *requestError = nil;

    /* And execute the fetch request on the context */
    NSArray *persons =
    [self.managedObjectContext executeFetchRequest:fetchRequest
                                error:&requestError];

    /* Make sure we get the array */
    if ([persons count] > 0){
```



```

/* Delete the last person in the array */
Person *lastPerson = [persons lastObject];

[self.managedObjectContext deleteObject:lastPerson];

NSError *savingError = nil;
if ([self.managedObjectContext save:&savingError]){
    NSLog(@"Successfully deleted the last person in the array.");
} else {
    NSLog(@"Failed to delete the last person in the array.");
}

} else {
    NSLog(@"Could not find any Person entities in the context.");
}

self.window = [[UIWindow alloc] initWithFrame:
                [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```



In this example code we are using the `createNewPersonWithFirstName:lastName:age:` method which we coded in the [Recipe 13.4](#).

Discussion

You can delete managed objects (records of a table in a database) using the `deleteObject:` instance method of `NSManagedObjectContext`.

This method doesn't return an error to you in any of its parameters and it doesn't return a `BOOL` value either so you really have no good way of knowing whether an object was successfully deleted or not using the managed object context. The best way to determine if an object was deleted successfully or not is to use that managed object's `isDeleted` method.

With this information, let's change the code that we wrote in this recipe previously:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [self createNewPersonWithFirstName:@"Anthony"
                                lastName:@"Robbins"
                                age:51];

    [self createNewPersonWithFirstName:@"Richard"
                                lastName:@"Branson"
                                age:61];
}

```

```

/* Create the fetch request first */
NSFetchRequest *fetchRequest = [[NSFetchRequest alloc] init];

/* Here is the entity whose contents we want to read */
NSEntityDescription *entity =
[NSEntityDescription entityForName:@"Person"
    inManagedObjectContext:self.managedObjectContext];

/* Tell the request that we want to read the
contents of the Person entity */
[fetchRequest setEntity:entity];

NSError *requestError = nil;

/* And execute the fetch request on the context */
NSArray *persons =
[self.managedObjectContext executeFetchRequest:fetchRequest
    error:&requestError];

/* Make sure we get the array */
if ([persons count] > 0){

    /* Delete the last person in the array */
    Person *lastPerson = [persons lastObject];

    [self.managedObjectContext deleteObject:lastPerson];

    if ([lastPerson isDeleted]){
        NSLog(@"Successfully deleted the last person...");

        NSError *savingError = nil;
        if ([self.managedObjectContext save:&savingError]){
            NSLog(@"Successfully saved the context.");
        } else {
            NSLog(@"Failed to save the context.");
        }
    }

    } else {
        NSLog(@"Failed to delete the last person.");
    }

} else {
    NSLog(@"Could not find any Person entities in the context.");
}

self.window = [[UIWindow alloc] initWithFrame:
    [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

And once you run the app, you will get results similar to this, printed to the console window:

Successfully deleted the last person...
Successfully saved the context.

13.6 Sorting Data in Core Data

Problem

You want to sort the managed objects (records) that you fetch from a managed object context (database).

Solution

Create instances of `NSSortDescriptor` for each attribute (column, in the database world) of an entity that has to be sorted. Add the sort descriptors to an array and assign the array to an instance of `NSFetchRequest` using the `setSortDescriptors:` instance method. In this example code, `Sorting_Data_in_Core_DataAppDelegate` is the class that represents the app delegate in a universal app. To understand how the `Person` entity is created, please refer to [Recipe 13.1](#) and [Recipe 13.2](#).

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [self createNewPersonWithFirstName:@"Richard"
                                lastName:@"Branson"
                                age:61];

    [self createNewPersonWithFirstName:@"Anthony"
                                lastName:@"Robbins"
                                age:51];

    /* Create the fetch request first */
    NSFetchRequest *fetchRequest = [[NSFetchRequest alloc] init];

    /* Here is the entity whose contents we want to read */
    NSEntityDescription *entity =
    [NSEntityDescription entityForName:@"Person"
     inManagedObjectContext:self.managedObjectContext];

    NSSortDescriptor *ageSort =
    [[NSSortDescriptor alloc] initWithKey:@"age"
                                     ascending:YES];

    NSSortDescriptor *firstNameSort =
    [[NSSortDescriptor alloc] initWithKey:@"firstName"
                                     ascending:YES];

    NSArray *sortDescriptors = [[NSArray alloc] initWithObjects:
                                ageSort,
                                firstNameSort, nil];

    fetchRequest.sortDescriptors = sortDescriptors;
```

```

/* Tell the request that we want to read the
   contents of the Person entity */
[fetchRequest setEntity:entity];

NSError *requestError = nil;

/* And execute the fetch request on the context */
NSArray *persons =
[self.managedObjectContext executeFetchRequest:fetchRequest
                                     error:&requestError];

for (Person *person in persons){

    NSLog(@"First Name = %@", person.firstName);
    NSLog(@"Last Name = %@", person.lastName);
    NSLog(@"Age = %lu", (unsigned long)[person.age unsignedIntegerValue]);

}

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

Discussion

An instance of `NSFetchRequest` can carry with itself an array of `NSSortDescriptor` instances. Each sort descriptor defines the attribute (column) on the current entity that has to be sorted and whether the sorting has to be ascending or descending. For instance, the `Person` entity we created in [Recipe 13.1](#) has `firstName`, `lastName`, and `age` attributes. If we want to read all the persons in a managed object context and sort them from youngest to oldest, we would create an instance of `NSSortDescriptor` with the `age` key and set it to be ascending:

```

NSSortDescriptor *ageSortDescriptor =
    [[NSSortDescriptor alloc] initWithKey:@"age"
                                     ascending:YES];

```



You can assign more than one sort descriptor to one fetch request

See Also

[Recipe 13.4](#)

13.7 Boosting Data Access in Table Views

Problem

In an application that uses table views to present managed objects to the user, you want to be able to fetch and present the data in a more fluid and natural way than managing your data manually.

Solution

Use fetched results controllers, which are instances of `NSFetchedResultsController`.

Discussion

Fetched results controllers work in the same way as table views. Both have sections and rows. A fetched results controller can read managed objects from a managed object context and separate them into sections and rows. Each section is a group (if you specify it) and each row in a section is a managed object. You can then easily map this data to a table view and display it to the user. There are a few very important reasons why you might want to modify your application to use fetched results controllers:

- After a fetched results controller is created on a managed object context, any change (insertion, deletion, modification, etc.) will immediately be reflected on the fetched results controller as well. For instance, you could create your fetched results controller to read the managed objects of the `Person` entity. Then in some other place in your application, you insert a new `Person` managed object into the context (the same context the fetched results controller was created on). Immediately, the new managed object will become available in the fetched results controller. This is just magical!
- With a fetched results controller you can manage cache more efficiently. For instance, you can ask your fetched results controller to only keep N number of managed objects in memory per controller instance.
- Fetched results controllers are exactly like table views in the sense that they have sections and rows, as explained before. You can use a fetched results controller to present managed objects in the GUI of your application with table views with ease.

Here are some of the important properties and instance methods of fetched results controllers (all are objects of type `NSFetchedResultsController`):

`sections` (*property, of type `NSArray`*)

A fetched results controller can group data together using a key path. The designated initializer of the `NSFetchedResultsController` class accepts this grouping filter through the `sectionNameKeyPath` parameter. The `sections` array will then contain each grouped section. Each object in this array conforms to the `NSFetchedResultsControllerSectionInfo` protocol.

objectAtIndexPath: (*instance method, returns a managed object*)

Objects fetched with a fetched results controller can be retrieved using their section and row index. Each section contains rows 0 to $N - 1$, where N is the total number of items in that section. An index path object comprises a section and row index, and perfectly matches the information needed to retrieve objects from a fetched results controller. The **objectAtIndexPath:** instance method accepts index paths. Each index path is of type **NSIndexPath**. If you need to construct a table view cell using a managed object in a fetched results controller, simply pass the index path object in the **cellForRowAtIndexPath** parameter of the **tableView:cellForRowAtIndexPath:** delegate method of a table view. If you want to construct an index path yourself anywhere else in your application, use the **indexPathForRow:inSection:** class method of **NSIndexPath**.

fetchRequest (*property, of type NSFetchedRequest*)

If at any point in your application, you believe you have to change the fetch request object for your fetched results controllers, you can do so using the **fetchRequest** property of an instance of **NSFetchedResultsController**. This is useful, for example, if you want to change the sort descriptors (refer to [Recipe 13.6](#) for sort descriptors) of the fetch request object after you have allocated and initialized your fetched results controllers.

In order to demonstrate the usefulness of fetch results controllers, we need to create an app that allows us to add new managed objects to and delete managed objects from our managed objects context using a user interface. For this, we will need two view controllers:

Persons List View Controller

This will be our root view controller and in it, we will display a table view and inside the table view we will list all the Person managed objects that we have in our managed objects context. Please refer to [Recipe 13.1](#) to see how we created the Person managed object. The table view on this view controller must allow the user to delete Person objects by swiping or pressing the Edit button on the navigation bar. We will display a + button on the navigation bar as well, to allow the user to add new Person objects to the managed object context.

Add New Person View Controller

We will use this view controller to allow the user to add new Person objects to the managed object context.

To do this, simply follow these instructions:

1. So let's start with an empty application. Go to Xcode, select File→New→New Project... and choose an Empty Application universal iOS project (with Core Data enabled. See [Recipe 13.1](#) for more information.) and name it *Boosting Data Access in Table Views*. Now select the *Boosting_Data_Access_in_Table_Views.xcdata-model* in Xcode and create the same exact Person entity that we created in [Recipe 13.1](#) and save it as Person.

2. In your project, create two view controllers, both subclassing `UIViewController`. Name one *PersonListViewController* and the other *AddPersonViewController*. Create both these view controllers without a xib file (we won't need Interface Builder as our UI is very simple indeed).
3. Now open the declaration of your app delegate and define a new property of type *PersonListViewController* and call it `personListViewController`. This will be the root view controller which we will display to our users. Remember that we also need a navigation controller so let's define that as a property too:

```
#import <UIKit/UIKit.h>

@class PersonListViewController;

@interface Boosting_Data_Access_in_Table_ViewsAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (strong, nonatomic) UIWindow *window;

@property (nonatomic, strong)
    PersonListViewController *personListViewController;

@property (nonatomic, strong) UINavigationController *navigationController;

@property (readonly, strong, nonatomic)
    NSManagedObjectContext *managedObjectContext;

@property (readonly, strong, nonatomic)
    NSManagedObjectModel *managedObjectModel;

@property (readonly, strong, nonatomic)
    NSPersistentStoreCoordinator *persistentStoreCoordinator;

- (void)saveContext;
- (NSURL *)applicationDocumentsDirectory;

@end
```

4. Now let's go to the implementation of our app delegate and synthesize both the view controller and the navigation controller properties and make sure that we have imported the *PersonListViewController.h* header file into the implementation file of our app delegate, since that is where we want to initialize an instance of this object:

```
#import "Boosting_Data_Access_in_Table_ViewsAppDelegate.h"
#import "PersonListViewController.h"

@implementation Boosting_Data_Access_in_Table_ViewsAppDelegate

@synthesize window = _window;
@synthesize managedObjectContext = __managedObjectContext;
@synthesize managedObjectModel = __managedObjectModel;
@synthesize persistentStoreCoordinator = __persistentStoreCoordinator;
```

```
@synthesize personListViewController;
@synthesize navigationController;
```

```
...
```

5. When our app loads up, we want to display the Person List View Controller to them, so let's do that now in the `application:didFinishLaunchingWithOptions:` method of our app delegate:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.personListViewController =
    [[PersonListViewController alloc]
     initWithNibName:nil
     bundle:nil];

    self.navigationController =
    [[UINavigationController alloc]
     initWithRootViewController:self.personListViewController];

    self.window = [[UIWindow alloc] initWithFrame:
    [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];

    self.window.rootViewController = self.navigationController;

    return YES;
}
```

6. When the Person List view controller is displayed, we want to place a table view on it to list all the person entities in our managed object context. Let's create the table now and set up our view controller as that table view's delegate and data source. We also need an Add button on the navigation bar with a little + sign on it so when the user taps on that button it will take the user to the Add Person view controller. In addition to these two properties, we will also need to have our fetched results controller in the root view controller. So let's define all these in our view controller's definition:

```
#import <UIKit/UIKit.h>
#import <CoreData/CoreData.h>

@interface PersonListViewController : UIViewController
    <UITableViewDelegate,
    UITableViewDataSource,
    NSFetchedResultsControllerDelegate>

@property (nonatomic, strong) UITableView *tableViewPersons;
@property (nonatomic, strong) UIBarButtonItem *barButtonAddPerson;
@property (nonatomic, strong) NSFetchedResultsController *personsFRC;

@end
```


7. As usual, let's synthesize our properties:

```
#import "PersonListViewController.h"

@implementation PersonListViewController

@synthesize tableViewPersons;
@synthesize barButtonAddPerson;
@synthesize personsFRC;

...
```

8. Next, we need to start implementing our view controller. In the `viewDidLoad` method, let's instantiate our Add navigation bar button. Also, let's instantiate our table view and set up the edit button on the navigation bar:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.title = @"Persons";

    self.tableViewPersons =
    [[UITableView alloc] initWithFrame:self.view.bounds
                                     style:UITableViewStylePlain];
    self.tableViewPersons.delegate = self;
    self.tableViewPersons.dataSource = self;

    [self.view addSubview:self.tableViewPersons];

    self.barButtonAddPerson = [[UIBarButtonItem alloc]
                               initWithBarButtonSystemItem:UIBarButtonSystemItemAdd
                               target:self
                               action:@selector(addNewPerson:)];

    [self.navigationItem setLeftBarButtonItem:[self editButtonItem]
                        animated:NO];
    [self.navigationItem setRightBarButtonItem:self.barButtonAddPerson
                        animated:NO];
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.barButtonAddPerson = nil;
    self.tableViewPersons = nil;
}
```

9. Obviously, now that we have elected the root view controller to become the delegate and the data source of the table view, we need to go and implement the required methods for the delegate and the data source. For now, we will return 0 cells to the table view. Later, when we properly read Person entities from the managed object context using the fetched results controller, we can return the appropriate count of Person objects:

```

- (NSInteger)tableView:(UITableView *)tableView
numberOfRowsInSection:(NSInteger)section{
    return 0;
}

- (UITableViewCell *)tableView:(UITableView *)tableView
cellForRowAtIndexPath:(NSIndexPath *)indexPath{
    return nil;
}

```

10. Now let's hook the + button to the Add Person view controller, so make sure you have imported the *AddPersonViewController.h* header file into the implementation file of Person List view controller:

```

- (void) addNewPerson:(id)sender{

    AddPersonViewController *controller = [[AddPersonViewController alloc]
                                           initWithNibName:nil
                                           bundle:nil];
    [self.navigationController pushViewController:controller
                                           animated:YES];

}

```

11. In the Add Person view controller, we need 4 properties. Three text fields one for first name, second one for last name and last one for age of the person and the fourth property would be for an Add navigation button which we will place on the navigation bar. The user will press this button once she is done, to add the new person to the list:

```

#import <UIKit/UIKit.h>
#import <CoreData/CoreData.h>

@interface AddPersonViewController : UIViewController

@property (nonatomic, strong) UITextField *textFieldFirstName;
@property (nonatomic, strong) UITextField *textFieldLastName;
@property (nonatomic, strong) UITextField *textFieldAge;
@property (nonatomic, strong) UIBarButtonItem *barButtonAdd;

@end

```

12. What's after this? You guessed it! Synthesizing our properties:

```

#import "AddPersonViewController.h"

@implementation AddPersonViewController

@synthesize textFieldFirstName;
@synthesize textFieldLastName;
@synthesize textFieldAge;
@synthesize barButtonAdd;

...

```

13. Now in the `viewDidLoad` method of our Add Person view controller, let's instantiate these properties and place them on the view and put the bar button on the navigation bar:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.title = @"New Person";

    CGRect textFieldRect = CGRectMake(20.0f,
                                       20.0f,
                                       self.view.bounds.size.width - 40.0f,
                                       31.0f);

    self.textFieldFirstName = [[UITextField alloc] initWithFrame:textFieldRect];
    self.textFieldFirstName.placeholder = @"First Name";
    self.textFieldFirstName.borderStyle = UITextBorderStyleRoundedRect;
    self.textFieldFirstName.autoresizingMask = UIViewAutoresizingFlexibleWidth;
    self.textFieldFirstName.contentVerticalAlignment =
        UIControlContentVerticalAlignmentCenter;
    [self.view addSubview:self.textFieldFirstName];

    textFieldRect.origin.y += 37.0f;
    self.textFieldLastName = [[UITextField alloc] initWithFrame:textFieldRect];
    self.textFieldLastName.placeholder = @"Last Name";
    self.textFieldLastName.borderStyle = UITextBorderStyleRoundedRect;
    self.textFieldLastName.autoresizingMask = UIViewAutoresizingFlexibleWidth;
    self.textFieldLastName.contentVerticalAlignment =
        UIControlContentVerticalAlignmentCenter;
    [self.view addSubview:self.textFieldLastName];

    textFieldRect.origin.y += 37.0f;
    self.textFieldAge = [[UITextField alloc] initWithFrame:textFieldRect];
    self.textFieldAge.placeholder = @"Age";
    self.textFieldAge.borderStyle = UITextBorderStyleRoundedRect;
    self.textFieldAge.autoresizingMask = UIViewAutoresizingFlexibleWidth;
    self.textFieldAge.keyboardType = UIKeyboardTypeNumberPad;
    self.textFieldAge.contentVerticalAlignment =
        UIControlContentVerticalAlignmentCenter;
    [self.view addSubview:self.textFieldAge];

    self.barButtonItemAdd =
    [[UIBarButtonItem alloc] initWithTitle:@"Add"
                                       style:UIBarButtonItemStylePlain
                                       target:self
                                       action:@selector(createNewPerson:)];
    [self.navigationItem setRightBarButtonItem:self.barButtonItemAdd
                       animated:NO];
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.textFieldFirstName = nil;
    self.textFieldLastName = nil;
```

```

        self.textFieldAge = nil;
        self.barButtonAdd = nil;
    }

```

14. As you can see, the Add button is now linked to the `createNewPerson:` method of our Add Person view controller so all we have to do is to implement this method and get the values in our text fields and place them in a new Person object. Then we will need to save this object into the managed object context and then pop the view controller to go back to the Person List view controller (at which time the Person View Controller will need to display the new person in the list. For all this, we need to make sure we have imported the *Person.h* and the *Boosting_Data_Access_in_Table_ViewsAppDelegate.h* header files into the Add Person view controller's implementation file so that we can create a new person and use the managed object context in the app delegate to insert that person into the database:

```

#import "AddPersonViewController.h"
#import "Person.h"
#import "Boosting_Data_Access_in_Table_ViewsAppDelegate.h"

```

```

@implementation AddPersonViewController

```

```

    @synthesize textFieldFirstName;
    @synthesize textFieldLastName;
    @synthesize textFieldAge;
    @synthesize barButtonAdd;

```

```

    ...

```

15. Now let's implement the `createNewPerson:` method in the Add Person view controller:

```

- (void) createNewPerson:(id)paramSender{

    Boosting_Data_Access_in_Table_ViewsAppDelegate *appDelegate =
        (Boosting_Data_Access_in_Table_ViewsAppDelegate *)
        [[UIApplication sharedApplication] delegate];

    NSManagedObjectContext *managedObjectContext =
        appDelegate.managedObjectContext;

    Person *newPerson =
        [NSEntityDescription insertNewObjectForEntityForName:@"Person"
        inManagedObjectContext:managedObjectContext];

    if (newPerson != nil){

        newPerson.firstName = self.textFieldFirstName.text;
        newPerson.lastName = self.textFieldLastName.text;
        newPerson.age = [NSNumber numberWithInt:
            [self.textFieldAge.text integerValue]];

        NSError *savingError = nil;

        if ([managedObjectContext save:&savingError]){

```

```

        [self.navigationController popViewControllerAnimated:YES];
    } else {
        NSLog(@"Failed to save the managed object context.");
    }

    } else {
        NSLog(@"Failed to create the new person object.");
    }
}

```

16. To offer a better user experience, when our view appears on the screen, we can automatically display the keyboard on the first name text field:

```

- (void) viewWillAppear:(BOOL)paramAnimated{
    [super viewWillAppear:paramAnimated];
    [self.textFieldFirstName becomeFirstResponder];
}

```

17. We are done with the Add Person view controller. You can actually now go ahead and try it out for yourself. Let's now go to the Person List view controller and during its initialization, let's instantiate our fetched results controller:

```

#import "PersonListViewController.h"
#import "AddPersonViewController.h"
#import "Boosting_Data_Access_in_Table_VIEWSAppDelegate.h"
#import "Person.h"

@implementation PersonListViewController

@synthesize tableViewPersons;
@synthesize barButtonAddPerson;
@synthesize personsFRC;

- (NSManagedObjectContext *) managedObjectContext{
    Boosting_Data_Access_in_Table_VIEWSAppDelegate *appDelegate =
        (Boosting_Data_Access_in_Table_VIEWSAppDelegate *)
        [[UIApplication sharedApplication] delegate];

    NSManagedObjectContext *managedObjectContext =
        appDelegate.managedObjectContext;

    return managedObjectContext;
}

- (id) initWithNibName:(NSString *)nibNameOrNil
    bundle:(NSBundle *)nibBundleOrNil{

    self = [super initWithNibName:nibNameOrNil
        bundle:nibBundleOrNil];

    if (self != nil){

```

```

/* Create the fetch request first */
NSFetchRequest *fetchRequest = [[NSFetchRequest alloc] init];

/* Here is the entity whose contents we want to read */
NSEntityDescription *entity =
[NSEntityDescription entityForName:@"Person"
    inManagedObjectContext:[self managedObjectContext]];

NSSortDescriptor *ageSort =
[[NSSortDescriptor alloc] initWithKey:@"age"
    ascending:YES];

NSSortDescriptor *firstNameSort =
[[NSSortDescriptor alloc] initWithKey:@"firstName"
    ascending:YES];

NSArray *sortDescriptors = [[NSArray alloc] initWithObjects:
    ageSort,
    firstNameSort, nil];

fetchRequest.sortDescriptors = sortDescriptors;

/* Tell the request that we want to read the
    contents of the Person entity */
[fetchRequest setEntity:entity];

self.personsFRC =
[[NSFetchedResultsController alloc]
    initWithFetchRequest:fetchRequest
    managedObjectContext:[self managedObjectContext]
    sectionNameKeyPath:nil
    cacheName:nil];

self.personsFRC.delegate = self;
NSError *fetchingError = nil;
if ([self.personsFRC performFetch:&fetchingError]){
    NSLog(@"Successfully fetched.");
} else {
    NSLog(@"Failed to fetch.");
}
}

return self;
}

```

18. Now let's go ahead and implement various methods of our table view delegate (we had left them to their minimum required implementation before). We must now be able to read the fetched managed objects from the fetched results controller and display the Person managed objects in the table view:

```

- (NSInteger)tableView:(UITableView *)tableView
    numberOfRowsInSection:(NSInteger)section{

```

```

        id <NSFetchedResultsControllerSectionInfo> sectionInfo = [self.personsFRC.sections
                                                                objectAtIndex:section];
        return [sectionInfo numberOfObjects];
    }

- (UITableViewCell *)tableView:(UITableView *)tableView
    cellForRowAtIndexPath:(NSIndexPath *)indexPath{

    UITableViewCell *result = nil;

    static NSString *PersonTableViewCell = @"PersonTableViewCell";

    result = [tableView dequeueReusableCellWithIdentifier:PersonTableViewCell];

    if (result == nil){
        result =
            [[UITableViewCell alloc] initWithStyle:UITableViewCellStyleSubtitle
                                    reuseIdentifier:PersonTableViewCell];

        result.selectionStyle = UITableViewCellSelectionStyleNone;
    }

    Person *person = [self.personsFRC objectAtIndex:indexPath.index];

    result.textLabel.text =
        [person.firstName stringByAppendingFormat:@" %@", person.lastName];

    result.detailTextLabel.text =
        [NSString stringWithFormat:@"Age: %lu",
        (unsigned long)[person.age integerValue]];

    return result;
}

```

19. You can now run the app and test it for yourself. One of the issues in our app at the moment is that if the user goes to the Add Person view controller and adds a new person to the managed object context, when she is sent back to the Person List view controller, the new person she just inserted into the context will not appear in the list. That is because our fetched results controller doesn't know about the new object in the managed object context. The way to solve this is to implement the `controllerDidChangeContent:` delegate method of our fetched results controller object in the Person List view controller. When we created our fetched results controller, we nominated this view controller to become the delegate of the fetched results controller so let's implement this method. This method gets called when the fetched results controller detects a change in the objects in the managed object context so once this method gets called, we can go ahead and reload our table view:

```

- (void)controllerDidChangeContent:(NSFetchedResultsController *)controller{
    [self.tableViewPersons reloadData];
}

```

20. The next thing we have to do in our Person List view controller is to handle editing:

```
- (void) tableView:(UITableView *)tableView
    commitEditingStyle:(UITableViewCellEditingStyle)editingStyle
    forRowAtIndexPath:(NSIndexPath *)indexPath{

    Person *personToDelete = [self.personsFRC objectAtIndex:indexPath.index];

    /* Very important: we need to make sure we are not reloading the table view
    while deleting the managed object */
    self.personsFRC.delegate = nil;

    [[self managedObjectContext] deleteObject:personToDelete];

    if ([personToDelete isDeleted]){
        NSError *savingError = nil;
        if ([[self managedObjectContext] save:&savingError]){

            NSError *fetchingError = nil;
            if ([self.personsFRC performFetch:&fetchingError]){
                NSLog(@"Successfully fetched.");

                NSArray *rowsToDelete = [[NSArray alloc]
                                           initWithObjects:indexPath, nil];

                [tableViewPersons
                 deleteRowsAtIndexPaths:rowsToDelete
                 withRowAnimation:UITableViewRowAnimationAutomatic];

            } else {
                NSLog(@"Failed to fetch with error = %@", fetchingError);
            }

        } else {
            NSLog(@"Failed to save the context with error = %@", savingError);
        }
    }

    self.personsFRC.delegate = self;
}

- (UITableViewCellEditingStyle)tableView:(UITableView *)tableView
    editingStyleForRowAtIndexPath:(NSIndexPath *)indexPath{
    return UITableViewCellEditingStyleDelete;
}

- (void) setEditing:(BOOL)paramEditing
    animated:(BOOL)paramAnimated{

    [super setEditing:paramEditing
     animated:paramAnimated];

    if (paramEditing){
        [self.navigationItem setRightBarButtonItem:nil
```



```

                                animated:YES];
    } else {
        [self.navigationItem setRightBarButtonItem:self.barButtonItemAddPerson
                                animated:YES];
    }

    [self.tableViewPersons setEditing:paramEditing
                            animated:YES];
}

```

We are all done. Go ahead and try it out for yourself.

13.8 Implementing Relationships in Core Data

Problem

You want to be able to link your managed objects to each other: for instance, linking a `Person` to the `Home` she lives in.

Solution

Use inverse relationships in the model editor.

Discussion

Relationships in Core Data can be one-way, inverse one-to-many, or inverse many-to-many. Here is an example for each type of relationship:

One-way relationship

For instance, the relationship between a person and her nose. Each person can have only one nose and each nose can belong to only one person.

Inverse one-to-many relationship

For instance, the relationship between an employee and his manager. The employee can have only one direct manager, but his manager can have multiple employees working for her. Here the relationship of the employee with the manager is one-to-one, but from the manager's perspective, the relationship is one (manager) to many (employees); hence the word *inverse*.

Inverse many-to-many relationship

For instance, the relationship between a person and a car. One car can be used by more than one person, and one person can have more than one car.

In Core Data, you can create one-way relationships, but I highly recommend that you avoid doing so because, going back to the example in the preceding list, the person will know what nose she has but the nose will not know who it belongs to. In an object-oriented programming language such as Objective-C, it is always best to create inverse relationships so that children elements can refer to parent elements of that relationship.

Let's go ahead and create a data model that takes advantage of an inverse one-to-many relationship:

1. In Xcode, find the *xcdatamodel* file that was created for you when you started your Core Data project, as shown earlier in [Figure 13-1](#) (refer to [Recipe 13.1](#) to create such a project).
2. Open the data model file in the editor by clicking on it.
3. Remove any entities that were created for you previously by selecting them and pressing the Delete key on your keyboard.
4. Create a new entity and name it **Employee**. Create three attributes for this entity, named **firstName** (of type **String**), **lastName** (of type **String**), and **age** (of type **Integer 32**), as shown in [Figure 13-13](#).




Figure 13-13. The *Employee* entity with three attributes

5. Create another entity named **Manager** with the same attributes you created for the **Employee** entity (**firstName** of type **String**, **lastName** of type **String**, and **age** of type **Integer 32**). See [Figure 13-14](#).




Figure 13-14. The Manager entity with three attributes

6. Create a new relationship for the **Manager** entity by first selecting the Manager entity in the list and then pressing the + button in the bottom of the Relationships box (see [Figure 13-15](#)).




Figure 13-15. Added a new relationship to the Manager entity

7. Set the name of the new relationship to FKManagerToEmployees (see [Figure 13-16](#)).




Figure 13-16. Changing the name of the new Manager to Employees relationship

8. Select the Employee entity and create a new relationship for it. Name the relationship FKEmployeeToManager (see [Figure 13-17](#)).




Figure 13-17. Changing the name of the new Employee to Manager relationship

9. Choose the **Manager** entity, and then select the **FKManagerToEmployees** relationship for the **Manager**. In the Relationships box, choose **Employee** in the Destination drop-down menu (because we want to connect a **Manager** to an **Employee** entity through this relationship), set the Inverse box's value to **FKEmployeeToManager** (because the **FKEmployeeToManager** relationship of the **Employee** will link an employee to her **Manager**), and tick the To-Many Relationship box in Data Model inspector (see [Recipe 13.1](#)). The results are shown in [Figure 13-18](#).




Figure 13-18. The Manager inverse relationship established with employees

10. Select both your `Employee` and `Manager` entities, select `File→New File`, and create the managed object classes for your model, as described in [Recipe 13.2](#).

After creating the inverse one-to-many relationship, open the `.h` file of your `Employee` entity:

```
#import <Foundation/Foundation.h>
#import <CoreData/CoreData.h>

@class Manager;

@interface Employee : NSObject {
@private
}
@property (nonatomic, retain) NSString * firstName;
@property (nonatomic, retain) NSString * lastName;
@property (nonatomic, retain) NSNumber * age;
@property (nonatomic, retain) Manager *FKEmployeeToManager;

@end
```

You can see that a new property is added to this file. The property is named `FKEmployeeToManager` and its type is `Manager`, meaning that from now on, if we have a reference to any object of type `Employee`, we can access its `FKEmployeeToManager` property to access that specific employee's `Manager` object (if any). Let's have a look at the `.h` file of the `Manager` entity:

```
#import <Foundation/Foundation.h>
#import <CoreData/CoreData.h>

@class Employee;
```

```

@interface Manager : NSObject {
@private
}
@property (nonatomic, retain) NSNumber * age;
@property (nonatomic, retain) NSString * firstName;
@property (nonatomic, retain) NSString * lastName;
@property (nonatomic, retain) NSSet *FKManagerToEmployees;
@end

@interface Manager (CoreDataGeneratedAccessors)

- (void)addFKManagerToEmployeesObject:(Employee *)value;
- (void)removeFKManagerToEmployeesObject:(Employee *)value;
- (void)addFKManagerToEmployees:(NSSet *)values;
- (void)removeFKManagerToEmployees:(NSSet *)values;
@end

```

The `FKManagerToEmployees` property is also created for the `Manager` entity. The data type of this object is `NSSet`. This simply means the `FKManagerToEmployees` property of any instance of the `Manager` entity can contain 1 to N number of `Employee` entities (a one-to-many relationship: one manager, many employees).

Another type of relationship that you might want to create is a many-to-many relationship. Going back to the `Manager` to `Employee` relationship, with a many-to-many relationship, any manager could have N number of employees and one employee could have N number of managers. To do this, follow the same instructions for creating a one-to-many relationship, but select the `Employee` entity and then the `FKEmployeeToManager` relationship. Change this name to `FKEmployeeToManagers` and tick the `To-Many Relationship` box, as shown in [Figure 13-19](#). Now the arrow has double arrowheads on both sides.




Figure 13-19. Creating a Many to Many relationship between the `Manager` and `Employee` entities

In your code, for a one-to-many relationship, you can simply create a new **Manager** managed object (read how you can insert objects to a managed object context in [Recipe 13.3](#)), save it to the managed object context, and then create a couple of **Employee** managed objects and save them to the context as well. Now, to associate the manager with an employee, set the value of the **FKEmployeeToManager** property of an instance of **Employee** to an instance of the **Manager** managed object. Core Data will then create the relationship for you.

Dates, Calendars and Events

14.0 Introduction

The Event Kit and Event Kit UI frameworks allow iOS developers to access the Calendar database on an iOS device. You can insert, read, and modify events using the Event Kit framework. The Event Kit UI framework allows you to present built-in SDK GUI elements that allow the user to manipulate the Calendar database manually. In this chapter, we will focus on the Event Kit framework first, and then learn about the Event Kit UI framework.

With the Event Kit framework, a programmer can modify the user's Calendar database without him knowing. However, this is not a very good practice. In fact, Apple prohibits programmers from doing so and asks us to always notify users about any changes that the program might make to the Calendar database. Here is a quote from Apple:

If your application modifies a user's Calendar database programmatically, it must get confirmation from the user before doing so. An application should never modify the Calendar database without specific instruction from the user.

iOS comes with a built-in Calendar app. The Calendar app can work with different types of calendars, such as local, CalDAV, and so forth. In this chapter, we will be working with different types of calendars as well. To make sure you are prepared to run the code in some of the recipes in this chapter, please create a Google account and associate it with Google Calendar. To get started, head over to <http://www.google.com/calendar/>.

Once there, create a Google account. After you are done, add Google Calendar to your iOS device by following these steps:

1. Go to the home screen of your iOS device.
2. Go to Settings.
3. Select Mail, Contacts, Calendars.
4. Select Add Account...
5. Select Other.

6. Under the Calendars group, select the Add CalDAV Account button.
7. On the CalDAV screen, enter the following (see [Figure 14-1](#)):
 - a. **www.google.com** for the Server
 - b. Your Google username for User Name
 - c. Your Google password for Password
 - d. A description of your choice for Description
8. Tap Next.



Figure 14-1. Adding a Google calendar to an iOS device

Once you add the new Google account with Calendar access to your iOS device, you can see this calendar appear in the Calendars list in the Calendar application, as shown in [Figure 14-2](#).




Figure 14-2. The new Google Calendar added to the list of calendars on an iOS device

CalDAV is a protocol that allows access to the standard Calendar format used by Google Calendar and is supported by iOS. For more information about CalDAV, please refer to RFC 4791 at <http://tools.ietf.org/html/rfc4791>.

Almost all the recipes in this chapter demonstrate the use of the Event Kit and Event Kit UI frameworks using a CalDAV calendar. Before reading the recipes, please take a few minutes and follow the instructions provided here to create a new CalDAV calendar and link it to your iOS device. Here are some of the benefits of using a CalDAV calendar:

- It's easy to set up.
- It can be shared among different platforms, so changes to a local instance of a CalDAV calendar object will be reflected—automatically by iOS—to the CalDAV server. This will give you a better understanding of how calendars work in iOS, and you can simply check your Google Calendar online and make sure the local changes are reflected there.

- You can add participants to an event using a CalDAV calendar. This is explained in [Recipe 14.6](#).
- You can add a CalDAV calendar to iCal on your Mac, as well as your iOS devices, syncing events across all machines.

To run the example code in this chapter, you must add the Event Kit framework, and in some cases the Event Kit UI framework, to your application by following these steps:

1. Click on your project's icon in Xcode
2. Select the target to which you want to add the frameworks.
3. Select the Build Phases tab from the top of the screen.
4. Expand the Link Binary with Libraries box under the Build Phases tab and press the little + button located on the bottom left corner of this box.
5. Choose the Event Kit and Event Kit UI frameworks and click Add.



The iOS Simulator on Mac OS X does not simulate the Calendar app on an iOS device. To test the recipes in this chapter, you must run and debug your program on a real iOS device. All examples in this chapter have been tested on the iPhone 4, and iPad 2

In most of the example code in this chapter, we will focus on manually reading and manipulating events in a calendar. If you want to use the built-in iOS capabilities to allow your users to quickly access their calendar events, please refer to [Recipe 14.9](#) and [Recipe 14.10](#).

14.1 Retrieving the List of Calendars

Problem

You want to retrieve the list of calendars available on the user's device before you attempt to insert new events into them.

Solution

Access the `calendars` array property of an instance of `EKEventStore`. Each calendar is of type `EKCalendar`:

```
- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    EKEventStore *eventStore = [[EKEventStore alloc] init];

    /* These are the calendar types an iOS Device can have. Please note
    that the "type" property of an object of type EKCalendar
    is of type EKCalendarType. The values in the "CalendarTypes"
```

```

        array reflect the exact same values in the EKCalendarType
        enumeration, but as NSString values */
NSArray *calendarTypes = [[NSArray alloc] initWithObjects:
                           @"Local",
                           @"CalDAV",
                           @"Exchange",
                           @"Subscription",
                           @"Birthday",
                           nil];

/* Go through the calendars one by one */
NSUInteger counter = 1;
for (EKCalendar *thisCalendar in eventStore.calendars){

    /* The title of the calendar */
    NSLog(@"Calendar %lu Title = %@",
          (unsigned long)counter, thisCalendar.title);

    /* The type of the calendar */
    NSLog(@"Calendar %lu Type = %@",
          (unsigned long)counter,
          [calendarTypes objectAtIndex:thisCalendar.type]);

    /* The color that is associated with the calendar */
    NSLog(@"Calendar %lu Color = %@",
          (unsigned long)counter,
          [UIColor colorWithCGColor:thisCalendar.CGColor]);

    /* And whether the calendar can be modified or not */
    if ([thisCalendar allowsContentModifications]){
        NSLog(@"Calendar %lu can be modified.",
              (unsigned long)counter);
    } else {
        NSLog(@"Calendar %lu cannot be modified.",
              (unsigned long)counter);
    }

    counter++;
}

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

Running this code on an iOS device with six calendars ([Figure 14-2](#)) will print results similar to this in the console window:

```

Calendar 1 Title = Birthdays
Calendar 1 Type = Birthday
Calendar 1 Color = UIColorDeviceRGBColorSpace 0.509804 0.584314 0.686275 1
Calendar 1 cannot be modified.
Calendar 2 Title = Calendar

```

```

Calendar 2 Type = Local
Calendar 2 Color = UIColorDeviceRGBColorSpace 0.054902 0.380392 0.72549 1
Calendar 2 can be modified.
Calendar 3 Title = Calendar
Calendar 3 Type = CalDAV
Calendar 3 Color = UIColorDeviceRGBColorSpace 0.054902 0.380392 0.72549 1
Calendar 3 can be modified.
Calendar 4 Title = Home
Calendar 4 Type = CalDAV
Calendar 4 Color = UIColorDeviceRGBColorSpace 0.443137 0.101961 0.462745 1
Calendar 4 can be modified.
Calendar 5 Title = Work
Calendar 5 Type = CalDAV
Calendar 5 Color = UIColorDeviceRGBColorSpace 0.964706 0.309804 0 1
Calendar 5 can be modified.
Calendar 6 Title = vandad.np@gmail.com
Calendar 6 Type = CalDAV
Calendar 6 Color = UIColorDeviceRGBColorSpace 0.160784 0.321569 0.639216 1
Calendar 6 can be modified.

```

Discussion

By allocating and initializing an object of type `EKEventStore`, you can access different types of calendars that are available on an iOS device. iOS supports common calendar formats such as CalDAV and Exchange. The `calendars` property of an instance of `EKEventStore` is of type `NSArray` and contains the array of calendars that are on an iOS device. Each object in this array is of type `EKCalendar` and each calendar has properties that allow us to determine whether, for instance, we can insert new events into that calendar.

As we will see in [Recipe 14.2](#), a calendar object allows modifications only if its `allowsContentModifications` property has a YES value.



You can use the `colorWithCGColor:` instance method of `UIColor` to retrieve an object of type `UIColor` from `CGColorRef`.

See Also

[Recipe 14.2](#)

14.2 Adding Events to Calendars

Problem

You would like to be able to create new events in users' calendars.

Solution

Find the calendar you want to insert your event into (please refer to [Recipe 14.1](#)). Create an object of type `EKEvent` using the `eventWithEventStore:` class method of `EKEvent` and save the event into the user's calendar using the `saveEvent:span:error:` instance method of `EKEventStore`:

```
- (BOOL) createEventWithTitle:(NSString *)paramTitle
                startDate:(NSDate *)paramStartDate
                endDate:(NSDate *)paramEndDate
inCalendarWithTitle:(NSString *)paramCalendarTitle
inCalendarWithType:(EKCalendarType)paramCalendarType
                notes:(NSString *)paramNotes{

    BOOL result = NO;

    EKEventStore *eventStore = [[EKEventStore alloc] init];

    /* Are there any calendars available to the event store? */
    if ([eventStore.calendars count] == 0){
        NSLog(@"No calendars are found.");
        return NO;
    }

    EKCalendar *targetCalendar = nil;

    /* Try to find the calendar that the user asked for */
    for (EKCalendar *thisCalendar in eventStore.calendars){
        if ([thisCalendar.title isEqualToString:paramCalendarTitle] &&
            thisCalendar.type == paramCalendarType){
            targetCalendar = thisCalendar;
            break;
        }
    }

    /* Make sure we found the calendar that we were asked to find */
    if (targetCalendar == nil){
        NSLog(@"Could not find the requested calendar.");
        return NO;
    }

    /* If a calendar does not allow modification of its contents
    then we cannot insert an event into it */
    if (targetCalendar.allowsContentModifications == NO){
        NSLog(@"The selected calendar does not allow modifications.");
        return NO;
    }

    /* Create an event */
    EKEvent *event = [EKEvent eventWithEventStore:eventStore];
    event.calendar = targetCalendar;

    /* Set the properties of the event such as its title,
    start date/time, end date/time, etc. */
    event.title = paramTitle;
```

```

event.notes = paramNotes;
event.startDate = paramStartDate;
event.endDate = paramEndDate;

/* Finally, save the event into the calendar */
NSError *saveError = nil;

result = [eventStore saveEvent:event
                    span:EKSpanThisEvent
                    error:&saveError];

if (result == NO){
    NSLog(@"An error occurred = %@", saveError);
}

return result;
}

```

You can use the method we just implemented to insert new events into a user's calendar:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    /* The event starts from today, right now */
    NSDate *startDate = [NSDate date];

    /* And the event ends this time tomorrow.
    24 hours, 60 minutes per hour and 60 seconds per minute
    hence 24 * 60 * 60 */
    NSDate *endDate = [startDate
                        dateByAddingTimeInterval:24 * 60 * 60];

    /* Create the new event */
    BOOL createdSuccessfully = [self createEventWithTitle:@"My event"
                                                            startDate:startDate
                                                            endDate:endDate
                                                            inCalendarWithTitle:@"Calendar"
                                                            inCalendarWithType:EKCalendarTypeLocal
                                                            notes:nil];

    if (createdSuccessfully){
        NSLog(@"Successfully created the event.");
    } else {
        NSLog(@"Failed to create the event.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
                    [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```


Discussion

To programmatically create a new event in a calendar on an iOS device, we must:

1. Allocate and initialize an instance of `EKEventStore`.
2. Find the calendar we want to save the event to (please refer to [Recipe 14.1](#)). We must make sure the target calendar supports modifications by checking that the calendar object's `allowsContentModifications` property is `YES`. If it is not, you must choose a different calendar or forego saving the event.
3. Once you find your target calendar, create an event of type `EKEvent` using the `eventWithEventStore:` class method of `EKEvent`.
4. Set the properties of the new event such as its `title`, `startDate`, and `endDate`.
5. Associate your event with the calendar that you found in step 2 using the `calendars` property of an instance of `EKEvent`.
6. Once you are done setting the properties of your event, add that event to the calendar using the `saveEvent:span:error:` instance method of `EKEventStore`. The return value of this method (a `BOOL` value) indicates whether the event was successfully inserted into the Calendar database. If the operation fails, the `NSError` object passed to the `error` parameter of this method will contain the error that has occurred in the system while inserting this event.
7. Release the event store object that you allocated in step 1.

If you attempt to insert an event without specifying a target calendar or if you insert an event into a calendar that cannot be modified, the `saveEvent:span:error:` instance method of `EKEventStore` will fail with an error similar to this:

```
Error Domain=EKErrorDomain Code=1 "No calendar has been set."  
UserInfo=0x15d860 {NSLocalizedString=No calendar has been set.}
```

Running our code on an iOS device, we will see an event created in the Calendar database, as shown in [Figure 14-3](#).




Figure 14-3. Programmatically adding an event to a calendar

iOS syncs online calendars with the iOS calendar. These calendars could be Exchange, CalDAV, and other common formats. Creating an event on a CalDAV calendar on an iOS device will create the same event on the server. The server changes are also reflected in the iOS Calendar database when the Calendar database is synced with the server.

See Also

[Recipe 14.1](#)

14.3 Accessing the Contents of Calendars

Problem

You want to retrieve events of type `EKEvent` from a calendar of type `EKCalendar` on an iOS device.

Solution

Follow these steps:

1. Instantiate an object of type `EKEventStore`.
2. Using the `calendars` property of the event store (instantiated in step 1), find the calendar you want to read from.
3. Determine the time and date where you want to start the search in the calendar and the time and date where the search must stop.
4. Pass the calendar object (found in step 2), along with the two dates you found in step 3, to the `predicateForEventsWithStartDate:endDate:calendars:` instance method of `EKEventStore`.
5. Pass the predicate created in step 4 to the `eventsMatchingPredicate:` instance method of `EKEventStore`. The result of this method is an array of `EKEvent` objects (if any) that fell between the given dates (step 3) in the specified calendar (step 2).

Code illustrating these steps follows:

```
- (EKCalendar *) calDAVCalendarWithTitleContaining
    :(NSString *)paramDescription{

    EKCalendar *result = nil;

    EKEventStore *eventStore = [[EKEventStore alloc] init];

    for (EKCalendar *thisCalendar in eventStore.calendars){
        if (thisCalendar.type == EKCalendarTypeCalDAV){
            if ([thisCalendar.title
                rangeOfString:paramDescription].location != NSNotFound){
                return thisCalendar;
            }
        }
    }

    return result;
}

- (void) readEvents{

    /* Find a calendar to base our search on */
    EKCalendar *targetCalendar =
        [self calDAVCalendarWithTitleContaining:@"gmail.com"];

    /* If we could not find a CalDAV calendar that we were looking for,
       then we will abort the operation */
    if (targetCalendar == nil){
        NSLog(@"No CalDAV calendars were found.");
        return;
    }

    /* We have to pass an array of calendars to the event store to search */
```

```

NSArray *targetCalendars = [[NSArray alloc] initWithObjects:
                             targetCalendar, nil];

/* Instantiate the event store */
EKEventStore *eventStore = [[EKEventStore alloc] init];

/* The start date will be today */
NSDate *startDate = [NSDate date];

/* The end date will be 1 day from today */
NSDate *endDate = [startDate dateByAddingTimeInterval:24 * 60 * 60];

/* Create the predicate that we can later pass to the
event store in order to fetch the events */
NSPredicate *searchPredicate =
[eventStore predicateForEventsWithStartDate:startDate
                                     endDate:endDate
                                     calendars:targetCalendars];

/* Make sure we succeeded in creating the predicate */
if (searchPredicate == nil){
    NSLog(@"Could not create the search predicate.");
    return;
}

/* Fetch all the events that fall between
the starting and the ending dates */
NSArray *events = [eventStore eventsMatchingPredicate:searchPredicate];

/* Go through all the events and print their information
out to the console */
if (events != nil){

    NSUInteger counter = 1;
    for (EKEvent *event in events){

        NSLog(@"Event %lu Start Date = %@",
              (unsigned long)counter,
              event.startDate);

        NSLog(@"Event %lu End Date = %@",
              (unsigned long)counter,
              event.endDate);

        NSLog(@"Event %lu Title = %@",
              (unsigned long)counter,
              event.title);

        counter++;
    }
} else {
    NSLog(@"The array of events for this start/end time is nil.");
}

```

```

}

- (BOOL) application:(UIApplication *)application
  didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [self readEvents];

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

When we run this code on an iOS device with 6 calendars set up (one of which is a Google CalDAV calendar), as shown in [Figure 14-2](#), we will see the events that are available between the day that we run the app on the device and the next day.

The Calendar app in iOS displays the same events in the format shown in [Figure 14-4](#). Please bear in mind that you will not see results similar to this unless you create the events in your Google Calendar just as I have created them, at the exact same date and time. However, if you do decide to create events in other calendars, such as the local calendar, on different dates, make sure you change the starting and ending dates of the event predicate and the calendar in which you are performing the search. For more information, please refer to this recipe's [Discussion](#).




Figure 14-4. The Calendar app on an iOS device

Discussion

As mentioned in this chapter's [Introduction](#), an iOS device can be configured with different types of calendars using CalDAV, Exchange, and so on. Each calendar that is accessible by the Event Kit framework is encompassed within an `EKCalendar` object that can be accessed using the `calendars` array property of an instance of `EKEventStore`. You can fetch events inside a calendar in different ways, but the easiest way is to create and execute a specially formatted specification of dates and times, called a *predicate*, inside an event store.

A predicate of type `NSPredicate` that we can use in the Event Kit framework can be created using the `predicateForEventsWithStartDate:endDate:calendars:` instance method of an `EKEventStore`. The parameters to this method are:

predicateForEventsWithStartDate

The starting date and time from when the events have to be fetched

`endDate`

The ending date up until which the events will be fetched

`calendars`

The array of calendars to search for events between the starting and ending dates

See Also

[Recipe 14.1](#)

14.4 Removing Events from Calendars

Problem

You want to be able to delete a specific event or series of events from users' calendars.

Solution

Use the `removeEvent:span:commit:error:` instance method of `EKEventStore`.

Discussion

The `removeEvent:span:commit:error:` instance method of `EKEventStore` can remove an instance of an event or all instances of a recurring event. For more information about recurring events, please refer to [Recipe 14.5](#). In this recipe, we will only remove an instance of the event and not the other instances of the same event in the calendar.

The parameters that we can pass to this method are:

`removeEvent`

This is the `EKEvent` instance to be removed from the calendar.

`span`

This is the parameter that tells the event store whether we want to remove only this event or all the occurrences of this event in the calendar. To remove only the current event, specify the `EKSpanThisEvent` value for the `removeEvent` parameter. To remove all occurrences of the same event from the calendar, pass the `EKSpanFutureEvents` value for the parameter.

`commit`

A boolean value that tells the event store if the changes have to be saved on the remote/local calendar immediately or not.

`error`

This parameter can be given a reference to an `NSError` object that will be filled with the error (if any), when the return value of this method is `NO`.

To demonstrate this, let's use the event creation method that we implemented in [Recipe 14.2](#). What we can do then is to create an event in our Google CalDAV calendar and after it has been created, attempt to delete it from the event store:

```
- (BOOL) createEventWithTitle:(NSString *)paramTitle
               startDate:(NSDate *)paramStartDate
               endDate:(NSDate *)paramEndDate
inCalendarWithTitle:(NSString *)paramCalendarTitle
inCalendarWithType:(EKCalendarType)paramCalendarType
               notes:(NSString *)paramNotes{

    BOOL result = NO;

    EKEventStore *eventStore = [[EKEventStore alloc] init];

    /* Are there any calendars available to the event store? */
    if ([eventStore.calendars count] == 0){
        NSLog(@"No calendars are found.");
        return NO;
    }

    EKCalendar *targetCalendar = nil;

    /* Try to find the calendar that the user asked for */
    for (EKCalendar *thisCalendar in eventStore.calendars){
        if ([thisCalendar.title isEqualToString:paramCalendarTitle] &&
            thisCalendar.type == paramCalendarType){
            targetCalendar = thisCalendar;
            break;
        }
    }

    /* Make sure we found the calendar that we were asked to find */
    if (targetCalendar == nil){
        NSLog(@"Could not find the requested calendar.");
        return NO;
    }

    /* If a calendar does not allow modification of its contents
       then we cannot insert an event into it */
    if (targetCalendar.allowsContentModifications == NO){
        NSLog(@"The selected calendar does not allow modifications.");
        return NO;
    }

    /* Create an event */
    EKEvent *event = [EKEvent eventWithEventStore:eventStore];
    event.calendar = targetCalendar;

    /* Set the properties of the event such as its title,
       start date/time, end date/time, etc. */
    event.title = paramTitle;
    event.notes = paramNotes;
    event.startDate = paramStartDate;
    event.endDate = paramEndDate;
}
```



```

/* Finally, save the event into the calendar */
NSError *saveError = nil;

result = [eventStore saveEvent:event
                  span:EKSpanThisEvent
                  error:&saveError];

if (result == NO){
    NSLog(@"An error occurred = %@", saveError);
}

return result;
}

- (BOOL) removeEventWithTitle:(NSString *)paramTitle
                  startDate:(NSDate *)paramStartDate
                  endDate:(NSDate *)paramEndDate
inCalendarWithTitle:(NSString *)paramCalendarTitle
inCalendarWithType:(EKCalendarType)paramCalendarType
                  notes:(NSString *)paramNotes{

    BOOL result = NO;

    EKEventStore *eventStore = [[EKEventStore alloc] init];

    /* Are there any calendars available to the event store? */
    if ([eventStore.calendars count] == 0){
        NSLog(@"No calendars are found.");
        return NO;
    }

    EKCalendar *targetCalendar = nil;

    /* Try to find the calendar that the user asked for */
    for (EKCalendar *thisCalendar in eventStore.calendars){
        if ([thisCalendar.title isEqualToString:paramCalendarTitle] &&
            thisCalendar.type == paramCalendarType){
            targetCalendar = thisCalendar;
            break;
        }
    }

    /* Make sure we found the calendar that we were asked to find */
    if (targetCalendar == nil){
        NSLog(@"Could not find the requested calendar.");
        return NO;
    }

    /* If a calendar does not allow modification of its contents
    then we cannot insert an event into it */
    if (targetCalendar.allowsContentModifications == NO){
        NSLog(@"The selected calendar does not allow modifications.");
        return NO;
    }

```

```

    }

    NSArray *calendars = [[NSArray alloc] initWithObjects:targetCalendar, nil];

    NSPredicate *predicate =
    [eventStore predicateForEventsWithStartDate:paramStartDate
                                     endDate:paramEndDate
                                     calendars:calendars];

    /* Get all the events that match the parameters */
    NSArray *events = [eventStore eventsMatchingPredicate:predicate];

    if ([events count] > 0){

        /* Delete them all */
        for (EKEvent *event in events){
            NSError *removeError = nil;
            /* Do not commit here, we will commit in batch after we have
               removed all the events that matched our criteria */
            if ([eventStore removeEvent:event
                                     span:EKSpanThisEvent
                                     commit:NO
                                     error:&removeError] == NO){
                NSLog(@"Failed to remove event %@ with error = %@",
                     event,
                     removeError);
            }
        }

        NSError *commitError = nil;
        if ([eventStore commit:&commitError]){
            result = YES;
        } else {
            NSLog(@"Failed to commit the event store.");
        }

    } else {
        NSLog(@"No events matched your input.");
    }

    return result;
}

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSDate *startDate = [NSDate date]; /* Now */

    const NSTimeInterval NSOneHour = 60 * 60; /* 60 minutes, each 60 seconds */
    NSDate *endDate = [startDate dateByAddingTimeInterval:NSOneHour];

    BOOL createdSuccessfully = [self createEventWithTitle:@"Shopping"
                                                         startDate:startDate

```

```

                                endDate:endDate
                                inCalendarWithTitle:@"vandad.np@gmail.com"
                                inCalendarWithType:EKCalendarTypeCalDAV
                                notes:@"Get bread"];

if (createdSuccessfully){

    NSLog(@"Successfully created the event.");

    BOOL removedSuccessfully =
    [self removeEventWithTitle:@"Shopping"
                        startDate:startDate
                        endDate:endDate
                        inCalendarWithTitle:@"vandad.np@gmail.com"
                        inCalendarWithType:EKCalendarTypeCalDAV
                        notes:@"Get bread"];

    if (removedSuccessfully){
        NSLog(@"Successfully removed the event.");
    } else {
        NSLog(@"Failed to remove the event.");
    }

} else {
    NSLog(@"Failed to create the event.");
}

self.window = [[UIWindow alloc] initWithFrame:
                [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

In this example, we are not committing the deletion of every event one by one. We are simply setting the `commit` parameter of the `removeEvent:span:commit:error:` method to `NO` and after we are done, we are invoking the `commit:` method of the event store explicitly. The reason behind this is that we don't really want to commit every single deletion. That would be an overhead. We can go ahead and delete as many events as we need to, and then commit them all in batch.

See Also

[Recipe 14.1](#); [Recipe 14.3](#)

14.5 Adding Recurring Events to Calendars

Problem

You want to add a recurring event to a calendar.

Solution

The steps to create a recurring event follow. In this example, we are creating an event that occurs on the same day, every month, for an entire year:

1. Create an instance of `EKEventStore`.
2. Find a modifiable calendar inside the `calendars` array of the event store (for more information, refer to [Recipe 14.1](#)).
3. Create an object of type `EKEvent` (for more information, refer to [Recipe 14.2](#)).
4. Set the appropriate values for the event, such as its `startDate` and `endDate` (for more information, refer to [Recipe 14.2](#)).
5. Instantiate an object of type `NSDate` that contains the exact date when the recurrence of this event ends. In this example, this date is one year from today's date.
6. Use the `recurrenceEndWithEndDate:` class method of `EKRecurrenceEnd` and pass the `NSDate` you created in step 5 to create an object of type `EKRecurrenceEnd`.
7. Allocate and then instantiate an object of type `EKRecurrenceRule` using the `initRecurrenceWithFrequency:interval:end:` method of `EKRecurrenceRule`. Pass the recurrence end date that you created in step 6 to the `end` parameter of this method. For more information about this method, please refer to this recipe's [Discussion](#).
8. Assign the recurring event that you created in step 7 to the `recurringRule` property of the `EKEvent` object that was created in step 3.
9. Invoke the `saveEvent:span:error:` instance method with the event (created in step 3) as the `saveEvent` parameter and the value `EKSpanFutureEvents` for the `span` parameter. This will create our recurring event for us.

Code illustrating these steps follows:

```
- (void) createRecurringEventInLocalCalendar{

    /* Step 1: And now the event store */
    EKEventStore *eventStore = [[EKEventStore alloc] init];

    /* Step 2: Find the first local calendar that is modifiable */
    EKCalendar *targetCalendar = nil;

    for (EKCalendar *thisCalendar in eventStore.calendars){
        if (thisCalendar.type == EKCalendarTypeLocal &&
            [thisCalendar allowsContentModifications]){
            targetCalendar = thisCalendar;
        }
    }

    /* The target calendar wasn't found? */
    if (targetCalendar == nil){
        NSLog(@"The target calendar is nil.");
        return;
    }
}
```

```

}

/* Step 3: Create an event */
EKEvent *event = [EKEvent eventWithEventStore:eventStore];

/* Step 4: Create an event that happens today and happens
every month for a year from now */

NSDate *eventStartDate = [NSDate date];

/* Step 5: The event's end date is one hour from the moment it is created */
NSTimeInterval NSOneHour = 1 * 60 * 60;
NSDate *eventEndDate = [eventStartDate dateByAddingTimeInterval:NSOneHour];

/* Assign the required properties, especially
the target calendar */
event.calendar = targetCalendar;
event.title = @"My Event";
event.startDate = eventStartDate;
event.endDate = eventEndDate;

/* The end date of the recurring rule
is one year from now */
NSTimeInterval NSOneYear = 365 * 24 * 60 * 60;
NSDate *oneYearFromNow = [eventStartDate dateByAddingTimeInterval:NSOneYear];

/* Step 6: Create an Event Kit date from this date */
EKRecurrenceEnd *recurringEnd =
[EKRecurrenceEnd recurrenceEndWithEndDate:oneYearFromNow];

/* Step 7: And the recurring rule. This event happens every
month (EKRecurrenceFrequencyMonthly), once a month (interval:1)
and the recurring rule ends a year from now (end:RecurringEnd) */

EKRecurrenceRule *recurringRule =
[[EKRecurrenceRule alloc]
initWithRecurrenceWithFrequency:EKRecurrenceFrequencyMonthly
interval:1
end:recurringEnd];

/* Step 8: Set the recurring rule for the event */
event.recurrenceRules = [[NSArray alloc] initWithObjects:recurringRule, nil];

NSError *saveError = nil;

/* Step 9: Save the event */
if ([eventStore saveEvent:event
span:EKSpanFutureEvents
error:&saveError]){
    NSLog(@"Successfully created the recurring event.");
} else {
    NSLog(@"Failed to create the recurring event %@", saveError);
}
}

```

Discussion

A recurring event is an event that happens more than once. We can create a recurring event just like a normal event. Please refer to [Recipe 14.2](#) for more information about inserting normal events into the Calendar database. The only difference between a recurring event and a normal event is that you apply a recurring rule to a recurring event. A recurring rule tells the Event Kit framework how the event has to occur in the future.

We create a recurring rule by instantiating an object of type `EKRecurrenceRule` using the `initWithFrequency:interval:end:` initialization method. The parameters to this method are:

`initWithFrequency`

Specifies whether you want the event to be repeated daily (`EKRecurrenceFrequencyDaily`), weekly (`EKRecurrenceFrequencyWeekly`), monthly (`EKRecurrenceFrequencyMonthly`), or yearly (`EKRecurrenceFrequencyYearly`).

`interval`

A value greater than zero that specifies the interval between each occurrence's start and end period. For instance, if you want to create an event that happens every week, specify the `EKRecurrenceFrequencyWeekly` value with an `interval` of 1. If you want this event to happen every other week, specify `EKRecurrenceFrequencyWeekly` with an `interval` of 2.

`end`

A date of type `EKRecurrenceEnd` that specifies the date when the recurring event ends in the specified calendar. This parameter is not the same as the event's end date (the `endDate` property of `EKEvent`). The end date of an event specifies when that specific event ends in the calendar, whereas the `end` parameter of the `initWithFrequency:interval:end:` method specifies the final occurrence of the event in the database.

[Figure 14-5](#) depicts how our recurring event appears in the Calendar app on the device:




Figure 14-5. Calendar app showing the My Event recurring event that we created

By editing this event (see [Figure 14-6](#)) in the Calendar application on an iOS device, you can see that the event is truly a recurring event that happens every month, on the same day the event was created, for a whole year.



Figure 14-6. Editing a recurring event in the Calendar app on an iOS device

See Also

[Recipe 14.2](#)

14.6 Retrieving the Attendees of an Event

Problem

You want to retrieve the list of attendees for a specific event.

Solution

Use the `attendees` property of an instance of `EKEvent`. This property is of type `NSArray` and includes objects of type `EKParticipant`.

Example code follows that will retrieve all the events that happen today (whatever the day may be), and will print out useful event information, including the attendees of that event, to the console window:

```
- (EKCalendar *) calDAVCalendarWithTitleContaining
    :(NSString *)paramDescription{

    EKCalendar *result = nil;

    EKEventStore *eventStore = [[EKEventStore alloc] init];

    for (EKCalendar *thisCalendar in eventStore.calendars){
        if (thisCalendar.type == EKCalendarTypeCalDAV){
            if ([thisCalendar.title
                rangeOfString:paramDescription].location != NSNotFound){
                return thisCalendar;
            }
        }
    }

    return result;
}

- (void) enumerateTodayEvents{

    /* Find a calendar to base our search on */
    EKCalendar *targetCalendar =
        [self calDAVCalendarWithTitleContaining:@"vandad.np@gmail.com"];

    /* If we could not find a CalDAV calendar that
       we were looking for, then we will abort the operation */
    if (targetCalendar == nil){
        NSLog(@"No CalDAV calendars were found.");
        return;
    }

    /* We have to pass an array of calendars
       to the event store to search */
    NSArray *targetCalendars = [[NSArray alloc]
        initWithObjects:targetCalendar, nil];

    /* Instantiate the event store */
    EKEventStore *eventStore = [[EKEventStore alloc] init];

    /* Construct the starting date for today */
    NSDate *startDate = [NSDate date];

    /* The end date will be 1a day from now */
    NSTimeInterval NSOneDay = 1 * 24 * 60 * 60;
    NSDate *endDate = [startDate dateByAddingTimeInterval:NSOneDay];

    /* Create the predicate that we can later pass to
       the event store in order to fetch the events */
    NSPredicate *searchPredicate =
```

```

[eventStore predicateForEventsWithStartDate:startDate
                                     endDate:endDate
                                     calendars:targetCalendars];

/* Make sure we succeeded in creating the predicate */
if (searchPredicate == nil){
    NSLog(@"Could not create the search predicate.");
    return;
}

/* Fetch all the events that fall between the
   starting and the ending dates */
NSArray *events = [eventStore eventsMatchingPredicate:searchPredicate];

/* Array of NSString equivalents of the values
   in the EKParticipantRole enumeration */
NSArray *attendeeRole = [NSArray arrayWithObjects:
                          @"Unknown",
                          @"Required",
                          @"Optional",
                          @"Chair",
                          @"Non Participant",
                          nil];

/* Array of NSString equivalents of the values
   in the EKParticipantStatus enumeration */
NSArray *attendeeStatus = [NSArray arrayWithObjects:
                           @"Unknown",
                           @"Pending",
                           @"Accepted",
                           @"Declined",
                           @"Tentative",
                           @"Delegated",
                           @"Completed",
                           @"In Process",
                           nil];

/* Array of NSString equivalents of the values
   in the EKParticipantType enumeration */
NSArray *attendeeType = [NSArray arrayWithObjects:
                         @"Unknown",
                         @"Person",
                         @"Room",
                         @"Resource",
                         @"Group",
                         nil];

/* Go through all the events and print their information
   out to the console */
if (events != nil){

    NSUInteger eventCounter = 0;
    for (EKEvent *thisEvent in events){

        eventCounter++;
    }
}

```

```

NSLog(@"Event %lu Start Date = %@",
      (unsigned long)eventCounter,
      thisEvent.startDate);

NSLog(@"Event %lu End Date = %@",
      (unsigned long)eventCounter,
      thisEvent.endDate);

NSLog(@"Event %lu Title = %@",
      (unsigned long)eventCounter,
      thisEvent.title);

if (thisEvent.attendees == nil ||
    [thisEvent.attendees count] == 0){
    NSLog(@"Event %lu has no attendees",
          (unsigned long)eventCounter);
    continue;
}

NSUInteger attendeeCounter = 1;
for (EKParticipant *participant in thisEvent.attendees){

    NSLog(@"Event %lu Attendee %lu Name = %@",
          (unsigned long)eventCounter,
          (unsigned long)attendeeCounter,
          participant.name);

    NSLog(@"Event %lu Attendee %lu Role = %@",
          (unsigned long)eventCounter,
          (unsigned long)attendeeCounter,
          [attendeeRole objectAtIndex:
           participant.participantRole]);

    NSLog(@"Event %lu Attendee %lu Status = %@",
          (unsigned long)eventCounter,
          (unsigned long)attendeeCounter,
          [attendeeStatus objectAtIndex:
           participant.participantStatus]);

    NSLog(@"Event %lu Attendee %lu Type = %@",
          (unsigned long)eventCounter,
          (unsigned long)attendeeCounter,
          [attendeeType objectAtIndex:
           participant.participantType]);

    NSLog(@"Event %lu Attendee %lu URL = %@",
          (unsigned long)eventCounter,
          (unsigned long)attendeeCounter,
          participant.URL);

    attendeeCounter++;
}

```

```

        } /* for (EKEvent *Event in Events){ */

    } else {
        NSLog(@"The array of events is nil.");
    }

}

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [self enumerateTodayEvents];

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

When we run this code on an iOS device with a couple of events set up on a CalDAV calendar named *vandad.np@gmail.com* (refer to this chapter’s [Introduction](#) for more information about CalDAV calendars and how you can set one up on your iOS device), we get results similar to these in the console window:

Discussion

Different types of calendars, such as CalDAV, can include participants in an event. iOS allows users to add participants to a calendar on the server, although not to the calendar on the iOS device. You can do this using Google Calendar, for instance.

Once the user adds participants to an event, you can use the `attendees` property of an instance of `EKEvent` to access the participant objects of type `EKParticipant`. Each participant has properties such as:

name

This is the name of the participant. If you just specified the email address of a person to add him to an event, this field will be that email address.

URL

This is usually the “mailto” URL for the attendee.

participantRole

This is the role the attendee plays in the event. Different values that can be applied to this property are listed in the `EKParticipantRole` enumeration.

participantStatus

This tells us whether this participant has accepted or declined the event request. This property could have other values, all specified in the `EKParticipantStatus` enumeration.

participantType

This is of type `EKParticipantType`, which is an enumeration and, as its name implies, specifies the type of participant, such as group (`EKParticipantTypeGroup`) or individual person (`EKParticipantTypePerson`).

See Also

[Recipe 14.2](#); [Recipe 14.3](#)

14.7 Adding Alarms to Calendars

Problem

You want to add alarms to the events in a calendar.

Solution

Use the `alarmWithRelativeOffset:` class method of `EKAlarm` to create an instance of `EKAlarm`. Add the alarm to an event using the `addAlarm:` instance method of `EKEvent`, like so:

```
- (EKCalendar *) getFirstModifiableLocalCalendar{
    EKCalendar *result = nil;

    EKEventStore *eventStore = [[EKEventStore alloc] init];

    for (EKCalendar *thisCalendar in eventStore.calendars){
        if (thisCalendar.type == EKCalendarTypeLocal &&
            [thisCalendar allowsContentModifications]){
            return thisCalendar;
        }
    }

    return result;
}

- (void) addAlarmToCalendar{
    EKCalendar *targetCalendar = [self getFirstModifiableLocalCalendar];

    if (targetCalendar == nil){
        NSLog(@"Could not find the target calendar.");
        return;
    }

    EKEventStore *eventStore = [[EKEventStore alloc] init];

    /* The event starts 60 seconds from now */
    NSDate *startDate = [NSDate dateWithTimeIntervalSinceNow:60.0f];
```

```

/* And end the event 20 seconds after its start date */
NSDate *endDate = [startDate dateByAddingTimeInterval:20.0f];

EKEvent *eventWithAlarm = [EKEvent eventWithEventStore:eventStore];

eventWithAlarm.calendar = targetCalendar;
eventWithAlarm.startDate = startDate;
eventWithAlarm.endDate = endDate;

/* The alarm goes off 2 seconds before the event happens */
EKAlarm *alarm = [EKAlarm alarmWithRelativeOffset:-2.0f];

eventWithAlarm.title = @"Event with Alarm";
[eventWithAlarm addAlarm:alarm];

NSError *saveError = nil;

if ([eventStore saveEvent:eventWithAlarm
                    span:EKSpanThisEvent
                    error:&saveError]){
    NSLog(@"Saved an event that fires 60 seconds from now.");
} else {
    NSLog(@"Failed to save the event. Error = %@", saveError);
}

}

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    [self addAlarmToCalendar];

    self.window = [[UIWindow alloc] initWithFrame:
                    [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

Discussion

An event of type `EKEvent` can have multiple alarms. Simply create the alarm using either the `alarmWithAbsoluteDate:` or `alarmWithRelativeOffset:` class method of `EKAlarm`. The former method requires an absolute date and time (you can use the `CFAbsoluteTimeGetCurrent` function to get the current absolute time), whereas the latter method requires a number of seconds relative to the start date of the event when the alarm must be fired. For instance, if the event is scheduled for today at 6:00 a.m., and we go ahead and create an alarm with the relative offset of -60 (which is counted in units of seconds), our alarm will be fired at 5:59 a.m. the same day. Only zero and negative numbers are

allowed for this offset. Positive numbers will be changed to zero automatically by iOS. Once an alarm is fired, iOS will display the alarm to the user, as shown in [Figure 14-7](#).



Figure 14-7. iOS displaying an alert on the screen when an alarm is fired

You can use the `removeAlarm:` instance method of `EKEvent` to remove an alarm associated with that event instance.

See Also

[Recipe 14.1](#)

14.8 Handling Event Changed Notifications

Problem

You want to get notified in your application when the user changes the contents of the Calendar database.

Solution

Register for the `EKEventStoreChangedNotification` notification:

```
- (EKCalendar *)
    calDAVCalendarWithTitleContaining:(NSString *)paramDescription
    inEventStore:(EKEventStore *)paramEventStore{

    EKCalendar *result = nil;

    for (EKCalendar *thisCalendar in paramEventStore.calendars){
        if (thisCalendar.type == EKCalendarTypeCalDAV){
            if ([thisCalendar.title
                rangeOfString:paramDescription].location != NSNotFound){
                return thisCalendar;
            }
        }
    }

    return result;
}

- (void) eventsChanged:(NSNotification *)paramNotification{

    NSMutableArray *invalidatedEvents = [[NSMutableArray alloc] init];

    NSLog(@"Refreshing array of events...");

    for (EKEvent *event in self.eventsForOneYear){
        if ([event refresh] == NO){
            [invalidatedEvents addObject:event];
        }
    }

    if ([invalidatedEvents count] > 0){
        [self.eventsForOneYear removeObjectsInArray:invalidatedEvents];
    }
}

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.eventStore = [[EKEventStore alloc] init];

    EKCalendar *calendar =
    [self calDAVCalendarWithTitleContaining:@"vandad.np@gmail.com"
     inEventStore:self.eventStore];

    NSTimeInterval NSOneYear = 1 * 365 * 24 * 60 * 60;

    NSDate *startDate = [NSDate date];
    NSDate *endDate = [startDate dateByAddingTimeInterval:NSOneYear];
```



```

NSArray *calendars = [[NSArray alloc] initWithObjects:calendar, nil];

NSPredicate *predicate =
[self.eventStore predicateForEventsWithStartDate:startDate
                                     endDate:endDate
                                     calendars:calendars];

NSArray *events = [self.eventStore eventsMatchingPredicate:predicate];

self.eventsForOneYear = [[NSMutableArray alloc] initWithArray:events];

[[NSNotificationCenter defaultCenter]
 addObserver:self
 selector:@selector(eventsChanged:)
 name:EKEventStoreChangedNotification
 object:nil];

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

Discussion

Multitasking is possible on iOS. Imagine you have fetched a series of events from `EKEventStore` into an array and you allow your user to work with them (edit them, add to them, and remove from them). The user could simply switch from your application to the Calendar application and delete the same event she is trying to delete in your application. Such a sequence of activities will generate an `EKEventStoreChangedNotification` notification that you can choose to receive.

The `EKEventStoreChangedNotification` notification will be sent to your application (only if you subscribe to this notification) even if your application is in the foreground. Because of this, you must make sure you treat this notification differently depending on whether your application is in the background or the foreground. Here are a couple of things to consider:

- If you receive the `EKEventStoreChangedNotification` notification while your application is in the foreground, it is best to implement a mechanism to find out whether the changes to the event store originated inside your own application or came from someone else outside the application. If they came from outside the application, you must make sure you are retaining the latest version of the events in the store, and not the old events. If for any reason you copied one of the events in the event store and kept the copy somewhere, you must call the `refresh` instance method of that event of type `EKEvent`. If the return value of this method is `YES`, you can keep the object in memory. If the return value is `NO`, you must dispose of the object,

because someone outside your application has deleted or somehow invalidated the event.

- If you receive the `EKEventStoreChangedNotification` notification while your application is in the background, according to documentation from Apple, your application should not attempt to do any GUI-related processing and should, in fact, use as little processing power as possible. You must therefore refrain from adding new screens to, or modifying in any way, the GUI of your application.
- If you receive the `EKEventStoreChangedNotification` notification while your application is in the background, you must make note of it inside the application (perhaps store this in a property of type `BOOL`) and react to this change when the application is brought to the foreground again. Normally, if you receive any notification about a change to an event while you are in the background, you should retrieve all events stored in the application when you return to the foreground.



Coalescing is not enabled on the `EKEventStoreChangedNotification` event store notification. In other words, you can receive multiple notifications of the same type if a single event changes in the Calendar database. It is up to you to determine how and when you need to refetch your retained events.

14.9 Presenting Event View Controllers

Problem

You want to use the built-in iOS SDK view controllers to display the properties of an event in the Calendar database.

Solution

Create an instance of `EKEventViewController` and push it into a navigation controller or present it as a modal view controller on another view controller.

Discussion

Users of iOS devices are already familiar with the interface they see on the Calendar application. When they select an event, they can see that event's properties and they might be allowed to modify the event. To present a view to a user using built-in iOS SDK event view controllers, we can instantiate an object of type `EKEventViewController` and assign an event of type `EKEvent` to its event property. Once that's done, we can push the event view controller into our navigation controller and let iOS take care of the rest.

We want to find an event (any event) in any of the calendars available on an iOS device, from one year ago to now. We will use `EKEventViewController` to present that event to the user. Here is the `.h` file of our view controller:

```
#import <UIKit/UIKit.h>
#import <EventKit/EventKit.h>
#import <EventKitUI/EventKitUI.h>

@interface Presenting_Event_View_ControllersViewController
    : UIViewController <EKEventViewDelegate>

@property (nonatomic, strong) EKEventStore *eventStore;

@end
```

We should now synthesize our `eventStore` property in the implementation of our view controller:

```
#import "Presenting_Event_View_ControllersViewController.h"

@implementation Presenting_Event_View_ControllersViewController

@synthesize eventStore;

...
```

Now let's go ahead and in the `viewDidLoad` method of our view controller, and display the instance of `EKEventViewController` on the first event we find in any of the calendars on the device, from a year ago:

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.eventStore = [[EKEventStore alloc] init];

    NSTimeInterval NSOneYear = 1 * 365 * 24.0f * 60.0f * 60.0f;
    NSDate *startDate = [[NSDate date] dateByAddingTimeInterval:-NSOneYear];
    NSDate *endDate = [NSDate date];

    NSPredicate *predicate =
        [self.eventStore predicateForEventsWithStartDate:startDate
                                                    endDate:endDate
                                                    calendars:self.eventStore.calendars];

    NSArray *events = [self.eventStore eventsMatchingPredicate:predicate];

    if ([events count] > 0){
        EKEvent *event = [events objectAtIndex:0];
        EKEventViewController *controller = [[EKEventViewController alloc] init];
        controller.event = event;
        controller.allowsEditing = NO;
        controller.allowsCalendarPreview = YES;
        controller.delegate = self;

        [self.navigationController pushViewController:controller
```

```

        animated:YES];
    }
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.eventStore = nil;
}

```

Last but not least, as you can see in the code, we have become the delegate object of the event view controller so let's make sure we are handling the delegate methods if required:

```

- (void)eventViewController:(EKEEventViewController *)controller
    didCompleteWithAction:(EKEEventViewAction)action{

    switch (action){

        case EKEEventViewActionDeleted:{
            NSLog(@"User deleted the event.");
            break;
        }
        case EKEEventViewActionDone:{
            NSLog(@"User finished viewing the event.");
            break;
        }
        case EKEEventViewActionResponded:{
            NSLog(@"User responded to the invitation in the event.");
            break;
        }
    }
}

```

Once we run this application on an iOS device, we can see the built-in event view controller displaying the contents of the event that we have found (see [Figure 14-8](#)).




Figure 14-8. The built-in iOS event view controller

Different properties of an instance of `EKEventViewController` that we can use to change the behavior of this object are as follows:

allowsEditing

If this property's value is set to `YES`, the Edit button will appear on the navigation bar of the event view controller, allowing the user to edit the event. This happens only on modifiable calendars and only for events that have been created by the user on this device. For instance, if you create an event on the Web using Google Calendar and the event appears in your iOS device, you are not allowed to edit that event.

allowsCalendarPreview

If this property's value is set to `YES` and the event the user is viewing is an invitation, the user will be given the option to view this current event in a calendar with other events that have been scheduled on the same date.

event

This property must be set before presenting the event view controller. This will be the event that the event view controller will display to the user.

When you push the event view controller, the Back button will appear with the title “Back” by default, so you do not have to change it manually. However, if you decide to change the Back button, you can do so by assigning a new object of type `UIBarButtonItem` to the `backBarButtonItem` property of your navigation item. In our example code, we can modify the `pushViewController:` method to give our root view controller a custom Back button before pushing the event view controller.

```
- (void)viewDidLoad{
    [super viewDidLoad];

    self.eventStore = [[EKEEventStore alloc] init];

    NSTimeInterval NSOneYear = 1 * 365 * 24.0f * 60.0f * 60.0f;
    NSDate *startDate = [[NSDate date] dateByAddingTimeInterval:-NSOneYear];
    NSDate *endDate = [NSDate date];

    NSPredicate *predicate =
        [self.eventStore predicateForEventsWithStartDate:startDate
                                                    endDate:endDate
                                                    calendars:self.eventStore.calendars];

    NSArray *events = [self.eventStore eventsMatchingPredicate:predicate];

    if ([events count] > 0){
        EKEEvent *event = [events objectAtIndex:0];
        EKEEventViewController *controller = [[EKEEventViewController alloc] init];
        controller.event = event;
        controller.allowsEditing = YES;
        controller.allowsCalendarPreview = YES;
        controller.delegate = self;

        self.navigationItem.backBarButtonItem =
            [[UIBarButtonItem alloc] initWithTitle:@"Go Back"
                                                style:UIBarButtonItemStylePlain
                                                target:nil
                                                action:nil];

        [self.navigationController pushViewController:controller
                                                animated:YES];
    }
}
```

The results of this modification are depicted in [Figure 14-9](#) (please note that in this example, editing is enabled for the event view controller).




Figure 14-9. An edit view controller with editing enabled and a custom back button

See Also

[Recipe 14.10](#)

14.10 Presenting Event Edit View Controllers

Problem

You want to allow your users to edit (insert, delete, and modify) events in the Calendar database from inside your application, using built-in SDK view controllers.

Solution

Instantiate an object of type `EKEventEditViewController` and present it on a navigation controller using the `presentModalViewController:animated:` instance method of `UINavigationController`.

Discussion

An instance of the `EKEventEditViewController` class allows us to present an event edit view controller to the user. This view controller, depending on how we set it up, can allow the user to either edit an existing event or create a new event. If you want this view controller to edit an event, set the `event` property of this instance to an event object. If you want the user to be able to insert a new event into the system, set the `event` property of this instance to `nil`.

The `editViewDelegate` property of an instance of `EKEventEditViewController` is the object that will receive delegate messages from this view controller telling the programmer about the action the user has taken. One of the most important delegate messages your delegate object must handle (a required delegate selector) is the `eventEditViewController:didCompleteWithAction:` method. This delegate method will be called whenever the user dismisses the event edit view controller in one of the possible ways indicated by the `didCompleteWithAction` parameter. This parameter can have values such as the following:

`EKEventEditViewActionCanceled`

The user pressed the Cancel button on the view controller.

`EKEventEditViewActionSaved`

The user saved (added/modified) an event in the Calendar database.

`EKEventEditViewActionDeleted`

The user deleted an event from the Calendar database.

Please make sure to dismiss the event edit view controller after receiving this delegate message, if you are displaying the edit view controller as a modal view controller.

So let's go ahead and define our view controller:

```
#import <UIKit/UIKit.h>
#import <EventKit/EventKit.h>
#import <EventKitUI/EventKitUI.h>

@interface Presenting_Event_Edit_View_ControllersViewController
    : UIViewController <EKEventEditViewDelegate>

@property (nonatomic, strong) EKEventStore *eventStore;

@end
```

Next step, synthesizing the `eventStore` property in the implementation file of our view controller:

```
#import "Presenting_Event_Edit_View_ControllersViewController.h"

@implementation Presenting_Event_Edit_View_ControllersViewController

@synthesize eventStore;

...
```


Now let's try to find the first event from a year ago (whatever event that might be) and allow the user to edit that event by displaying an edit event view controller:

```
- (void)eventEditViewController:(EKEventEditViewController *)controller
    didFinishWithAction:(EKEventEditViewAction)action{

    switch (action){

        case EKEventEditViewActionCanceled:{
            NSLog(@"Cancelled");
            break;
        }
        case EKEventEditViewActionSaved:{
            NSLog(@"Saved");
            break;
        }
        case EKEventEditViewActionDeleted:{
            NSLog(@"Deleted");
            break;
        }
    }

}

- (void)viewDidLoad{
    [super viewDidLoad];

    self.eventStore = [[EKEventStore alloc] init];

    NSTimeInterval NSOneYear = 1 * 365 * 24.0f * 60.0f * 60.0f;
    NSDate *startDate = [[NSDate date] dateByAddingTimeInterval:-NSOneYear];
    NSDate *endDate = [NSDate date];

    NSPredicate *predicate =
    [self.eventStore predicateForEventsWithStartDate:startDate
                                              endDate:endDate
                                              calendars:self.eventStore.calendars];

    NSArray *events = [self.eventStore eventsMatchingPredicate:predicate];

    if ([events count] > 0){
        EKEvent *event = [events objectAtIndex:0];

        EKEventEditViewController *controller =
            [[EKEventEditViewController alloc] init];

        controller.event = event;
        controller.editViewDelegate = self;

        [self.navigationController presentViewController:controller
                                              animated:YES];
    }
}
```

```

- (void)viewDidUnload{
    [super viewDidUnload];
    self.eventStore = nil;
}

```

Depending on the event that is found on the device, the user will see something similar to that shown in [Figure 14-10](#):




Figure 14-10. An edit event view controller displaying an event

See Also

[Recipe 14.9](#)

Graphics and Animations

15.0 Introduction

You've certainly seen applications with beautiful graphics effects on iPhones or iPads. And you've probably also encountered impressive animations in games and other apps. When the iOS runtime and Cocoa programming frameworks combine, they make an amazing variety of graphics and animation effects possible with relatively simple coding. The quality of these graphics and animations depends partly, of course, on the aesthetic sensitivities of the programmer and artistic collaborators. But in this chapter, you'll see how much you can accomplish with modest programming skills.

I'll dispense with conceptual background, preferring to introduce ideas such as color spaces, transformation, and the graphics context as we go along. I'll just mention a few basics before leaping into code.

In Cocoa Touch, an app is made up of *windows* and *views*. An app with a UI has at least one window that contains, in turn, one or more views. In Cocoa Touch, a window is an instance of `UIWindow`. Usually, an app will open to the main window and the programmer will then add views to the window to represent different parts of the UI: parts such as buttons, labels, images, and custom controls. All these UI-related components are handled and drawn by UIKit.

Some of these things might sound relatively difficult to understand, but I promise you that as we proceed through this chapter, you will understand them step-by-step with the many examples I will give.

Apple has provided developers with powerful frameworks that handle graphics and animations in iOS and OS X. Some of these frameworks and technologies are:

UIKit

The high-level framework that allows developers to create views, windows, buttons, and other UI related components. It also incorporates some of the low-level APIs into an easier-to-use high-level API.

Quartz 2D

The main engine running under the hood to facilitate drawing in iOS; UIKit uses Quartz.

Core Graphics

A framework that supports the graphics context (more on this later), loading images, drawing images, and so on.

Core Animation

A framework that, as its name implies, facilitates animations in iOS.

When drawing on a screen, one of the most important concepts to grasp is the relation between points and pixels. I'm sure you're familiar with pixels, but what are *points*? They're the device-independent counterpart of pixels. For instance, compare the iPhone 3GS to the iPhone 4. Both devices have 3.5-inch displays. However, the number of pixels that iPhone 3GS can draw in portrait mode is 320×480. The same screen size on the iPhone 4 is capable of drawing twice as many, or 640×960, pixels in portrait mode.

Now imagine you are writing an iPhone app that has only one screen, and that you are simply filling the whole screen with the color green. Imagine that you naïvely specify a rectangular area of 320×480 pixels. When iPhone 3GS users run your app, they will be quite happy because “it does what it says it does”—fill the entire screen with the color green. iPhone 4 users, on the other hand, will be quite unhappy: what they will see is quite different, as shown in [Figure 15-1](#).




Figure 15-1. Device-dependent pixel rendering yields different results on different devices

To remedy this problem, Apple introduced device-independent drawing methods to help developers focus on how their shapes and graphics have to appear on a device instead of worrying about the screen sizes and resolutions of different devices that run the same code. To fix the issue we saw in [Figure 15-1](#), the developer of the app can simply use the relevant APIs to specify the green rectangle in points instead of pixels. That will allow the same code to run on the iPhone 3GS and the iPhone 4, ensuring that the screen on the iPhone 4 will be filled with the rectangle. For this reason, many of the methods that you will see in this chapter will rely on points (or as Apple calls them, *logical points*) instead of pixels.



The origin point of the screen on an iOS device is the top-left corner. Screens whose drawing origin is on the top-left corner are also referred to as Upper Left Origin, or ULO, screens. This means that point (0, 0) is the topmost and the leftmost point on the screen, and that positive values of the x axis extend towards the right, while positive values of the y axis extend towards the bottom. In other words, an x position of 20 is further right on the screen than a position of 10 is. On the y axis, point 20 is further down than point 10.

In this chapter, we will be using view objects of type `UIView` to draw shapes, strings, and everything else that's visible on the screen.



I assume you have the latest Xcode from Apple. If not, please head to [Xcode's website](#) in order to download it.

In order to be able to incorporate some of these code snippets in an application, I will first show you the required steps to create a new project in Xcode and subclass `UIView`, where we can place our code:

1. Open Xcode.
2. From the File menu, select New→Project.
3. On the left side of the screen, make sure the iOS category is selected. Select Application under that category (see [Figure 15-2](#)).




Figure 15-2. Creating a Single View Application for iOS in Xcode

4. On the right side of the screen, select View-based Application, and press Next (see [Figure 15-2](#)).
5. In the Product Name box ([Figure 15-3](#)), select a name for your project. I've entered Graphics and I suggest you choose the same name to avoid confusion later on
6. In the Company Identifier box, enter a bundle identifier prefix, which will be prepended to the Product Name you chose. This is usually `com.company`. I have chosen `com.pixolity`. Xcode usually automatically picks this up for you.
7. In the Device Family, select iPhone, and then press Next.
8. On the next screen ([Figure 15-4](#)), select where you want to save your project. I've selected Desktop. Press Create.

Now your Xcode project is open. On the left side of Xcode, expand the Graphics group to reveal all the files that Xcode created for us when we created the project. Now we shall create a view object for our view controller. Please follow these steps to do so:

1. Select the Graphics group from the left hand side in Xcode.
2. Right click on the Graphics group and select New File....
3. In the New File dialog box, make sure iOS is selected as the category on the left side, and select Cocoa Touch as the subcategory (see [Figure 15-5](#)).




Figure 15-3. Setting the options for a new project in Xcode




Figure 15-4. Saving our Xcode project on disk

4. On the right side, select Objective-C class, and then press Next (see [Figure 15-5](#)).




Figure 15-5. Creating a new Objective-C class in Xcode

5. In the next screen (Figure 15-6), make sure that the Subclass box has *UIView* written inside it, and then press Next.
6. In the Save As dialog, set the file name to *GraphicsViewControllerView.m*.
7. Select Graphics in the Group drop-down box (see Figure 15-7).
8. Make sure the “Add to targets” checkbox is checked for the project that we created earlier, and then press Save (see Figure 15-7).
9. On the left side of Xcode’s main window, click on the *GraphicsViewController.xib* file. Interface Builder will be displayed on the right side of Xcode’s screen, as shown in Figure 15-8. We will not be using the *.xib* file at this point.
10. From the Xcode menu, select View→Utilities→File Inspector. The file inspector will be displayed, by default, on the right side of Xcode’s window.
11. Click somewhere inside the gray view that is created for you in Interface Builder. The contents displayed in File Inspector (on the right) will change to reflect your selection (see Figure 15-9).




Figure 15-6. Creating a subclass of UIView




Figure 15-7. Saving a subclass of `UIView` to disk

12. In File Inspector, choose the Identity Inspector tab on top (see [Figure 15-10](#)).
13. In the Class box, under the Custom Class section, enter `GraphicsViewControllerView` (the view object we created before), and press Return on your keyboard.




Figure 15-8. Selecting the xib file of our view controller

Now we are ready to start coding. What we did was simply creating a view class of type `UIView` so that later on in this chapter, we can change the code in that class. Then we used Interface Builder to set our view controller's view class to the same view object that we created. This means that now our view controller's view will be an instance of the `GraphicsViewControllerView` class that we created.




Figure 15-9. The file inspector in Interface Builder




Figure 15-10. The Identity Inspector shows information for our view object

You have probably already looked at the contents of the view object that Xcode generated. One of the most important methods inside this object is `drawRect:`. Cocoa Touch automatically calls this method whenever it is time to draw the view, and uses it to ask the view object to draw its contents on the graphical context that Cocoa Touch automatically prepares for the view. A graphical context can be thought of as a canvas, offering an enormous number of properties such as pen color, pen thickness, etc. Given

the context, you can start *painting* straight away inside the `drawRect:` method, and Cocoa Touch will make sure that the attributes and properties of the context are applied to your drawings. We will talk about this more later, but now, let's move on to more interesting subjects.

15.1 Enumerating and Loading Fonts

Problem

You want to use fonts which come pre-installed on an iOS device, in order to render some text on the screen.

Solution

Use the `UIFont` class.

Discussion

Fonts are fundamental to displaying text on a graphical user interface. The UIKit framework provides programmers with high-level APIs that facilitate the enumerating, loading, and use of fonts. Fonts are encapsulated in the `UIFont` class in Cocoa Touch. Each iOS device comes with built-in system fonts. Fonts are organized into *families*, and each family contains *faces*. For instance, Helvetica is a font family, and Helvetica *Bold* is one of the faces of the Helvetica family. To be able to load a font, you must know the font's face (that is, its name)—and to know the face, you have to know the family. So first, let's enumerate all the font families that are installed on the device, using the `familyNames` class method of the `UIFont` class:

```
- (void) enumerateFonts{  
    for (NSString *familyName in [UIFont familyNames]){  
        NSLog(@"Font Family = %@", familyName);  
    }  
}
```

Running this program in iOS Simulator, I get results similar to this:

```
Font Family = Heiti TC  
Font Family = Sinhala Sangam MN  
Font Family = Kannada Sangam MN  
Font Family = Georgia  
Font Family = Heiti J  
Font Family = Times New Roman  
Font Family = Snell Roundhand  
Font Family = Geeza Pro  
Font Family = Helvetica Neue  
...
```

After getting the font families, we can enumerate the font names inside each family. We'll use the `fontNamesForFamilyName:` class method of the `UIFont` class, and get back an array of font names for the family name that we pass as a parameter:

```
- (void) enumerateFonts{

    for (NSString *familyName in [UIFont familyNames]){
        NSLog(@"Font Family = %@", familyName);
        for (NSString *fontName in
            [UIFont fontNamesForFamilyName:familyName]){
            NSLog(@"\t%@", fontName);
        }
    }
}
```

Running this code in iOS Simulator gives me the following results:

```
...
Font Family = Geeza Pro
GeezaPro
GeezaPro-Bold
Font Family = Helvetica Neue
HelveticaNeue-Italic
HelveticaNeue-Bold
HelveticaNeue-BoldItalic
HelveticaNeue
...
```

So as you can see, *Helvetica Neue* is the font family and *HelveticaNeue-Bold* is one of the font names in this family. Now that we know the font name, we can load the fonts into objects of type `UIFont` using the `fontWithName:size:` class method of the `UIFont` class:

```
UIFont *helveticaBold = [UIFont fontWithName:@"HelveticaNeue-Bold"
                                         size:12.0f];
```



If the result of the `fontWithName:size:` class method of the `UIFont` class is `nil`, the given font name could not be found. Make sure that the font name you have provided is available in the system by first enumerating all the font families and then all font names available in each family.

You can also use the `systemFontOfSize:` instance method of the `UIFont` class (or its bold alternative, `boldSystemFontOfSize:`) to load local system fonts, whatever they might be, from the device that is running your code. The default system font for iOS devices is Helvetica.

After you have loaded fonts, you can proceed to [Recipe 15.2](#), where we will use the fonts that we loaded here in order to draw text on a graphical context.

See Also

XXX

15.2 Drawing Text

Problem

You want to be able to draw text on the screen of an iOS device.

Solution

Use the `drawAtPoint:withFont:` method of `NSString`.

Discussion

To draw text, we can use some really handy methods that are built into the `NSString` class, such as `drawAtPoint:withFont:`. Before we proceed further, make sure that you have followed the instructions in [Recipe 15.0](#). You should now have a view object, subclassed from `UIView`, named `GraphicsViewControllerView`. Open that file. If the `drawRect:` instance method of the view object is commented out, remove the comments until you have that method in your view object:

```
#import "GraphicsViewControllerView.h"

@implementation GraphicsViewControllerView

- (id)initWithFrame:(CGRect)frame{
    self = [super initWithFrame:frame];
    if (self) {
        // Initialization code
    }
    return self;
}

- (void)drawRect:(CGRect)rect{

}

@end
```

The `drawRect:` method is where we'll do our drawing, as mentioned before. Here, we can start loading our font, and then draw a simple string on the screen at point 40 on the x axis and 180 on the y axis ([Figure 15-11](#)):

```
- (void)drawRect:(CGRect)rect{

    UIFont *helveticaBold = [UIFont fontWithName:@"HelveticaNeue-Bold"
                                                size:40.0f];

    NSString *myString = @"Some String";
```

```
[myString drawAtPoint:CGPointMake(40, 180)
      withFont:helveticaBold];

}
```

In this code, we are simply loading a bold Helvetica font at size 40, and using it to draw the text `Some String` at point (40, 180).



Figure 15-11. A_random_string_drawn_on_the_graphical_context_of_a_view

See Also

XXX

15.3 Constructing, Setting, and Using Colors

Problem

You want to be able obtain reference to color objects in order to use them while you are drawing various forms on a view, such as text, rectangles, triangles and line segments.

Solution

Use the `UIColor` class.

Discussion

UIKit provides programmers with a high-level abstraction of colors, encapsulated in the `UIColor` object. This class has a few really handy class methods such as `redColor`, `blueColor`, `brownColor`, and `yellowColor`. However, if the color you are looking for isn't one of the options provided by such explicitly named `UIColor` methods, you can always use the `colorWithRed:green:blue:alpha:` class method of `UIColor` class to load the color that you are looking for. The return value of this class method is a value of type `UIColor`. The parameters of this method are:

`red`

The amount of red to use in the color. This value can be anything between `0.0f` to `1.0f`, where `0.0f` omits all red and `1.0f` makes the red component as dark as possible.

`green`

The amount of green to mix with the red in the color. This value also ranges from `0.0f` to `1.0f`.

`blue`

The amount of blue to mix with the red and green in the color. This value also ranges from `0.0f` to `1.0f`.

`alpha`

The opaqueness of the color. This value can range from `0.0f` to `1.0f`, with `1.0f` making the color completely opaque and `0.0f` making the color completely transparent (in other words, invisible).

After you have an object of type `UIColor`, you can use its `set` instance method to make the current graphics context use that color for subsequent drawing.



You can use the `colorWithRed:green:blue:alpha:` class method of the `UIColor` class to load primary colors like red by simply passing `1.0f` as the `red` parameter, and `0.0f` for the green and blue parameters. The alpha is up to you.

If you look at [Figure 15-11](#), you will notice that the background color of the view object we have created by default is a really ugly gray color. Let's change that, shall we? Simply find the `viewDidLoad` instance method of your view controller, `GraphicsViewController`, and set the background color of your view to white as shown here:

```
- (void)viewDidLoad{
    [super viewDidLoad];
    self.view.backgroundColor = [UIColor whiteColor];
}
```



We will be using instance methods of the `NSString` class to draw text on the current graphics context, as we shall soon discuss.

Now let's load a magenta color into an object of type `UIColor` and then draw the text **I Learn Really Fast** on our view's graphical context using a bold Helvetica font of size 30 (see [Recipe 15.1](#) for loading fonts):

```
- (void)drawRect:(CGRect)rect{
    // Drawing code

    /* Load the color */
    UIColor *magentaColor =[UIColor colorWithRed:0.5f
                                           green:0.0f
                                           blue:0.5f
                                           alpha:1.0f];

    /* Set the color in the graphical context */
    [magentaColor set];

    /* Load the font */
    UIFont *helveticaBold = [UIFont fontWithName:@"HelveticaNeue-Bold"
                                           size:30.0f];

    /* Our string to be drawn */
    NSString *myString = @"I Learn Really Fast";

    /* Draw the string using the font. The color has
       already been set */
    [myString drawAtPoint:CGPointMake(25, 190)
                  withFont:helveticaBold];
}
```

The results are shown in [Figure 15-12](#).



Figure 15-12. String drawn with a color on a graphical context

We can also use the `drawInRect:withFont:` instance method of the `NSString` class to draw text inside a rectangular space. The text will get stretched to fit into that rectangle. UIKit will even wrap the text if it doesn't fit horizontally within the given rectangle. Rectangular bounds are encapsulated in `CGRect` structures. You can use the `CGRectMake` function to create the bounds of a rectangle. This function takes four parameters:

x

The x position of the origin point of the rectangle in relation to the graphics context. In iOS, this is the number of points heading right, starting from the left side of the rectangle.

y

The y position of the origin point of the rectangle in relation to the graphics context. In iOS, this is the number of points heading down, starting from the top of the rectangle.

width

The width of the rectangle in points.

height

The height of the rectangle in points.

```
- (void)drawRect:(CGRect)rect{
    // Drawing code

    /* Load the color */
    UIColor *magentaColor = [UIColor colorWithRed:0.5f
                                              green:0.0f
                                              blue:0.5f
                                              alpha:1.0f];

    /* Set the color in the graphical context */
    [magentaColor set];

    /* Load the font */
    UIFont *helveticaBold = [UIFont boldSystemFontOfSize:30];

    /* Our string to be drawn */
    NSString *myString = @"I Learn Really Fast";

    /* Draw the string using the font. The color has
       already been set */
    [myString drawInRect:CGRectMake(100, /* x */
                                    120, /* y */
                                    100, /* width */
                                    200) /* height */
                  withFont:helveticaBold];
}
```

The output is shown in [Figure 15-13](#).



Figure 15-13. Drawing a string in rectangular space

`UIColor` is really a `UIKit` wrapper around the Core Graphics class `CGColor`. When we get as low-level as Core Graphics, we suddenly gain more control over how we use our color objects, and we can even determine the components from which the color is made. Let's say some other code passed you an object of type `UIColor`, and you want to detect its red, green, blue, and alpha components. To get the components that make up a `UIColor` object, follow these steps:

1. Use the `CGColor` instance method of our instance of the `UIColor` class. This will give us a color object of type `CGColorRef`, which is a Core Graphics Color Reference object.
2. Use the `CGColorGetComponents` function to get the components that construct the color object.
3. Use the `CGColorGetNumberOfComponents` function to determine the number of components that were used to construct the color (red + green + etc.) if need be.

Here is an example:

```
/* Load the color */
UIColor *steelBlueColor = [UIColor colorWithRed:0.3f
                                green:0.4f
                                blue:0.6f
                                alpha:1.0f];

CGColorRef colorRef = [steelBlueColor CGColor];

const CGFloat *components = CGColorGetComponents(colorRef);

NSUInteger componentsCount = CGColorGetNumberOfComponents(colorRef);

NSUInteger counter = 0;
for (counter = 0;
     counter < componentsCount;
     counter++){
    NSLog(@"Component %lu = %.02f",
          (unsigned long)counter + 1,
          components[counter]);
}
```

The output that we get in the console window after running this code is:

```
Component 1 = 0.30
Component 2 = 0.40
Component 3 = 0.60
Component 4 = 1.00
```

See Also

XXX

15.4 Drawing Images

Problem

You want to be able to draw images on the screen of an iOS device.

Solution

Use the `UIImage` class to load an image and then use the `drawInRect:` method of the image to draw it on a graphics context.

Discussion

UIKit helps you draw images with ease. All you have to do is to load your images in instances of type `UIImage`. The `UIImage` class provides various class and instance methods to load your images. Here are some of the important ones in iOS:

`imageNamed:` *class method*

Loads the image (and caches the image if it can load it properly). The parameter to this method is the name of the image in the bundle, such as *Tree Texture.png*.

`imageWithData:` *class method*

Loads an image from the data encapsulated in an instance of a `NSData` object that was passed as the parameter to this method.

`initWithContentsOfFile:` *instance method (for initialization)*

Uses the given parameter as the path to an image that has to be loaded and used to initialize the image object.



This path should be the full path to the image in the app bundle.

`initWithData:` *instance method (for initialization)*

Uses the given parameter of type `NSData` to initialize the image. This data should belong to a valid image.

Please follow these steps to add an image to your Xcode project:

1. Find where the image is located in your computer.
2. Drag and drop the image into Xcode (onto the lefthand side, where the rest of your project files are stored).
3. A new dialog box will appear on the screen. Check the “Copy items into destination group's folder (if needed)” checkbox only if you want the image file to be copied into your project’s structure. Uncheck this box if you don’t intend to copy the image into your project file, instead allowing Xcode to read it from the original file that you dragged and dropped.
4. In the Folders section, make sure that the “Create groups for any added folders” radio button is selected.
5. In the “Add to targets” section, make sure that you check the targets to which you want to add your image.



You can search for `xcode filetype:png` in Google Images to find Xcode's icon as a PNG file. We will be drawing this image on a graphics context to demonstrate how to draw images in this section of the book. I've already found the file and dragged and dropped that image into my iOS app. Now I have an image called `xcode.png` in my app bundle. The image is shown in [Figure 15-14](#).



Figure 15-14. Xcode's icon, found by searching in Google

Here is the code for drawing an image:

```
- (void)drawRect:(CGRect)rect{  
    UIImage *image = [UIImage imageNamed:@"Xcode.png"];
```

```

        if (image != nil){
            NSLog(@"Successfully loaded the image.");
        } else {
            NSLog(@"Failed to load the image.");
        }
    }
}

```

If you have the *Xcode.png* image in your app bundle, running this code will print *Successfully loaded the image.* in the console. If you don't have the image, *Failed to load the image.* will get printed. For the remainder of this section, I assume you have this image in your app bundle. Feel free to place other images in your app bundle and refer to those images instead of *Xcode.png*, which I will be using in example code.

The two easiest ways to draw an image of type `UIImage` on a graphics context are:

`drawAtPoint:` *instance method of UIImage class*

Draws the image at its original size at the given point. Construct the point using the `CGPointMake` function.

`drawInRect:` *instance method of UIImage class*

Draws the image in the given rectangular space. To construct this rectangular space, use the `CGRectMake` function:

```

- (void)drawRect:(CGRect)rect{

    /* Assuming the image is in your app bundle and we can load it */
    UIImage *xcodeIcon = [UIImage imageNamed:@"Xcode.png"];

    [xcodeIcon drawAtPoint:CGPointMake(0.0f,
                                       20.0f)];

    [xcodeIcon drawInRect:CGRectMake(50.0f,
                                     10.0f,
                                     40.0f,
                                     35.0f)];
}

```

The **`drawAtPoint:`** call shown above will draw the image at its full size at point (0, 20), and the **`drawInRect:`** call will draw the image at point (50, 10) at 40×35 points, as shown in [Figure 15-15](#).



Figure 15-15. Drawing an image on a graphics context can be accomplished with two different methods



Aspect ratio is the ratio between the width and the height of an image (or a computer screen). Let's assume you have an image that is 100×100 pixels. If you draw this image at point (0, 0) with a size of (100, 200), you can immediately see on the screen that the image is stretched in height (200 pixels instead of 100). The `drawInRect:` instance method of `UIImage` leaves it up to you how you want to draw your images. In other words, it is *you* who has to specify the *x*, *y*, width, and height of your image as it appears on the screen.

See Also

XXX

15.5 Drawing Lines

Problem

You simply want to be able to draw lines on a graphics context.

Solution

Retrieve the handle to your graphics context and then use the `CGContextMoveToPoint` and the `CGContextAddLineToPoint` functions to draw your line.

Discussion

When we talk about drawing shapes in iOS or OS X, we are implicitly talking about *paths*. What are paths, you may ask? A path is constructed from one or more series of points drawn on a screen. There is a big difference between paths and lines. A path can contain many lines, but a line cannot contain many paths. Think of paths as series of points—it's as simple as that.

Lines have to be drawn using paths. Specify the start and end points, and then ask Core Graphics to fill that path for you. Core Graphics realizes that you have created a line on that path, and will paint that path for you using the color that you specified (see [Recipe 15.3](#)).

We will be talking about paths more in-depth later (see [Recipe 15.6](#)), but for now let's focus on using paths to create straight lines. To do this, follow these steps:

1. Choose a color on your graphics context (see [Recipe 15.3](#)).
2. Retrieve the handle to the graphics context, using the `UIGraphicsGetCurrentContext` function.
3. Set the starting point for your line using the `CGContextMoveToPoint` procedure.

4. Move your pen on the graphics context using the `CGContextAddLineToPoint` procedure to specify the ending point of your line.
5. Create the path that you have laid out using the `CGContextStrokePath` procedure. This procedure will draw the path using the current color that has been set on the graphics context.

Optionally, you can use the `CGContextSetLineWidth` procedure to set the width of the lines that you are drawing on a given graphics context. The first parameter to this procedure is the graphics context that you are drawing on, and the second parameter is the width of the line, expressed as a floating-point number (`CGFloat`).



In iOS, the line width is measured in logical points.

Here is an example:

```
- (void)drawRect:(CGRect)rect{

    /* Set the color that we want to use to draw the line */
    [[UIColor brownColor] set];

    /* Get the current graphics context */
    CGContextRef currentContext = UIGraphicsGetCurrentContext();

    /* Set the width for the line */
    CGContextSetLineWidth(currentContext,
                          5.0f);

    /* Start the line at this point */
    CGContextMoveToPoint(currentContext,
                          50.0f,
                          10.0f);

    /* And end it at this point */
    CGContextAddLineToPoint(currentContext,
                            100.0f,
                            200.0f);

    /* Use the context's current color to draw the line */
    CGContextStrokePath(currentContext);

}
```

Running this code in iOS Simulator will show you results similar to those in [Figure 15-16](#).




Figure 15-16. Drawing a line on a current graphics context

Let me show you another example. As mentioned earlier, the `CGContextAddLineToPoint` procedure specifies the end point of the current line. Now what if we have already drawn a line from point (20, 20) to point (100, 100), and want to draw a line from (100, 100) to (300, 100)? You might think that after drawing the first line, we have to move our pen to point (100, 100) using the `CGContextMoveToPoint` procedure, and then draw the line to point (300, 100) using the `CGContextAddLineToPoint` procedure. While that will work, there is a more efficient way to do this. After you call the `CGContextAddLineToPoint` procedure to specify the ending point of your current line, your pen's position

will change to what you pass to this method. In other words, after you issue a method using the pen, it leaves the pen's position at the ending point of whatever it drew. So to draw another line from the current ending point to another point, all you have to do is to call the `CGContextAddLineToPoint` procedure again with another ending point. Here is an example:

```
- (void)drawRect:(CGRect)rect{
    // Drawing code

    /* Set the color that we want to use to draw the line */
    [[UIColor brownColor] set];

    /* Get the current graphics context */
    CGContextRef currentContext = UIGraphicsGetCurrentContext();

    /* Set the width for the lines */
    CGContextSetLineWidth(currentContext,
                           5.0f);

    /* Start the line at this point */
    CGContextMoveToPoint(currentContext,
                          20.0f,
                          20.0f);

    /* And end it at this point */
    CGContextAddLineToPoint(currentContext,
                             100.0f,
                             100.0f);

    /* Extend the line to another point */
    CGContextAddLineToPoint(currentContext,
                             300.0f,
                             100.0f);

    /* Use the context's current color to draw the lines */
    CGContextStrokePath(currentContext);
}
```

The results are shown in [Figure 15-17](#). You can see that both lines are successfully drawn without us having to move the pen for the second line.




Figure 15-17. Drawing two lines at once

The point where two lines meet is, not surprisingly, called a join. With Core Graphics, you can specify what type of join you want to have between lines that are connected to each other. To make your choice, you must use the `CGContextSetLineJoin` procedure. It takes two parameters: a graphics context on which you are setting the join type, and the join type itself, which must be of type `CGLineJoin`. `CGLineJoin` is an enumeration of the following values:

`kCGLineJoinMiter`

Joins will be made out of sharp corners. This is the default join type.

`kCGLineJoinBevel`

Joins will be squared off on the corner.

`kCGLineJoinRound`

As the name implies, this makes round joins.

Let's have a look at an example. Let's say we want to write a program that can draw "rooftops" on a graphics context (three of them, one for each join type), and also draws text below each rooftop describing the type of join it is using. Something similar to [Figure 15-18](#) will be the result.




Figure 15-18. Three types of line joins in Core Graphics

To accomplish this, I've written a method named `drawRooftopAtTopPointof:text ToDisplay:lineJoin:`, which takes three parameters:

1. A point at which the top of the rooftop should be placed
2. The text to display inside the rooftop
3. The join type to be used.

The code is as follows:

```
- (void) drawRooftopAtTopPointof:(CGPoint)paramTopPoint
                        textToDisplay:(NSString *)paramText
                        lineJoin:(CGLineJoin)paramLineJoin{

    /* Set the color that we want to use to draw the line */
    [[UIColor brownColor] set];

    /* Get the current graphics context */
    CGContextRef currentContext = UIGraphicsGetCurrentContext();

    /* Set the line join */
    CGContextSetLineJoin(currentContext,
                          paramLineJoin);

    /* Set the width for the lines */
    CGContextSetLineWidth(currentContext,
                          20.0f);

    /* Start the line at this point */
    CGContextMoveToPoint(currentContext,
                        paramTopPoint.x - 140,
                        paramTopPoint.y + 100);

    /* And end it at this point */
    CGContextAddLineToPoint(currentContext,
                          paramTopPoint.x,
                          paramTopPoint.y);

    /* Extend the line to another point to
       make the rooftop */
    CGContextAddLineToPoint(currentContext,
                          paramTopPoint.x + 140,
                          paramTopPoint.y + 100);

    /* Use the context's current color to draw the lines */
    CGContextStrokePath(currentContext);

    /* Draw the text in the rooftop using a black color */
    [[UIColor blackColor] set];

    /* Now draw the text */
    CGPoint drawingPoint = CGPointMake(paramTopPoint.x - 40.0f,
                                      paramTopPoint.y + 60.0f);
    [paramText drawAtPoint:drawingPoint
                  withFont:[UIFont boldSystemFontOfSize:30.0f]];
```

```
}
```

Now let's call this method in the `drawRect:` instance method of our view object where we have a graphics context:

```
- (void)drawRect:(CGRect)rect{

    [self drawRooftopAtTopPointof:CGPointMake(160.0f, 40.0f)
      textToDisplay:@"Miter"
      lineJoin:kCGLineJoinMiter];

    [self drawRooftopAtTopPointof:CGPointMake(160.0f, 180.0f)
      textToDisplay:@"Bevel"
      lineJoin:kCGLineJoinBevel];

    [self drawRooftopAtTopPointof:CGPointMake(160.0f, 320.0f)
      textToDisplay:@"Round"
      lineJoin:kCGLineJoinRound];

}
```

See Also

XXX

15.6 Constructing Paths

Problem

You want to be able to draw any shape that you wish on a graphics context.

Solution

Construct and draw paths.

Discussion

A series of points placed together can form a shape. A series of shapes put together builds a path. Paths can easily be managed by Core Graphics. In [Recipe 15.5](#), we worked indirectly with paths using `CGContext` functions. But Core Graphics also has functions that work directly with paths, as we shall soon see.

Paths belong to whichever graphics context they are drawn on. Paths do not have boundaries or specific shapes, unlike the shapes we draw on them. But paths do have bounding boxes. Please bear in mind that boundaries are not the same as bounding boxes. Boundaries are limits above which you cannot draw on a canvas, while the bounding box of a path is the smallest rectangle that contains all the shapes, points, and other objects that have been drawn on that specific path. Think of paths as stamps and think of your graphics context as the envelope. Your envelope could be the same

every time you mail something to your friend, but what you put on that context (the stamp or the path) can be different.

After you finish drawing on a path, you can then draw that path on the graphics context. Developers familiar with game programming know the concept of *buffers*, which draw their scenes and, at appropriate times, *flush* the images onto the screen. Paths are those buffers. They are like blank canvases that can be drawn on graphics contexts when the time is right.

The first step in directly working with paths is to create them. The method creating the path returns a handle that you use whenever you want to draw something on that path, passing the handle to Core Graphics for reference. After you create the path, you can add different points, lines, and shapes to it and then draw the path. You can either fill the path or paint it with a stroke on a graphics context. Here are the methods you have to work with:

CGPathCreateMutable *function*

Creates a new mutable path of type **CGMutablePathRef** and returns its handle. We should dispose of this path once we are done with it, as you will soon see.

CGPathMoveToPoint *procedure*

Moves the current pen position on the path to the point specified by a parameter of type **CGPoint**.

CGPathAddLineToPoint *procedure*

Draws a line segment from the current pen position to the specified position (again, specified by a value of type **CGPoint**).

CGContextAddPath *procedure*

Adds a given path (specified by a path handle) to a graphics context, ready for drawing.

CGContextDrawPath *procedure*

Draws a given path on the graphics context.

CGPathRelease *procedure*

Releases the memory allocated for a path handle.

CGPathAddRect *procedure*

Adds a rectangle to a path. The rectangle's boundaries are specified by a **CGRect** structure.

There are three important drawing methods that you can ask the **CGContextDrawPath** procedure to perform:

kCGPathStroke

Draws a line (stroke) to mark the boundary or edge of the path, using the currently selected stroke color.

kCGPathFill

Fills the area surrounded by the path with the currently selected fill color.

kCGPathFillStroke

Combines stroke and fill. Uses the currently selected fill color to fill the path, and the currently selected stroke color to draw the edge of the path. We'll see an example of this method in the following section.

Let's have a look at an example. We will draw a blue line from the top-left to the bottom-right corner and another from the top-right to the bottom-left corner, to create a gigantic X across the screen.



For this example, I have removed the status bar from the application in iOS Simulator. If you don't want to bother doing this, please continue to the example code. With a status bar, the output of this code will only be slightly different from the screenshot I'll show. To hide the status bar, find the *Info.plist* file in your Xcode project and add a key to it named `UIStatusBarHidden` with the value of `YES`, as shown in [Figure 15-19](#). This will force your app's status bar to be hidden when it opens.

Key	Type	Value
Localization native development region	String	en
Bundle display name	String	\$(PRODUCT_NAME)
Executable file	String	\$(EXECUTABLE_NAME)
Icon file	String	
Bundle identifier	String	com.pixolity.\$(PRODUCT_NAME:rfc1034identifier)
InfoDictionary version	String	6.0
Bundle name	String	\$(PRODUCT_NAME)
Bundle OS Type code	String	APPL
Bundle versions string, short	String	1.0
Bundle creator OS Type code	String	????
Bundle version	String	1.0
Application requires iPhone environment	Boolean	YES
Main nib file base name	String	MainWindow
Status bar is initially hidden	Boolean	YES
Supported interface orientations	Array	(3 items)

Figure 15-19. Hiding the status bar in an iOS app using the *Info.plist* file

```
- (void)drawRect:(CGRect)rect{  
  
    /* Create the path */  
    CGMutablePathRef path = CGPathCreateMutable();  
  
    /* How big is our screen? We want the X to cover  
    the whole screen */  
    CGRect screenBounds = [[UIScreen mainScreen] bounds];  
  
    /* Start from top-left */  
    CGPathMoveToPoint(path,  
                      NULL,  
                      screenBounds.origin.x,  
                      screenBounds.origin.y);
```

```

/* Draw a line from top-left to bottom-right of the screen */
CGPathAddLineToPoint(path,
                      NULL,
                      screenBounds.size.width,
                      screenBounds.size.height);

/* Start another line from top-right */
CGPathMoveToPoint(path,
                  NULL,
                  screenBounds.size.width,
                  screenBounds.origin.y);

/* Draw a line from top-right to bottom-left */
CGPathAddLineToPoint(path,
                      NULL,
                      screenBounds.origin.x,
                      screenBounds.size.height);

/* Get the context that the path has to be drawn on */
CGContextRef currentContext = UIGraphicsGetCurrentContext();

/* Add the path to the context so we can
draw it later */
CGContextAddPath(currentContext,
                 path);

/* Set the blue color as the stroke color */
[[UIColor blueColor] setStroke];

/* Draw the path with stroke color */
CGContextDrawPath(currentContext,
                  kCGPathStroke);

/* Finally release the path object */
CGPathRelease(path);
}

```



The NULL parameters getting passed to procedures such as `CGPathMoveToPoint` represent possible transformations that can be used when drawing the shapes and lines on a given path. For information about transformations, refer to [Recipe 15.10](#), [Recipe 15.11](#), and [Recipe 15.12](#).

You can see how easy it is to draw a path on a context. All you really have to remember is how to create a new mutable path (`CGPathCreateMutable`), add that path to your graphics context (`CGContextAddPath`), and draw it on a graphics context (`CGContextDrawPath`). If you run this code, you will get an output similar to that shown in [Figure 15-20](#).




Figure 15-20. Drawing on a graphics context using paths

See Also

XXX

15.7 Drawing Rectangles

Problem

You want to be able to draw rectangles on a graphics context.

Solution

Use the `CGPathAddRect` to add a rectangle to a path and then draw that path on a graphics context.

Discussion

As we learned in [Recipe 15.6](#), you can construct and use paths quite easily. One of the procedures that you can use on paths in Core Graphics is `CGPathAddRect`, which lets you draw rectangles as part of paths. Here is an example:

```
- (void)drawRect:(CGRect)rect{

    /* Create the path first. Just the path handle. */
    CGMutablePathRef path = CGPathCreateMutable();

    /* Here are our rectangle boundaries */
    CGRect rectangle = CGRectMake(10.0f,
                                  10.0f,
                                  200.0f,
                                  300.0f);

    /* Add the rectangle to the path */
    CGPathAddRect(path,
                  NULL,
                  rectangle);

    /* Get the handle to the current context */
    CGContextRef currentContext = UIGraphicsGetCurrentContext();

    /* Add the path to the context */
    CGContextAddPath(currentContext,
                     path);

    /* Set the fill color to cornflower blue */
    [[UIColor colorWithRed:0.20f
                  green:0.60f
                  blue:0.80f
                  alpha:1.0f] setFill];

    /* Set the stroke color to brown */
    [[UIColor brownColor] setStroke];

    /* Set the line width (for the stroke) to 5 */
    CGContextSetLineWidth(currentContext,
                           5.0f);
```

```
/* Stroke and fill the path on the context */
CGContextDrawPath(currentContext,
                  kCGPathFillStroke);

/* Dispose of the path */
CGPathRelease(path);

}
```

Here, we are drawing a rectangle on the path, filling it with cornflower blue, and stroking the edges of the rectangle with brown. [Figure 15-21](#) shows how the output will look when we run our program.




Figure 15-21. Drawing a rectangle using paths

If you have multiple rectangles to draw, you can pass an array of `CGRect` objects to the `CGPathAddRects` procedure. Here is an example:

```
- (void)drawRect:(CGRect)rect{  
  
    /* Create the path first. Just the path handle. */  
    CGMutablePathRef path = CGPathCreateMutable();  
  
    /* Here are our first rectangle boundaries */  
    CGRect rectangle1 = CGRectMake(10.0f,  
                                   10.0f,
```

```

                200.0f,
                300.0f);

/* And the second rectangle */
CGRect rectangle2 = CGRectMake(40.0f,
                               100.0f,
                               90.0f,
                               300.0f);

/* Put both rectangles into an array */
CGRect rectangles[2] = {
    rectangle1, rectangle2
};

/* Add the rectangles to the path */
CGPathAddRects(path,
               NULL,
               (const CGRect *)&rectangles,
               2);

/* Get the handle to the current context */
CGContextRef currentContext = UIGraphicsGetCurrentContext();

/* Add the path to the context */
CGContextAddPath(currentContext,
                 path);

/* Set the fill color to cornflower blue */
[[UIColor colorWithRed:0.20f
                green:0.60f
                blue:0.80f
                alpha:1.0f] setFill];

/* Set the stroke color to black */
[[UIColor blackColor] setStroke];

/* Set the line width (for the stroke) to 5 */
CGContextSetLineWidth(currentContext,
                      5.0f);

/* Stroke and fill the path on the context */
CGContextDrawPath(currentContext,
                  kCGPathFillStroke);

/* Dispose of the path */
CGPathRelease(path);
}

```

Figure 15-22 shows how the output of this code will look when run in iOS Simulator. The parameters that we pass to the `CGPathAddRects` procedure are (in this order):

1. The handle to the path where we will add the rectangles.

2. The transformation, if any, to use on to the rectangles. (For information about transformations, refer to [Recipe 15.10](#), [Recipe 15.11](#), and [Recipe 15.12](#).)
3. A reference to the array holding the CGRect rectangles.
4. The number of rectangles in the array that we passed in the previous parameter. It is very important that you pass exactly as many rectangles as you have in your array, to avoid unknown behavior by this procedure.




Figure 15-22. Drawing multiple rectangles at once

See Also

XXX

15.8 Adding Shadows to Shapes

Problem

You want to be able to apply shadow to shapes that you draw on graphic contexts.

Solution

Use the `CGContextSetShadow` procedure.

Discussion

It is easy to draw shadows using Core Graphics. The graphics context is the element that bears the shadow. What that means is that you need to apply the shadow to the context, draw the shapes that need the shadow, and then remove the shadow from the context (or set a new context). We will see an example of this soon.

In Core Graphics, we can use two procedures to apply a shadow to a graphics context:

CGContextSetShadow procedure

This procedure, which creates black or gray shadows, accepts three parameters:

- The graphics context on which the shadow has to be applied.
- The offset, specified by a value of type `CGSize`, from the right and the bottom part of each shape where the shadow has to be applied. The greater the *x* value of this offset is, the farther to the right of each shape the shadow will extend. The greater the *y* value of this offset is, the lower the shadow will extend.
- The blur value that has to be applied to the shadow, specified as a floating point value (`CGFloat`). Specifying `0.0f` will cause the shadow to be a solid shape. The higher this value goes, the more blurred the shadow will get. We will see an example of this soon.

CGContextSetShadowWithColor procedure

This procedure accepts the exact same parameters as `CGContextSetShadow`, with one addition. This fourth parameter, of type `CGColorRef`, sets the color of the shadow.

At the beginning of this section, I mentioned that the graphics context retains its shadow properties until we explicitly remove the shadow. Let me make that point clearer by showing you an example. Let us go ahead and write code that allows us to draw two rectangles, the first one with a shadow and the second one without a shadow. We will draw the first one in this way:

```
- (void) drawRectAtTopOfScreen{
```

```

/* Get the handle to the current context */
CGContextRef currentContext = UIGraphicsGetCurrentContext();

CGContextSetShadowWithColor(currentContext,
                             CGSizeMake(10.0f, 10.0f),
                             20.0f,
                             [[UIColor grayColor] CGColor]);

/* Create the path first. Just the path handle. */
CGMutablePathRef path = CGPathCreateMutable();

/* Here are our rectangle boundaries */
CGRect firstRect = CGRectMake(55.0f,
                              60.0f,
                              150.0f,
                              150.0f);

/* Add the rectangle to the path */
CGPathAddRect(path,
              NULL,
              firstRect);

/* Add the path to the context */
CGContextAddPath(currentContext,
                 path);

/* Set the fill color to cornflower blue */
[[UIColor colorWithRed:0.20f
                green:0.60f
                blue:0.80f
                alpha:1.0f] setFill];

/* Fill the path on the context */
CGContextDrawPath(currentContext,
                  kCGPathFill);

/* Dispose of the path */
CGPathRelease(path);
}

```

If we call this method in the `drawRect:` instance method of our view object, we will see the rectangle drawn on the screen with a nice shadow just like we wanted it, as shown in [Figure 15-23](#).




Figure 15-23. Shadow applied to a rectangle

Now let's go ahead and draw a second rectangle after the first one. We won't ask for a shadow, but we'll leave the shadow property of the graphics context the way it was for the first rectangle:

```
- (void) drawRectAtBottomOfScreen{  
    /* Get the handle to the current context */  
    CGContextRef currentContext = UIGraphicsGetCurrentContext();  
  
    CGMutablePathRef secondPath = CGPathCreateMutable();
```



```

CGRect secondRect = CGRectMake(150.0f,
                                250.0f,
                                100.0f,
                                100.0f);

CGPathAddRect(secondPath,
               NULL,
               secondRect);

CGContextAddPath(currentContext,
                  secondPath);

[[UIColor purpleColor] setFill];

CGContextDrawPath(currentContext,
                  kCGPathFill);

CGPathRelease(secondPath);
}

- (void)drawRect:(CGRect)rect{
    [self drawRectAtTopOfScreen];
    [self drawRectAtBottomOfScreen];
}

```

The `drawRect:` method first calls the `drawRectAtTopOfScreen` method, and right after that, calls the `drawRectAtBottomOfScreen` method. We haven't asked for a shadow for the `drawRectAtBottomOfScreen` rectangle, yet if you run the app, you will see something similar to what is shown in [Figure 15-24](#).




Figure 15-24. Shadow applied to a second rectangle is not on purpose

It's immediately obvious that the shadow is applied to the second rectangle at the bottom of the screen. To avoid this, we will save the state of the graphics context *before* applying the shadow effect, and then restore the state when we want to remove the shadow effect.

Broadly speaking, saving and restoring the state of a graphics context is not limited to shadows only. Restoring the state of a graphics context restores everything (fill color, font, line thickness, etc.) to the values they had before you set them. So for instance, if you applied fill and stroke colors in the meantime, those colors will be reset.

You can save the state of a graphics context through the `CGContextSaveGState` procedure and restore the previous state through the `CGContextRestoreGState` procedure. So if we modify the `drawRectAtTopOfScreen` procedure by saving the state of the graphics context before applying the shadow, and restore that state after drawing the path, we will have different results, shown in [Figure 15-25](#):

```
- (void) drawRectAtTopOfScreen{

    /* Get the handle to the current context */
    CGContextRef currentContext = UIGraphicsGetCurrentContext();

    CGContextSaveGState(currentContext);

    CGContextSetShadowWithColor(currentContext,
                                CGSizeMake(10.0f, 10.0f),
                                20.0f,
                                [[UIColor grayColor] CGColor]);

    /* Create the path first. Just the path handle. */
    CGMutablePathRef path = CGPathCreateMutable();

    /* Here are our rectangle boundaries */
    CGRect firstRect = CGRectMake(55.0f,
                                   60.0f,
                                   150.0f,
                                   150.0f);

    /* Add the rectangle to the path */
    CGPathAddRect(path,
                  NULL,
                  firstRect);

    /* Add the path to the context */
    CGContextAddPath(currentContext,
                     path);

    /* Set the fill color to cornflower blue */
    [[UIColor colorWithRed:0.20f
                    green:0.60f
                    blue:0.80f
                    alpha:1.0f] setFill];

    /* Fill the path on the context */
    CGContextDrawPath(currentContext,
                      kCGPathFill);

    /* Dispose of the path */
    CGPathRelease(path);

    /* Restore the context to how it was
     when we started */
    CGContextRestoreGState(currentContext);
}
```




Figure 15-25. Saving the state of the graphics context for accurate shadows

See Also

XXX

15.9 Drawing Gradients

Problem

You want to draw gradients on graphics contexts, using different colors.

Solution

Use the `CGGradientCreateWithColor` function.

Discussion

After learning about colors in [Recipe 15.3](#), we're ready to put our skills to better use than drawing simple rectangles and colorful text!

Core Graphics allows programmers to create two types of gradients: axial and radial. (We will only discuss axial gradients in this book.) Axial gradients are gradients that start from one point with one color and end at another point with another color (although they can start and stop with the same color, which does not make them much of a gradient). “Axial” means relating to an axis. The two points (start and end point) create a line segment, which will be the axis on which the gradient will be drawn. An example of an axial gradient is shown in [Figure 15-26](#).



Figure 15-26. An axial gradient starting from the color blue and ending in the color green

In order to create an axial gradient, you must call the `CGGradientCreateWithColorComponents` function. The return value of this function will be the new gradient of type `CGGradientRef`. This is the handle to the gradient. Once you are done with the gradient, you *must* call the `CGGradientRelease` procedure, passing the handle to the gradient that you had previously retrieved from `CGGradientCreateWithColorComponents`.

The `CGGradientCreateWithColorComponents` function takes four parameters:

A color space

This is a container for a range of colors, and must be of type `CGColorSpaceRef`. For this parameter, we can just pass the return value of the `CGColorSpaceCreateDeviceRGB` function, which will give us an RGB color space.

An array of color components (for details, see [Recipe 15.3](#))

This array has to contain red, green, blue, and alpha values, all represented as `CGFloat` values. The number of elements in the array is tightly linked to the next two parameters. Essentially, you have to include enough values in this array to specify the number of locations in the fourth parameter. So if you ask for two locations (the start and end point), you have to provide two colors in the array here. And since each color is made out of red, green, blue, and alpha, this array has to have 2×4 items: four for the first color and four for the second. Don't worry if you didn't get all this, you will eventually understand it through the examples that follow in this section.

Locations of colors in the array of colors

This parameter controls how quickly the gradient shifts from one color to another. The number of elements must be the same as the value of the fourth parameter. If we ask for four colors, for example, and we want the first color to be the starting color and the last color to be the ending color in the gradient, we have to provide an array of two items of type `CGFloats`, with the first item set to `0.0f` (as in the *first* item in the array of colors) and the second item set to `3.0f` (as in the *fourth* item in the array of colors). The values of the two intermediate colors determine how the gradient actually inserts colors to get from the start to the end. Again, don't worry if this is too difficult to grasp. I will give you many examples to help you fully understand the concept.

Number of locations

This specifies how many colors and locations we want.

Let's have a look at an example. Suppose we want to draw the same gradient we saw in [Figure 15-26](#)? Here's how:

1. Pick the start and end points of the gradient—the axis along which it will shift. In this case, I've chosen to move from left to right. Think of this as changing color as you move along a hypothetical horizontal line. Along that line, we will spread the colors so that every perpendicular line to this horizontal line contains only one color. In this case, the perpendicular lines would be every vertical line in [Figure 15-26](#). Look at those vertical lines closely. Every single one contains only one color, which runs all the way from top to the bottom. That's how axial gradients work. OK, that's enough theory—let's go to the second step.
2. Now we have to create a color space to pass to the first parameter of the `CGGradientCreateWithColorComponents` function, as mentioned before:

```
CGColorSpaceRef colorSpace =  
    CGColorSpaceCreateDeviceRGB();
```



We will release this color space once we are done with it.

3. Select blue as the starting point (left) and green as the ending point (right), according to the colors chosen in [Figure 15-26](#). The names I've selected (`startColorComponents` and `endColorComponents`) are arbitrarily chosen to help us remember what we're doing with each color. We'll actually use array positions to specify which one is the start and which one is the end:

```
UIColor *startColor = [UIColor blueColor];
CGFloat *startColorComponents =
(CGFloat *)CGColorGetComponents([startColor CGColor]);

UIColor *endColor = [UIColor greenColor];
CGFloat *endColorComponents =
(CGFloat *)CGColorGetComponents([endColor CGColor]);
```



If you don't remember the concept behind color components, I suggest that you look at the section [Recipe 15.3](#), before you continue reading these instructions.

4. After retrieving the components of each color, we place them all in one flat array to pass to the `CGGradientCreateWithColorComponents` function:

```
CGFloat colorComponents[8] = {

    /* Four components of the blue color (RGBA) */
    startColorComponents[0],
    startColorComponents[1],
    startColorComponents[2],
    startColorComponents[3], /* First color = blue */

    /* Four components of the green color (RGBA) */
    endColorComponents[0],
    endColorComponents[1],
    endColorComponents[2],
    endColorComponents[3], /* Second color = green */

};
```

5. Because we have only two colors in this array, we need to specify that the first is positioned at the very beginning of the gradient (position 0.0) and the second at the very end (position 1.0). So let's place these indices in an array to pass to the `CGGradientCreateWithColorComponents` function:

```
CGFloat colorIndices[2] = {
    0.0f, /* Color 0 in the colorComponents array */
```



```
1.0f, /* Color 1 in the colorComponents array */
};
```

- Now all we have to do is to actually call the `CGGradientCreateWithColorComponents` function with all these values that we generated:

```
CGGradientRef gradient =
CGGradientCreateWithColorComponents
(colorSpace,
(const CGFloat *)&colorComponents,
(const CGFloat *)&colorIndices,
2);
```

- Fantastic! Now we have our gradient object in the `gradient` variable. Before we forget, we have to release the color space that we created using the `CGColorSpaceRelease` function:

```
CGColorSpaceRelease(colorSpace);
```

Now we'll use the `CGContextDrawLinearGradient` procedure to draw the axial gradient on a graphics context. This procedure takes five parameters:

Graphics context

Specifies the graphics context on which the axial gradient will be drawn.

Axial gradient

The handle to the axial gradient object. We created this gradient object using the `CGGradientCreateWithColorComponents` function.

Start point

A point on the graphics context, specified by a `CGPoint`, that indicates the start point of the gradient.

End point

A point on the graphics context, specified by a `CGPoint`, that indicates the end point of the gradient.

Gradient drawing options

Specifies what happens if your start or end point isn't at the edge of the graphical context. You can use your start or end color to fill the space that lies outside the gradient. Specify one of the following values for this parameter:

`kCGGradientDrawsAfterEndLocation`

Extends the gradient to all points after the ending point of the gradient.

`kCGGradientDrawsBeforeStartLocation`

Extends the gradient to all points before the starting point of the gradient.

`0`

Does not extend the gradient in any way.

To extend colors on both sides, specify both the “after” and “before” parameters as a logical OR (using the `|` operator). We'll see an example later:

```

CGRect screenBounds = [[UIScreen mainScreen] bounds];

CGPoint startPoint, endPoint;

startPoint = CGPointMake(0.0f,
                          screenBounds.size.height / 2.0f);

endPoint = CGPointMake(screenBounds.size.width,
                        startPoint.y);

CGContextDrawLinearGradient
(currentContext,
 gradient,
 startPoint,
 endPoint,
 0);

CGGradientRelease(gradient);

```



The gradient handle we are releasing at the end of this code was created in another code block in an earlier example.

The output of this code will obviously look similar to that shown in [Figure 15-26](#). Because we started the gradient from the leftmost point of our view and stretched it all the way to the rightmost point, we couldn't take advantage of the values that could be passed to the final *Gradient drawing options* parameter of the `CGContextDrawLinearGradient` procedure. Let's remedy that, shall we? How about we draw a gradient that looks similar to that which is shown in [Figure 15-27](#)?



Figure 15-27. An axial gradient with start and end point color extensions

We will use the same procedure explained earlier in this section to code the result:

```
- (void)drawRect:(CGRect)rect{  
    CGContextRef currentContext = UIGraphicsGetCurrentContext();  
    CGContextSaveGState(currentContext);  
    CGColorSpaceRef colorSpace =  
    CGColorSpaceCreateDeviceRGB();
```

```

UIColor *startColor = [UIColor orangeColor];
CGFloat *startColorComponents =
(CGFloat *)CGColorGetComponents([startColor CGColor]);

UIColor *endColor = [UIColor blueColor];
CGFloat *endColorComponents =
(CGFloat *)CGColorGetComponents([endColor CGColor]);

CGFloat colorComponents[8] = {

    /* Four components of the orange color (RGBA) */
    startColorComponents[0],
    startColorComponents[1],
    startColorComponents[2],
    startColorComponents[3], /* First color = orange */

    /* Four components of the blue color (RGBA) */
    endColorComponents[0],
    endColorComponents[1],
    endColorComponents[2],
    endColorComponents[3], /* Second color = blue */

};

CGFloat colorIndices[2] = {
    0.0f, /* Color 0 in the colorComponents array */
    1.0f, /* Color 1 in the colorComponents array */
};

CGGradientRef gradient = CGGradientCreateWithColorComponents
(colorSpace,
 (const CGFloat *)&colorComponents,
 (const CGFloat *)&colorIndices,
 2);

CGColorSpaceRelease(colorSpace);

CGPoint startPoint, endPoint;

startPoint = CGPointMake(120,
                        260);

endPoint = CGPointMake(200.0f,
                      220);

CGContextDrawLinearGradient (currentContext,
                            gradient,
                            startPoint,
                            endPoint,
                            kCGGradientDrawsBeforeStartLocation |
                            kCGGradientDrawsAfterEndLocation);

CGGradientRelease(gradient);

```

```
CGContextRestoreGState(currentContext);  
}
```

It might be difficult to understand how mixing `kCGGradientDrawsBeforeStartLocation` and `kCGGradientDrawsAfterEndLocation` values passed to the `CGContextDrawLinearGradient` procedure is creating a diagonal effect like that shown in [Figure 15-27](#). So let's remove those values and set that parameter of the `CGContextDrawLinearGradient` procedure to 0 like we had it before. [Figure 15-28](#) shows what the results will be.



Figure 15-28. Axial gradient without stretched colors

It's easy to conclude that the gradient in [Figure 15-28](#) is the same gradient that we see in [Figure 15-27](#). However, the gradient in [Figure 15-27](#) extends the start and end points' colors all the way across the graphics context, which is why you can see the whole screen covered with color.

See Also

XXX

15.10 Displacing Shapes Drawn on Graphic Contexts

Problem

You want to move everything that is drawn on a graphics context, to a new location, without changing your drawing code. Or you would simply like to displace your context's contents with ease.

Solution

Use the `CGAffineTransformMakeTranslation` function to create an affine translation transformation.

Discussion

[Recipe 15.7](#) mentioned transformations. These are exactly what the name suggests: changes to the way a graphic is displayed. Transformations in Core Graphics are objects that you apply to shapes before they get drawn. For instance, you can create a translation transformation. Translating what, you might be asking? A translation transformation is a mechanism by which you can *displace* a shape or a graphics context.

Other types of transformations include rotation (see [Recipe 15.12](#)) and scaling (see [Recipe 15.11](#)). These are all examples of *affine* transformations, which map each point in the origin to another point in the final version. All the transformations we discuss in this book will be affine transformations.

A translation transformation *translates* the current position of a shape on a path or graphics context to another relative place. For instance, if you draw a point at location (10, 20), apply a translation transformation of (30, 40) to it, and then draw it, the point will be drawn at (40, 60), because 40 is the sum of 10+30 and 60 is the sum of 20+40.

In order to create a new translation transformation, we must use the `CGAffineTransformMakeTranslation` function, which will return an affine transformation of type `CGAffineTransform`. The two parameters to this function specify the x and the y translation in points.

In [Recipe 15.7](#), we saw that the `CGPathAddRect` procedure accepts, as its second parameter, a transformation object of type `CGAffineTransform`. To displace a rectangle from

its original place to another, you can simply create an affine transformation specifying the changes you want to make in the *x* and *y* coordinates, and pass the transformation to the second parameter of the `CGPathAddRect` procedure as shown here:

```
- (void)drawRect:(CGRect)rect{

    /* Create the path first. Just the path handle. */
    CGMutablePathRef path = CGPathCreateMutable();

    /* Here are our rectangle boundaries */
    CGRect rectangle = CGRectMake(10.0f,
                                  10.0f,
                                  200.0f,
                                  300.0f);

    /* We want to displace the rectangle to the right by
       100 points but want to keep the y position
       untouched */
    CGAffineTransform transform = CGAffineTransformMakeTranslation(100.0f,
                                                                      0.0f);

    /* Add the rectangle to the path */
    CGPathAddRect(path,
                   &transform,
                   rectangle);

    /* Get the handle to the current context */
    CGContextRef currentContext =
    UIGraphicsGetCurrentContext();

    /* Add the path to the context */
    CGContextAddPath(currentContext,
                     path);

    /* Set the fill color to cornflower blue */
    [[UIColor colorWithRed:0.20f
                  green:0.60f
                  blue:0.80f
                  alpha:1.0f] setFill];

    /* Set the stroke color to brown */
    [[UIColor brownColor] setStroke];

    /* Set the line width (for the stroke) to 5 */
    CGContextSetLineWidth(currentContext,
                           5.0f);

    /* Stroke and fill the path on the context */
    CGContextDrawPath(currentContext,
                       kCGPathFillStroke);

    /* Dispose of the path */
    CGPathRelease(path);
}
```

Figure 15-29 shows the output of this block of code when placed inside a view object.




Figure 15-29. A rectangle with an affine translation transformation

Compare Figure 15-29 with Figure 15-21. Can you see the difference? Check the source code for both figures and you'll see that the x and y points specified for both rectangles in both code blocks are the same. It is just that in Figure 15-29, we have applied an affine translation transformation to the rectangle when we added it to the path.

In addition to applying transformations to shapes that get drawn to a path, we can apply transformations to graphics contexts using the `CGContextTranslateCTM` proce-

ture. This applies a translation transformation on the current transformation matrix (CTM). The current transformation matrix, although its name might be complex, is quite simple to understand. Think of CTM as how your graphics context's center is set up, and how each point that you draw gets projected onto the screen. For instance, when you ask Core Graphics to draw a point at (0, 0), Core Graphics finds the center of the screen by looking at the CTM. The CTM will then do some calculations and tell Core Graphics that point (0, 0) is indeed at the top-left corner of the screen. Using procedures such as `CGContextTranslateCTM`, you can change how CTM is configured and subsequently force every shape drawn on the graphics context to be shifted to another place on the canvas. Here is an example where we achieve the exact same effect we saw in [Figure 15-29](#) by applying a translation transformation to the CTM instead of directly to our rectangle:

```
- (void)drawRect:(CGRect)rect{

    /* Create the path first. Just the path handle. */
    CGMutablePathRef path = CGPathCreateMutable();

    /* Here are our rectangle boundaries */
    CGRect rectangle = CGRectMake(10.0f,
                                   10.0f,
                                   200.0f,
                                   300.0f);

    /* Add the rectangle to the path */
    CGPathAddRect(path,
                  NULL,
                  rectangle);

    /* Get the handle to the current context */
    CGContextRef currentContext = UIGraphicsGetCurrentContext();

    /* Save the state of the context to revert
       back to how it was at this state, later */
    CGContextSaveGState(currentContext);

    /* Translate the current transformation matrix
       to the right by 100 points */
    CGContextTranslateCTM(currentContext,
                          100.0f,
                          0.0f);

    /* Add the path to the context */
    CGContextAddPath(currentContext,
                    path);

    /* Set the fill color to cornflower blue */
    [[UIColor colorWithRed:0.20f
                  green:0.60f
                  blue:0.80f
                  alpha:1.0f] setFill];

    /* Set the stroke color to brown */
```

```

[[UIColor brownColor] setStroke];

/* Set the line width (for the stroke) to 5 */
CGContextSetLineWidth(currentContext,
                       5.0f);

/* Stroke and fill the path on the context */
CGContextDrawPath(currentContext,
                  kCGPathFillStroke);

/* Dispose of the path */
CGPathRelease(path);

/* Restore the state of the context */
CGContextRestoreGState(currentContext);
}

```

After running this program, you will notice that the results are exactly like those shown in [Figure 15-29](#).

See Also

XXX

15.11 Scaling Shapes Drawn on Graphic Contexts

Problem

You want to scale shapes on your graphics context up and down dynamically.

Solution

Create an affine scale transformation using the `CGAffineTransformMakeScale` function.

Discussion

[Recipe 15.10](#) explained what a transformation is, and how to apply it to shapes and graphics contexts. One of the transformations that you can apply is scaling. You can easily ask Core Graphics to scale a shape, such as a circle, to 100 times its original size.

To create an affine scale transformation, use the `CGAffineTransformMakeScale` function, which returns a transformation object of type `CGAffineTransform`. If you want to apply a scale transformation directly to a graphics context, use the `CGContextScaleCTM` procedure to scale the Current Transformation Matrix (CTM). For more information about CTM, see [Recipe 15.10](#).

Scale transformation functions take two parameters: one to scale the x axis and the other to scale the y axis. Take another look at the rectangle in [Figure 15-21](#). If we want

to scale this rectangle to half its normal length and width, shown in [Figure 15-21](#), we can simply scale the x and the y axis by 0.5 (half their original value), as shown here:

```
/* Scale the rectangle to half its size */
CGAffineTransform transform =
    CGAffineTransformMakeScale(0.5f, 0.5f);

/* Add the rectangle to the path */
CGPathAddRect(path,
               &transform,
               rectangle);
```

[Figure 15-30](#) shows what we will see after applying the scale transformation to the code we wrote in [Recipe 15.7](#).




Figure 15-30. Scaling a rectangle

In addition to the `CGAffineTransformMakeScale` function, you can use the `CGContextScaleCTM` procedure to apply a scale transformation to a graphics context. The following code will achieve the exact same effect as the previous example, as you can see in [Figure 15-30](#):

```
- (void)drawRect:(CGRect)rect{  
    /* Create the path first. Just the path handle. */  
    CGMutablePathRef path = CGPathCreateMutable();
```

```

/* Here are our rectangle boundaries */
CGRect rectangle = CGRectMake(10.0f,
                              10.0f,
                              200.0f,
                              300.0f);

/* Add the rectangle to the path */
CGPathAddRect(path,
              NULL,
              rectangle);

/* Get the handle to the current context */
CGContextRef currentContext = UIGraphicsGetCurrentContext();

/* Scale everything drawn on the current
   graphics context to half its size */
CGContextScaleCTM(currentContext,
                  0.5f,
                  0.5f);

/* Add the path to the context */
CGContextAddPath(currentContext,
                 path);

/* Set the fill color to cornflower blue */
[[UIColor colorWithRed:0.20f
              green:0.60f
              blue:0.80f
              alpha:1.0f] setFill];

/* Set the stroke color to brown */
[[UIColor brownColor] setStroke];

/* Set the line width (for the stroke) to 5 */
CGContextSetLineWidth(currentContext,
                      5.0f);

/* Stroke and fill the path on the context */
CGContextDrawPath(currentContext,
                  kCGPathFillStroke);

/* Dispose of the path */
CGPathRelease(path);
}

```

See Also

XXX

15.12 Rotating Shapes Drawn on Graphic Contexts

Problem

You want to be able to rotate the contents that you have drawn on a graphics context without changing your drawing code.

Solution

Use the `CGAffineTransformMakeRotation` function to create an affine rotation transformation.

Discussion



I strongly suggest that you read the material in [Recipe 15.10](#) and in [Recipe 15.11](#) before proceeding with this section. To avoid redundancy of material, I have tried to keep material that has been taught in earlier sections out of later sections.

Just like scaling and translation, you can apply rotation translation to shapes drawn on paths, and graphics contexts. You can use the `CGAffineTransformMakeRotation` function and pass the rotation value in radians to get back a rotation transformation, of type `CGAffineTransform`. You can then apply this transformation to paths and shapes. If you want to rotate the whole context by a specific angle, you must use the `CGContextRotateCTM` procedure.

Let's rotate the same rectangle we had in [Figure 15-21](#) 45 degrees clockwise (see [Figure 15-31](#)). The values you supply for rotation must be in radians. Positive values cause clockwise rotation, while negative values cause counterclockwise rotation:

```
/* Rotate the rectangle 45 degrees clockwise */
CGAffineTransform transform =
CGAffineTransformMakeRotation((45.0f * M_PI) / 180.0f);

/* Add the rectangle to the path */
CGPathAddRect(path,
               &transform,
               rectangle);
```




Figure 15-31. Rotating a rectangle

As we saw in [Recipe 15.11](#), we can also apply a transformation directly to a graphics context using the `CGContext RotateCTM` procedure.

See Also

XXX

15.13 Animating and Moving Views

Problem

You want to animate the displacement of views.

Solution

Use the animation methods of `UIView` while displacing your views.

Discussion

There are various ways of performing animations in iOS: capabilities are provided at a relatively low level, but also at a higher level. The highest level we can get is through UIKit, which is what we will be discussing in this section. UIKit includes some low-level Core Animation functionalities and presents us with a really clean API to work with.

The starting point for performing animations in UIKit is to call the `beginAnimations:context:` class method of the `UIView` class. Its first parameter is an optional name that you choose for your animation, and the second is an optional context that you can retrieve later to pass to delegate methods of the animations. We will talk about these shortly.

After you start an animation with the `beginAnimations:context:` method, it won't actually take place until you call the `commitAnimations` class method of `UIView` class. The calculation you perform on a view object (such as moving it) between calling `beginAnimations:context:` and `commitAnimations` will be animated after the `commitAnimations` call. Let's have a look at an example.

As we saw in [Recipe 15.4](#), I included in my bundle an image called *Xcode.png*. This is Xcode's icon, which I found by searching in Google Images (see [Figure 15-14](#)). Now, in my view controller (see [Recipe 15.0](#)), I want to place this image in an image view of type `UIImageView` and then move that image view from the top-left corner of the screen to the bottom-right corner.

Here are the steps that complete this task:

1. Open the *.h* file of your view controller.
2. Define an instance of `UIImageView` as a property of the view controller, and call it `xcodeImageView`, like so:

```
#import <UIKit/UIKit.h>

@interface Animating_and_Moving_ViewsViewController : UIViewController

@property (nonatomic, strong) UIImageView *xcodeImageView;

@end
```


3. In the *.m* file of your view controller, synthesize the image view you created in the previous step and make sure you dispose of it when the time comes:

```
#import "Animating_and_Moving_ViewsViewController.h"

@implementation Animating_and_Moving_ViewsViewController

@synthesize xcodeImageView;

- (void)viewDidUnload{
    [super viewDidUnload];
    self.xcodeImageView = nil;
}

...
```

4. Load the *Xcode.png* image into an instance of *UIImageView* when your view is loaded:

```
- (void) viewDidLoad{
    [super viewDidLoad];

    UIImage *xcodeImage = [UIImage imageNamed:@"Xcode.png"];

    self.xcodeImageView = [[UIImageView alloc]
                           initWithImage:xcodeImage];

    /* Just set the size to make the image smaller */
    [self.xcodeImageView setFrame:CGRectMake(0.0f,
                                             0.0f,
                                             100.0f,
                                             100.0f)];

    self.view.backgroundColor = [UIColor whiteColor];
    [self.view addSubview:self.xcodeImageView];
}
```

5. [Figure 15-32](#) shows how our view will look when we run our program in iOS Simulator.



Figure 15-32. Adding an image view to a view object

6. Now when our view appears on the screen, in the `viewDidAppear:` instance method of our view controller, we will start the animation block for our image view and start an animation that moves the image from its initial location at the top-left corner of the screen to the bottom-right corner. We will make sure this animation happens over a 5-second time period:

```
- (void) viewDidAppear:(BOOL)paramAnimated{  
    [super viewDidAppear:paramAnimated];  
}
```

```

/* Start from top left corner */
[self.xcodeImageView setFrame:CGRectMake(0.0f,
                                         0.0f,
                                         100.0f,
                                         100.0f)];

[UIView beginAnimations:@"xcodeImageViewAnimation"
      context:(__bridge void *)self.xcodeImageView];

/* 5 seconds animation */
[UIView setAnimationDuration:5.0f];

/* Receive animation delegates */
[UIView setAnimationDelegate:self];

[UIView setAnimationDidStopSelector:
 @selector(imageViewDidStop:finished:context:)];

/* End at the bottom right corner */
[self.xcodeImageView setFrame:CGRectMake(200.0f,
                                         350.0f,
                                         100.0f,
                                         100.0f)];

[UIView commitAnimations];
}

```

7. Provide the implementation for a `imageViewDidStop:finished:context:` delegate method for your view controller so that it gets called by UIKit when the animation finishes. This is optional, and for our example I will just log some messages to prove that the method was called. Later examples will show how you can use the method to kick off other activity the moment the animation is finished:

```

- (void)imageViewDidStop:(NSString *)paramAnimationID
    finished:(NSNumber *)paramFinished
    context:(void *)paramContext{

    NSLog(@"Animation finished.");

    NSLog(@"Animation ID = %@", paramAnimationID);

    UIImageView *contextImageView = (__bridge UIImageView *)paramContext;
    NSLog(@"Image View = %@", contextImageView);

}

```

Now if you run the app, you will notice that as soon as your view gets displayed, the image shown in [Figure 15-32](#) will start moving towards the bottom-right corner, as shown in [Figure 15-33](#), over a period of 5 seconds.



Figure 15-33. The image is animated to the bottom-right corner of the screen

Also, if you look at the output printed to the console, you will see something similar to this if you wait for the animation to finish:

```
Animation finished.  
Animation ID = xcodeImageViewAnimation  
Image View = <UIImageView: 0x68221a0;  
    frame = (200 350; 100 100);  
    opaque = NO;  
    userInteractionEnabled = NO;  
    layer = <CALayer: 0x68221d0>>
```

Now let's go through some of the concepts and how we actually animated this image view. Here are the important class methods of `UIView` that you should know about when performing animations using `UIKit`:

`beginAnimations:context:`

Starts an animation block. Any animatable property change that you apply to views after calling this class method will be animated after the animation is committed.

`setAnimationDuration:`

Sets the duration of the animation in seconds.

`setAnimationDelegate:`

Sets the object that will receive delegate objects for various events that could happen before, during, or after the animation. Setting a delegate object will *not* immediately start firing animation delegates. You must also use different setter class methods on the view object to tell `UIKit` which selectors in your delegate object have to receive which delegate messages.

`setAnimationDidStopSelector:`

Sets the method in the delegate object that has to be called when the animation finishes. This method has to accept three parameters in this order:

1. An animation identifier of type `NSString`: this will contain the animation identifier passed to the `beginAnimations:context:` class method of `UIView` when the animation was started.
2. A “finished” indicator, of type `NSNumber`: this parameter contains a boolean value inside the `NSNumber`, which the run-time sets to YES if it could fully finish the animation before it was stopped by the code. If this value is set to NO, it means the animation was interrupted before it was completed.
3. A context of type `void *`: this is the context that was passed to the `beginAnimations:context:` class method of `UIView` when the animation was started.

`setAnimationWillStartSelector:`

Sets the selector that has to be called in the delegate object when the animation is about to start. The selector passed to this class method has to have two parameters, in this order:

1. An animation identifier of type `NSString`: the runtime sets this to the animation identifier passed to the `beginAnimations:context:` class method of `UIView` when the animation was started.
2. A context of type `void *`: this is the context that was passed to the `beginAnimations:context:` class method of `UIView` when the animation was started.

`setAnimationDelay:`

Sets a delay (in seconds) for the animation before it starts. If this value is set to 3.0f, for instance, the animation will start 3 seconds after it has been committed.

`setAnimationRepeatCount:`

Sets the number of times an animation block has to repeat its animation.

Now that we know some of the most useful `UIView` class methods that help us animate views, let's look at another animation. In this example code, I want to have two image views, both displaying the same image, to appear on the screen at the same time: one at the top-left corner and the other at the bottom-right corner, as shown in [Figure 15-34](#).



Figure 15-34. The starting position of the animation



In this section, I will call the top-left image *image 1* and the bottom-right image *image 2*.

What we are going to do in this code is create two images, as mentioned, in the top-left and bottom-right corners. Next, we want *image 1* to start moving towards *image 2* over a 3-second period, and then fade away. While *image 1* is approaching *image 2*, we want *image 2* to start its animation and move towards the top-left corner of the screen, where *image 1* used to be. We also want *image 2* to complete its animation over a 3-second time period, and fade away at the end. This will look *really* cool when you run it on a device or the iOS Simulator. Let me show you how to code it:

1. In the *.h* file of your view controller, define two image views:

```
#import <UIKit/UIKit.h>

@interface Animating_and_Moving_ViewsViewController : UIViewController

@property (nonatomic, strong) UIImageView *xcodeImageView1;
@property (nonatomic, strong) UIImageView *xcodeImageView2;

@end
```

2. In the *.m* file of the view controller, make sure that you synthesize these two image views, because they are properties.

```
#import "Animating_and_Moving_ViewsViewController.h"

@implementation Animating_and_Moving_ViewsViewController

@synthesize xcodeImageView1;
@synthesize xcodeImageView2;

...
```

3. Make sure you deallocate both image views when the view is unloaded:

```
- (void)viewDidUnload{
    [super viewDidUnload];
    self.xcodeImageView1 = nil;
    self.xcodeImageView2 = nil;
}
```

4. In the *viewDidLoad* instance method of your view controller, initialize both of the image views and place them on your view:

```
- (void) viewDidLoad{
    [super viewDidLoad];

    UIImage *xcodeImage = [UIImage imageNamed:@"Xcode.png"];

    self.xcodeImageView1 = [[UIImageView alloc]
```

```

        initWithImage:xcodeImage];

self.xcodeImageView2 = [[UIImageView alloc]
    initWithImage:xcodeImage];

/* Just set the size to make the images smaller */
[xcodeImageView1 setFrame:CGRectMake(0.0f,
    0.0f,
    100.0f,
    100.0f)];

[xcodeImageView2 setFrame:CGRectMake(220.0f,
    350.0f,
    100.0f,
    100.0f)];

self.view.backgroundColor = [UIColor whiteColor];
[self.view addSubview:self.xcodeImageView1];
[self.view addSubview:self.xcodeImageView2];
}

```

5. Implement an instance method called `startTopLeftImageViewAnimation` for your view controller. This method, as its name suggests, will carry out the animation for *image 1*, moving it from the top-left corner of the screen to the bottom-right corner while fading it out. Fading is accomplished simply by setting the alpha value to 0:

```

- (void) startTopLeftImageViewAnimation{

    /* Start from top left corner */
    [self.xcodeImageView1 setFrame:CGRectMake(0.0f,
        0.0f,
        100.0f,
        100.0f)];

    [self.xcodeImageView1 setAlpha:1.0f];

    [UIView beginAnimations:@"xcodeImageView1Animation"
        context:(__bridge void *)self.xcodeImageView1];

    /* 3 seconds animation */
    [UIView setAnimationDuration:3.0f];

    /* Receive animation delegates */
    [UIView setAnimationDelegate:self];

    [UIView setAnimationDidStopSelector:
        @selector(imageViewDidStop:finished:context:)];

    /* End at the bottom right corner */
    [self.xcodeImageView1 setFrame:CGRectMake(220.0f,
        350.0f,
        100.0f,

```



```
100.0f)];
```

```
[self.xcodeImageView1 setAlpha:0.0f];
```

```
[UIView commitAnimations];
```

```
}
```

6. When the animation for any of these image views stops, we intend to remove those image views from their parent views, as they are not useful anymore. As we saw in the `startTopLeftImageViewAnimation` method, we passed a delegate selector to the `setAnimationDidStopSelector:` class method of `UIView`, and this selector will get called when the animations for *image 1* (as we saw before) and for *image 2* (as we will soon see) stop. Here is the implementation for this delegate selector:

```
- (void)imageViewDidStop:(NSString *)paramAnimationID
    finished:(NSNumber *)paramFinished
    context:(void *)paramContext{

    UIImageView *contextImageView = (__bridge UIImageView *)paramContext;
    [contextImageView removeFromSuperview];

}
```

7. We also need a method that will animate *image 2*. There is a little difference between how I've written the animation method for *image 2* as compared to that for *image 1*. I want to be able to start *image 2*'s animation *almost* as *image 1* is finishing its animation. So if *image 1* performs its animation in 3 seconds, I want *image 2* to start its animation at second 2.0 in *image 1*'s animation, so that I can see *image 2* starting to animate before *image 1* gets to the bottom right of the screen and fades away. To accomplish this, I am starting both animations at the same time, but the animation for *image 2* will include a 2-second delay at the beginning. So if I start both animations at 1 p.m., *image 1* will start its animation at 13:00:00 and finish it at 13:00:03, while *image 2* starts at 13:00:02 and finishes at 13:00:05. Here is how we will animate *image 2*:

```
- (void) startBottomRightViewAnimationAfterDelay:(CGFloat)paramDelay{

    /* Start from bottom right corner */
    [self.xcodeImageView2 setFrame:CGRectMake(220.0f,
                                              350.0f,
                                              100.0f,
                                              100.0f)];

    [self.xcodeImageView2 setAlpha:1.0f];

    [UIView beginAnimations:@"xcodeImageView2Animation"
        context:(__bridge void *)self.xcodeImageView2];

    /* 3 seconds animation */
    [UIView setAnimationDuration:3.0f];
```

```

[UIView setAnimationDelay:paramDelay];

/* Receive animation delegates */
[UIView setAnimationDelegate:self];

[UIView setAnimationDidStopSelector:
 @selector(imageViewDidStop:finished:context:)];

/* End at the top left corner */
[self.xcodeImageView2 setFrame:CGRectMake(0.0f,
                                           0.0f,
                                           100.0f,
                                           100.0f)];

[self.xcodeImageView2 setAlpha:0.0f];

[UIView commitAnimations];
}

```

8. Last but not least, we have to fire both the `startTopLeftImageViewAnimation` and the `startBottomRightViewAnimationAfterDelay:` methods at the same time when our view becomes visible:

```

- (void) viewDidAppear:(BOOL)paramAnimated{

    [super viewDidAppear:paramAnimated];
    [self startTopLeftImageViewAnimation];
    [self startBottomRightViewAnimationAfterDelay:2.0f];

}

```

See Also

XXX

15.14 Animating and Scaling Views

Problem

You want to be able to animate the scaling up or down of your views.

Solution

Create a scale affine transformation for your view and use the `UIView` animation methods to animate the scale transformation.

Discussion



I highly recommend that you read [Recipe 15.13](#) before proceeding with this section of the book.

In order to scale a view while animating it, you can either apply a scale transformation to it within an animation block (see [Recipe 15.11](#)), or just increase the view’s width and/or height.

Let’s have a look at scaling an image view by applying a scale transformation to it:

```
- (void) viewWillAppear:(BOOL)paramAnimated{
    [super viewWillAppear:paramAnimated];

    /* Place the image view at the center of the view of this view controller */
    self.xcodeImageView.center = self.view.center;

    /* Make sure no translation is applied to this image view */
    self.xcodeImageView.transform = CGAffineTransformIdentity;

    /* Begin the animation */
    [UIView beginAnimations:nil
             context:NULL];

    /* Make the animation 5 seconds long */
    [UIView setAnimationDuration:5.0f];

    /* Make the image view twice as large in
       width and height */
    self.xcodeImageView.transform = CGAffineTransformMakeScale(2.0f,
                                                                2.0f);

    /* Commit the animation */
    [UIView commitAnimations];
}
```

This code uses an affine scale transformation to scale the image view to become twice as big as it originally was. The best thing about applying scale transformations to a view is that the width and height are scaled using the center of the view as the center of the scaling. Suppose that the center of your view is at point (100, 100) on the screen, and you scale your view to be twice as big in width and height. The resulting view will have its center remain at point (100, 100) on the screen, while being twice as big in each direction. If you were to scale a view by increasing its frame’s width and height explicitly, you would end up with the final view being located somewhere else on the screen. That’s because when changing the frame of the image view to scale the width and height, you are also changing the value of the *x* and the *y* of the frame, whether you want to or not. Because of that, your image view will not be scaled up from its center.

Fixing this issue is outside the scope of this book, but feel free to play with it for a while and maybe you will find the solution. One hint that I *will* give you is that you can run two animations at the same time in parallel: one for changing the width and height, and the other for changing the center of the image view!

See Also

XXX

15.15 Animating and Rotating Views

Problem

You want to animate the rotation of your views.

Solution

Create a rotation affine transform and use the animation methods of `UIView` to animate the rotation.

Discussion



I highly recommend that you read [Recipe 15.13](#) before proceeding with this section of the book.

In order to rotate a view while animating it, you must apply a rotation transformation to it while in an animation block (see [Recipe 15.11](#)). Let's have a look at some sample code which will make this clearer. Let's say we have an image named *Xcode.png* (see [Figure 15-14](#)), and we want to display it in the center of the screen. After the image is displayed, we want to rotate it 90 degrees over a 5-second time period and then rotate it back to its original orientation. So when our view appears on the screen, let's rotate the image view 90 degrees clockwise:

```
- (void) viewWillAppear:(BOOL)paramAnimated{
    [super viewWillAppear:paramAnimated];

    self.xcodeImageView.center = self.view.center;

    /* Begin the animation */
    [UIView beginAnimations:@"clockwiseAnimation"
        context:NULL];

    /* Make the animation 5 seconds long */
    [UIView setAnimationDuration:5.0f];
```

```

[UIView setAnimationDelegate:self];

[UIView setAnimationDidStopSelector:
 @selector(clockwiseRotationStopped:finished:context:)];

/* Rotate the image view 90 degrees */
self.xcodeImageView.transform =
CGAffineTransformMakeRotation((90.0f * M_PI) / 180.0f);

/* Commit the animation */
[UIView commitAnimations];
}

```

We've chosen the `clockwiseRotationStopped:finished:context:` selector to get called when the clockwise rotation animation finishes. In that method, we will be rotating the image view counterclockwise back to 0 degrees (where it originally was) over a 5-second time period:

```

- (void)clockwiseRotationStopped:(NSString *)paramAnimationID
    finished:(NSNumber *)paramFinished
    context:(void *)paramContext{

    [UIView beginAnimations:@"counterclockwiseAnimation"
        context:NULL];

    /* 5 seconds long */
    [UIView setAnimationDuration:5.0f];

    /* Back to original rotation */
    self.xcodeImageView.transform = CGAffineTransformIdentity;

    [UIView commitAnimations];
}

```

As you saw in [Recipe 15.13](#), [Recipe 15.14](#), and in this section, there are many ways to animate views (direct or indirect subclasses of `UIView`) and many properties that you can modify while carrying out your animations. Be creative and inspect other properties in `UIView` which you might have not previously known about. You may also want to take a look at the documentation for `UIView` in Xcode Organizer.

See Also

XXX

Core Motion

16.0 Introduction

iOS devices such as the iPhone and iPad are usually equipped with accelerometer hardware. Some iOS devices might also include a gyroscope, such as the iPhone 4 and iPad 2. Before attempting to use either the accelerometer or the gyroscope in your iOS applications, you must check the availability of these sensors on the iOS device on which your app runs. [Recipe 16.1](#) and [Recipe 16.2](#) include techniques you can use to detect the availability of the accelerometer and gyroscope. With a gyroscope, iOS devices such as the iPhone 4 and iPad 2 are able to detect motion in six axes.

Let's set up a simple example you can try out to see the value of the gyroscope. The accelerometer cannot detect the rotation of the device around its vertical axis if you are holding the device perfectly still in your hands, sitting in a computer chair, and rotating your chair in a clockwise or counterclockwise fashion. From the standpoint of the floor or the Earth, the device is rotating around the vertical axis, but it's not rotating around its own y-axis, which is the vertical center of the device. So, the accelerometer does not detect any motion.

However, the gyroscope included in some iOS devices allows us to detect such movements. This allows more fluid and flawless movement detection routines. This is typically useful in games, where the developers need to know not only whether the device is moving on the x-, y-, and z-axes—information they can get from the accelerometer—but also whether it is changing in relation to the Earth along these directions, which requires a gyroscope.

Programmers can use the Core Motion framework to access both the accelerometer and the gyroscope data (if available). All recipes in this chapter make use of the Core Motion framework. Please follow these steps to add this framework to your project:

1. Click on your project icon in Xcode.
2. Select your target to which you want to add the Core Motion framework.
3. On the top of the screen, select the Build Phases tab.

4. Under Build Phases, find and expand the Link Binary with Libraries box and press the little + button on its bottom left corner.
5. In the list of frameworks, select the CoreMotion.framework and press the Add button (see [Figure 16-1](#).)




Figure 16-1. Adding the Core Motion framework to a target

iOS Simulator does not simulate the accelerometer or the gyroscope hardware. However, you can generate a *shake* with iOS Simulator using Hardware→Shake Gesture (see [Figure 16-2](#)).




Figure 16-2. The Shake Gesture option in iOS Simulator

16.1 Detecting the Availability of an Accelerometer

Problem

In your program, you want to detect whether the accelerometer hardware is available.

Solution

Use the `isAccelerometerAvailable` method of `CMMotionManager` to detect the accelerometer hardware. The `isAccelerometerActive` method can also be used to detect whether the accelerometer hardware is currently sending updates to the program.

Let's first make sure we have imported the required header files:

```
#import <UIKit/UIKit.h>
#import <CoreMotion/CoreMotion.h>

@interface Detecting_the_Availability_of_an_AccelerometerAppDelegate
    : UIResponder <UIApplicationDelegate>

@property (strong, nonatomic) UIWindow *window;

@end
```

Then we will go on and detect the availability of accelerometer in the implementation file of our app delegate:

```

- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    CMMotionManager *motionManager = [[CMMotionManager alloc] init];

    if ([motionManager isAccelerometerAvailable]){
        NSLog(@"Accelerometer is available.");
    } else{
        NSLog(@"Accelerometer is not available.");
    }

    if ([motionManager isAccelerometerActive]){
        NSLog(@"Accelerometer is active.");
    } else {
        NSLog(@"Accelerometer is not active.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```

Accelerometer hardware might be available on the iOS device that is running your program. This, however, does not mean the accelerometer hardware is sending updates to your program. If the accelerometer or gyroscope is sending updates to your program, we say it is *active*, which requires you to define a delegate object, as we will soon see.

If you run this code on iOS Simulator, you will get values similar to these in the console window:

```

Accelerometer is not available.
Accelerometer is not active.

```

Running the same code on an iPhone 4 device, you will get values similar to these:

```

Accelerometer is available.
Accelerometer is not active.

```

Discussion

An iOS device could have a built-in accelerometer. As we don't know yet which iOS devices might have accelerometer hardware built into them and which ones won't, it is best to test the availability of the accelerometer before using it.

You can detect the availability of this hardware by instantiating an object of type `CMMotionManager` and accessing its `isAccelerometerAvailable` method. This method is of type `BOOL` and returns `YES` if the accelerometer hardware is available and `NO` if not.

In addition, you can detect whether the accelerometer hardware is currently sending updates to your application (whether it is active) by issuing the `isAccelerometerAc`

tive method of `CMMotionManager`. You will learn about retrieving accelerometer data in [Recipe 16.3](#).

See Also

[Recipe 16.3](#)

16.2 Detecting the Availability of a Gyroscope

Problem

You want to find out whether the current iOS device that is running your program has gyroscope hardware available.

Solution

Use the `isGyroAvailable` method of an instance of `CMMotionManager` to detect the gyroscope hardware. The `isGyroActive` method is also available if you want to detect whether the gyroscope hardware is currently sending updates to your program (in other words, whether it is active).

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    CMMotionManager *motionManager = [[CMMotionManager alloc] init];

    if ([motionManager isGyroAvailable]){
        NSLog(@"Gyro is available.");
    } else {
        NSLog(@"Gyro is not available.");
    }

    if ([motionManager isGyroActive]){
        NSLog(@"Gyro is active.");
    } else {
        NSLog(@"Gyro is not active.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

iOS Simulator does not have gyroscope simulation in place. If you run this code on the simulator, you will receive results similar to these in the console window:

```
Gyro is not available.
Gyro is not active.
```

If you run the same code on the original iPad, you will get the same results as you get from iOS Simulator. However, if you run this code on an iOS device with a gyroscope, such as the iPhone 4 or iPad 2, the results could be different:

```
Gyro is available.  
Gyro is not active.
```

Discussion

If you plan to release an application that makes use of the gyroscope, you must make sure other iOS devices without this hardware can run your application. If you are using the gyroscope as part of a game, for instance, you must make sure other iOS devices that are capable of running your application can play the game, although they might not have a gyroscope installed.

To achieve this, you must first instantiate an object of type `CMMotionManager`. After this, you must access the `isGyroAvailable` method (of type `BOOL`) and see whether the gyroscope is available on the device running your code. You can also use the `isGyroActive` method of the `CMMotionManager` instance to find out whether the gyroscope is currently sending your application any updates. For more information about this, please refer to [Recipe 16.5](#).

See Also

[Recipe 16.5](#)

16.3 Retrieving Accelerometer Data

Problem

You want to ask iOS to send accelerometer data to your application.

Solution

Use the `startAccelerometerUpdatesToQueue:withHandler:` instance method of `CMMotionManager`. Here is the header file of a view controller that utilizes `CMMotionManager` to get accelerometer updates:

```
#import <UIKit/UIKit.h>  
#import <CoreMotion/CoreMotion.h>  
  
@interface Retrieving_Accelerometer_DataViewController : UIViewController  
  
@property (nonatomic, strong) CMMotionManager *motionManager;  
  
@end
```

We will now implement our view controller and take advantage of the `startAccelerometerUpdatesToQueue:withHandler:` method of the `CMMotionManager` class:

```

#import "Retrieving_Accelerometer_DataViewController.h"

@implementation Retrieving_Accelerometer_DataViewController

@synthesize motionManager;

- (void)viewDidLoad{
    [super viewDidLoad];

    self.motionManager = [[CMMotionManager alloc] init];

    if ([self.motionManager isAccelerometerAvailable]){
        NSOperationQueue *queue = [[NSOperationQueue alloc] init];
        [self.motionManager
         startAccelerometerUpdatesToQueue:queue
         withHandler:^(CMAccelerometerData *accelerometerData, NSError *error) {
             NSLog(@"X = %.04f, Y = %.04f, Z = %.04f",
                   accelerometerData.acceleration.x,
                   accelerometerData.acceleration.y,
                   accelerometerData.acceleration.z);
         }];
    } else {
        NSLog(@"Accelerometer is not available.");
    }
}

- (void)viewDidUnload{
    [super viewDidUnload];
    self.motionManager = nil;
}

- (BOOL)shouldAutorotateToInterfaceOrientation
    :(UIInterfaceOrientation)interfaceOrientation{
    return YES;
}

@end

```

Discussion

The accelerometer reports three-dimensional data (three axes) that iOS reports to your program as *x*, *y*, and *z* values. These values are encapsulated in a `CMAcceleration` structure:

```

typedef struct {
    double x;
    double y;
    double z;
} CMAcceleration;

```

If you hold your iOS device in front of your face with the screen facing you in portrait mode:

- The x-axis runs from left to right at the horizontal center of the device with values ranging from -1 to +1 from left to right.
- The y-axis runs from bottom to top at the vertical center of the device with values ranging from -1 to +1 from bottom to top.
- The z-axis runs from the back of the device, through the device, toward you, with values ranging from -1 to +1 from back through to the front.

The best way to understand the values reported from the accelerometer hardware is by taking a look at a few examples. Here is one: let's assume you have your iOS device facing you with the bottom of the device pointing to the ground and the top pointing up. If you hold it perfectly still without tilting it in any specific direction, the values you have for the x-, y-, and z-axes at this moment will be (x: 0.0, y: -1.0, z: 0.0). Now try the following while the screen is facing you and the bottom of the device is pointing to the ground:

1. Turn the device 90 degrees clockwise. The values you have at this moment are (x: +1.0, y: 0.0, z: 0.0).
2. Turn the device a further 90 degrees clockwise. Now the top of the device must be pointing to the ground. The values you have at this moment are (x: 0.0, y: +1.0, z: 0.0).
3. Turn the device a further 90 degrees clockwise. Now the top of the device must be pointing to the left side. The values you have at this moment are (x: -1.0, y: 0.0, z: 0.0).
4. Finally, if you rotate the device a further 90 degrees clockwise, where the top of the device once again points to the sky and the bottom of the device points to the ground, the values will be as they were originally (x: 0.0, y: -1.0, z: 0.0).

So, from these values, we can conclude that rotating the device around the z-axis changes the x and y values reported by the accelerometer, but not the z value.

Let's conduct another experiment. Hold the device again while it's facing you with its bottom pointing to the ground and its top pointing to the sky. The values that a program will get from the accelerometer, as you already know, are (x: 0.0, y: -1.0, z: 0.0). Now try these movements:

1. Tilt the device backward 90 degrees around the x-axis so that its top will be pointing backward. In other words, hold it as though it is sitting faceup on a table. The values you get at this moment will be (x: 0.0, y: 0.0, z: -1.0).
2. Now tilt the device backward 90 degrees again so that its back is facing you, its top is facing the ground, and its bottom is facing the sky. The values you get at this moment will be (x: 0.0, y: 1.0, z: 0.0).
3. Tilt the device backward 90 degrees so that it's facing the ground with its back facing the sky and its top pointing toward you. The reported values at this moment will be (x: 0.0, y: 0.0, z: 1.0).

4. And finally, if you tilt the device one more time in the same direction, so the device is facing you and its top is facing the sky, the values you get will be the same values you started with.

Therefore, we can observe that rotating the device around the x-axis changes the values of the y- and z-axes, but not x. I encourage you to try the third type of rotation—around the y-axis (pointing from top to bottom)—and observe the changes in the values reported for the x- and the z-axes.

To be able to receive accelerometer updates, you have two options:

1. The `startAccelerometerUpdatesToQueue:withHandler:` instance method of `CMMotionManager`

This method will deliver accelerometer updates on an operation queue (of type `NSOperationQueue`) and will require a basic knowledge of blocks that are used extensively in Grand Central Dispatch (GCD). For more information about blocks, please refer to [Chapter 5](#).

2. The `startAccelerometerUpdates` instance method of `CMMotionManager`

Once you call this method, the accelerometer (if available) will start updating accelerometer data in the motion manager object. You need to set up your own thread to continuously read the value of the `accelerometerData` property (of type `CMAccelerometerData`) of `CMMotionManager`.

In this recipe, we are using the first method (with blocks). I highly recommend that you read [Chapter 5](#) first before proceeding with this recipe. The block we provide to the `startAccelerometerUpdatesToQueue:withHandler:` instance method of `CMMotionManager` must be of type `CMAccelerometerHandler`:

```
typedef void (^CMAccelerometerHandler)
(CMAccelerometerData *accelerometerData, NSError *error);
```

In other words, we must accept two parameters on the block. The first one must be of type `CMAccelerometerData` and the second must be of type `NSError`, as implemented in our example code.

See Also

[Recipe 16.1](#)

16.4 Detecting Shakes on an iOS Device

Problem

You want to know when the user shakes an iOS device.

Solution

Use the `motionEnded:withEvent:` method of your app's window object.

Discussion

The `motionEnded:withEvent:` method of your app's window will get called whenever a motion has been captured by iOS. The simplest implementation of this method is this:

```
- (void) motionEnded:(UIEventSubtype)motion
    withEvent:(UIEvent *)event{

    /* Do something with the motion */

}
```

The `motion` parameter, as you can see, is of type `UIEventSubtype`. One of the values of type `UIEventSubtype` is `UIEventSubtypeMotionShake` which is what we are interested in. As soon as we detect this event, we know that the user has shaken her iOS device. In order to get to our app's window though, we need to subclass `UIWindow`. To do so, follow these steps:

1. In Xcode, while you have your project opened, go to `File→New File`.
2. From the left hand side, make sure iOS is the main category and Cocoa Touch is the sub category.
3. In the list on the right hand side, select Objective-C class and then press Next, as shown in [Figure 16-3](#).



Figure 16-3. Creating a new Objective-C class for our window

4. Now make sure that you are subclassing `UIWindow` and then press Next, as shown in [Figure 16-4](#).




Figure 16-4. Subclassing UIWindow

5. In this screen, set the file name to *MyWindow* and press the Save button, as shown in [Figure 16-5](#).




Figure 16-5. Saving the class file

Now that we have our window class, let's go to our app delegate and make sure that the app delegate's window object is an instance of our class, `MyWindow`:

```
#import "Detecting_Shakes_on_an_iOS_DeviceAppDelegate.h"
#import "Detecting_Shakes_on_an_iOS_DeviceViewController.h"
#import "MyWindow.h"

@implementation Detecting_Shakes_on_an_iOS_DeviceAppDelegate

@synthesize window = _window;
@synthesize viewController = _viewController;

- (BOOL)application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    self.window = [[MyWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    UIUserInterfaceIdiom device = [[UIDevice currentDevice] userInterfaceIdiom];

    if (device == UIUserInterfaceIdiomPhone) {

        self.viewController =
        [[Detecting_Shakes_on_an_iOS_DeviceViewController alloc]
         initWithNibName:@"Detecting_Shakes_on_an_iOS_DeviceViewController_iPhone"
         bundle:nil];
```

```

    } else {
        self.viewController =
            [[Detecting_Shakes_on_an_iOS_DeviceViewController alloc]
             initWithNibName:@"Detecting_Shakes_on_an_iOS_DeviceViewController_iPad"
             bundle:nil];
    }

    self.window.rootViewController = self.viewController;
    [self.window makeKeyAndVisible];
    return YES;
}

```

Now let's go to the implementation of the `MyWindow` class and handle the `motionEnded:withEvent:` method:

```

#import "MyWindow.h"

@implementation MyWindow

- (void) motionEnded:(UIEventSubtype)motion
  withEvent:(UIEvent *)event{

    if (motion == UIEventSubtypeMotionShake){
        NSLog(@"Detected a shake");
    }

}

@end

```

If you now simulate a shake event even if you are on iOS Simulator (see [Recipe 16.0](#)), you will see that our window will print the text *Detected a shake* to the console window.

16.5 Retrieving Gyroscope Data

Problem

You want to be able to retrieve information about the device's motion from the gyroscope hardware on an iOS device.

Solution

Follow these steps:

1. Find out whether the gyroscope hardware is available on the iOS device. Please refer to [Recipe 16.2](#) for directions on how to do this.
2. If the gyroscope hardware is available, make sure it is not sending you updates already. Please refer to [Recipe 16.2](#) for directions.

3. Use the `setGyroUpdateInterval:` instance method of `CMMotionManager` to set the number of updates you want to receive per second. For instance, for 20 updates per second (one second), set this value to `1.0/20.0`.
4. Invoke the `startGyroUpdatesToQueue:withHandler:` instance method of `CMMotionManager`. The queue object could simply be the main operation queue (as we will see later) and the handler block must follow the `CMGyroHandler` format.

The following code implements these steps:

```
- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    CMMotionManager *manager = [[CMMotionManager alloc] init];

    if ([manager isGyroAvailable]){

        if ([manager isGyroActive] == NO){

            [manager setGyroUpdateInterval:1.0f / 40.0f];

            NSOperationQueue *queue = [[NSOperationQueue alloc] init];

            [manager
             startGyroUpdatesToQueue:queue
             withHandler:^(CMGyroData *gyroData, NSError *error) {

                NSLog(@"Gyro Rotation x = %.04f", gyroData.rotationRate.x);
                NSLog(@"Gyro Rotation y = %.04f", gyroData.rotationRate.y);
                NSLog(@"Gyro Rotation z = %.04f", gyroData.rotationRate.z);

            }];
        } else {
            NSLog(@"Gyro is already active.");
        }

    } else {
        NSLog(@"Gyro isn't available.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
                    [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}
```

Discussion

With `CMMotionManager`, application programmers can attempt to retrieve gyroscope updates from iOS. You must first make sure the gyroscope hardware is available on the iOS device on which your application is running (please refer to [Recipe 16.2](#)). After doing so, you can call the `setGyroUpdateInterval:` instance method of `CMMotionManager`.

`ager` to set the number of updates you would like to receive per second on updates from the gyroscope hardware. For instance, if you want to be updated N times per second, set this value to $1.0/N$.

After you set the update interval, you can call the `startGyroUpdatesToQueue:withHandler:` instance method of `CMMotionManager` to set up a handler block for the updates. For more information about blocks, please refer to [Chapter 5](#). Your block object must be of type `CMGyroHandler`, which accepts two parameters:

`gyroData`

The data that comes from the gyroscope hardware, encompassed in an object of type `CMGyroData`. You can use the `rotationRate` property of `CMGyroData` (a structure) to get access to the x , y , and z values of the data, which represent all three Euler angles known as roll, pitch, and yaw. You can learn more about these by reading about flight dynamics.

`error`

An error of type `NSError` that might occur when the gyroscope is sending us updates.

If you do not wish to use block objects, you must call the `startGyroUpdates` instance method of `CMMotionManager` instead of the `startGyroUpdatesToQueue:withHandler:` instance method, and set up your own thread to read the gyroscope hardware updates that are posted to the `gyroData` property of the instance of `CMMotionManager` you are using.

See Also

[Recipe 16.2](#)

17.0 Introduction

iCloud is Apple's cloud infrastructure. A cloud is a name given to a service that stores information on a centralized location, where the user cannot physically access the disk/memory that stores the information. For instance, an iCloud storage space could be allocated by Apple in California and all iPhone devices in New York could have all their iCloud traffic go to the California's iCloud data center.

The purpose of using iCloud from a programmer's perspective is to give their users the ability to seamlessly have their apps' data transferred from one machine to the other. Let's have a look at a real life example of when iCloud would come in very handy: imagine there that you have developed a game called GameXYZ. Sarah is a hypothetical user of your game and she has purchased it through the App Store. Your game is a universal app and hence can be run on both the iPhone and the iPad. It just happens that Sarah has an iPad and an iPhone and she has installed your game on both her devices. She is at home playing your game and she is at level 12. She goes back home now and picks up her iPad to play the game just to see that your game starts from level 1 on her iPad because she has been playing it on her iPhone all along. This is definitely not a pretty situation. What is better is for your game to be intelligent enough to save its state and resume that state when your users start the game, regardless on which device they have been running the game. To handle this situation, you could use iCloud to store the Sarah's game state on her iPhone and let iCloud synchronize this data to the data-centers that are maintained by Apple. When she picks her iPad up, you could use your app to contact iCloud and find out if there is a recent game state saved for Sarah. If yes, then you can load that state for her to give her the feeling that she really didn't even leave your game. She just switched devices. This is a bit more work for you but at the end you will get really happy customers.

Before being able to use iCloud services, you first need to enable your app for iCloud. This requires creating the correct provisioning profiles in iOS Provisioning Portal and then enabling the correct entitlements in your project. You can read more about this in [Recipe 17.1](#).



I use the terms "folder" and "directory" interchangeably throughout this chapter.

17.1 Setting Up Your App For iCloud

Problem

You want to start using iCloud in your apps and you would like to know how you should set up your Xcode project.

Solution

Follow these steps to enable iCloud storage in your app:

1. Create an app in Xcode and set its bundle identifier using a reverse-domain style. For instance, *com.pixolity.Setting-Up Your-App-For-iCloud*.
2. Using the iOS Provisioning Portal, create a new App ID for your app.
3. In iOS Provisioning Portal, create a new Ad Hoc, App Store and Development provisioning profile and make sure they are linked to your new App ID.
4. Select your target in Xcode and set the appropriate provisioning profiles for different schemes, such as Debug, Release, etc.
5. In Xcode, select your target and in the Summary tab, scroll down to the Entitlements section and enable entitlements for your target. This will prepopulate the relevant iCloud storage entitlements for you.

Discussion

To enable iCloud for an app, you need to do a bit of a setting-up. The high level requirement was described in the Solution section but let's now go into details about what we really need to do:

1. Open Xcode and from the File menu select New→New Project...
2. On the left hand side of the New Project dialog, make sure iOS is the main category and Application is the sub-category. From the list that now appears on the right hand side of the New Project dialog, choose Empty Application and press the Next button (see [Figure 17-1](#)).




Figure 17-1. Creating an Empty Application to use with iCloud storage

3. In this screen (see [Figure 17-2](#)), set the Product Name to *Setting Up Your App For iCloud* and set the Company Identifier to the reverse domain-name of your company name. For instance, I have set this value to *com.pixolity*. If your company name is XYZ, then you set this value to *com.XYZ*. Once you are done and your settings look like those shown in [Figure 17-2](#), press the Next button.




Figure 17-2. Setting the product name and company identifier for a new iCloud app

4. Now you are asked to save your project. Simply save the project on disk or wherever that you wish. Once done, press the Create button.
5. We now need to create our App ID in iOS Provisioning Portal. Login to the [iOS Dev Center](#) and from the menus, select the iOS Provisioning Portal.
6. In the provisioning portal, select the App IDs option and then press the New APP ID button.
7. In the Description field (see [Figure 17-3](#)), enter *Setting Up Your App For iCloud*. In the Bundle Seed ID (App ID Prefix), select the Use Team ID option. In the Bundle Identifier (App ID Suffix) box, choose *com.TEAM ID.Setting-Up-Your-App-For-iCloud* where *TEAM ID* is your company name. For instance, for me this would be *com.pixolity.Setting-Up-Your-App-For-iCloud*. Once you are done, press the Submit button.

Create App ID

Description

Enter a common name or description of your App ID using alphanumeric characters. The description you specify will be used throughout the Provisioning Portal to identify this App ID.

You cannot use special characters as @, &, *, " in your description.

Bundle Seed ID (App ID Prefix)

Use your Team ID or select an existing Bundle Seed ID for your App ID.

Use Team ID

If you are creating a suite of applications that will share the same Keychain access, use the same bundle Seed ID for each of your application's App IDs.

Bundle Identifier (App ID Suffix)

Enter a unique identifier for your App ID. The recommended practice is to use a reverse-domain name style string for the Bundle Identifier portion of the App ID.

Example: com.domainname.appname

Cancel

Submit

Figure 17-3. Setting up a new App ID for our iCloud app

- You are now back in the provisioning portal. Select the Provisioning item from the menu and then under the Development tab, select the New Profile button.
- In the Profile Name field, enter *Setting Up Your App For iCloud Development*. In the Certificates field, check the box for the your Development Certificate. *In the App ID dropdown, select the Setting Up Your App For iCloud ID which we created earlier.* In the Devices section, select the devices which you would like to allow the development version of your app to run. After you are done, select the Submit button (see [Figure 17-4](#)).

The screenshot shows the 'Create iOS Development Provisioning Profile' interface. At the top, there are four tabs: 'Development' (selected), 'Distribution', 'History', and 'How To'. Below the tabs is the title 'Create iOS Development Provisioning Profile' and a subtext: 'Generate provisioning profiles here. All fields are required unless otherwise noted. To learn more, visit the [How To](#) section.'

The form contains the following fields:

- Profile Name:** A text input field containing 'Setting Up Your App For iCloud Developme'.
- Certificates:** A dropdown menu with a checkmark icon and the text 'Vandad Nahavandipoor'.
- App ID:** A dropdown menu with a checkmark icon and the text 'Setting Up Your App For iCloud'.
- Devices:** A section with a 'Deselect All' link and a list of devices with checkboxes:
 - ☐ Agusia iPhone
 - ☒ Vandad's iPhone4
 - ☒ Vandad's iPad

At the bottom right, there are two buttons: 'Cancel' and 'Submit'.

Figure 17-4. Creating a new Development provision profile for iCloud

10. Once our app goes through the development and testing process, we are going to want to submit it to the App Store so let's go ahead and create our App Store provisioning profile as well. In the Provisioning section of the iOS Provisioning Portal, select the Distribution tab and then press the New Profile button.
11. Set the Distribution Method to App Store. Set the Profile Name to *Setting Up Your App For iCloud App Store*. In the App ID dropdown, select the *Setting Up Your App For iCloud* ID which we created earlier. Once you are done, press the Submit button (see [Figure 17-5](#)).

Create iOS Distribution Provisioning Profile

Generate provisioning profiles here. All fields are required unless otherwise noted. To learn more, visit the [How To](#) section.

Distribution Method ☒ App Store ☐ Ad Hoc

Profile Name

Distribution Certificate **Pixolity Ltd.** (expiring on Dec 6, 2011)

App ID

Devices (optional) Select up to 100 devices for distributing the final application; the final application will run only on these selected devices.

[Select All](#)

☐ Agusia iPhone ☐ Vandad's iPad

☐ Vandad's iPhone4

Figure 17-5. Creating a new Distribution provision profile for iCloud

12. Navigate to the Development and then the Distribution tabs of the Provisioning section of the iOS Provisioning Portal screen and press the Download button on the Development and the App Store provisioning profiles that you just created.
13. Once you have downloaded the two provision profiles, drag and drop them into iTunes. iTunes will then automatically install these provision profiles for you.
14. In Xcode now, select your project file (with the blue icon) and then select your target and then choose the Build Settings tab. From the bar menu, make sure the All and the Combined options are selected, as shown in [Figure 17-6](#).




Figure 17-6. The Combined and All bar items should be selected in the Build Settings tab

1. Scroll down the Build Settings list until you get to the Code Signing section. In that section, for Debug, select the Development provision profile and for Release, select the App Store provision profile which we created earlier (see [Figure 17-7](#)).



If you cannot see these profiles in your list, it could be because you have not yet installed them. Downloading the profiles is not sufficient. You need to drag and drop the downloaded provision profiles into iTunes. iTunes will then install those profiles for you.



Figure 17-7. Setting the appropriate provisioning profiles for Debug and Release schemes

2. While you have your target selected, move from the Build Settings tab to the Summary tab (see [Figure 17-8](#)).




Figure 17-8. The Summary tab of our target

3. Scroll down in the Summary tab until you get to the Entitlements section. In that section, tick the Enable Entitlements checkbox and Xcode will automatically set the required entitlements values for iCloud for you.

Fantastic, we are now done. Our app is now set up for iCloud because of the entitlements and the provision profiles that we created earlier and used in the Build Settings of our target. Now it's time to start using iCloud in our apps. You can have a look at the

See Also

XXX

17.2 Storing and Synchronizing Dictionaries in iCloud

Problem

You want to store key-value data in dictionary form into iCloud and seamlessly read and write to this centralized and synchronized dictionary from various devices and from various iCloud accounts.

Solution

Use the `NSUbiquitousKeyValueStore` class.



The data that you store in iCloud using the `NSUbiquitousKeyValueStore` is uniquely created in iCloud using the provision profile using which you sign the app and the end-user's iCloud account. In other word, you simply store values in iCloud using the `NSUbiquitousKeyValueStore` class not worrying if one user's data is going to clash with another user's data. iCloud does that separation for you.

Discussion

The `NSUbiquitousKeyValueStore` class works very similar to the `NSUserDefaults` class. It can store strings, boolean, integer, float and other values. Each one of the values has to have a key associated with it. You will then be able to read the values by passing the keys to this class. The difference between the `NSUbiquitousKeyValueStore` and the `NSUserDefaults` class is that the former synchronizes its dictionary data with iCloud whereas the latter stores the dictionary only locally, to a `.plist` file and this data will be deleted once the app gets deleted from the user's device.



Before you can use the `NSUbiquitousKeyValueStore` class to store key-value data in iCloud, you must set up the appropriate entitlements for your project. Please refer to [Recipe 17.1](#) to learn how to do this.

An instance of your application uses a unique identifier to store data in the iCloud. This unique identifier is made out of three key pieces:

Team ID

This is the unique identifier for your iOS Developer Program. When you sign up for iOS Developer Program, Apple will automatically generate a unique identifier for your account. To retrieve this identifier, simply log into [Developer Center](#) and then select Your Account from the top menu items. Then choose Organization Profile from the menus on the left. On the screen to the right, your Team ID is displayed under the *Company/Organization ID* section. No two iOS Developer accounts can have the same Team ID.

Reverse domain-style of company identifier

This string is usually in the form of `com.COMPANYNAME` where `COMPANYNAME` is the name of your company and `APPNAME` is the name of your app. For instance, my company name is Pixolity so my reverse domain-style of company identifier will be `com.pixolity`.

App identifier and optional suffix

This is the string that gets attached as the suffix to the Reverse domain-style of company identifier. For instance *Storing and Synchronizing Dictionaries in iCloud* is the name of the product that I have created for this recipe. Once I fed this value to Xcode's project dialog when creating the project itself, the resulting string became *Storing-and-Synchronizing-Dictionaries-in-iCloud* since spaces are not allowed in the app identifier.



The Team ID is always bound to the provision profile using which you will sign your app. You do *not* have to enter this value into your project settings. For instance, if my company name is *Pixolity* and I set the reverse domain style name for my app to *com.pixolity* and my app ID to *Storing-and-Synchronizing-Dictionaries-in-iCloud*, the name that iCloud will use in the entitlements will be *\$(TeamIdentifierPrefix)com.pixolity.Storing-and-Synchronizing-Dictionaries-in-iCloud*. The *\$(TeamIdentifierPrefix)* value is the Team ID and that will be resolved to my actual Team ID when Xcode compiles my application and signs it with a provision profile.

Now that we are sure we have set up our project properly and entitlements are set up as well, then we can move on to using the `NSUbiquitousKeyValueStore` class to store keys and values in iCloud. There are various methods that `NSUbiquitousKeyValueStore` class exposes to us in order for us to save our values in iCloud. Some of these methods are listed and explained here:

setString:forKey:

Sets a string value for the given key. The string must be of type `NSString`. Obviously, classes that subclass `NSString`, such as `NSMutableString` can also be stored in iCloud using this method.

setArray:forKey:

Sets an array value for the given key. The array can be either a mutable or an immutable array.

setDictionary:forKey:

Sets a mutable or an immutable dictionary for the given key.

setBool:forKey:

Sets a boolean value of type `BOOL` for the given key.

setData:forKey:

Sets a mutable or an immutable data for the given key.

None of these methods will actually do the saving for you. If you are done setting the values, then you must call the `synchronize` method of `NSUbiquitousKeyValueStore` for your settings to be flushed first to iOS and then synchronized with iCloud.



All the work that we do with the `NSUbiquitousKeyValueStore` is done through the `defaultStore` class method of this class. This class method will return an instance of the `NSUbiquitousKeyValueStore` class which is ready for us to use.

Obviously, after setting the values for keys, we are going to want to retrieve those values at some point during the runtime of our app. We can do this using some of the methods that the `NSUbiquitousKeyValueStore` provides us with. Some of these methods are listed here:

stringForKey:

Returns the string associated with the given key or nil if that key cannot be found. This will be an immutable string even if you stored a mutable string into iCloud using this key.

arrayForKey:

Returns the array associated with the given key or nil if that key cannot be found. This will be an immutable array even if the original array that you stored into iCloud for this key was a mutable array.

dictionaryForKey:

Returns the dictionary associated with the given key or nil if that key cannot be found. The dictionary returned by this method will be immutable even if the original dictionary that you stored into iCloud for this key was a mutable dictionary.

boolForKey:

Returns the boolean value of type `BOOL` associated with the given key or nil if that key cannot be found.

dataForKey:

Returns the data of type `NSData` associated with the given key or nil if that key cannot be found. The data returned by this method will be immutable even if the original data stored in iCloud for this key was a mutable data.

So let's have a look at how we can perhaps use this class in our apps. Obviously as you already know, iCloud's power really proves handy when you are sharing data between two or more devices for the same user. So for instance, the user picks her iPhone up and reads a book up to page 40 and then she picks her iPad up and the app that presents the book can read the last page that she was at when she last read the book and opens the book from the same page. Two devices, pretending to be one, for the sake of usability for the end-user. For this example, we will store a string and a boolean value into iCloud using the `NSUbiquitousKeyValueStore` class. We will place a check to see if those values had already been stored in iCloud, if yes, we will read their value. So I can then build this app and run it on my iPhone and then on my iPad and see what happens:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{
```

```

NSMutableDictionary *kvoStore =
    [NSMutableDictionary dictionaryWithDictionary:defaultStore];

NSString *stringValue = @"My String";
NSString *stringValueKey = @"MyStringKey";

BOOL boolValue = YES;
NSString *boolValueKey = @"MyBoolKey";

BOOL mustSynchronize = NO;

if ([kvoStore objectForKey:stringValueKey] length] == 0){
    NSLog(@"Could not find the string value in iCloud. Setting...");
    [kvoStore setObject:stringValue
                forKey:stringValueKey];
    mustSynchronize = YES;
} else {
    NSLog(@"Found the string in iCloud, getting...");
    stringValue = [kvoStore objectForKey:stringValueKey];
}

if ([kvoStore objectForKey:boolValueKey] == NO){
    NSLog(@"Could not find the boolean value in iCloud. Setting...");
    [kvoStore setBool:boolValue
                forKey:boolValueKey];
    mustSynchronize = YES;
} else {
    NSLog(@"Found the boolean in iCloud, getting...");
    boolValue = [kvoStore objectForKey:boolValueKey];
}

if (mustSynchronize){
    if ([kvoStore synchronize]){
        NSLog(@"Successfully synchronized with iCloud.");
    } else {
        NSLog(@"Failed to synchronize with iCloud.");
    }
}

self.window = [[UIWindow alloc] initWithFrame:
    [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```

After setting up the correct provision profiles and enabling entitlements for this project and running this app on an iPhone that has already been set up with an iCloud account, we can observe these results printed to the console screen:

```

Could not find the string value in iCloud. Setting...
Could not find the boolean value in iCloud. Setting...
Successfully synchronized with iCloud.

```

Now, I will leave my iPhone sitting here for a minute or two just to make sure that iCloud has enough time to synchronize my data with the cloud. I will then run the same code on an iPad to see what happens:

```
Found the string in iCloud, getting...  
Found the boolean in iCloud, getting...
```

Fantastic. This demonstrates that iCloud is indeed synchronizing our data for users and their iOS devices which are hooked to the same iCloud account.

See Also

XXX

17.3 Creating and Managing Folders for Apps in iCloud

Problem

You want to store specific files into specific folders within the user's iCloud storage for your app.

Solution

Follow these steps:

1. Make sure your app is set up to use iCloud (see [Recipe 17.1](#))
2. Select your project file (with the blue icon) in Xcode and select the Summary tab.
3. In the Summary tab, scroll down until you get to the Entitlements section. Find the iCloud Containers list and copy the first value in that list. That value for the project that I have set up for this recipe is *com.pixolity.Creating-and-Managing-Folders-for-Apps-in-iCloud*. This value will be different for your app.
4. In your app delegate, place the string that you copied from iCloud Containers list, into a string. Prefix this string with your Team ID (see [Recipe 17.2](#) on how to find your Team ID).
5. Now instantiate an object of type `NSFileManager` and pass the path that you created in the previous two steps, to the `URLForUbiquityContainerIdentifier:` method of this class. The value of this method will be the *local* address for iCloud storage on the device that is running your app. Let's call this path *Root iCloud Path*.
6. Append the folder name that you want to create, to the Root iCloud Path (see previous step). Keep the resulting path in a string or an instance of `NSURL`.
7. Invoke the `fileExistsAtPath:isDirectory:` method of your file manager. If this method returns NO, then go on to create the folder using the `createDirectoryAtPath:withIntermediateDirectories:attributes:error:` method of the file manager. If the return value of the `fileExistsAtPath:isDirectory:` method is YES, check if the boolean value that comes out of the `isDirectory` parameter is NO. If it is NO,

then you must go on to create your folder again as instructed because the path that was found by the `fileExistsAtPath:isDirectory:` method was not a directory, but rather a file.

Discussion

One of the things that can make iCloud *sound* complicated to developers is that they assume, since it is a cloud storage, that they have to deal with URLs outside their apps or URLs on the internet. Well this is not true. With iCloud, the URLs that you deal with are actually iOS related URLs and by that I mean, the URLs are local to the device that is connected to iCloud. iCloud will then synchronize these local URLs and their data with the iCloud storage hosted by Apple on the cloud. The developer doesn't really have to worry about this part unless there is conflict that needs to be resolved because two devices using the same iCloud account running your app simultaneously modified a resource that cannot automatically be merged. We will talk about this later so let's just focus on creating folders in iCloud for now.

So let's now implement what we learned in the Solution section of this chapter:

```
- (BOOL) application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    NSFileManager *fileManager = [[NSFileManager alloc] init];

    /* Place your team ID here */
    NSString *teamID = @"TEAM ID";

    NSString *rootFolderIdentifier = [NSString stringWithFormat:
        @"%@.com.pixolity.Creating-and-Managing-Folders-for-Apps-in-iCloud",
        teamID];

    NSURL *containerURL =
        [fileManager URLForUbiquityContainerIdentifier:rootFolderIdentifier];

    NSString *documentsDirectory = [[containerURL path]
        stringByAppendingPathComponent:@"Documents"];

    BOOL isDirectory = NO;
    BOOL mustCreateDocumentsDirectory = NO;

    if ([fileManager fileExistsAtPath:documentsDirectory
        isDirectory:&isDirectory]){
        if (isDirectory == NO){
            mustCreateDocumentsDirectory = YES;
        }
    } else {
        mustCreateDocumentsDirectory = YES;
    }

    if (mustCreateDocumentsDirectory){
        NSLog(@"Must create the directory.");

        NSError *directoryCreationError = nil;
```

```

if ([fileManager createDirectoryAtPath:documentsDirectory
    withIntermediateDirectories:YES
    attributes:nil
    error:&directoryCreationError]){
    NSLog(@"Successfully created the folder.");
} else {
    NSLog(@"Failed to create the folder with error = %@",
        directoryCreationError);
}

} else {
    NSLog(@"This folder already exists.");
}

self.window = [[UIWindow alloc] initWithFrame:
    [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```



The Container Identifier that Xcode by default sets up for your application is made out of Team ID + Bundle Identifier. If you want, you can simply change this. One of the great features of iCloud for developers is that the container identifiers that you specify for your app's iCloud storage don't have to necessarily be linked in any way to your app or your app's bundle identifier. If you believe the default identifier is confusing, just change it to something that makes more sense to you and those who work with you in the same team.

What we can do now is to wrap our code into a method for re-use:

```

- (BOOL) createiCloudDirectory:(NSString *)paramDirectory
    recursiveCreation:(BOOL)paramRecursiveCreation
    teamID:(NSString *)paramTeamID
    iCloudContainer:(NSString *)paramContainer
    finalPath:(NSString **)paramFinalPath{

    BOOL result = NO;

    NSFileManager *fileManager = [[NSFileManager alloc] init];

    NSString *rootFolderIdentifier = [NSString stringWithFormat:
        @"%@.%@", paramTeamID, paramContainer];

    NSURL *containerURL =
        [fileManager URLForUbiquityContainerIdentifier:rootFolderIdentifier];

    NSString *documentsDirectory = [[containerURL path]
        stringByAppendingPathComponent:@"Documents"];

```

```

if (paramFinalPath != nil){
    *paramFinalPath = documentsDirectory;
}

BOOL isDirectory = NO;
BOOL mustCreateDocumentsDirectory = NO;

if ([fileManager fileExistsAtPath:documentsDirectory
    isDirectory:&isDirectory]){
    if (isDirectory == NO){
        mustCreateDocumentsDirectory = YES;
    }
} else {
    mustCreateDocumentsDirectory = YES;
}

if (mustCreateDocumentsDirectory){
    NSLog(@"Must create the directory.");

    NSError *directoryCreationError = nil;

    if ([fileManager createDirectoryAtPath:documentsDirectory
        withIntermediateDirectories:paramRecursiveCreation
        attributes:nil
        error:&directoryCreationError]){
        result = YES;
        NSLog(@"Successfully created the folder.");
    } else {
        NSLog(@"Failed to create the folder with error = %@",
            directoryCreationError);
    }
} else {
    NSLog(@"This folder already exists.");
    result = YES;
}

return result;
}

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    /* Place your Team ID here */
    NSString *teamID = @"TEAM ID";

    NSString *containerID =
@"com.pixolity.Creating-and-Managing-Folders-for-Apps-in-iCloud";

    NSString *documentsDirectory = nil;

    if ([self createiCloudDirectory:@"Documents"
        recursiveCreation:YES

```

```

        teamID:teamID
        iCloudContainer:containerID
        finalPath:&documentsDirectory]){
    NSLog(@"Successfully created the directory in %@", documentsDirectory);
} else {
    NSLog(@"Failed to create the directory.");
}

self.window = [[UIWindow alloc] initWithFrame:
               [[UIScreen mainScreen] bounds]];

self.window.backgroundColor = [UIColor whiteColor];
[self.window makeKeyAndVisible];
return YES;
}

```



The `finalPath` parameter in our new method is an out parameter meaning that it can store the final path of the directory that you requested to be created, into an output string, should you need it for any other method or anywhere in your app.

Ok, now that we have this method, we can go ahead and save a resource into the Documents folder for the current user's iCloud storage for our app:

```

- (BOOL)      application:(UIApplication *)application
didFinishLaunchingWithOptions:(NSDictionary *)launchOptions{

    /* Place your Team ID here */
    NSString *teamID = @"TEAM ID";

    NSString *containerID =
        @"com.pixolity.Creating-and-Managing-Folders-for-Apps-in-iCloud";

    NSString *documentsDirectory = nil;

    if ([self createiCloudDirectory:@"Documents"
        recursiveCreation:YES
        teamID:teamID
        iCloudContainer:containerID
        finalPath:&documentsDirectory]){
        NSLog(@"Successfully created the directory in %@", documentsDirectory);

        NSString *stringToSave = @"My String";

        NSString *pathToSave = [documentsDirectory
                                stringByAppendingPathComponent:@"MyString.txt"];

        NSError *savingError = nil;

        if ([stringToSave writeToFile:pathToSave
                                atomically:YES
                                encoding:NSUTF8StringEncoding
                                error:&savingError]){

```

```

        NSLog(@"Successfully saved the string in iCloud.");
    } else {
        NSLog(@"Failed to save the string with error = %@", savingError);
    }

    } else {
        NSLog(@"Failed to create the directory.");
    }

    self.window = [[UIWindow alloc] initWithFrame:
        [[UIScreen mainScreen] bounds]];

    self.window.backgroundColor = [UIColor whiteColor];
    [self.window makeKeyAndVisible];
    return YES;
}

```



Saving a file in a cloud URL does not explicitly tell iOS that the file has to be stored in the cloud storage. We will learn about saving files in the cloud storage in [Recipe 17.5](#).

If I run this app on an iPad that has been set up to backup data and files to an iCloud account, I can go to the Settings app and then select the iCloud option in the list. In the iCloud screen, I would then select Storage & Backup. Once in the Storage & Backup screen, select Manage Storage and you will be presented with a screen similar to that shown in [Figure 17-9](#).




Figure 17-9. The Documents and Data of our app is listed in the Settings app on the iPad

Now if you select your app from the list (our app is listed as Unknown, for reasons which we will go through later in this chapter), you can see a screen similar to that shown in [Figure 17-10](#).



Figure 17-10. Our string saved into the disk is indeed syncing with iCloud

See Also

XXX

17.4 Searching for Files and Folders in iCloud

Problem

You want to search for files and/or folders inside the current iCloud user's cloud space allocated for your app.

Solution

Use the `NSMetadataQuery` class.

Discussion

OS X Developers are probably familiar with the `NSMetadataQuery` class. This class allows developers to query Spotlight items, whether they are files or folders. In iOS, we will use this class to search for files and folders in the iCloud space assigned to our app for the current user, if she has set up iCloud for her iOS device on which our app is running.

To set up a metadata query, there are three very important things that we need to do:

1. We need to set the predicate of our metadata query. The predicate is the *search criteria* of the query. This predicate will tell the query what items we are searching for.
2. We also need to set the query's search scope. In order to search in the user's iCloud Documents folder, we set this scope to `NSMetadataQueryUbiquitousDocumentsScope`. Otherwise, you can use the `NSMetadataQueryUbiquitousDataScope` which represents the Data folder in iCloud, a folder that your app can use to store data related to the documents created by the user. Remember that the files that you store in the user's iCloud should not be your app's temporary files or any other files that your app can retrieve in some other way if those files weren't present in the user's iCloud storage. Things that you store in the user's iCloud storage should be his or her creations.
3. After we start the query, we shall start listening for the `NSMetadataQueryDidFinishGatheringNotification` notification. This notification gets called when the query has finished its search. In the method that handles this notification we can then look through the results that the query could gather for us and determine if any of those files/folders which are found are the files/folders that we are looking for.

The `setPredicate:` instance method of `NSMetadataQuery` class allows us to set the predicate of the query. The predicate must be of type `NSPredicate`. We will use the `predicateWithFormat:` class method of `NSPredicate` class to initialize our predicate. Remember, the predicate will tell the query what to search for. The `predicateWithFormat:` accepts a format string in the following format:

QUERY ITEM COMPARISON CRITERIA PATTERN

The *QUERY ITEM* part of the format of our predicate can be any of the `NSMetadataItem` constant values. For instance, we can use the `NSMetadataItemFSNameKey` constant value to tell the predicate that our search pattern targets the file-system name of the items in the cloud. Since the format provided to the `predicateWithFormat:` method can be variable-number of arguments with the first argument being the format of the rest of the arguments, you can pass `%K` as the *QUERY ITEM*. For instance, the following two predicates are basically the same in terms of how they will supply an input to the metadata query:

```

NSPredicate *predicate = [NSPredicate predicateWithFormat:@"%K like %@",
                          NSMetadataItemFSNameKey,
                          @"*"];

NSPredicate *samePredicate = [NSPredicate predicateWithFormat:
                              @"%NSMetadataItemFSNameKey like %@",
                              @"*"];

```

The *COMPARISON CRITERIA* part of the format of our predicate can be any of the following values:

>

To indicate that you are searching for query items that are, in value, bigger than your criteria patterns. For instance, you can search for all files, in the documents folder in iCloud container of an app, whose size is bigger than a X kilobytes where X is defined by you.

<

This comparison criteria is similar to the previous criteria. This criteria looks for items in the iCloud container of an app whose size (as an example) is smaller than the file size that you have specifies in the PATTERN.

like

This comparison criter is used for searching for file names display names of files. You can even use wildcards with this criteria, for instance, looking for all files whose name starts with a specific character.

We can go on and on about this but I suggest we dive into the development piece to get a better understanding of how metadata queries work. For this example, what we will do is:

1. When our app loads (in our app delegate), we will simply search for *all* files in our app's iCloud container.
2. We will then log the name of all the files that we found to the console, using `NSLog`.
3. At the end of every search, we will create a new file whose name we will generate randomly using a random integer. We will then make sure that file doesn't already exist in iCloud container for our app. If it doesn't, we will save it to the iCloud container. Simple, isn't it? This way, whenever our app opens up, we are creating a new file to the user's iCloud storage.



Storing unnecessary files in users' iCloud storage is a really bad practice. Make sure, as stated before, that you are only use iCloud to store files that have been directly created by your user, such as document, or creative images. For this example, since we need to find files/folders in the user's iCloud container to prove that our solution works, we need to at least have something stored in the iCloud container for our app.

Although we are going to learn about storing files in the iCloud in [Recipe 17.5](#), for the sake of this recipe, we will use another, and easier, method to store files into iCloud. We will accomplish this using the `setUbiquitous:itemAtURL:destinationURL:error:` instance method of `NSFileManager`. The parameters that we will pass to this method are:

setUbiquitous

This is a boolean value that you set to YES if you want to move a file to the iCloud.

itemAtURL

The parameter passed to this method is the `NSURL` pointing to the file, in your app's bundle, which needs to be moved to iCloud.

destinationURL

This is the URL of where the source file has to be copied in user's iCloud storage. This URL must be an iCloud URL.

error

A pointer to an `NSError` object which will get set to an error, if one occurs during process.

So let's go ahead and create a Single view application and then define our view controller with a metadata query property that we will use for searching in our app's iCloud container:

```
#import <UIKit/UIKit.h>

@interface ViewController : UIViewController

@property (nonatomic, strong) NSMetadataQuery *metadataQuery;

@end
```

Next step, synthesizing our property in the implementation file of our view controller:

```
#import "ViewController.h"

@implementation ViewController

@synthesize metadataQuery;

...
```

When our view controller is loaded, in the `viewDidLoad` method, we shall start the query and search for all files in the Documents directory of our app's iCloud container:

```
- (void)viewDidLoad{

    [super viewDidLoad];

    /* Listen for a notification that gets fired when the metadata query
    has finished finding the items we were looking for */
    [[NSNotificationCenter defaultCenter]
     addObserver:self
     selector:@selector(handleMetadataQueryFinished:)
     name:NSMetadataQueryDidFinishGatheringNotification
```

```

        object:nil];

        // Do any additional setup after loading the view, typically from a nib.
        self.metadataQuery = [[NSMetadataQuery alloc] init];
        NSArray *searchScopes = [[NSArray alloc] initWithObjects:
                                   NSMetadataQueryUbiquitousDocumentsScope, nil];
        [self.metadataQuery setSearchScopes:searchScopes];
        NSPredicate *predicate = [NSPredicate predicateWithFormat:
                                   @"%K like %@",
                                   NSMetadataItemFSNameKey,
                                   @"*"];
        [self.metadataQuery setPredicate:predicate];
        if ([self.metadataQuery startQuery]){
            NSLog(@"Successfully started the query.");
        } else {
            NSLog(@"Failed to start the query.");
        }
    }

    - (void)viewDidUnload{
        [super viewDidUnload];
        // Release any retained subviews of the main view.
        [[NSNotificationCenter defaultCenter] removeObserver:self];
        [self setMetadataQuery:nil];
    }
}

```

In this code, we have elected the `handleMetadataQueryFinished:` instance method of our view controller (yet to be implemented) as the method that our query will call whenever it has finished searching inside the Documents folder of our app's iCloud container. Let's go and implement this method. What we want to do in this method is to look for all the files that our metadata query found (if any) and then list them by printing them out to the console. After this, we will proceed to create a new random file and place it in our app's iCloud container. Here are the steps that we have to take in order to achieve this:

1. Generate a URL for a new random file in our app's iCloud container. For this we need to first find our app's iCloud container URL.
2. If the URL for this new random file already exists in the results returned by our metadata query, then we will ignore the whole operation.
3. If a file with the exact same name as our new random file has *not* been created in the Documents directory of our app's iCloud container, then we will proceed to first save a file with the same name to Documents directory of our app in our app's sandbox on the device.
4. After the file has been created in our app's sandbox, we will set it to ubiquitous where the file will be moved to iCloud and will automatically be deleted from our app's sandbox.

As described before, we are going to have to store a file into our app's Documents folder, on our app's sandbox and in iCloud. So we need to have some methods that give us

these URLs. First we will start with a method that will return the URL for our app's Documents folder in iCloud:

```
- (NSURL *) urlForDocumentsFolderIniCloud{

    NSURL *result = nil;

    #error Put your TEAM ID here
    const NSString *TeamID = @"YOUR TEAM ID";

    NSString *containerID = [[NSBundle mainBundle] bundleIdentifier];

    NSString *teamIDAndContainerID = [[NSString alloc] initWithFormat:@"%@.%@",
                                     TeamID,
                                     containerID];

    NSFileManager *fileManager = [[NSFileManager alloc] init];

    NSURL *appiCloudContainerURL =
    [fileManager URLForUbiquityContainerIdentifier:teamIDAndContainerID];

    result = [appiCloudContainerURL URLByAppendingPathComponent:@"Documents"
                                     isDirectory:YES];

    if ([fileManager fileExistsAtPath:[result path]] == NO){

        /* The Documents directory does NOT exist in our app's iCloud container;
           attempt to create it now */

        NSError *creationError = nil;
        BOOL created = [fileManager createDirectoryAtURL:result
                                     withIntermediateDirectories:YES
                                     attributes:nil
                                     error:&creationError];

        if (created){
            NSLog(@"Successfully created the Documents folder in iCloud.");
        } else {
            NSLog(@"Failed to create the Documents folder in iCloud. Error = %@",
                  creationError);
            result = nil;
        }
    } else {
        /* the Documents directory already exists in our app's iCloud container;
           we don't have to do anything */
    }

    return result;
}
```

Now we will use this method to determine the URL of our random file in the Documents folder in iCloud container for our app:

```

- (NSURL *) urlForRandomFileInDocumentsFolderIniCloud{

    NSURL *result = nil;

    NSUInteger randomNumber = arc4random() % NSUIntegerMax;

    NSString *randomFileName = [[NSString alloc] initWithFormat:@"%llu.txt",
                                (unsigned long)randomNumber];

    /* Check in the metadata query if this file already exists */
    _block BOOL fileExistsAlready = NO;
    [self.metadataQuery.results enumerateObjectsUsingBlock:
     ^(NSMetadataItem *item, NSUInteger idx, BOOL *stop) {
        NSString *itemFileName = [item valueForKey:NSMetadataItemFSNameKey];
        if ([itemFileName isEqualToString:randomFileName]){
            NSLog(@"This file already exists. Aborting...");
            fileExistsAlready = YES;
            *stop = YES;
        }
    }];

    if (fileExistsAlready){
        return nil;
    }

    result = [[self urlForDocumentsFolderIniCloud]
              URLByAppendingPathComponent:randomFileName];

    return result;
}

```

Now that we have the URL for the random file (yet to be created) in iCloud, we also need to write a method that we can use to get the URL for the same file in our app bundle. Since we created this random file name in the `urlForRandomFileInDocumentsFolderIniCloud` method, our new method won't know about this name and thus we need to pass the file name to our method as a parameter:

```

- (NSURL *) urlForRandomFileInDocumentsFolderInAppSandbox
    :(NSString *)paramFileName{

    NSURL *result = nil;

    NSString *documentsFolderInAppSandbox =
    [NSSearchPathForDirectoriesInDomains(NSDocumentDirectory,
                                         NSUserDomainMask,
                                         YES) objectAtIndex:0];

    NSString *filePath = [documentsFolderInAppSandbox
                          stringByAppendingPathComponent:paramFileName];

    result = [NSURL fileURLWithPath:filePath];

    return result;
}

```



```
}
```

Next stop is the implementation of a method that we will soon use to enumerate through the metadata items returned by our metadata query:

```
- (void) enumerateMetadataResults:(NSArray *)paramResults{

    [paramResults enumerateObjectsUsingBlock:
    ^(NSMetadataItem *item, NSUInteger index, BOOL *stop) {

        NSString *itemName = [item valueForKey:NSMetadataItemFSNameKey];
        NSURL *itemURL = [item valueForKey:NSMetadataItemURLKey];
        NSNumber *itemSize = [item valueForKey:NSMetadataItemFSSizeKey];

        NSLog(@"Item name = %@", itemName);
        NSLog(@"Item URL = %@", itemURL);
        NSLog(@"Item Size = %llu",
            (unsigned long long)[itemSize unsignedLongLongValue]);

    }];

}
```

Last but not least, we will implement the `handleMetadataQueryFinished:` method which will get called by the notification center when the metadata query finishes searching for our query:

```
- (void) handleMetadataQueryFinished:(id)paramSender{

    NSLog(@"Search finished");

    if ([[paramSender object] isEqual:self.metadataQuery] == NO){
        NSLog(@"An unknown object called this method. Not safe to proceed.");
        return;
    }

    /* Stop listening for notifications as we are not expecting anything more */
    [[NSNotificationCenter defaultCenter] removeObserver:self];

    /* We are done with the query, let's stop the process now */
    [self.metadataQuery disableUpdates];
    [self.metadataQuery stopQuery];

    [self enumerateMetadataResults:self.metadataQuery.results];

    if ([self.metadataQuery.results count] == 0){
        NSLog(@"No files were found.");
    }

    NSURL *urlForFileIniCloud = [self urlForRandomFileInDocumentsFolderIniCloud];

    if (urlForFileIniCloud == nil){
        NSLog(@"Cannot create a file with this URL. URL is empty.");
        return;
    }

}
```

```

NSString *fileName = [[[urlForFileIniCloud path]
                        componentsSeparatedByString:@"("/") lastObject];

NSURL *urlForFileInAppSandbox =
[self urlForRandomFileInDocumentsFolderInAppSandbox:fileName];

NSString *fileContent =
[[NSString alloc] initWithFormat:@"Content of %@",
 [[self urlForRandomFileInDocumentsFolderIniCloud] path]];

/* Save the file temporarily in the app bundle and then move
it to the cloud */
NSError *writingError = nil;
BOOL couldWriteToAppSandbox =
[fileContent writeToFile:[urlForFileInAppSandbox path]
                 atomically:YES
                 encoding:NSUTF8StringEncoding
                 error:&writingError];

/* If cannot save the file, just return from method because it won't make
any sense to continue as we, ideally, should have stored the file in iCloud
from the app sandbox but here, if an error has occurred,
we cannot continue */
if (couldWriteToAppSandbox == NO){
    NSLog(@"Failed to save the file to app sandbox. Error = %@", writingError);
    return;
}

NSFileManager *fileManager = [[NSFileManager alloc] init];

/* Now move the file to the cloud */
NSError *ubiquitousError = nil;
BOOL setUbiquitousSucceeded =
[fileManager setUbiquitous:YES
              itemAtURL:urlForFileInAppSandbox
              destinationURL:urlForFileIniCloud
              error:&ubiquitousError];

if (setUbiquitousSucceeded){
    NSLog(@"Successfully moved the file to iCloud.");
    /* The file has been moved from App Sandbox to iCloud */
} else {
    NSLog(@"Failed to move the file to iCloud with error = %@",
          ubiquitousError);
}
}
}

```

You can now go ahead and run the app and see for yourself. Once you open and close the app a few times, you will be able to see something similar to that shown in [Figure 17-11](#) in the Settings app on your iOS device:



Our app only creates a new file when the metadata query finishes. The metadata query gets fired in the `viewDidLoad` method of our view controller which itself gets fired when our only view gets loaded. Therefore, if you simply open the app and press the Home button on your iOS device, and then opening the app again, our app might not create a new file as our app was simply sent to the background as opposed to be getting terminated and re-opened. To make sure our app creates a new file every time you open it, before opening the app, close it manually from the apps bar in iOS by double pressing the Home button and closing the app from the list of running apps.



Figure 17-11. The list of random files that our app has created in iCloud

See Also

XXX

17.5 Storing User Documents in iCloud

Problem

You want to allow the users of your app to create documents in your app and you want to have those document present on all devices that the user owns.

Solution

Use `UIDocument`.

Discussion

Although a user can have many files of different types stored on her device by different apps, each app has to be considerate of the amount of data that it stores on the user's iCloud storage. Therefore, only the data that the user generates while using your app might need to be saved to the user's iCloud storage space. For instance, if you are creating a web-browser app, the data that your browser app caches on disk on the device should not be stored on the cloud. Why? Because that data was not generated by the user. Your app simply was trying to give a better user-experience by caching the data so that the next time accesses the same series of web-pages, the pages load faster. If you look at it from the user's perspective, she didn't really ask you to cache the data. What's even worse is that your app is now using the user's iCloud storage (for which she might have probably paid) to store cached data. That is simply wrong. You must ask the user what data your app is storing on the cloud and if she doesn't allow you to use her cloud storage space, then you should avoid using that space and store the data just locally on your app's sandbox.

One of the most confusing facts about iCloud is how you, as the programmer, will need to manage the data stored in the cloud. Before iCloud, as programmers, we were only concerned about the data that we were storing in our apps' sandbox. Now we need to learn about a secondary storage space called iCloud storage. A lot of programmers tend to get confused when it comes to iCloud storage, and I personally think that Apple might have made it a bit complicated in their documentations. Perhaps this is something that will be solved at a later stage of the iOS' development, but for now, here are a few key-points that you will need to learn about in order to integrate iCloud storage into your apps and allow the loading and saving of users' documents from and to iCloud:

1. A file that is present on the user's cloud storage is ubiquitous. Ubiquitous files are files that are stored outside an app's sandbox. We will talk about these more but for now, remember that a ubiquitous file is a file that is no longer present in the app's sandbox, but rather in the cloud.
2. The `UIDocument` class is a class that we will subclass in order to manage to manage users' documents. Each document will be given a ubiquitous URL to load its con-

tents from. In our subclass, all we really have to do is to implement 2 very important methods that will allow iOS to pass data to us (when iOS reads the data from iCloud) and for us to be able to pass data to iOS to store on iCloud.

3. Your ubiquitous files do *not* necessarily have to be in your app sandbox. If you want to store a file in iCloud, you will simply retrieve a direct URL to the iCloud folder (more on this later) and you will place your files there.
4. Before you go and create files in user's iCloud storage, you must first query the iCloud storage to see if that file already exists or not.
5. Each app has an identifier; iCloud uses that identifier to separate the iCloud files for that app with files from other apps present on users' iOS devices. If you use the same app identifier across multiple apps, all those apps will be able to share each-other's iCloud storage space. This can be good if you are developing a "lite" version of your app and you want the full version to be able to access the iCloud storage of the "lite" version of your app, and vice versa.
6. You can search for files in your app's iCloud storage for the current user, using the `NSMetadataQuery` class (refer to [Recipe 17.4](#) for more information).

In this recipe, we would like to write an app that simply creates a document for the user (text file) and allows her to edit that document. In the background, we will save that document to iCloud so that if she has another iOS device set up with the same iCloud credentials (username and password), she can see the most up-to-date version of the file that she is editing, regardless of which iOS device she is editing it on. So here is the checklist for this app:

1. We need to set up the appropriate provision profiles for our app and we will also need to correctly set up entitlements (see [Recipe 17.1](#) for more information).
2. Now we have to give our document a name. For instance, let's call our document file *UserDocument.txt*.
3. When our app opens (whether it is for the first time or not), we will fire up a metadata query and we will try to find the file in the user's iCloud storage. If that file already exists, we will retrieve its URL. If that file doesn't exist, we will create an empty/dummy file in that URL.
4. Now that we have the URL for the document file in the user's iCloud storage, we will open that document into our instance of the subclass of `UIDocument`. We will learn about this in a minute.

Something that can confuse any programmer is using the `UIDocument` class but to be perfectly honest, if you want to start with the basics, there are only four things you need to learn about this class:

1. You must always subclass this class. This class itself doesn't know how to load its contents and how to pass its contents as data to iOS to store in the cloud.

2. You must initialize this class with the URL of a file. In this recipe, we will pass the URL of a file in the user's cloud storage to the designated initializer of this class.
3. In your subclass, you must override the `contentsForType:error:` instance method of `UIDocument`. The return value of this method can be an `NSData` snapshot of the document you are managing. For instance, if it is a text file whose URL you passed to the initializer of your document class, then you must simply convert that text (presumably in the form of `NSString`) to `NSData` and return that data as the return value of this method. iOS calls this method in your document whenever it needs to store that data to the cloud or it simply needs to read that content to present it to the user.
4. You must override the `loadFromContents ofType:error:` instance method of your `UIDocument` subclass. In this method, iOS passes you the data (that perhaps was read from the cloud storage) and you must read that data into text, if text is what your document manages.

So, assuming that we have already set up our app with iCloud (see [Recipe 17.1](#)), we will go ahead and start subclassing `UIDocument`. In this recipe, we want to create a Documents folder in the user's iCloud storage for our app (if this folder doesn't exist yet) and we will then read from/store a file named *UserDocument.txt* in this folder. Follow these steps to subclass the `UIDocument` class:

1. In Xcode, select File→New→New File... from the menus.
2. In the New File dialog, make sure Cocoa Touch sub-category of iOS category is selected on the left hand side and then select the Objective-C class item on the right hand side of the dialog and press the Next button (see [Figure 17-12](#)).




Figure 17-12. Beginning to create a new document class

3. In the next screen, give the name `CloudDocument` to your new class and make sure you are subclassing `UIDocument`, as shown in [Figure 17-13](#). Once you are done, press the Next button.




Figure 17-13. Subclassing `UIDocument`

4. In the next dialog, select where you wish to save the new class and press the Create button (see [Figure 17-14](#)).




Figure 17-14. Saving the subclass to disk

Now that we have our `UIDocument` subclass, we need to go and see how we can initialize it. The designated initializer of `UIDocument` class is the `initWithFileURL:` method. However, we need to change this a bit as we are going to need a delegate object as well. Why do we need a delegate object, you might be asking? We want to let the delegate object know whenever iOS downloads a newer version of our document from iCloud. Imagine this scenario: the user has two iOS devices running your app and she has already set up those devices with her iCloud credentials. Now she opens your app on her iPhone and starts writing some text into the text-view. Then she leaves the app and goes to run some errands. She comes back and then picks up her *iPad* (as opposed to her iPhone that was used to write the content into our app) and she sees that our app picked the latest version of the document (the one she was editing on her iPhone) and presents the content. Remember that our app is still present in the background on her iPhone. She adds some text to the document on the iPad and goes back to the iPhone. At this point, iCloud has probably already picked up the version that her iPad synced to the

cloud and has downloaded that document into her iPhone. At this point, our document object has to be intelligent enough to present the new content to a delegate object. In this case, we can nominate our view controller (the owner of our text-view) as the delegate object of the document. The whole point being that we need to make sure a delegate object is there to get notified whenever iCloud gives us the new version of data present for the file using which we initialize the document. Let's define this protocol in the header file of our document and define a new designated initializer for our class:

```
#import <UIKit/UIKit.h>

@class CloudDocument;

@protocol CloudDocumentProtocol<NSObject>
- (void) cloudDocumentChanged:(CloudDocument *)paramSender;
@end

@interface CloudDocument : UIDocument

@property (nonatomic, strong) NSString *documentText;
@property (nonatomic, weak) id<CloudDocumentProtocol> delegate;

/* Designated Initializer */
- (id) initWithFileURL:(NSURL *)paramURL
    delegate:(id<CloudDocumentProtocol>)paramDelegate;

@end
```

Here is a brief description of what is going on in this header file:

The CloudDocumentProtocol protocol.

This is the protocol that this document's delegate object has to adapt in order to stay up-to-date about the changes to the current document which are brought into the user's current device via iCloud.

The documentText string.

This is a simple string that we will use to house the content of our document. The user will pass, to our class's designated initializer, the URL of the file using which we need to initialize our document. The `UIDocument` class will then read the contents of that URL for us (we don't have to do it manually) and will pass the data of that file to our class. All we have to do is to convert that data to the format we are managing in our document (in this case, `NSString`).

The initWithFileURL:delegate: designated initializer.

This is our class's designated initializer and very similar to the designated initializer of our superclass. The difference is that we are asking for a second parameter that will be the delegate of an instance of our class. We will keep our delegate object updated whenever new content is downloaded by iOS from iCloud for the document we are managing.

Now let's move to the implementation of our document. We will start by synthesizing our properties:

```
#import "CloudDocument.h"

@implementation CloudDocument

@synthesize documentText;
@synthesize delegate;

...
```

We will follow that by the implementation of our class's designated initializer:

```
- (id) initWithFileURL:(NSURL *)paramURL
    delegate:(id<CloudDocumentProtocol>)paramDelegate{

    self = [super initWithFileURL:paramURL];

    if (self != nil){

        if (paramDelegate == nil){
            NSLog(@"Warning: no delegate is given.");
        }

        delegate = paramDelegate;
    }

    return self;
}

- (id) initWithFileURL:(NSURL *)paramURL{
    return [self initWithFileURL:paramURL
        delegate:nil];
}
```

As described before, now we shall implement the `contentsForType:error:` instance method of our class. This method gets called whenever iOS decides to read the contents of the document that the instance of our class is managing. For instance, iOS might ask our instance to say what contents it is managing so that iOS can store that content on iCloud. In this method, we will simply convert our string to an instance of `NSData` and return it:

```
- (id) contentsForType:(NSString *)typeName
    error:(NSError *__autoreleasing *)outError{

    if ([self.documentText length] == 0){
        self.documentText = @"New Document";
    }

    return [self.documentText dataUsingEncoding:NSUTF8StringEncoding];
}
```



We are setting a default text for our document if the text that we are managing at the moment is empty so that when the user creates a new document (our app creates the document for the user) the first time, the text won't be empty and the user at least sees something on the screen.

Moving on to the implementation of the `loadFromContents:ofType:error:` instance method of our document class now, we shall simply read the content that is passed to us as the first parameter of this method and turn it into the text that our document instance is managing. This method gets called when iOS gives reads the contents of the URL using which the instance of our class gets initialized. So we will take the data and turn it into string in this example. In addition to that, we also let our delegate object know (if one is set) that the text that our instance is managing has changed:

```
- (BOOL) loadFromContents:(id)contents
        ofType:(NSString *)typeName
        error:(NSError *__autoreleasing *)outError{

    NSData *data = (NSData *)contents;

    if ([data length] == 0){
        self.documentText = @"New Document";
    } else {
        self.documentText = [[NSString alloc] initWithData:data
                                                             encoding:NSUTF8StringEncoding];
    }

    if ([delegate respondsToSelector:@selector(cloudDocumentChanged:)]) {
        [delegate cloudDocumentChanged:self];
    }

    return YES;
}
```



In this method, we will notify our delegate object that the contents of the document have changed, to give the delegate object a chance to update things, such as the UI.

That was really all we had to implement in our document class. The rest of the heavy-lifting has to happen in our view controller. The first thing in our view controller that we need to do is to find the iCloud path of the *UserDocument.txt* file that we are creating for the user. For this, as we learnt in [Recipe 17.3](#), we will use the `URLForUbiquityContainerIdentifier:` instance method of `NSFileManager`. Also, as we learnt in [Recipe 17.3](#) again, we will create a Documents directory in our app's root iCloud directory, if one doesn't exist. So let's begin with a method that returns the URL for the Documents directory in iCloud for our app and creates this directory if it doesn't exist already:

```

- (NSURL *) urlForDocumentsDirectoryIniCloud{

    NSURL *result = nil;

    #error Replace this with your own Team ID
    NSString *teamID = @"TEAM ID";

    #error Replace this with your own app identifier
    NSString *containerID = @"com.pixolity.Storing-User-Documents-in-iCloud";

    NSString *teamIDAndContainerID = [NSString stringWithFormat:@"%@.%@",
                                     teamID,
                                     containerID];

    NSFileManager *fileManager = [[NSFileManager alloc] init];

    NSURL *iCloudURL = [fileManager
                        URLForUbiquityContainerIdentifier:teamIDAndContainerID];

    NSURL *documentsFolderURLIniCloud = [iCloudURL URLByAppendingPathComponent:@"Documents"
                                          isDirectory:YES];

    /* If it doesn't exist, create it */
    if ([fileManager fileExistsAtPath:[documentsFolderURLIniCloud path]] == NO){
        NSLog(@"The documents folder does NOT exist in iCloud. Creating...");
        NSError *folderCreationError = nil;
        BOOL created = [fileManager createDirectoryAtURL:documentsFolderURLIniCloud
                                     withIntermediateDirectories:YES
                                     attributes:nil
                                     error:&folderCreationError];

        if (created){
            NSLog(@"Successfully created the Documents folder in iCloud.");
            result = documentsFolderURLIniCloud;
        } else {
            NSLog(@"Failed to create the Documents folder in iCloud. Error = %@",
                  folderCreationError);
        }
    } else {
        NSLog(@"The Documents folder already exists in iCloud.");
        result = documentsFolderURLIniCloud;
    }

    return result;
}

```

We will use the URL returned by the `urlForDocumentsDirectoryIniCloud` method to create the URL for the *UserDocument.txt* that our app wants to create/edit/manage:

```

- (NSURL *) urlForFileInDocumentsDirectoryIniCloud{

    return [[self urlForDocumentsDirectoryIniCloud]
            URLByAppendingPathComponent:@"UserDocument.txt"];

}

```

Now let's go to the header file of our view controller and define the appropriate instance variables. We need:

1. An instance of the `CloudDocument` class that will manage our document in the cloud.
2. An instance of the `UITextView` class which we will use to allow the user to enter her text and we will sync it to iCloud as she types.
3. An instance of the `NSMetadataQuery` class that we will use to find the existing document in the cloud, if one exists.

```
#import <UIKit/UIKit.h>
#import "CloudDocument.h"

@interface ViewController : UIViewController
    <CloudDocumentProtocol, UITextViewDelegate>

@property (nonatomic, strong) CloudDocument *cloudDocument;
@property (nonatomic, strong) UITextView *textViewCloudDocumentText;
@property (nonatomic, strong) NSMetadataQuery *metadataQuery;

@end
```

Now that we have our text view declared in the header file of our view controller, let's go instantiate it in the implementation of our view controller:

```
- (void) setupTextView{
    /* Create the text view */

    CGRect textViewRect = CGRectMake(20.0f,
                                     20.0f,
                                     self.view.bounds.size.width - 40.0f,
                                     self.view.bounds.size.height - 40.0f);

    self.textViewCloudDocumentText = [[UITextView alloc] initWithFrame:
                                     textViewRect];

    self.textViewCloudDocumentText.delegate = self;
    self.textViewCloudDocumentText.font = [UIFont systemFontOfSize:20.0f];
    [self.view addSubview:self.textViewCloudDocumentText];
}
```

We will be using this method in the `viewDidLoad` method of our view controller which will be discussed soon. Now let's start implementing a method that will allow our view controller to react to keyboard notifications. As it was discussed in [Recipe 2.24](#), when the user starts to change the text in our text view, the keyboard will popup (if a bluetooth keyboard isn't set up) and the keyboard will cover almost half of the iPhone screen. So in this case, we need to change the content inset of our text view. We start by listening to keyboard notifications:

```
- (void) listenForKeyboardNotifications{
    /* As we have a text view, when the keyboard shows on screen, we want to
       make sure our textview's content is fully visible so start
       listening for keyboard notifications */
    [[NSNotificationCenter defaultCenter]
```

```

addObserver:self
selector:@selector(handleKeyboardWillShow:)
name:UIKeyboardWillShowNotification
object:nil];

[[NSNotificationCenter defaultCenter]
addObserver:self
selector:@selector(handleKeyboardWillHide:)
name:UIKeyboardWillHideNotification
object:nil];
}

```

The next thing that we shall take care of is to, when our view controller's view is loaded (in the `viewDidLoad` method), search for existing user documents. If a document exists in the cloud, then we will load that; if not, then we will create a new document:

```

- (void) startSearchingForDocumentIniCloud{
/* Start searching for existing text documents */
self.metadataQuery = [[NSMetadataQuery alloc] init];
NSPredicate *predicate = [NSPredicate predicateWithFormat:@"%K like %@",
                        NSMetadataItemFSNameKey,
                        @"*"];
[self.metadataQuery setPredicate:predicate];
NSArray *searchScopes = [[NSArray alloc] initWithObjects:
                        NSMetadataQueryUbiquitousDocumentsScope,
                        nil];
[self.metadataQuery setSearchScopes:searchScopes];

NSString *metadataNotification = NSMetadataQueryDidFinishGatheringNotification;
[[NSNotificationCenter defaultCenter] addObserver:self
                                selector:@selector(handleMetadataQueryFinished:)
                                name:metadataNotification
                                object:nil];

[self.metadataQuery startQuery];
}

```

So let's utilize all these methods in our view controller:

```

- (void)viewDidLoad{
[super viewDidLoad];
[self listenForKeyboardNotifications];
self.view.backgroundColor = [UIColor brownColor];
[self setupTextView];
[self startSearchingForDocumentIniCloud];
}

- (void)viewDidUnload
{
[[NSNotificationCenter defaultCenter] removeObserver:self];
[self setTextViewCloudDocumentText:nil];
[self setMetadataQuery:nil];
[super viewDidUnload];
}

```

In the `startSearchingForDocumentIniCloud` method, we started listening for `NSMetadataQueryDidFinishGatheringNotification` notifications on the `handleMetadataQueryFin`

ished: method. We need to have a look at the implementation of this method. The way we have to implement this method is to first find out if the metadata query could find any existing iCloud documents. If yes, then we will look for the specific document that our app creates for the user which is called *UserDocument.txt*. If this file is found in the user's cloud space, then we will open that document. If not, we will create it:

```
- (void) handleMetadataQueryFinished:(NSNotification *)paramNotification{

    /* Make sure this is the metadata query that we were expecting... */
    NSMetadataQuery *senderQuery = (NSMetadataQuery *)[paramNotification object];

    if ([senderQuery isEqual:self.metadataQuery] == NO){
        NSLog(@"Unknown metadata query sent us a message.");
        return;
    }

    [self.metadataQuery disableUpdates];

    /* Now we stop listening for these notifications because we don't really
       have to, any more */
    NSString *metadataNotification =
        NSMetadataQueryDidFinishGatheringNotification;

    [[NSNotificationCenter defaultCenter] removeObserver:self
                                                name:metadataNotification
                                                object:nil];

    [self.metadataQuery stopQuery];

    NSLog(@"Metadata query finished.");

    /* Let's find out if we had previously created this document in the user's
       cloud space because if yes, then we have to avoid overwriting that
       document and just use the existing one */
    __block BOOL documentExistsInICloud = NO;
    NSString *FileNameToLookFor = @"UserDocument.txt";

    NSArray *results = self.metadataQuery.results;

    [results enumerateObjectsUsingBlock:^(id obj, NSUInteger idx, BOOL *stop) {
        NSMetadataItem *item = (NSMetadataItem *)obj;
        NSURL *itemURL = (NSURL *)[item valueForKey:NSMetadataItemURLKey];
        NSString *lastComponent = (NSString *)[itemURL pathComponents] lastObject];
        if ([lastComponent isEqualToString:FileNameToLookFor]){
            if ([itemURL isEqual:[self urlForFileInDocumentsDirectoryInICloud]]){
                documentExistsInICloud = YES;
                *stop = YES;
            }
        }
    }];

    NSURL *urlOfDocument = [self urlForFileInDocumentsDirectoryInICloud];
    self.cloudDocument = [[CloudDocument alloc] initWithFileURL:urlOfDocument
                                                            delegate:self];
}
```



```

__weak ViewController *weakSelf = self;

/* If the document exists, open it */
if (documentExistsIn iCloud){
    NSLog(@"Document already exists in iCloud. Loading it from there...");
    [self.cloudDocument openWithCompletionHandler:^(BOOL success) {
        if (success){
            ViewController *strongSelf = weakSelf;
            NSLog(@"Successfully loaded the document from iCloud.");
            strongSelf.textViewCloudDocumentText.text =
                strongSelf.cloudDocument.documentText;
        } else {
            NSLog(@"Failed to load the document from iCloud.");
        }
    }];
} else {
    NSLog(@"Document does not exist in iCloud. Creating it...");

    /* If the document doesn't exist, ask the CloudDocument class to
       save a new file on that address for us */
    [self.cloudDocument saveToURL:[self urlForFileInDocumentsDirectoryIn iCloud]
        forSaveOperation:UIDocumentSaveForCreating
        completionHandler:^(BOOL success) {
            if (success){
                NSLog(@"Successfully created the new file in iCloud.");
                ViewController *strongSelf = weakSelf;

                strongSelf.textViewCloudDocumentText.text =
                    strongSelf.cloudDocument.documentText;

            } else {
                NSLog(@"Failed to create the file.");
            }
        }];
}
}
}

```

What is left now is to listen for changes in the text view and once the changes have been applied by the user, we will try to save them into the document. We do this by implementing the `textViewDidChange:` delegate method of the `UITextViewDelegate` protocol:

```

- (void) textViewDidChange:(UITextView *)textView{
    self.cloudDocument.documentText = textView.text;
    [self.cloudDocument updateChangeCount:UIDocumentChangeDone];
}

```

With this method we are letting our document know that the user has updated the contents of the text in the text view. We call the `updateChangeCount:` instance method of `UIDocument` to give our document to reflect those changes to the cloud. Now we also

have to implement the `cloudDocumentChanged:` delegate method of the `CloudDocument Protocol` protocol and change the text inside the text view once the text in the document changes. This method will get called, for instance, when the user opens the app in two devices with the same iCloud credentials, changes the document in one device and leaves the document just open in the other device. The second device's iCloud daemon will then retrieve the latest version of the document from the cloud and the document class will call the `cloudDocumentChanged:` delegate message to give us a chance to update our UI:

```
- (void) cloudDocumentChanged:(CloudDocument *)paramSender{
    self.textViewCloudDocumentText.text = paramSender.documentText;
}
```

Before we forget, we also have to implement the keyboard notification handlers:

```
- (void) handleKeyboardWillShow:(NSNotification *)paramNotification{

    NSDictionary *userInfo = [paramNotification userInfo];

    NSValue *animationCurveObject =
    [userInfo valueForKey:UIKeyboardAnimationCurveUserInfoKey];

    NSValue *animationDurationObject =
    [userInfo valueForKey:UIKeyboardAnimationDurationUserInfoKey];

    NSValue *keyboardEndRectObject =
    [userInfo valueForKey:UIKeyboardFrameEndUserInfoKey];

    NSInteger animationCurve = 0;
    double animationDuration = 0.0f;
    CGRect keyboardEndRect = CGRectMake(0, 0, 0, 0);

    [animationCurveObject getValue:&animationCurve];
    [animationDurationObject getValue:&animationDuration];
    [keyboardEndRectObject getValue:&keyboardEndRect];

    UIWindow *window = [[[UIApplication sharedApplication] delegate] window];

    /* Convert the frame from window's coordinate system to
    our view's coordinate system */
    keyboardEndRect = [self.view convertRect:keyboardEndRect
                                fromView:window];

    [UIView beginAnimations:@"changeTextViewContentInset"
                      context:NULL];
    [UIView setAnimationDuration:animationDuration];
    [UIView setAnimationCurve:(UIViewAnimationCurve)animationCurve];

    CGRect intersectionOfKeyboardRectAndWindowRect =
    CGRectIntersection(window.frame, keyboardEndRect);

    CGFloat bottomInset = intersectionOfKeyboardRectAndWindowRect.size.height;

    self.textViewCloudDocumentText.contentInset = UIEdgeInsetsMake(0.0f,
```

```

0.0f,
bottomInset,
0.0f);

[UIView commitAnimations];
}

- (void) handleKeyboardWillHide:(NSNotification *)paramNotification{
    if (UIEdgeInsetsEqualToEdgeInsets(self.textViewCloudDocumentText.contentInset,
                                      UIEdgeInsetsZero)){
        /* Our text view's content inset is intact so no need to reset it */
        return;
    }

    NSDictionary *userInfo = [paramNotification userInfo];

    NSValue *animationCurveObject =
    [userInfo valueForKey:UIKeyboardAnimationCurveUserInfoKey];

    NSValue *animationDurationObject =
    [userInfo valueForKey:UIKeyboardAnimationDurationUserInfoKey];

    NSInteger animationCurve = 0;
    double animationDuration = 0.0f;

    [animationCurveObject getValue:&animationCurve];
    [animationDurationObject getValue:&animationDuration];

    [UIView beginAnimations:@"changeTextViewContentInset"
                     context:NULL];
    [UIView setAnimationDuration:animationDuration];
    [UIView setAnimationCurve:(UIViewAnimationCurve)animationCurve];

    self.textViewCloudDocumentText.contentInset = UIEdgeInsetsZero;

    [UIView commitAnimations];
}

```

Go ahead and run this app on a device. It is actually better if you can run the same app on two iOS devices that use the same iCloud credentials and then update the document on one device and wait for the second device to automatically update its contents from the cloud.

See Also

XXX

I

iOS applications (see applications)
iPhone SDK (see iOS SDK)

L

leaks (see memory leaks)

S

scrolling views (see table views)
SDK (see iOS SDK)

W

windows (see table views; views and
controllers)

About the Author

Colophon

The animal on the cover of *iOS 4 Programming Cookbook* is an Egyptian mongoose (*Herpestes ichneumon*), also known as an ichneumon. In ancient and medieval writings, the ichneumon is described as the enemy of the dragon, though it is more famous for battling snakes. Historic notables such as Pliny the Elder and Leonardo da Vinci recorded how the ichneumon would coat itself in several layers of mud, let it dry into a form of armor, and then attack a snake, eventually going for the reptile's throat. Later, Rudyard Kipling's short story *Rikki-Tikki-Tavi* describes the exploits of the eponymous Indian mongoose that saves his human family from the scheming cobras in their garden.

There are more than 30 species of mongoose, and all are skilled snake-killers, due in part to their resistance to venom. Because mongooses have chemical receptors shaped like those of snakes, it is difficult for neurotoxins to attach and paralyze them. Their agility, thick fur, and highly developed carnassial teeth (ideal for tearing) are also of use.

The Egyptian mongoose is the largest of all the African species, ranging from 19-23 inches long (with their black-tipped tail adding 13-21 inches more) and weighing 4-7 pounds. The animal's fur is coarse, generally colored gray with brown flecks. Despite its name, the Egyptian mongoose can also be found throughout most of sub-Saharan Africa, and has even been introduced to Madagascar, Spain, Portugal, and Italy. It lives in forest, savanna, and scrub habitats, never far from water.

The diet of the Egyptian mongoose is primarily carnivorous: it eats rodents, fish, birds, amphibians, reptiles (including venomous snakes), and insects, though eggs and fruit are also common. To crack eggs open, the mongoose will hold one between its legs and throw it at a rock or other hard surface. Mongooses are very versatile in action as well as diet; they can run backwards, roll over, swim, and stand on their hind feet.

The cover image is from Wood's *Animate Creation*. The cover font is Adobe ITC Garamond. The text font is Linotype Birka; the heading font is Adobe Myriad Condensed; and the code font is LucasFont's TheSansMonoCondensed.

